

Cambridge Natural Science Manuals.
BIOLOGICAL SERIES.

GENERAL EDITOR :—ARTHUR E. SHIPLEY, M.A.
FELLOW AND TUTOR OF CHRIST'S COLLEGE, CAMBRIDGE.

ZOOLOGY

**London: C. J. CLAY AND SONS,
CAMBRIDGE UNIVERSITY PRESS WAREHOUSE
AVE MARIA LANE,
AND
H. K. LEWIS,
136, GOWER STREET, W.C.**

**Glasgow: 50, WELLINGTON STREET.
Leipzig: F. A. BROCKHAUS.
New York: THE MACMILLAN COMPANY.
Bombay: E. SEYMOUR HALE.**

ZOOLOGY

AN ELEMENTARY TEXT-BOOK.

BY

A. E. SHIPLEY, M.A.,

FELLOW AND TUTOR OF CHRIST'S COLLEGE, CAMBRIDGE,
AND UNIVERSITY LECTURER IN ADVANCED MORPHOLOGY OF THE
INVERTEBRATA;

AND

E. W. MACBRIDE, M.A. (Cantab.), D.Sc. (Lond.),

SOMETIME FELLOW OF ST JOHN'S COLLEGE, CAMBRIDGE,
PROFESSOR OF ZOOLOGY IN M'GILL UNIVERSITY, MONTREAL.

CAMBRIDGE:
AT THE UNIVERSITY PRESS.
1901.

Cambridge:
PRINTED BY J. & C. F. CLAY,
AT THE UNIVERSITY PRESS.

PREFACE.

WE have tried in the following book to write an elementary treatise on Zoology which could readily be understood by a student who had no previous knowledge of the subject. We have endeavoured to explain the technical terms as they occur, and since one of the difficulties proper to the science of Zoology is the enormous number and the prodigious length of these terms, we have in many cases given derivations which may help the beginner to fix them in his mind.

The attempt to construct the book on the plan that each section is built on what precedes it, has rendered it impossible to keep the treatment of the various groups at the same level, for much space is taken up in the earlier chapters in explaining processes a knowledge of which is assumed in the later. A book such as we have aimed at is bound to be progressive, and the later chapters will be intelligible to the beginner only if he has read the earlier. Thus the part of this book which deals with the Vertebrata is in many respects more advanced than those which deal with the several Invertebrate groups.

In order to give some account of the leading types of animal structure within a book of moderate compass, we have been compelled to make but scanty reference to Histology, Embryology and Palaeozoology; in fact the book in the main deals with the normal structure of the adult forms of recent

animals. Wherever possible we have endeavoured to exhibit this structure as the outcome of function and habit. We have tried to show that Zoology deals at least as much with living as with dead organisms.

In tracing the relationship of the animals described to one another we have at times put forward hypotheses which we fear will not commend themselves to all zoologists, but we have *thought it better to run the risk of submitting views which further research may compel us to abandon rather than leave the student with the idea that the object of zoological study is the mere collection of facts.* We try everywhere to make it clear that the ultimate end of the science is the discovery of the laws underlying and binding together the facts.

At the end of the sections dealing with each phylum a short table of classification is given. These tables do not attempt to be complete but are intended to indicate the position of the animals mentioned in the text in the general scheme of classification, and since the book appears in both an English and an American edition, these examples are in most cases drawn from the British and North American Faunas.

In one respect this book differs from many of the elementary treatises which have appeared within the last few years. It has been drawn up with an eye to no examination and does not claim to correspond with any of the numerous syllabuses and schedules, issued from time to time by the various Boards of Examiners scattered through the United Kingdom and North America.

Many of the illustrations are new and whatever merit they possess is due to the skill of Mr E. Wilson of Cambridge and Mr F. M. Howlett of Christ's College. We owe our grateful thanks to Mr S. H. Reynolds for permission to use many of the illustrations of his book on "The Vertebrate

Skeleton," and to Messrs Macmillan & Co. and Messrs A. and C. Black and the Council of the Royal Agricultural Society for granting the use of certain other illustrations. We are also much indebted to many friends for help in special chapters. Mr E. S. Thompson and Mr J. Graham Kerr have read through the proof-sheets, a most tedious task, as the authors can abundantly testify; Dr Harmer, Dr Gadow, Dr Anderson, Dr Hopkins, Mr G. P. Bidder, Mr J. Stanley Gardiner, Mr R. Evans, Mr H. H. Brindley, and Mr C. Warburton, have most freely given us the help of their special knowledge. Whilst saving us from many mistakes they are by no means responsible for those that remain. We tender them all our sincere thanks.

A. E. S.

E. W. M.

August, 1901.

TABLE OF CONTENTS.

CHAP.		PAGE
I.	Introduction	1
II.	Phylum Protozoa	13
III.	Phylum Coelenterata	40
IV.	Phylum Porifera	69
V.	Introduction to the Coelomata	76
VI.	Phylum Annelida	82
VII.	Phylum Arthropoda	110
VIII.	Phylum Mollusca	197
IX.	Phylum Echinodermata	236
X.	Phylum Brachiopoda	276
XI.	Phylum Polyzoa	282
XII.	Phylum Chaetognatha	287
XIII.	Introduction to the Phylum Vertebrata; Sub-phyla I—III. Hemichordata, Cephalochordata and Urochordata	291
XIV.	Introduction to Sub-phylum IV. Craniata. Division I. Cyclostomata	318
XV.	Craniata. Division II. Gnathostomata. Class I. Pisces	352
XVI.	Craniata. Division II. Gnathostomata. Class II. Amphibia	400
XVII.	Craniata. Division II. Gnathostomata. Class III. Reptilia	440
XVIII.	Craniata. Division II. Gnathostomata. Class IV. Aves	475
XIX.	Craniata. Division II. Gnathostomata. Class V. Mammalia	498
XX.	Phylum Platyhelminthes	577
XXI.	Phylum Nemertinea	598
XXII.	Phylum Rotifera	603
XXIII.	Phylum Nematoda	611
	Index	617

LIST OF ILLUSTRATIONS.

FIG.	PAGE
1. <i>Amoeba proteus</i>	14
2. <i>Diffugia urceolata</i>	18
3. <i>Arcella discoides</i>	19
4. <i>Gromia oviformis</i>	20
5. <i>Polystomella crispa</i>	22
6. <i>Heliosphaera inermis</i>	23
7. <i>Chondrioderma difforme</i>	24
8. <i>Actinophrys sol</i>	26
9. <i>Actinosphaerium eichhornii</i>	27
10. <i>Vorticella microstoma</i>	28
11. Diagram of <i>Vorticella</i>	30
12. <i>Opalina ranarum</i>	32
13. <i>Paramoecium caudatum</i>	33
14. <i>Euglena viridis</i>	35
15. <i>Clepsidrina longa</i>	37
16. <i>Hydra fusca</i>	41
17. Longitudinal section through the body of <i>Hydra</i>	42
18. Transverse section of <i>Hydra fusca</i>	44
19. Cnidoblast from the body-wall of <i>Hydra fusca</i>	45
20. Section through body-wall of <i>Hydra fusca</i>	47
21. <i>Obelia helgolandica</i>	48
22. Part of a branch of <i>Obelia</i>	49
23. Free-swimming Medusa of <i>Obelia</i>	50
24. <i>Bougainvillia frutuosa</i>	51
25. Radial section through the edge of the umbrella of <i>Carmarina hastata</i>	53
26. Planula of <i>Clava squamata</i>	54
27. Part of a colony of <i>Alcyonium digitatum</i>	56
28. Transverse section through a polyp of <i>Alcyonium digitatum</i> below the level of the oesophagus	57
29. Transverse section through a polyp of <i>Alcyonium digitatum</i> through the region of the oesophagus	58
30. Semi-diagrammatic view of half a simple Coral	61
31. <i>Aurelia aurita</i>	63

FIG.	PAGE
32. Strobilization of <i>Aurelia aurita</i>	64
33. <i>Hormiphora plumosa</i>	66
34. View of a branch of <i>Leucosolenia</i> showing osculum	70
35. Vertical section through an osculum of <i>Leucosolenia</i>	71
36. Section of a flagellated chamber of <i>Spongilla lacustris</i>	72
37. Section of a portion of <i>Grantia extusarticulata</i>	73
38. Three transverse sections through a developing <i>Amphioxus</i> to show the origin of mesoderm	77
39. Two stages in the early development of a common fresh-water mollusc, <i>Planorbis</i> , to show the origin of the mesoderm.	78
40. Latero-ventral view of an Earth-worm, <i>Lumbricus terrestris</i>	83
41. Anterior view of the internal organs of <i>Lumbricus terrestris</i>	86
42. Six segments from the intestinal region of <i>Lumbricus terrestris</i> dissected so as to show the arrangement of the parts	87
43. Diagram of the anterior end of <i>Lumbricus herculeus</i> to show the arrangement of the nervous system	92
44. Transverse section through <i>Lumbricus terrestris</i> in the region of the intestine	94
45. View of the reproductive organs of <i>Lumbricus terrestris</i>	97
46. <i>Nereis pelagica</i>	101
47. Transverse section through <i>Nereis cultrifera</i>	102
48. <i>Hirudo medicinalis</i>	103
49. View of the internal organs of <i>Hirudo medicinalis</i>	106
50. Three stages in the emergence of the adult Dragon-fly from the larval skin	112
51. A Centipede, <i>Lithobius forficatus</i>	114
52. A male Cockchafer, <i>Melolontha vulgaris</i>	115
53. The Garden Spider, <i>Epeira diadema</i> , sitting in the centre of its web	116
54. The mouth appendages of <i>Gammarus neglectus</i>	117
55. Pedipalp of the large House-spider, <i>Tegenaria guyonii</i>	118
56. Left mouth-appendages of the Crayfish, <i>Astacus fluviatilis</i>	119
57. <i>Asellus aquaticus</i>	120
58. View of the nervous system of the Cockchafer, <i>Melolontha</i> <i>vulgaris</i>	121
59. Sections through the central and lateral eyes of a Scorpion, <i>Euscorpius italicus</i>	123
60. View of internal organs of male Crayfish, <i>Astacus fluviatilis</i> , seen from the side	124
61. Views of the gills of the left side of a Prawn, <i>Penaeus semi-</i> <i>culcatus</i>	127
62. View of internal organs of the male Cockchafer, <i>Melolontha</i> <i>vulgaris</i>	128
63. Horizontal section through the abdomen of a Spider, <i>Argy-</i> <i>roneta</i>	129

FIG.		PAGE
64.	Longitudinal section through the operculum and gills of a King-crab, <i>Limulus</i>	130
65.	Longitudinal section through the lung-book of a Spider	130
66.	Male reproductive organs of <i>Astacus fluviatilis</i>	132
67.	Female reproductive organs of <i>Astacus fluviatilis</i>	132
68.	Dorsal view of a female <i>Branchipus</i>	135
69.	Side view of male of <i>Daphnia similis</i>	136
70.	Side view of female of <i>Daphnia similis</i>	136
71.	Lateral view of <i>Cypris candida</i>	138
72.	Ventral view of a male <i>Cyclops</i>	139
73.	Dorsal view of a female <i>Cyclops</i>	140
74.	View of <i>Lepas anatifera</i> cut open longitudinally	142
75.	A Schizopod, <i>Nyctiphanes norwegica</i>	145
76.	The Shore-crab, <i>Carcinus moenas</i>	147
77.	Female of <i>Diastylis stygia</i> , one of the Cumacea	149
78.	Side view of <i>Gammarus neglectus</i> showing internal organs	150
79.	A Wood-louse, <i>Porcellio scaber</i>	151
80.	<i>Peripatus capensis</i>	152
81.	<i>Peripatus capensis</i> , male, dissected to show the internal organs	153
82.	A Centipede, <i>Lithobius forficatus</i>	155
83.	<i>Lithobius forficatus</i> , dissected to show the internal organs	157
84.	<i>Iulus terrestris</i>	158
85.	Two views of a male Cockroach, <i>Periplaneta orientalis</i>	161
86.	Mouth appendages of <i>Periplaneta</i>	163
87.	Female Cockroach dissected to show the viscera	166
88.	A Grasshopper, <i>Pachytylus migratorius</i>	174
89.	Larva of <i>Bombyx mori</i> , the Silk-worm	176
90.	Cocoon of <i>Bombyx mori</i>	176
91.	Silk-worm moth, <i>Bombyx mori</i>	176
92.	The Lady-bird, <i>Coccinella septem-punctata</i> , and its larva	179
93.	Male, Female and Neuter of the Wood-ant, <i>Formica rufa</i>	179
94.	Drone, Queen and Worker of the Honey-bee, <i>Apis mellifica</i>	179
95.	A Wasp, <i>Polistes tepidus</i> , and its nest	180
96.	The Tsetse-fly, <i>Glossinia morsitans</i>	181
97.	The Hessian-fly, <i>Cecidomyia destructor</i>	181
98.	The Garden Spider, <i>Epeira diadema</i> , sitting in the centre of its web	184
99.	Front view of the head of a Spider, <i>Textrix denticulata</i>	184
100.	Pedipalp of the large House-spider, <i>Tegenaria guyonii</i>	185
101.	Lateral view of the internal organs of a Spider, <i>Epeira diademata</i>	186
102.	Diagrammatic view of a palpal organ	188
103.	A Phalangid or Harvestman, <i>Oligolophus spinosus</i>	189
104.	Male and female of the Cheese-mite, <i>Tyroglyphus siro</i>	190

FIG.	
105.	Dorsal and ventral views of the Indian Scorpion, <i>Scorpio swammerdami</i> 203
106.	Dorsal view of the King-crab, <i>Limulus polyphemus</i> 205
107.	Ventral view of the King-crab, <i>Limulus polyphemus</i> 206
108.	Side view of a Snail, <i>Helix pomatia</i> , the animal being expanded 207
109.	Dorsal view of a Snail, <i>Helix pomatia</i> , after removal of the shell 211
110.	<i>Helix pomatia</i> , with the pulmonary chamber cut open 213
111.	Longitudinal section of the head of <i>Helix</i> to show the radula 214
112.	Dissection of the Snail, <i>Helix pomatia</i> , to show the internal organs 216
113.	View of the nervous system of <i>Helix pomatia</i> 218
114.	Optical section through the auditory vesicle of <i>Pterotrachea friederici</i> 220
115.	Nervous system of the Pond-snail, <i>Limnaea</i> 221
116.	Nervous system, osphradium and gills of <i>Hydrobia</i> 222
117.	The Pond-mussel, <i>Anodonta mutabilis</i> , with foot expanded and the empty shell of the same 224
118.	Right side of <i>Anodonta mutabilis</i> with mantle cut away and gills folded back 228
119.	Diagrammatic transverse sections of <i>Anodonta</i> 230
120.	Right side of <i>Anodonta mutabilis</i> dissected to show the viscera 232
121.	Dorsal view of <i>Anodonta mutabilis</i> , with the upper wall of the pericardium removed to show the heart 234
122.	<i>Solen vagina</i> , the Razor-shell 236
123.	Diagrams of a series of Mollusca to show the relations of the foot and visceral hump to each other and to the antero-posterior and dorso-ventral axes 241
124.	Posterior view of a male Cuttle-fish, <i>Sepia officinalis</i> , with the mantle-cavity opened 242
125.	A diagram showing the relation of the kidneys to the pericardium in <i>Sepia</i> 244
126.	View of heart and chief blood-vessels of <i>Sepia caltrata</i> 246
127.	Diagrammatic longitudinal section of <i>Sepia</i> to show the relation to one another of some of the principal viscera 247
128.	Lateral view of the central nervous system of <i>Sepia officinalis</i> 248
129.	Ventral view of <i>Sepia officinalis</i> dissected so as to show the nervous system 250
130.	Side view of the pearly Nautilus, <i>Nautilus pompilius</i> 252
131.	Oral view of a Star-fish, <i>Echinaster sentus</i> 257
132.	Dissection of the common Star-fish, <i>Asterias rubens</i> , so as to show the motor, digestive and reproductive organs 259
133.	A Star-fish, <i>Echinaster sentus</i> , in the act of devouring a mussel 261
134.	Diagram of a transverse section of the arm of a Star-fish 262
135.	Pedicellariae from <i>Asterias glacialis</i> 266

FIG.		PAGE
136.	Dorsal view of a Brittle-star, <i>Ophioglypha bullata</i> . . .	249
137.	Diagram of a transverse section of the arm of a Brittle-star .	250
138.	Diagram of a longitudinal vertical section through a Brittle-star	251
139.	Ventral view of a portion of <i>Ophioglypha bullata</i> . . .	252
140.	Dorsal view of a Sea-urchin, <i>Strongylocentrus dröbachiensis</i> , with the tube-feet expanded	254
141.	Dorsal view of the dried shell of the common British Sea-urchin, <i>Echinus esculentus</i>	255
142.	A gemmiform pedicellaria from <i>Echinus esculentus</i> . . .	256
143.	Dissection of <i>Echinus esculentus</i> so as to show the structure of "Aristotle's lantern"	257
144.	Diagram of a longitudinal vertical section of a Sea-urchin .	258
145.	Transverse sections through the madreporite and the radius of <i>Echinus esculentus</i>	260
146.	Dissection of a Sea-urchin so as to show the course of the alimentary canal	261
147.	The oral field or peristome of <i>Echinus esculentus</i> . . .	262
148.	The aboral system of plates, or periproct and calyx of <i>Echinus esculentus</i>	264
149.	Dissection of a Sea-cucumber, <i>Holothuria tubulosa</i> , so as to show the arrangement of the viscera	266
150.	A Feather-star, <i>Antedon acoela</i>	269
151.	Diagram of a longitudinal vertical section of the common Feather-star, <i>Antedon rosaceus</i>	270
152.	A stalked Feather-star, <i>Rhizocrinus</i>	272
153.	Ventral view of the larva of a Sea-cucumber	273
154.	Shell of a fossil Brachiopod, <i>Terebratulina obesa</i> . . .	277
155.	Section through the shell of <i>Waldheimia flarescens</i> . . .	277
156.	Dissection of <i>Waldheimia australis</i> so as to show the internal organs	278
157.	Longitudinal vertical section of <i>Argiope neapolitana</i> . .	279
158.	Portions of two Polyzoon colonies	282
159.	Longitudinal vertical section of <i>Plumatella fungosa</i> . . .	283
160.	An avicularium of <i>Bugula</i>	285
161.	Ventral view of <i>Sagitta hexaptera</i>	288
162.	Transverse sections of <i>Sagitta bipunctata</i> and of <i>Spadella cephaloptera</i>	289
163.	<i>Ptychodera kowalewskii</i> , a species of <i>Balanoglossus</i> . . .	292
164.	Longitudinal vertical section of <i>Ptychodera</i>	294
165.	Longitudinal horizontal section of <i>Ptychodera</i>	295
166.	<i>Amphioxus lanceolatus</i> seen from the left side	296
167.	Views of the velum and of the oral cartilages of <i>Amphioxus</i> .	296
168.	Diagram of longitudinal section through a young embryo of <i>Amphioxus</i>	297

FIG.	PAGE
169. Anterior region of a young <i>Amphioxus</i> seen from the left side	298
170. Diagrammatic transverse section through the pharyngeal region of a female <i>Amphioxus</i>	299
171. Transverse section through the intestinal region of a young <i>Amphioxus</i>	300
172. Front end of a young transparent <i>Amphioxus</i>	301
173. Anterior portion of the nerve-cord of <i>Amphioxus</i>	301
174. Longitudinal vertical section through the cerebral vesicle of <i>Amphioxus</i>	302
175. Transverse section through the middle region of the nerve-cord of <i>Amphioxus</i>	303
176. A nephridium of <i>Amphioxus</i> , belonging to the left side of the body	304
177. Portion of a transverse section through the pharynx of <i>Amphioxus</i> , in order to show the relations of the excretory tubule	305
178. Ventral view of an <i>Amphioxus</i> dissected so as to show the reproductive organs	306
179. Diagrammatic transverse section of <i>Amphioxus</i> to show the relations of the excretory and genital organs	307
180. Side view of the anterior end of a larva of <i>Ascidia</i>	309
181. Dorsal view of the anterior end of a larva of <i>Ascidia</i>	309
182. Diagrams showing the changes undergone by a larval Ascidian in its metamorphosis	311
183. <i>Ciona intestinalis</i>	312
184. Dissection of <i>Ciona intestinalis</i> so as to show the internal organs	313
185. Portion of a colony of <i>Botryllus violaceus</i>	315
186. Dorsal view of a fully developed asexual person of <i>Salpa democratica</i>	316
187. Longitudinal vertical section of <i>Salpa</i>	317
188. Views of the brain of a Dogfish, <i>Scyllium catulus</i> , from various aspects	320
189. Transverse section through the snout of a Dogfish, <i>Scyllium canicula</i>	323
190. Ear of <i>Chimaera monstrosa</i>	324
191. Section of an ampulla of the internal ear	325
192. Transverse section through the head of an embryo Chick of the third day of incubation in order to show the origin of the retina and lens of the eye	326
193. Diagram to illustrate the structure of the retina	327
194. Diagram of the arterial system of the Dogfish, <i>Scyllium</i>	335
195. Diagram of the venous system of the Shark, <i>Mustelus antarcticus</i>	338

FIG.		PAGE
196.	Dissection of the muscles of the eye of <i>Scyllium canicula</i>	339
197.	Diagrams illustrating the development of the excretory and reproductive organs of Craniata	341
198.	Diagram of a transverse section through a hypothetical ancestral Elasmobranch in order to show the origin of the excretory and genital organs	343
199.	The Musk Lamprey, <i>Petromyzon wilderi</i> , in the act of spawning	345
200.	Longitudinal vertical section through a female Lamprey, <i>Petromyzon marinus</i>	346
201.	Three views of the skull of <i>Petromyzon marinus</i> , from different aspects	347
202.	Section through the skin of an Elasmobranch showing the origin of a scale	354
203.	Diagrammatic transverse section of the jaw of a Shark, <i>Odonaspis americanus</i>	355
204.	Lateral view of the skull of a Dogfish, <i>Scyllium canicula</i>	356
205.	Dorso-lateral view of the pectoral girdle and fins of a Dogfish, <i>Scyllium canicula</i>	358
206.	Dorsal view of the pelvic girdle and fins of a male Dogfish, <i>Scyllium canicula</i>	359
207.	Dissection of <i>Scyllium canicula</i> , so as to show the viscera viewed from the ventral aspect	362
208.	Dissection of <i>Scyllium canicula</i> , so as to show the viscera seen from the right side	364
209.	Adult <i>Scyllium canicula</i> , and opened egg-case of the same	366
210.	A Ray, <i>Raia maculata</i>	368
211.	Skull of a male <i>Chimaera monstrosa</i>	369
212.	<i>Chimaera monstrosa</i>	370
213.	<i>Lepidosiren paradoxa</i>	371
214.	Dorsal and ventral views of the cranium of <i>Ceratodus miolepis</i>	372
215.	Lateral view of the skeleton of <i>Ceratodus miolepis</i>	373
216.	Diagram of the arterial arches of <i>Ceratodus</i>	374
217.	Diagram of the venous system of a Dipnoan	375
218.	<i>Polypterus</i>	377
219.	The Sturgeon, <i>Acipenser sturio</i>	380
220.	The right half of the pectoral girdle and the right pectoral fin of a Cod, <i>Gadus morrhua</i>	382
221.	Dorsal and ventral views of the cranium of a Salmon, <i>Salmo salar</i> , from which the membrane bones have been removed	384
222.	Lateral view of the cartilaginous cranium of a Salmon, <i>Salmo salar</i>	385
223.	Mandibular and hyoid arches of a Cod, <i>Gadus morrhua</i>	386
224.	Lateral view of the skull of a Salmon, <i>Salmo salar</i>	387
225.	Dissection of a Roach, <i>Leuciscus rutilus</i> , to show the viscera	389

FIG.	PAGE
226. A Cat-fish, <i>Amiurus catus</i>	390
227. The Plaice, <i>Pleuronectes platessa</i>	392
228. The Sea-horse, <i>Hippocampus</i>	394
229. Skeletons of the anterior and posterior limbs of a Newt, <i>Molge cristata</i>	401
230. Skeleton of <i>Molge cristata</i> , seen from the side	403
231. Male and female specimens of <i>Molge cristata</i>	406
232. Dorsal, ventral and lateral views of the skull of <i>Molge cristata</i>	409
233. Visceral arches of <i>Molge cristata</i>	410
234. Ventral and lateral views of the pectoral girdle and sternum of <i>Molge cristata</i>	411
235. Skeletons of (a) right fore-arm and hand of the Salamander, <i>Salamandra maculosa</i> , and (b) the right ankle of the Newt, <i>Molge cristata</i>	412
236. Pelvic girdle of <i>Molge cristata</i>	412
237. Dissection of a male <i>Molge cristata</i>	413
238. Diagram of the venous system of a Urodele	415
239. Diagram of the arterial arches of <i>Molge</i>	416
240. Dorsal view of the brain of <i>Molge cristata</i>	417
241. Excretory and reproductive organs of a female <i>Molge cristata</i>	418
242. Excretory and reproductive organs of a male <i>Molge cristata</i>	419
243. Larva of <i>Molge cristata</i>	420
244. Dorsal and ventral views of the cranium of the common Frog, <i>Rana temporaria</i> , from which the membrane bones have been removed	425
245. Dorsal and ventral views of the skull of <i>Rana temporaria</i>	426
246. Lateral and posterior views of the skull of <i>Rana temporaria</i>	427
247. Visceral arches of (a) a tadpole, (b) an adult Frog	428
248. Pectoral girdle and sternum of (a) a very old male specimen of <i>Rana temporaria</i> , (b) an adult female <i>Docidophryne gigantea</i>	429
249. Diagram of arterial arches of a Frog	430
250. Dorsal view and dissections of the heart of a Frog	431
251. Dorsal view of the brain and spinal cord of a Frog	432
252. The excretory and reproductive organs of (a) a male, and (b) a female Frog	433
253. Tadpole of <i>Rana esculenta</i>	434
254. Section through the scale of a Lizard	441
255. Ventral view of the pectoral girdle and sternum of a Lizard, <i>Loemancetus longipes</i>	444
256. Lateral view and longitudinal section of the skull of a Lizard, <i>Varanus varius</i>	445
257. Diagrams of the cranial roof in a Stegocephalian, various types of reptile and a bird	447

FIG.		PAGE
258.	Lateral view of the pectoral girdle of a Lizard, <i>Varanus</i> .	449
259.	View of the interior of the mouth of <i>Varanus indicus</i> .	451
260.	Diagram of the arterial arches of <i>Lacerta</i> .	452
261.	Diagram of the venous system in <i>Anura</i> and <i>Reptilia</i> .	453
262.	Excretory and reproductive organs of a male Lizard.	454
263.	Lateral, dorsal, ventral and posterior views of the skull of <i>Sphenodon punctatus</i> .	456
264.	The blind-worm, <i>Anguis fragilis</i> , a limbless Lizard.	458
265.	Dorsal and ventral views of the skull of the common Snake, <i>Tropidonotus natrix</i> .	460
266.	Diagram of the arterial arches of a Snake.	461
267.	The Texas Rattlesnake, <i>Crotalus atrox</i> .	462
268.	Dorsal and ventral views of the carapace of a loggerhead Turtle, <i>Thalassochelys caretta</i> .	464
269.	The plastron of a green Turtle, <i>Chelone midas</i> .	465
270.	Ventral view of the skeleton of the green Turtle, <i>Chelone midas</i> .	466
271.	Longitudinal vertical section of the skull of the green Turtle, <i>Chelone midas</i> .	467
272.	Ventral view of the skull, and dorsal view of the lower jaw of an Alligator, <i>Caiman latirostris</i> .	469
273.	The first four cervical vertebrae of a Crocodile, <i>Crocodilus vulgaris</i> .	470
274.	Sternum and associated membrane bones of a Crocodile, <i>Crocodilus palustris</i> .	471
275.	Left half of the pectoral girdle of an Alligator, <i>Caiman latirostris</i> .	472
276.	Pelvic girdle and sacral vertebrae of an Alligator, <i>Caiman latirostris</i> .	472
277.	Section through the skin of a Bird showing the developing feather.	477
278.	Skeleton of the right wing of a Gannet, <i>Sula alba</i> .	478
279.	Pectoral girdle and sternum of a Peacock, <i>Pavo cristatus</i> .	479
280.	Dorsal and ventral views of the wing of the Wild-Duck, <i>Anas boschas</i> .	480
281.	Lateral view of the pelvic girdle and sacrum of the Duck, <i>Anas boschas</i> .	482
282.	Skeleton of the common Fowl, <i>Gallus bankiva</i> .	483
283.	Lateral and dorsal views of the brain of the Pigeon, <i>Columba livia</i> .	486
284.	Anterior, posterior and dorsal views of the third cervical vertebra of an Ostrich, <i>Struthio camelus</i> .	487
285.	Diagram of the arterial arches of a Bird.	488
286.	Diagram of the venous system of a Bird.	489
287.	Dissection of the Pigeon, <i>Columba livia</i> .	490

FIG.	PAGE
288. The lungs, kidneys and reproductive organs of the Pigeon, <i>Columba livia</i>	494
289. Section through the skin of a Mammal showing the developing hair	499
290. Ventral view of the skull of the Dog, <i>Canis familiaris</i>	501
291. Dorsal view of the skull of the Dog, <i>Canis familiaris</i>	502
292. Dentition of the Dog, <i>Canis familiaris</i>	504
293. Dorsal and ventral views of the brain of the Rabbit, <i>Lepus cuniculus</i>	507
294. Sternum and sternal ribs of the Dog, <i>Canis familiaris</i>	508
295. Skeleton of the Rabbit, <i>Lepus cuniculus</i>	509
296. Diagram of arterial arches of the Rabbit	511
297. Diagram of the venous system of a Mammal	512
298. The Duckbill, <i>Ornithorhynchus anatinus</i>	514
299. Diagram to show the arrangement of the female genital ducts in Prototheria	514
300. Ventral view of the pectoral girdle and sternum of a Duckbill, <i>Ornithorhynchus paradoxus</i>	515
301. Diagram to show the arrangement of the female genital ducts in Metatheria	516
302. The Rock Wallaby, <i>Petrogale xanthopus</i> , with young in the pouch	517
303. Skull of Lesueur's Kangaroo-rat, <i>Bettongia lesueuri</i>	518
304. The banded Ant-eater, <i>Myrmecobius fasciatus</i>	519
305. Diagrams to show the arrangement of the female genital ducts in the Rabbit and Man as types of Eutheria	522
306. Tamandua Ant-eater, <i>Tamandua tetradactyla</i>	523
307. The six-banded Armadillo, <i>Dasypus sexcinctus</i>	524
308. The white-bellied Pangolin, <i>Manis tricuspis</i>	525
309. Lateral view and longitudinal section of the skull of a young Cæling Whale, <i>Globicephalus melas</i>	528
310. Skull of the African Manatee, <i>Manatus senegalensis</i>	529
311. Front views of the head of the American Manatee, <i>Manatus americanus</i>	530
312. An African Jumping-shrew, <i>Macroscelides tetradactylus</i>	531
313. The Russian Desman, <i>Myogale moschata</i>	532
314. Vertical longitudinal section of the skull of a Dog, <i>Canis familiaris</i>	534
315. The common Skunk, <i>Mephitis mephitis</i>	537
316. The Patagonian Sea-lion, <i>Otaria jubata</i>	538
317. The skull of <i>Hyrax</i> (<i>Procavia</i>) <i>dorsalis</i>	540
318. Left view of skull of a young Indian Elephant, <i>Elephas indicus</i> , with the outer sides of the jawbones removed so as to expose the roots of the teeth	541
319. Bones of the right fore-foot in living Perissodactyles	543

FIG.		PAGE
320.	The Indian Rhinoceros, <i>Rhinoceros unicornis</i>	544
321.	Stomach of a Sheep cut open so as to show the different compartments	547
322.	Skeleton of a Cape Buffalo, <i>Bubalus caffer</i>	548
323.	The African Chevrotain, <i>Dorcatherium aquaticum</i>	550
324.	The Musk-ox, <i>Ovibos moschatus</i>	552
325.	Side view of the skull of the Rabbit, <i>Lepus cuniculus</i>	553
326.	Dorsal view of the skull of the Rabbit, <i>Lepus cuniculus</i>	554
327.	The African Flying Squirrel, <i>Anomalurus fulgens</i>	556
328.	The Musquash, <i>Fiber zibethicus</i>	557
329.	Skeleton of a fruit-eating Bat, <i>Pteropus medius</i>	558
330.	Female with young of a Bat, <i>Xantharpyia collaris</i>	560
331.	Skulls of an old and of a young specimen of the Gorilla, <i>Gorilla savagei</i>	561
332.	The Ring-tailed Lemur, <i>Lemur catta</i>	562
333.	The Orang-utan, <i>Simia satyrus</i> , sitting in its nest	564
334.	A transparent Turbellarian, <i>Mesostoma splendidum</i> , showing the viscera	580
335.	<i>Planaria polychroa</i> , with everted proboscis	584
336.	Diagram of the reproductive and nervous systems of a Trematode, <i>Distoma hepaticum</i>	586
337.	Diagram of the digestive and excretory systems of a Trematode, <i>Distoma hepaticum</i>	588
338.	A Tape-worm, <i>Taenia solium</i>	591
339.	Transverse section through a mature proglottis of <i>Taenia</i>	592
340.	Diagram of a ripe proglottis of <i>Taenia solium</i>	593
341.	A Nemertine Worm, <i>Lineus geniculatus</i>	599
342.	A young transparent Nemertine Worm, <i>Cerebratulus fuscus</i>	601
343.	A Rotifer <i>Floscularia</i> ; (a) female of <i>Floscularia cornuta</i> , (b) male of <i>Floscularia campanulata</i>	604
344.	Diagram to show the arrangement of the viscera in <i>Floscularia</i>	605
345.	Diagram of a median longitudinal section of a free-swimming Rotifer	607
346.	Ventral view of <i>Hydatina senta</i>	608
347.	Dissection of female <i>Ascaris lumbricoides</i> so as to show the arrangement of the viscera	612
348.	Dissection of male <i>Ascaris lumbricoides</i> so as to show the arrangement of the viscera	614
349.	<i>Trichina spiralis</i> , encysted amongst muscular fibres	615

CHAPTER I.

INTRODUCTION.

THE word Zoology (Gr. ζῷον, an animal; λόγος, a discourse) denotes the science, which concerns itself with animals, endeavouring to find out what they are and how they came into being. It is a branch of the wider science of Biology (Gr. βίος, life, λόγος, a discourse)¹, which deals with all living things, plants as well as animals. Before any progress can be made with the study of Zoology, it is necessary to get clear ideas on two points: firstly, as to what is meant by life and living things; and secondly, as to how an animal is to be distinguished from a plant.

The idea implied in calling a thing living, is that in some respects its existence is similar to our own. Our own existence is the only thing immediately known to us, the standard with which we compare everything else. Every material object has certain points of resemblance to our bodies, inasmuch as all are composed of matter obeying the same laws of chemical affinity, gravitation, and so forth; it is necessary therefore to define the amount of resemblance which constitutes life. Now everyone knows that human beings grow, that is, increase in size at the expense of matter different from themselves, called food, and that further, they give rise at intervals to fresh human beings. These two fundamental characteristics—the power of growth and of multiplication—define life; everything that can increase its bulk by building up foreign matter into itself and that reproduces its like, is said to be alive.

The idea originally underlying the word animal was a self-moving object, as distinguished from a plant which was regarded as motionless². This distinction, however, will not stand close

¹ This term is too well established to admit of alteration but it implies a mistranslation of βίος. This does not mean 'life' in the physiological sense but a period of life, a career, a life-time or circumstances of life, environment.

² It is true that to all general statements of Zoology, as to this, exceptions could be found. The rule followed in this book is to have regard only to the

examination. Plants as well as animals move, and although the motions of animals are conspicuous and such as to catch the eye, whilst those of plants are usually slow and imperceptible, yet there is no essential difference between the nature of the movements in the two cases.

The fundamental difference between animals and plants is to be found in the nature of their food. Animals can only live on complex substances, not very different in chemical composition from their own bodies, and further, they can live on solid food. Plants, on the other hand, build themselves up out of carbonic acid and other gases and water with a few simple salts in solution, and they only take in fluids or gases. There are, however, a certain number of living beings which combine the characters of animals and plants, and the question in which division they should be ranked is a matter to be determined only after a study of the special circumstances of each case.

It has been pointed out that our own existence is the original type from which the idea of life is derived. But we know ourselves not only as bodies in which growth and reproduction occur, but also as conscious, thinking beings, and we are naturally inclined to imagine that animals at least, which not only grow and multiply, but in many other respects also resemble us, are likewise conscious. How far this belief is well-founded is open to serious question, if by consciousness we mean anything at all resembling our own inner life—the only consciousness we know anything about. The movements of the higher animals suggest that they experience the feelings of fear, anger, desire, etc., and it would be foolish to deny all similarity between them and man in these respects, but the habit many people have of uncritically attributing purely human feelings to dogs, cats, horses, etc., is apt to lead us into serious error. Our forefathers went further than even we are inclined to do and supposed all natural objects, the sun, wind, trees, etc., to have spirits, that is, to be conscious. Since we can never learn much about the consciousness of beings with whom we cannot speak, zoologists content themselves with looking at animals entirely from the outside, without enquiring as to whether or no they are conscious; animals are for them bodies in which certain changes take place, changes such as growth, reproduction, movement, and others.

vast bulk of normal cases which gave rise to the *idea*. The reasons for classifying abnormal cases in one category or another are not general but special, and have to be considered in each case.

A close study of animals reveals the fact that though the chemical constitution of no two is exactly alike, yet all contain certain highly complex substances of very obscure chemical composition, known as proteids. These substances occur in the form of a thick, viscous fluid, in which are suspended not only numerous solid granules of most varied composition, but also minute drops of other fluids. Such a mixture is called by chemists an emulsion, and it is the emulsion just described which is the seat of all those processes which we call life. This substance is termed protoplasm (Gr. *πρῶτος*, first; *πλάσμα*, a mould or image).

Further, it has been found that, so long as any sign of life is visible, this protoplasm is in a continual state of slow combustion, absorbing oxygen from outside and decomposing with the liberation of energy, and whilst some of the products of decomposition are cast off, others apparently reconstitute the original substance by combining with some of the materials of the food. The energy liberated is the cause of the movements which constitute the visible manifestation of life.

An animal then is only the more or less constant form of a flow of particles; it may be compared to a flame, which has a constant form, although the particles which compose it vary from moment to moment; unburned particles coming in at one end and the oxidised products escaping at the other.

The deepest insight, which can be obtained into the nature of life viewed as a series of changes in the shape and position of bodies, reveals to us this continual chemical change as the ultimate cause of all manifestations of life. It is known by the convenient name of metabolism (Gr. *μεταβάλλειν*, to change, to alter). The ultimate object of Zoology is therefore to discover the nature, cause, and conditions of the metabolism in the case of every animal; but the means of attaining this object are still to seek, and for the most part the zoologist has to be content with describing and comparing with one another the outer and visible effects of the metabolism in various cases.

The proteids, which form the essential basis of protoplasm, consist of carbon, nitrogen, hydrogen, oxygen, and sulphur; besides these elements phosphorus, chlorine, potassium, sodium, magnesium, calcium, and iron are constantly found in the bodies of animals, and some of them are doubtless chemically combined with the proteid. Phosphorus is a constituent of nucleic acid, a substance which in combination with proteid is characteristic of the nucleus (see

p. 16). Proteids have a percentage composition which varies somewhat, though not widely, in different cases.

Carbon	from	50	to	55	per cent.
Hydrogen	„	6·5	to	7·3	„ „
Nitrogen	„	15	to	17·6	„ „
Oxygen	„	19	to	24	„ „
Sulphur	„	·3	to	2·4	„ „

The molecular weight is undoubtedly very great. While we have no definite knowledge as to its value all the evidence tends to show that it is in any case not less than from 6000 to 8000 and it is probably a multiple of this¹. But the proteids known to the chemist are of course taken from the dead bodies of animals and are themselves to be regarded as products of the decomposition of the molecules which existed during life. The proteid as the seat of life has probably a decidedly different composition from the dead substance. To avoid confusion, we may call the living molecules biogens.

The biogen molecule is continually absorbing oxygen from the outside. This process is called respiration or breathing. It decomposes and some of the products are no longer capable of being built up again into other biogen molecules and are therefore got rid of, since otherwise they would interfere with the chemical action, just as accumulating ashes may put out a fire or cause it to burn smokily and to produce abnormal products such as Carbon monoxide. The process of ejecting these waste products is called excretion, the waste substances themselves, excreta, and the chemical changes which lead to their production, katabolism (Gr. *καταβάλλειν*, to cast or throw down). The commonest excreta are water, carbon dioxide, urea, and uric acid; the last two substances containing nitrogen. But it is not necessary that in all cases excreta should be ejected. They may remain within the bounds of a mass of protoplasm; if they are removed from the sphere of chemical action of the protoplasm this is sufficient. In some animals uric acid is stored up in this way. Many of the excreta, though injurious if they remain in the protoplasm, are indirectly useful to the animal after ejection. Such useful excreta are called secretions. Thus, all the hard skeletons of animals are really insoluble excreta. On the other hand, the gastric juice which digests the food in the human stomach, and the slime or mucus, which

¹ See Verworn, *General Physiology* (Engl. Edition), 1899, p. 93.

prevents a frog from drying up when taken out of water, are fluid excreta. A part of the body specially adapted to produce a secretion is termed a gland.

Other products of decomposition reconstitute, as we have seen, the original molecule by combining with the necessary elements from the food; this process is known as anabolism (Gr. ἀναβάλλειν, to put back or up) or assimilation. Inasmuch as, generally speaking, from the breaking up of one molecule more than one residue is produced capable of regeneration, there is an increase in the number of biogen molecules causing an increase in bulk of the protoplasm, or growth¹.

The regeneration of the biogen takes place at the expense of the food. Taking in food is called eating, or ingestion. Since however, the food must penetrate to every portion of the protoplasm it must be dissolved—a process effected by the chemical action of certain products of the decomposition of the biogens, known as ferments. The process is called digestion. The casting out of an insoluble remnant of the food is called defaecation, and inasmuch as such remnants have never formed part of the biogen molecule, this process is carefully to be distinguished from excretion. The accumulation of excreta soon stops metabolism, whereas the intermission of defaecation need only interfere very slightly with metabolism.

Of the numerous solid particles found in protoplasm some are secretions, others are solid deposits of partly assimilated food, which act as reserve stores, others are indigestible remains. The fluid drops consist largely of water—some have in solution excreta or secretions; others contain the results of digestion.

Animals, as we have seen, possess the power of executing movements; this power is exercised in order to seek their food and escape their enemies. However complicated these movements may be, they are all found to be dependent on the capacity of protoplasm to alter its shape in a characteristic manner, suddenly contracting and then slowly expanding. By contraction is meant such an alteration of shape of the moving part as will tend to diminish its surface; that is, the contracting part tends to assume a spherical shape; by expansion, on the other hand, is meant an alteration of shape leading to increase of surface. A bird flies by contracting the muscles first on one side of the wing, then on the other; a fish swims by alternate contractions of the two sides of the fleshy tail. Any part of an animal fitted to execute

Movement.

¹ See Verworn, *General Physiology* (Engl. Edition), 1899, p. 486.

movements more quickly in one direction than in another and so to bring about the movement of the whole animal, is called a locomotor organ. Protoplasm, in which the power of contraction is highly developed, is called muscle.

A contraction is the result of an explosive decomposition of the living substance; there have been a great many theories as to how the chemical change brings about the change of shape but since all of them account for some of the facts and none of them for all, *there is no need to mention any of them here.*

The sudden chemical change which brings about contraction, although dependent on the unstable character of the biogen molecule, must be precipitated by some change occurring either in the living matter itself or in the surrounding medium, just as an explosion of gunpowder is not brought about without a spark. In either case the change causing the contraction is known as a stimulus, and the capacity of contracting under the influence of stimuli is known as irritability. Thus when a moth flies into a flame, it is acting under the stimulus of light; when a hungry lion in the Zoological Gardens rises up and commences running violently round its cage, it is obeying the stimulus of hunger. In the first case we have to deal with an external stimulus, in the second with an internal one. Of course since all internal changes are ultimately due to changes in the surrounding medium,—e.g. hunger to a disappearance by digestion of the food in contact with the stomach,—the distinction between external and internal stimuli, though convenient, cannot be sharply drawn. The power of protoplasm to originate movement through internal changes is called automatism. In the case of external stimuli we can often observe that the disturbance caused at the point of application of the stimulus is propagated to widely different parts of the animal. Nerves contain protoplasm in which this power of transmission is powerfully developed.

We have seen that, at some period in the life of all animals, when food is abundant more living matter is formed than is broken down; in a word, that the animal increases in size, grows. But whereas volume increases proportionately to the cube of the length (or breadth), surface increases only proportionately to the square of the same dimension. Hence the amount of volume per unit of surface continually increases, and thus the chemical action between the internal portions of the protoplasm and the surrounding medium, which can only go on through the

Growth.

surface, is slowed down; in other words, the activity of growth is checked and when a certain size is reached waste becomes equal to repair. At this stage there is a tendency for the protoplasm to divide into two or more pieces of smaller size. This division into smaller pieces is called Reproduction, and it is a necessary result of growth. When an animal divides into two equal portions, the process is called fission, but when one portion is very much smaller than the other, the process is known as gemmation; the smaller portion is called the germ, and the larger the parent, since the latter is—somewhat illogically—regarded as identical with the original animal before division. A germ very rarely resembles the parent; usually it has to undergo a series of changes during growth by which it at last attains the shape of the animal which gave rise to it; this series of changes in shape and size is known as Development.

Reproduction in the higher animals is closely associated with another process called Conjugation or Sexual Union. This process consists in the coalescence with one another of two portions of living matter. Conjugation probably occurs in all animals, but the interesting thing about the higher animals is that they give rise to special germs of two kinds, called ova (eggs) and spermatozoa respectively, which cannot develop without first conjugating, one of the first kind uniting with one of the second.

The ovum is devoid of the power of movement and has a larger or smaller amount of undigested or at any rate unassimilated food stored in it; this reserve material is called yolk. The spermatozoon, on the other hand, has no such reserve and is in consequence very much smaller than the ovum, but it possesses in nearly every case the power of movement by which it is enabled to seek and find the ovum. Reproduction, which thus requires conjugation before development can take place is called Sexual Reproduction. In most cases ova and spermatozoa are developed in different individuals. The individual giving rise to ova is called the female, that giving rise to spermatozoa the male. In this case the animals are said to be bisexual. When both ova and spermatozoa are developed in the same individual, it is spoken of as hermaphrodite.

It is obvious to the most casual observation that there is an amazing variety of animals in the world. Closer observation reveals the fact that whilst no two animals are exactly alike, all can be nevertheless sorted into a

Species.

number of kinds called species, the individuals composing which—apart from the difference between males and females—resemble each other exceedingly closely. Where the observation has been made, it is always found that the members of a species conjugate freely with one another; and indeed this is assumed to be the case in every species; that is, we group a number of specimens into a species under the assumption that they can conjugate with one another, and that healthy young will develop as the result. If this can be shown to be not the case, we conclude that a mistake has been made and that two or more species have been confounded with one another. It follows that the vast majority of species rest on provisional hypotheses; these hypotheses nevertheless possess a very high degree of probability, for by the use of them only can the great resemblance between the individuals grouped together be accounted for. When, as occasionally happens, members of different species are fertile *inter se*, the offspring is termed a hybrid, and hybrids may or may not be fertile.

It has been pointed out, that whereas germs are in most cases exceedingly different from their parents, they nevertheless in process of growth come to resemble them. This tendency to reproduce the characters of the parent is called heredity. If the germ undergoes a large part of its development within a hard case, like a chick within the eggshell or in a cavity of the parent's body, it is called an embryo; if it moves freely about, it is termed a larva.

In the case of the development of an animal which has originated sexually, that is from the coalescence of two germs, the tendency is for it to assume characters intermediate between those of the two parents. Thus it is easy to see how sexual reproduction tends to annul the differences existing between members of the same species, by constantly producing means between them. When therefore a large number of individuals are found with very close resemblances, it is a reasonable supposition that the agent, which has caused this, is sexual reproduction; in other words, that they constitute a species. It is not however to be assumed that in every case conjugation results in the production of an animal exactly intermediate in character between the parents. Sometimes the child resembles closely the father or the mother, a result denoted by the phrase the "prepotency" of the father or of the mother. Sometimes in an unexplained way an exaggeration of a character found in one or both parents is produced. Sometimes even an apparently

Heredity
and
Variation.

entirely new character arises. Such deviations of the offspring from the average of the parent constitute variation. If the difference is striking the individual exhibiting it is called a sport.

It is obvious that so vast a science as Zoology must be divided into various branches, since the different questions it seeks to solve, must each require that special attention should be given to one side of the subject. Thus, the nature and conditions of the metabolism and the mechanism by which movements are effected, etc., constitute the subject-matter of Physiology; the investigation of the structure of individuals and of the differences in structure between the various species and the search for the causes of these differences is termed Morphology; whilst Bionomics is the name given to the study of the means whereby an animal obtains its food and orders its life, in other words, of its habits. But it must be remembered that all such divisions are purely arbitrary, and indeed no great progress can be made in any one department if the others be ignored. Bionomics, when followed to its sources, passes into Physiology, and in trying to explain the different structures studied in Morphology, constant recourse must be had to both Physiology and Bionomics.

Of all divisions of the subject, that of Physiology has been most neglected; it has indeed only been studied systematically in the case of man and of a few of the higher animals. Hence this work will be mainly concerned with the questions of Morphology and Bionomics. Of these questions, by far the greatest is the problem how the distinctions between the various species are to be explained. The question of the "Origin of Species" involves nearly all others in Zoology.

The distinctions between species are of very different degrees, so that for convenience species closely resembling each other are collected into genera—genera into families—families into orders—orders into classes—and classes into phyla. These are the names in commonest use, but often the nature of the subject requires the introduction of further grades of difference, and the number of grades actually employed depends to a large extent on the point to which the analysis is pushed.

The only theory of the origin of species which has so far commanded any considerable agreement amongst naturalists is the famous theory of Charles Darwin. According to this theory, the resemblances between a number of living species are due to the fact, that these species

Branches
of Zoology.

Classification.

Origin
of Species.

are descended from a common ancestral species, which possessed the common features as characters of its own. Therefore, the degree of likeness between species is the expression of a nearer or remoter blood relationship, and it logically follows that since no part of the animal kingdom is without resemblances to the rest, if we recede far enough in time we reach a period when all the animals in the world constituted one species.

To a certain extent Darwin's theory was only the expression of ideas that had first occurred to Greek philosophers, and had in one form or other been put forward by many naturalists before him. His distinct merit lies in that he pointed out various processes at present going on in nature which must lead to the modification of species.

He recalled attention to the well-known fact, that although the offspring in general resemble the parents, yet this resemblance is never exact, and further that the young of one brood often differ quite perceptibly from one another, and that these differences are often inherited by the offspring of the individuals showing them. Such differences, as has been mentioned above, are denoted by the term Variation.

Again, another fact well-known but usually ignored, was emphasised by Darwin: viz., that if the state of the animal population of the globe remains fairly constant, out of all the young produced by a pair of parents during their lifetime, on an average only two will survive, since if more were to live the species would inevitably increase in numbers. Hence since each animal tends to multiply at a rate at which if unchecked it would soon overrun the globe, a competition must result between the members of each species both for food and in the escape from enemies, as a result of which the "fittest" will survive. So long as the surroundings of the species remain the same, this struggle for existence will only weed out those individuals least perfectly adapted to their environment, so that the species will be kept up to a high level of adaptation to its surroundings. This elimination of imperfect individuals which results in the survival of the fittest is known as Natural Selection. Thus we can well imagine that if white-haired individuals turned up amongst hares, they would be more conspicuous and hence more easily discovered by the animals which prey on hares. If however the circumstances of a species change, a different class of individuals will survive. For instance, if for the greater part of the year the country inhabited by the hares were covered by snow, as is the case

in the North of Canada, the whitest-haired individuals would have the best chance, and from generation to generation would be selected until the colour of the hare was totally changed. The progressive modification of species by the agency of natural selection is called evolution. If the modification tends towards simplification of structure it is called degeneration, if on the contrary it tends towards great complexity it is spoken of as differentiation.

So far the theory shows how a species will become slowly modified as its surroundings change. But it has been postulated that distinct species have arisen from the same ancestors. It is of course not difficult to see that if a species is distributed over a wide area the conditions in different portions may vary independently of one another, and hence the species may become modified in one place in one direction and in another situation in a different direction by the agency of natural selection. So long however as the species inhabits a continuous area this tendency to split up into divergent groups will be checked by inter-breeding between the sections of the species which are thus becoming modified in different directions. But if through geographical changes the species becomes divided into groups of individuals cut off from access to another, then no interbreeding can take place and in time two species will be formed. Thus when birds have been blown far out to sea and have colonised a distant island they have often given rise to a new species. The same result may be brought about by the sea overflowing a part of the area inhabited by the species, an event which we know from geology to have occurred often. The important fact to be borne in mind is that at bottom the evolution of several species out of one is due to the formation of colonies, and that the same causes which have led to the differences between the American and the Englishman have acted again and again in the world's history so as to produce the marvellous variety of species inhabiting the globe, the only difference between human and animal colonies being that, in the latter case, the divergence has become so great that animal colonists will no longer breed with the original race. Thus, accepting Darwin's theory, we find it possible to give a rational explanation of those resemblances between animals which are expressed in a system of classification¹. If the theory be rejected these resemblances are pure figments of the human mind, and the species must be regarded

¹ Most of the names employed in classification were in use before Darwin's views were accepted. The word phylum (Gr. *φῶλον*, tribe or stock) is however an exception. This term expresses the central idea of the evolution theory, and its proper use is to denote the whole of a group of animals characterised

as just as independent of one another as are the chemical atoms. Hence since it is a choice between this explanation or none, the Darwinian theory is accepted by the overwhelming majority of naturalists.

One or two interesting consequences follow from the acceptance of this theory. The structural features of animals are to be regarded as adaptations to their surroundings, since they have been built up by natural selection. Hence an isolated resemblance in a particular feature between two species need not necessarily indicate that this feature was present in the common ancestral species, for similar surroundings may have evolved a similar modification in two animals only remotely related. Such similarities are called homoplasy, whereas resemblances believed to indicate blood-relationships are grouped under the term homology.

Again, the immature forms of some animals are found to exhibit strong resemblances to the adults of others, and the eggs of all the highest animals show the strongest general resemblance to the simplest animals—the so-called Protozoa (Gr. *πρῶτος*, first, *ζῶον*, animal). If these resemblances are to be interpreted in the same way as those prevailing between adults—and it is illogical to refuse to do so—then we are driven to conclude that most animals in their development pass through stages when they exhibit many characters once possessed by their ancestors, commencing at the stage of the Protozoa. These latter animals, since they are about as simply constructed as we can imagine living matter to be, may be looked on as slightly modified survivors of the first animals which appeared on the globe.

This method of interpreting the changes which occur during development is what is known as the Recapitulation Theory, because during Ontogeny (Gr. *ὄν*, *ὄντος*, being) or the development of the individual, nature recapitulates to some extent the development of the species in past time, Phylogeny (*φῶλον*, a stock, a race). There are, however, a great many other factors which have modified development, and the determination of these and their separation from the hereditary factor is a task requiring careful study and one which is as yet far from complete.

by having the same ground-plan of structure and believed to be the descendants of a common ancestor, from whom no other living animals are descended. The essential feature about a phylum is its isolation, in the present state of our knowledge, from other phyla. Of course it is believed that at bottom all living beings constituted one phylum, but there are enormous differences in structure which can only be bridged by imaginative hypotheses.

CHAPTER II.

PHYLUM PROTOZOA.

THE Protozoa are distinguished from all other animals (1) by the fact that they do not produce ova and spermatozoa but that the whole animal engages in the processes of conjugation and reproduction, and (2) by the fact that the protoplasm of the body is never differentiated into tissues nor exhibits cellular structure (see p. 27)¹. The higher animals are often grouped under the name Metazoa (Gr. μετά, after; ζῷον, an animal) in order to contrast them with the Protozoa, but whereas the Protozoa, since they have a common structural ground-plan, constitute a phylum in the sense defined in the last chapter the same is by no means true of the Metazoa. Hence the name Metazoa does not denote a phylum but is a mere convenient collective term.

The term Invertebrata is also a mere collective name; it is employed to designate all animals which do not belong to the phylum Vertebrata. Like the name Metazoa its convenience in promoting terseness of expression is its only justification. The Protozoa are thus Invertebrata and the Vertebrata are Metazoa.

The phylum Protozoa includes the simplest and lowest members of the animal kingdom. With few exceptions the members of this phylum are too small to be seen by the naked eye, and yet many of them are of great importance in the economy of nature.

In order to fix our ideas we may select one of the simplest

Protozoa as a type for examination. *Amoeba*, some-

Amoeba. times called the Proteus animalcule, from its power of continually changing its shape, is found in the mud at the

¹ To both these statements there are some exceptions and as our knowledge increases the number of the exceptions seems to augment.

bottom of ditches, ponds and pools of stagnant water. There are several species varying somewhat in size included under the generic name *Amoeba*, all of them, however, are so small as to necessitate the use of a microscope for their examination. When magnified an *Amoeba* appears like a small, almost transparent lump of jelly, in which we can distinguish a thin outer rind and inner




FIG. 1. *Amoeba proteus* $\times 330$. From Gruber.

1. Nucleus. 2. Contractile vacuole. 3. Pseudopodia, the dotted line points to the clear ectoplasm. 4. Food vacuoles. 5. Grains of sand.

substance. The first, called the ectoplasm, is almost absolutely transparent, the second, called the endoplasm, has usually a grayish tinge, due to the presence of minute solid particles or granules, and is therefore described as granular. Often indeed, good sized objects of various shapes and generally of a green or yellow colour, can be seen in the endoplasm; these are the undigested remains of the microscopic plants which the animal has eaten and are surrounded by bubbles of water, termed vacuoles. *Amoebae* frequently engulf particles of sand, though for what purpose is unknown; possibly to render themselves less palatable to animals which might eat them. If the *Amoeba* is healthy we shall see it move. The transparent ectoplasm slowly sends out a

projection, and then the granular endoplasm flows into it. As of course the size of the animal does not alter, when a process is thrust out in front, the rest of the animal must follow it by shrinking away behind; indeed it would no doubt be more correct to say, that it is the shrinking or contraction of the animal's body behind, which forces out the projection in front, for the movement of an *Amoeba*, like the movement of every other kind of animal, is brought about by a series of contractions.

These projections are called by the awkward name of pseudopodia (Gr. ψευδής, false; πόδιον, a little foot); the adjective pseudo-implies that they are not fixed organs like our own limbs, but are made at any part of the surface of the body. When *Amoeba* comes across anything it desires to eat, it throws out pseudopodia on each side of it; these then unite beyond the object, and so the latter becomes engulfed, so to speak, in the body of the animal, where it is digested. It may thus be said, that *Amoeba* flows round its prey. Once the prey is inside, it is surrounded by a drop of water, poured out of the surrounding protoplasm or enclosed with the food. There is probably some substance secreted into this water which acts on the prey and dissolves it.

One of the most marked features in which *Amoeba* differs from other animals, from ourselves for instance, is, that it possesses no separate parts or organs, such as stomach, heart, lungs, etc., fitted to perform the separate vital actions, or functions as they are called. It breathes, that is, absorbs oxygen and gives off carbon dioxide all over the body; and it likewise excretes, that is, gets rid of the oxidized protoplasm, at all points of the surface. If, however, we are so fortunate as to come across a large *Amoeba*, which is at the same time comparatively clear of granules, and moving only sluggishly, we may be able to make out two definite objects in the endoplasm. The first of these is called the contractile vacuole (2, Fig. 1); this is a clear round space, which slowly enlarges and then suddenly vanishes; and then reappears in the same place and goes through the same series of changes. It is believed that the cause of this appearance is that at a certain point in the endoplasm a substance is produced by katabolism with a strong affinity for water; this substance attracts to itself from the surrounding protoplasm water, carrying in it the soluble waste products, in fact draining the protoplasm and forming a drop. This drop swells until it, so to speak, bursts the covering of protoplasm separating it from the outside water; the space it occupies then collapses, but

as soon as the fluid has escaped, the rent in the protoplasm joins up again, and as the excretory process continues, the drop of fluid again accumulates.

The other object, which we may perceive, is the nucleus. This is a spherical body consisting apparently of the same kind of material as the endoplasm, only slightly denser (1, Fig 1). If we, however, kill the animal, by running in some iodine under the coverslip, the nucleus stands out at once in contrast to the rest of the protoplasm by its property of taking up more iodine and appearing stained a much deeper colour, and this happens in the case of any *Amoeba*, whether we have been able to see the nucleus whilst it was living or not. The nucleus is an essential part of the body: when deprived of it, metabolism within the protoplasm slackens and finally stops. All living things, animals or plants, possess one or more nuclei, though in some rare cases, the nucleus appears to take on the form, not of a compact body, but of a network, branching through the protoplasm. The bigger the plant or animal, the more nuclei it possesses. The so-called "Flowers of Tan" (*Mycetozoa*), which creep over the hides in tan-pits, are some of the few Protozoa which are distinctly visible to the naked eye; they may be compared to gigantic *Amoebae* with branching pseudopodia, and they have thousands of nuclei. In the case of certain Protozoa it has been proved that if the animal be broken in pieces, those bits which contain a nucleus can repair themselves and continue to live, eventually growing to form an animal like the one of which they are fragments; but those bits which contain no nucleus, though they continue to live for a short time, have no power of feeding themselves, nor of growth. On the other hand if the nucleus be freed from protoplasm it dies; life depends on the mutual reactions of protoplasm and nucleus.

The reproduction of *Amoeba* takes place by the simplest conceivable process; the animal divides itself into two. This process is called fission: and it is found that the nucleus always divides into two, before the body as a whole shows any signs of the process. When *Amoebae* are exposed to unfavourable conditions, such as the drying up of their surroundings, they have the power of enclosing themselves in a cyst. They draw in all their pseudopodia and assume a spherical form, and the cyst appears as a membrane on the outside, which then thickens. Once enclosed within its cyst, *Amoeba* can be blown about like a particle of dust, and in this way we can account for

Reproduction
and Encyst-
ment.

the fact that we sometimes find *Amoeba* in infusions, that is, solutions made by allowing some animal or vegetable matter to stand in water exposed to the air. If we put some hay or meat into perfectly pure water and expose it to the air, it will putrefy; this is due to the development of minute microscopic plants called Bacteria, the germs of which are carried by the air: at a later stage, various Protozoa and sometimes *Amoebae* will appear. At one time it was supposed that both Bacteria and Protozoa were spontaneously developed out of the dead meat, but it has been shown that if the water and meat be boiled, so as to kill any spores which may be in them, and the mouth of the vessel plugged with cotton-wool whilst steam is issuing, so that the air penetrating from outside through the interstices of the wool has all the spores it may carry strained off before it comes in contact with the water, neither Bacteria nor Protozoa will appear. The cyst which invests the body of the *Amoeba* is the first instance we have met with of what is called a secretion. A secretion has already been defined as dead substance which is of use to the animal, and which is produced by the decomposition of protoplasm.

When we were describing the endoplasm of *Amoeba* above, we called it granular, owing to its containing solid particles. When the highest powers of the best microscopes are used, it appears that both endoplasm and ectoplasm have a structure comparable to that exhibited by a mass of soap-bubbles. The walls of the bubbles consist of the actual living substance which is probably composed of the biogen molecules; the cavities are filled with water which has in solution the products of digestion, from which the living framework repairs itself, and likewise the excretory products. This water also conveys in solution the oxygen necessary for life and removes the carbon dioxide. It is only by means of a structure like this, that the complicated chemical changes which constitute life can be perfectly carried out by every particle of the living substance. The granules are temporary deposits in a solid form, either of matter resulting from katabolism, or of nutritious matter not yet assimilated.

We must now glance at some animals allied to *Amoeba*, in order to gain some idea of the group Protozoa as a whole.

Diffugia and *Arcella* are both found in the mud of pools and ponds; they resemble *Amoeba* in general structure but differ from it in being provided with shells. In consequence of having these, they are only able to put out

Lobosa.

pseudopodia at one spot, the mouth of the shell. The shell of *Diffugia* is composed simply of grains of sand stuck together with a secretion; it has the shape of a pointed egg with the thick end cut off (1, Fig. 2). *Arcella*, on the other hand, makes its shell entirely out of its own secretion; this is colourless when thin, but as the animal grows older, the shell becomes thicker and acquires a characteristic brown colour, and we are enabled to recognize that it consists of chitin. This is really a name for a class of substances which are constantly met with in the animal kingdom and which are probably allied in composition to uric acid. Out of chitin, for instance, all insects construct their hard cases. It seems probable, that the self-destruction of protoplasm, which results from the




FIG. 2. *Diffugia urceolata* $\times 100$. After Leidy.

1. Shell composed of particles of sand containing body of the animal.
2. Pseudopodia.

ordinary vital functions, may in many cases give rise to chitin, so that perhaps in *Arcella*, the shell is at once a protection and the ordinary excretion. The shape of this shell is like a watch-glass, with a flat lid resting on it, and in the middle of the lid there is a round hole, through which the pseudopodia come out. Sometimes gas bubbles (7, Fig. 3) can be seen in the body of the animal, which tend no doubt to balance the weight of the shell. Owing to the blunt character of the pseudopodia, *Amoeba*, *Diffugia*, *Arcella* and similar forms are united into a class termed Lobosa (Gr. λοβός, a lobe).

The Protozoon *Gromia* possesses a thin membranous shell, shaped somewhat like that of *Diffugia*: but the animal shows two important differences; first, the

Foraminifera.

protoplasm of which the body is composed, besides filling the shell, extends in a thin layer all over its outer surface (2, Fig. 4), and secondly, the pseudopodia, which are given off from this layer, are thin and delicate threads, which join and interlace with each other so as to form a network. *Gromia* seizes its prey by entangling it in these fine pseudopodia; these then flow together and form a little island of protoplasm surrounding the captive, which is thus digested quite outside the main part of the body; the products of digestion




FIG. 3. *Arcella discoides* $\times 500$. From Leidy.

- A. Seen from above. B. Seen from the side, optical section. 1. Shell.
 2. Pseudopodia. 3. Edge of opening into shell. 4. Thread attaching
 animal to inner surface of shell. 5. Nucleus. 6. Food vacuole.
 7. Gas vacuole.

being carried along the pseudopodia into the protoplasm which is inside the shell.

We may next consider a rather larger Protozoon, which is allied to *Gromia* and like it possesses a shell, which however is composed not of chitin but of calcium carbonate. The name of this animal is *Polystomella* (Fig. 5). Like *Gromia* it possesses delicate interwoven pseudopodia which spring from the whole surface, since there is a thin layer of protoplasm covering the outside of the shell, as well as the main mass inside it. Unlike *Gromia*, however,




FIG. 4. *Gromia oviformis* $\times 250$, but the pseudopodia are less than one-third their relative natural length. From M. S. Schultze.

1. Shell. 2. Protoplasm surrounding shell. 3. Pseudopodia, fusing together in places, and surrounding food particles such as diatoms.

Polystomella has a shell which is perforated by a large number of minute holes, through which pass cords of protoplasm, connecting the inner and outer parts of the animal. *Polystomella* is therefore a typical example of the Foraminifera (Lat. *foramen*, a hole; *fero*, to carry), a class which includes countless varieties of microscopic shells, generally composed of calcium carbonate, less frequently of flint (silica). *Gromia* is included in the Foraminifera though it does not possess the peculiarity indicated by the name, because its whole structure shows that it is really the same kind of animal. There is another most instructive feature of the structure of *Polystomella*, wherein it differs from *Gromia*. If we examine the shell with the low power of a microscope, we shall see that it is shaped like a rather flat snail shell, or the shell of the Pearly Nautilus. If, however, we dissolve away the shell with dilute acid so as to expose the proper body of the animal, it will be seen that this is made up of separate parts, united to each other by two or three little bridges of protoplasm, and arranged one behind the other in a spiral series. This is the first example we have met with of the repetition of similar parts in a definite order, but upon this principle of the repetition of similar parts, the bodies of the most complicated animals are built up. It is no doubt fundamentally the same thing as reproduction, only the various units which are produced, instead of separating from each other and leading separate existences, remain connected, and, as we say, are co-ordinated to form an individual of a more complex kind. In *Polystomella*, the various parts are called chambers; a name which properly belongs, and was first applied to, the segments of the shell enclosing them. It is worthy of note that it is only the protoplasmic body of *Polystomella* which shows this composition out of definite units arranged in a definite order; there may be one large nucleus or a considerable number of smaller nuclei, but they are not arranged in correspondence with the chambers.

The group Foraminifera, of which *Gromia* and *Polystomella* are examples, is of an enormous extent, and includes an immense variety of forms, the variety being brought about by differences in the number of chambers and the way they are arranged in series. The Foraminifera almost all live in the sea; some, like the two we have described, creep about amongst the sand and débris at the bottom of pools or other places where the water is quiet; many others float at the surface of the ocean, the protoplasm which clothes the outside of the shell having numerous vacuoles filled with fluid

probably less dense than the sea-water, and thus serving as floats
In such inconceivable myriads do these floating Foraminifera exist




FIG. 5. *Polystomella crista*. Highly magnified. After M. S. Schultze.

1. Shell. 2. Pseudopodia. 3. A mass of protoplasm formed by the fusion of pseudopodia.

that their empty shells form thick banks of impalpable white chalky mud at the bottom of the ocean, and the familiar white chalk of

our English cliffs and hills is largely made up of the shells of Foraminifera.

We may pass now to the consideration of some Protozoa, which show a good deal of resemblance in many points to the Foraminifera, though they have very marked peculiarities of their own. These are the Radiolaria; they have delicate threadlike interlacing pseudopodia, and their protoplasm is divided into two parts—an inner and an outer—by a membranous case pierced with pores, through which the two parts communicate with each other. This membranous case may be obviously compared to the Foraminiferan shell, but the interesting fact is that these Radiolaria have in addition to this another skeleton composed not of chalky—calcareous—but of flinty—siliceous—substance, as are also some of the shells of the Foraminifera. This flinty skeleton may consist simply of isolated needles sticking out on all sides from the centre; oftener, however, it consists of a beautiful basketwork as in *Heliosphaera inermis* (Fig. 6), and some-




FIG. 6. *Heliosphaera inermis* $\times 350$. From Bütschli.

1. Skeleton. 2. Central capsule. 3. Nucleus.

times we find several of these baskets one within the other, like the Chinese ivory ball. The Radiolaria, like the free-swimming Foraminifera, have a bubbly outer protoplasm, and often drops of oil in the inner protoplasm; these structures serve to sustain them and they are found floating at the surface of the sea amongst the Foraminifera. At the bottom, in medium depths, their flinty skeletons, though mixed with the calcareous shells of the Foraminifera, do not

affect the general character of the chalky mud (called the *Globigerina* ooze, from the name of one of the commonest Foraminifera found in it), but at greater depths, owing to the enormous pressure, the quantity of carbonic acid dissolved in the water increases very much—on the same principle that the pressure inside a soda-water bottle keeps the gas dissolved—and all the shells composed of chalky matter are dissolved, only the flinty skeletons being left. The bottom mud here entirely changes its character and is called Radiolarian ooze.




FIG. 7. Various stages of *Chondrioderma difforme*. From Strasburger.

- A. Flagellula leaving cyst. B & C. Flagellulae. D young and E older amoebulae. F. Amoebulae fusing to form plasmodium. All $\times 540$. G. Plasmodium $\times 90$. 1. The nucleus.

The next group of Protozoa to be considered is a very remarkable one, including the largest forms known. The so-called "Flowers of Tan" (Mycetozoa) are brightly coloured patches, which may be seen on the surface of the oak-bark used in tan-pits. Similar patches may be seen on old tree stumps and on the surface of beanstalks which have been wet for a considerable time. These patches under the microscope are seen to resemble enormous *Amoebae* with thin branching pseudopodia,

Mycetozoa.

which are apt to join one another to form networks, although these networks are much coarser than in the case of the Foraminifera. The fluid endoplasm is seen to have a regular flow alternately backwards and forwards in these pseudopodia; the movement of the whole mass in any direction being due to the predominance of the forward flow over the backward, or vice versa. When stained the protoplasm is seen to include thousands of very small nuclei. The name Mycetozoa literally means Fungus animals (from Gr. *μύκης*, a fungus, *ζῷα*, animals). They are also often called Myxomycetes—literally Slime-Fungi, both names having been suggested because the extraordinary mode of reproduction leads some naturalists to consider them to be plants. Their power of encystment is very marked, the slightest tendency to drought calls it into action, and then a mass will break up into numerous cysts, which will remain perfectly passive until wetted. Before reproduction, the same process occurs, but the contents of the cyst divide repeatedly so as to form a mass of small germs—spores—which acquire walls of cellulose, a constant product of plant life. Some of the protoplasm not used in the formation of spores forms long threads of cellulose, called collectively a capillitium, which when wetted expands and so expels the spores. The appearance of cellulose was the only justification for regarding these animals as in any way allied to plants, and it is known that cellulose is quite a constant product in some groups of animals. The contents of the spore escape as a germ propelling itself by a vibratile thread called a flagellum (B and C, Fig. 7), the germ itself being termed a flagellula. This thread is soon withdrawn and the germ takes on the form of a small Amoeba and is then called an amoebula (D, E, and F, Fig. 7). Many of these amoebulae coalesce to form the adult form, which is called the plasmodium (G, Fig. 7), a name given to the result of the fusion of a number of originally separate animals.

The Sun animalcules, or Heliozoa (Gr. *ἥλιος*, the sun), which inhabit, with few exceptions, fresh water, were formerly
Heliozoa.
confounded with the Radiolaria, but they are in reality totally different from these. They are spherical in shape and have a large number of stiff pointed pseudopodia sticking straight out all round them, like the conventional rays in pictures of the sun. The common and scientific names are taken from this circumstance. Since these animals float about, it is not surprising to find much the same structure in the outer protoplasm as we found

in Radiolaria and the floating Foraminifera. The pseudopodia are different in character from those of the Radiolaria, since they do not interlace, nor do they run together when they seize prey; the captured food is simply pressed in towards the body by the bending of the pseudopodia, and when it is brought quite close, a broad irregular pseudopodium, like one of those of *Amoeba*, shoots out and engulfs it. Pseudopodia were defined, in the case of *Amoeba*, as irregular projections shot out at intervals from the body and soon withdrawn and the question arises, how far we have any




FIG. 8. *Actinophrys sol* \times about 800. From Bronn.

1. Ectoplasm. 2. Endoplasm. 3. Contractile vacuole. 4. Food vacuole.
5. Nucleus. 6. Axis of a pseudopodium.

right to call by the same name these stiff projections of the Heliozoa. They are, however, true pseudopodia, for if the animal be subjected to strong irritation, they are all withdrawn. These animals show a most interesting example of the repetition of parts. The species *Actinophrys sol* and *Actinosphaerium eichhornii* are both comparatively common inhabitants of our ditches. The first is, however, exceedingly minute, not more than $\frac{1}{1000}$ th of an inch in diameter, and possesses only a single nucleus, whereas the second is large enough to be just visible to the naked eye, and has about 200 nuclei. There is here repetition of the nuclei, but no division of the protoplasm, whereas in *Polystomella* there is segmentation of

the protoplasm, but no corresponding multiplication of the nuclei. If both were to occur simultaneously and to correspond so that the body were to consist of a number of segments of protoplasm, each with its nucleus, the animal would be said to be multicellular, each unit being spoken of as a cell; but it would no longer be a Protozoon.




FIG. 9. *Actinosphaerium eichhornii* $\times 200$. From Leidy. The endoplasm is crowded with food vacuoles containing Diatoms, and nuclei represented in the figure by the dark areas.

1. Contractile vacuole. 2. Food vacuole which has just swallowed a Rotifer.
3. Pseudopodia.

So far we have been considering animals, which however much they may differ in details, are all essentially naked masses of protoplasm, and in them no very definite organs are set apart for the performance of special functions. We must now examine some Protozoa of a distinctly higher grade of

Ciliata.

structure, where definite organs exist; by the word organ being meant a part of the body definitely fitted to perform some special function for the general benefit of the whole. If we examine the roots of Duckweed with a lens, we shall probably find some coated with a whitish scum; if these be cut off and mounted in a drop of water on a slide and examined with a low power, they will be seen to be covered by numerous specimens of a most beautiful animal called *Vorticella*. *Vorticella* has something the shape of a blue-bell



FIG. 10. *Vorticella microstoma* \times about 200.
From Stein.

flower; it consists of a long delicate stalk and a bell-shaped body; by means of the stalk it is fixed to some definite support, such as, for instance, the Duckweed root. The part of the body corresponding to the lip of the bell is broad and turned outwards; encircled by this lip, which is called the peristome, there is a flattened projection called the disc. Between the peristome and disc there is a groove, and in this we can make out some short hair-like structures waving to and fro; there is a circle, or rather one twist of a spiral of these, as we can see when the animal turns the surface of the disc upwards. By the regular rhythmical bending of these cilia (Lat. *cilium*, an eyelash) as they are called, and possibly by the movement of a rolled membrane which projects into

the gullet, a vortex is produced in the water, which draws particles of food to the *Vorticella*. The cilia and the stalk are definite permanent organs, the first of the kind we have met with. But the possession of these organs is not by any means the only difference between *Vorticella* and the lower Protozoa. The shape of the body, though it varies slightly with the state of expansion or contraction, is practically constant; no pseudopodia are given out. This is the result partly of the possession of a firm membrane covering the whole of the body, called the cuticle, which is a protective secretion like the shell of *Arcella* only much thinner and so intimately connected with the protoplasm under it as to be inseparable; but the constancy of shape is also due to the fact that the outermost layer of the protoplasm itself is finely striated, constituting a specially contractile sheet, surrounding the body and distinctly marked off from the inner protoplasm. This sheet is called the cortical layer and the striation is caused by the differentiation of the

protoplasm into parallel strings called fibrils, embedded in different material acting as a cement. This arrangement of protoplasm makes its appearance whenever the contractile power is specially developed. The stalk, which is entirely composed of this layer, might almost be regarded as a muscular fibre. The stalk is slightly twisted and attached in a long spiral to the inner side of an elastic tube of cuticle. When contraction occurs the stalk is necessarily thrown into the most evident spiral curves, like a corkscrew; the restoration of the form after contraction is due to the elasticity of the tube.

Vorticella possesses a contractile vacuole and a nucleus just as *Amoeba* does; in small nearly transparent specimens both are easily detected during life; in fact, if the specimen under observation only keeps moderately still, we can follow the expansion and contraction of the vacuole with the greatest ease. The nucleus is very large, and has more or less the shape of a horse-shoe, though the two ends are generally at different levels, so that in reality it forms part of a spiral. If we run in some iodine, it at once absorbs the stain and stands out very distinctly; the *Vorticella*, however, frequently shows its dislike to the operation by contracting its body into the shape of a ball and snapping itself off from the stalk: it is then apt to get washed away from its position by the inflowing iodine and we may have to search over the slide to find it. When a *Vorticella* is irritated, the peristomial lip is turned in so as to lie against the disc, and thus the groove in which the cilia lie becomes converted into a tube and thus they are efficiently protected.

We have seen above that *Vorticella* uses its cilia in order to produce a miniature whirlpool in the water, by means of which particles of edible matter—whether living or not—are drawn towards it. Since, however, it possesses a firm cuticle and in addition a specialized outer layer of protoplasm, the question arises, how the food is taken into the interior of the body. If we run some Indian ink under the cover-glass, we shall have a demonstration how this is managed. The black particles are caught in the whirlpool made by the cilia, they course round and round and finally accumulate in a pit which opens into the ciliated groove and from the bottom of this they pass one by one into the internal protoplasm of the body. This pit which obviously passes through both the cuticle and the outer protoplasm—the cortical layer as it is called—is termed the pharynx and its opening the mouth. The particles of Indian ink which have passed into the body are

surrounded by little drops of fluid, which are partly swallowed with it, partly secreted by the protoplasm, in order to effect the solution of the particle, that is, its digestion. Such a drop is called a food-vacuole to distinguish it from the contractile vacuole, which as we have seen, has probably an excretory office to perform. As there is nothing nutritious in Indian ink, the *Vorticella* soon




FIG. 11. Diagram of *Vorticella*. The cilia at the side of the mouth have been omitted.

1. Disk. 2. Mouth. 3. Groove. 4. Vibratile membrane in mouth.
5. Ectoplasm. 6. Endoplasm. 7. Food-vacuoles. The last of the food-vacuoles is nearing the position of the anus. 8. Pharynx showing formation of food-vacuoles. 9. Contractile vacuole. 10. Permanent receptacle into which the contractile vacuole opens. 11. Micronucleus.
12. Nucleus. 13. Contractile fibrils running into muscle in stalk.
14. Stalk, contracted.

gets tired of trying to digest it, and the particles after having travelled round the body in a more or less definite tract are thrust out into the ciliated groove. Since this takes place at the same spot, there must be a permanent hole in the cuticle here though we cannot discern it, and this opening may be called the anus.

Therefore in contradistinction to *Amoeba*, where food can be taken in, and undigested remnants cast out at any spot on the surface, in *Vorticella* it is only at one particular spot that either action can take place.

The reproduction of *Vorticella* is a most interesting process. It takes place by longitudinal splitting, or as it is technically called fission. The disc splits into two, and the cleft soon reaches right down to the beginning of the stalk, so that for a time we have two bodies attached to the same stalk. One of these acquires a new row of cilia round its base; soon after the original circle of cilia and the ciliary groove disappear; the animal then breaks loose from the stalk and swimming by means of its new circle of cilia, seeks a new place of rest. The other body remains on the original stalk and resumes its life. This simple style of reproduction can go on for a long time unchecked, but experiments made on other Protozoa more or less allied to *Vorticella*, show that it has a limit. When we were speaking of reproduction in the introductory chapter, we mentioned that in sexual reproduction two germs had to fuse together before they could give rise to a new individual. Something like this has to happen at intervals in the case of *Vorticella*, in order that the reproduction by division may go on in a healthy manner. When this process (conjugation) is about to take place, one individual divides repeatedly by longitudinal division without any of the new individuals produced breaking away from the stalk, so that we have a bunch of minute *Vorticellae* attached to the same stalk. These afterwards become free and swimming away attach themselves to the sides of large stalked individuals. There then ensues an interchange of substance between the two individuals which thus adhere to one another; the large nucleus of each breaks up and disappears and a small subsidiary nucleus, the micronucleus (11, Fig. 11), exceedingly difficult to detect at ordinary times, now comes into view. It also breaks up and many of the portions disappear, but a part of the micronucleus of the large one passes into the little one and vice versa. In the case of the allies of *Vorticella*, when the two individuals which thus conjugate are of the same size, they separate after the operation, and each goes on dividing on its own account. In the case of *Vorticella*, however, the small individual seems to be exhausted by the process and is absorbed into the body of the other. It appears that this process of conjugation is only effective when it takes place between individuals of different parentages; if care is taken to exclude all *Vorticellae* of

foreign stock from a collection consisting of the descendants of a single one, either no conjugation takes place, or if it does take place, it fails to produce the results which normally follow, viz., increased vigour of reproduction and other vital processes. The individuals which are produced by fission, after a certain time, are badly formed, unable to feed themselves and die, and this is the nearest approach to natural death which is met with amongst the Protozoa.

Like *Amoeba*, *Vorticella* encysts and it appears still more frequently than *Amoeba* in infusions. The *Vorticellae* which are found under these circumstances are usually small and transparent and more favourable for observation than those occurring in ditches. The genus occurs both in fresh and salt water.

Vorticella is but one example of a large class of Protozoa termed Ciliata, which agree with it in all the essential points of structure, but differ in the arrangement of cilia, the absence of a stalk, and more rarely in the absence of a mouth and pharynx. This last feature is found only in those species which live in places where the surrounding fluid contains dissolved nutriment, which can percolate in at any spot.

An example of such a Ciliate is *Opalina* found in the intestine of the Frog. This animal is thin and plate-like and covered all over with cilia of the same size arranged in regular lines; this arrangement of cilia which is called the holotrichous arrangement (ὅλος, entire; ὀρίξ, hair), is always associated with the absence of a stalk and of a free-swimming life. *Vorticella*, on the other hand, is said to be peritrichous (περί = around). *Opalina* is further remarkable for possessing a large number of nuclei (1, Fig. 12), this is a rare occurrence amongst the Ciliata. When, however, division commences it continues until the resulting pieces have only one nucleus each; they then grow




FIG. 12. *Opalina ranarum*.
Highly magnified.
From Bronn.

1. Nuclei. 2. Ectoplasm.

and do not divide again till they acquire the size they had before division took place and also the same number of nuclei. So that we might regard the multiplication of the nuclei as the real reproduction of this form, the division of the protoplasmic body being of lesser importance and setting in later.

Paramoecium is one of the commonest free-swimming Ciliata.

It is of an elongated oval outline; seen sideways it has a thin scoop-like anterior end and a thick posterior part, so that it is usually described as slipper-shaped. It is holotrichous like *Opalina*, but like *Vorticella* it possesses only two nuclei, one large and easily visible and one, the micronucleus, small and difficult to detect. It



Paramoecium caudatum \times about 250. After Bütschli.

- | | | |
|-------------------------------|---|------------------------------------|
| 1. Mouth at bottom of groove. | 2. Oesophagus. | 3. Food vacuole just being formed. |
| 4. Contractile vacuoles. | 5. Trichocysts which have exploded: the unexploded ones line the cuticle. | 6. Cilia. |
| 7. Nucleus. | 8. Micronucleus. | 9. Contractile fibrils. |

has a well-developed mouth and deep pharynx situated on one side and lined with specially long cilia. *Paramoecium* is a beautiful form in which to study the contractile vacuole; there are two of these present, one in the anterior and another in the posterior

portion of the animal. If one of these vacuoles be watched it can be seen to contract and then slowly to re-appear. In the process of reappearance five or six isolated drops are seen which elongate into streaks arranged like the rays of a star. These streaks coalesce with one another and soon form a perfectly spherical drop.

Paramoecium possesses peculiar organs named trichocysts (5, Fig. 13) embedded in the outer layer of the protoplasm. They look like minute rods. When the *Paramoecium* is irritated—for instance if it is deluged with dilute iodine—or approaches prey it wishes to seize, these are suddenly shot out, assuming the form of long threads, and they appear to exercise a stunning action on any small animal with which they come in contact.

Passing from the Ciliata, we next come to a small group called the Suctoria, which are allied to the Ciliata, for their buds commence life as holotrichous forms. When they grow up they frequently become stalked like *Vorticella*, lose their cilia, and acquire instead a number of stiff rod-like outgrowths ending in knobs; these structures are termed tentacles. These are able in some way we do not understand to seize small animals and suck out their contents. Some secretion must be produced which eats its way through the cuticle and dissolves the contents of the prey.

The next group of the Protozoa we shall consider is a very large and important one. It is called the Flagellata. The members of it agree with the Ciliata in having a fixed shape and a firm cuticle and probably (though this is difficult to make out in the smaller ones) a specialized cortical layer of protoplasm; they differ, however, in not having cilia, but in possessing instead, one or two—rarely more—whip-like organs called flagella, which lash about in the water, and drag the animal after them by a spiral screw-like motion, just as a steamship is dragged after the screw when the engines are reversed. We may take as a type *Euglena viridis*, one of the numerous inhabitants of ditches. This animal has a narrow elongated shape, pointed at one end, and at the other—which is its front end—it possesses the vestige of a pharynx, which is exceedingly narrow. It has a flagellum which arises from the pharyngeal wall near its inner end. Slightly behind the pharynx there is a small contractile vacuole, and at the one side of this a small red spot, which may very possibly be associated with a sensitiveness to light. About the middle of the body is a nucleus which can sometimes be made out, as a clear spot, in the living

animal, but which is most satisfactorily observed when the animal is killed with osmic acid and stained with picrocarmine.




FIG. 14. *Euglena viridis*.

A $\times 100$, B, C, D, E, F $\times 200$ showing the different shapes assumed by the animal during the euglenoid movements. 1. Pharynx. 2. Contractile vacuole. 3. Pigment spot. 4. Nucleus.

Two features in *Euglena*, however, will strike us as very peculiar. One is, that in spite of possessing a cuticle and a cortical layer of protoplasm, it is able to change its shape. It does not possess the power of throwing out pseudopodia, but it bends its body in the most extraordinary way, and contracts it till it is almost spherical. The peculiar wriggling movements which it thus executes are so unlike anything else that they have been called euglenoid. The reason of their possibility is no doubt that the cuticle is flexible and the cortical layer powerfully contractile. The other peculiarity is still more striking, and it is that the protoplasm is coloured bright green, and that it contains particles of a substance very like starch. Now these things indicate that *Euglena* feeds itself like a plant, and that it constructs its protoplasm out of carbon dioxide and mineral salts dissolved in water in the presence of sunlight. The only points therefore that can be suggested in which it differs from plants are that it has a flagellum and moves, and that it does not possess a covering of cellulose. These supposed differences, however, will not stand examination; the germs of many undoubted plants, such as, for instance, the sea-weeds, have no cell wall and propel themselves by means of flagella. What justification then, it may be asked, have we for reckoning *Euglena* an animal? What do we mean by so classing it? It must be indeed admitted that when we come to deal with the simple Flagellata, the animal and plant kingdoms merge into one another, and the only valid line of division we can

draw is between forms which feed on solid food, and those which absorb dissolved nutriment; and amongst the latter we call those forms animals which we believe to have been derived from ancestors which fed on solid food. Now the pharynx in *Euglena* takes in solid particles from time to time and these passing into the protoplasm are apparently digested. Thus at times the nutrition of *Euglena* is carried on as in a plant and at times as in an animal, but taking into account its nearest allies it seems advisable to classify it with the animals rather than with the plants.

The reproduction of *Euglena* and of the Flagellata in general is quite similar to that of the Ciliata; they increase by longitudinal division, but they also divide when in an encysted condition into two or four, or a larger number of germs; these germs are not killed by drought. When dry they are blown about, and so appear in infusions. In infusions Bacteria appear first, then Flagellata, and finally Ciliata.

Many Flagellata are devoid of a pharynx altogether, but these rarely have chlorophyll and subsist on the nutritive substances which are dissolved in the fluid in which putrefying matter is soaking. These are reckoned as animals on no very good grounds; for it is well known that plants can lose their green matter when they can get the materials of protoplasm without building it up from carbon dioxide. How entirely arbitrary the decision is, is best shown by the fact that many forms are claimed by both botanists and zoologists. For this reason it is convenient to have a name which denotes simply a living thing without prejudging the question as to whether it is an animal or a plant. Such a name is supplied by the word *organism*, which is frequently used.

The last group of Protozoa, the Sporozoa, agree with the Ciliata in possessing a firm cuticle and a highly developed contractile cortical layer, but differ in never having any organs such as cilia or flagella; their movements, which are very sluggish, are carried out entirely by contractions of the cortex, which give rise to worm-like wriggings. All the Sporozoa are parasitic; that is to say all live at the expense of some other animal which is termed the host. All as a matter of fact pass the first period of their existence embedded in the protoplasm of some animal. Some—the Coccidia—remain throughout life in this position, but others when fully grown become at any rate partly free, adhering to their hosts only by one end. Only fluid nourishment is absorbed and consequently there is neither mouth nor

anus. There is never more than one nucleus, although the body may be divided by partitions running across the protoplasm into two or even three portions, placed one behind the other. Reproduction takes place after encystment, and this encystment is in most cases preceded by conjugation, so that two individuals are enclosed by a common cyst. The contents of the cyst break up into small germs called spores, which surround themselves with flinty cases and hence are called chlamydospores ($\chi\lambda\alpha\mu\acute{\upsilon}\varsigma$ = a cloak). The protoplasm inside these spores is sometimes liberated as a small amoeba-like creature which usually divides into two worm-like forms, which




FIG. 15. *Clepsidrina longa*, from larva of *Tipula*, the Daddy-long-legs. Highly magnified. From Léger.

A, B, C, D, E. Stages of the development of *C. longa*, at first within and then pushing its way out of one of the cells of the intestine of the *Tipula* larva. F. Mature form. G. Two forms conjugating. 1. Cell of intestine of host. 2. Its nucleus.

wander into suitable positions and become metamorphosed into the adult form. In very many cases, however, from two to eight

worm-like forms are formed by the division of the contents of the spore before the case breaks. The name *falciform embryo* has been given to these germs.

The best known Sporozoa are *Monocystis* found in the vesicula seminalis of the earthworm, with a long worm-like undivided body, *Clepsidrina blattarum* found in the intestine of the Cockroach and *C. longa* in the intestine of the larval grub of the Daddy-long-legs, which lives in damp soil. This last form is quite free when adult and is distinctly divided into two portions.

The *Haemamoeba* and *Haemonenus* which cause Malaria in man and allied forms which infest other vertebrates are classed with the Sporozoa.

The Coccidea is the name of one of the sub-divisions which remain entirely enclosed in the protoplasm of the infected animals throughout life, and in some cases cause disease.

The larger Sporozoa are often easily detected by the intense opaque white colour of the protoplasm, due to the inclusion of an immense number of granules. This is in marked contrast with the translucent protoplasm in which they are embedded.

Phylum PROTOZOA.

The Protozoa are classified as follows :—

Class GYMNAMEYXA.

Naked forms without distinct cortical layer and capable of emitting pseudopodia.

Order 1. Lobosa.

Simple forms with blunt pseudopodia which do not form networks ; with or without a shell.

Ex. *Amoeba*, *Diffugia*, *Arcella*.

Order 2. Reticularia.

Protozoa with thread-like pseudopodia which form networks ; a shell is formed and protoplasm covers the outside as well as the inside.

Suborder (α) **Foraminifera**. The shell consists of one or a series of chambers composed of lime or flint.

Ex. *Gromia*, *Polystomella*, *Globigerina*.

Suborder (*b*) **Radiolaria.** The shell is a single sac of membrane. In almost every case there is an additional skeleton of flinty needles, often joined so as to form complicated basket-works.

Ex. *Thalassicola*, *Heliosphaera*.

Order 3. **Mycetozoa.**

Protozoa with branching pseudopodia forming coarse networks and devoid of skeleton. Reproduction by means of spores coated with cellulose. The contents of many spores coalesce to form one individual.

Ex. *Chondrioderma*.

Order 4. **Heliozoa.**

Protozoa with stiff radiating pseudopodia. Skeleton when present only in the form of isolated needles.

Ex. *Actinosphaerium*, *Actinophrys*.

Class CORTICATA.

Protozoa with a distinct cuticle and almost always a distinct cortical layer.

Order 1. **Ciliata.**

Forms with cilia.

Ex. *Vorticella*, *Paramoecium*, *Opalina*.

Order 2. **Suctoria.**

Forms provided with sucking tentacles.

Ex. *Acineta*.

Order 3. **Flagellata.**

Forms provided with flagella.

Ex. *Euglena*.

Order 4. **Sporozoa.**

Parasitic forms, reproducing by spores. The younger stages at least are cell-parasites.

Ex. *Monocystis*, *Clepsidrina*, *Haemamoeba*.

CHAPTER III.

PHYLUM COELENTERATA.

It is difficult to say what idea the originator of the name Coelenterata meant to convey. Most animals have hollow insides (Gr. κοίλος, hollow; ἔντερον, inside); the Coelenterata however are distinguished from all the more highly organized groups in the animal kingdom by containing inside only one set of spaces, which all communicate with each other and with the exterior through the mouth.

The Coelenterate of simplest structure is undoubtedly the common fresh-water Polyp (*Hydra*), (Fig. 16). If a mass of weed and other débris from a ditch or even the edge of a river be placed in a glass vessel along with some of the water in which it was grown and allowed to settle, a number of these small animals frequently termed polyps will usually be found collected on the side of the vessel nearest the light. Several distinct species are collected under the name *Hydra*. There are three species recognized in Great Britain; *Hydra fusca*, about a third of an inch long when expanded and of whitish yellow colour, *Hydra viridis*, a quarter of an inch long, of a green colour, and *Hydra vulgaris*, which is almost colourless. Similar species to the first two, if indeed they are not identical, are common in Lower Canada. *Hydra fusca* may be selected as a type.

The shape of this animal is that of a minute cylinder. The base or foot is attached to the surface of the glass by an adhesive disc, whilst the other extremity carries a circle of delicate thread-like appendages called tentacles. In the centre of these, near their point of origin, we can with a lens detect a minute conical elevation, the oral cone (2, Fig. 16), at the end of which is the mouth. The mouth is the only opening to the body. It opens into a space, which occupies the whole extent of the animal, so that we might

with justice say that the polyp is really simply a tube closed at one end and open at the other: further, the tentacles can be seen with the microscope to be nothing but thin hollow tubes, opening into the central one (Fig. 17). The central space is often termed a stomach, and in the case of *Hydra* the idea suggested by this




FIG. 16. *Hydra fusca* \times about 12.

- A. Expanded condition. This specimen is budding off a young *Hydra*. It contains a large food mass in its coelenteron, probably a *Daphnia* or some other fresh-water Crustacean. B. Retracted condition. 1. Mouth. 2. Oral cone. 3. Tentacles. 4. Bud. 5. Endoderm. 6. Foot.

term is correct. In other Coelenterata the space performs other functions besides those of the human stomach, and the term coelenteron, which does not imply any function, is preferable.

With the microscope, however, we can make out a number of further points. If the edge of the animal be carefully focussed it can be seen that the body-wall consists of two layers, an outer




FIG. 17. A longitudinal section through the body of a *Hydra*, somewhat diagrammatic, the details of the cells are omitted. Magnified.

1. Mouth. 2. Foot. 3. Tentacle. 4. Coelenteron, digestive cavity.
 5. Ectoderm. 6. Endoderm. 7. Mesogloea or structureless lamella.
 8. Batteries of thread cells. 9. Testis. 10. Ovary with single ovum.

clear one, termed the ectoderm (Gr. ἐκτός, external; δέρμα, skin), and an inner one called the endoderm (Gr. ἐνδον, inside), which is green in *Hydra viridis* and brownish in *Hydra fusca*; so that we may speak of a skin as distinct from the lining of the coelenteron (Figs. 17 and 18). It is further possible to make out, under the microscope, that at any rate the outer layer is not homogeneous, but is composed of separate small pieces. It is necessary, however, to examine thin sections of specimens which have been hardened by being soaked in corrosive sublimate or some similar reagent, before one can really get a good idea of the structure of the "skin" and of the "inner lining" of the polyp. Then it is seen that both are made up of the repetition of similar parts, and that in each of these parts there is a single nucleus. Such a portion of protoplasm, marked off from the surrounding parts by a definite boundary, is called by Zoologists a cell. The wall or boundary of the cell probably consists of a thin layer of some secretion, in many cases, if not in most, traversed by bars or sheets of protoplasm connecting the cell with its neighbours. Around this term "cell" many battles have been waged, and its indiscriminate use has led to much misconception.

Cell.

It used to be said, for instance, that the Coelenterata were multicellular animals, as opposed to the Protozoa, which were unicellular. Now it has already been pointed out that the centre of the vital processes is the nucleus, which controls the processes going on in the protoplasm, and that in some of the Protozoa, such as *Actinosphaerium* and *Opalina*, this essential organ is repeated several hundred times. But an *Actinosphaerium* or an *Opalina* certainly does not correspond to a so-called cell of *Hydra*, with its single nucleus; the relation between them may rather be defined by saying that, whereas in *Actinosphaerium* the areas of control of the various nuclei are not visibly delimited from each other, in *Hydra*, on the other hand, this delimitation has to some extent taken place, leading to the appearance of cell-structure. But not only are cells to be detected in *Hydra*; the cells are not all of the same kind. Those forming the endoderm are very tall and often have great watery vacuoles near their inner ends; they also contain the coloured granules to which the colour of the animal is due. The cells of the ectoderm, or outer skin, on the contrary, are much shorter than those of the endoderm and are more or less pear-shaped, the broader end being turned out. Between their narrower bases we find groups of very small round cells

(2, Fig. 18). These so-called interstitial cells are young cells, which partly, no doubt, become developed into ordinary ectoderm cells as the older cells die and drop off, and in certain seasons of the year they increase very much in number at certain spots and form the reproductive organs (9 and 10, Fig. 17). The two kinds of organs, male and female, are borne by the same individual; in the male organ or testis all the cells remain small and become converted into the small spermatozoa; in the female organ or ovary one cell increases very much in size at the expense of the rest and becomes the egg-cell or ovum (10, Fig. 17). There is,




Fig. 18. Transverse section of *Hydra fusca*.

1. Ectoderm cells (myo-epithelial). 2. Interstitial cells. 3. Nematocysts.
4. Coelenteron. 5. Endoderm cells. 6. Vacuoles. 7. Food granules. 8. Nuclei.

however, a third change which these interstitial cells may undergo, which is of the utmost importance to the animal. Some of them move outwards and become wedged between and even embedded in the large ectoderm cells near the surface, each developing in its interior an oval bag filled with fluid. One end of this bag is turned into the interior of it, forming a long hollow thread. The whole bag is called a thread-capsule or nematocyst (Gr. *νήμα*, a thread; *κύστις*, a bladder) (Fig. 19). If now the cell in which the thread-capsule is situated contracts, since the fluid in the capsule is incompressible, the hollow thread must be quickly turned

inside-out and thus thrust out of the capsule. If the irritation of skin continues, the whole capsule will be pressed out by the animal. These thread-capsules are most abundantly developed in the tentacles, and a small amount of observation of the habits of *Hydra* will show how they are used. If a small Crustacean, or other animal, approaches too near a *Hydra*, the latter makes




FIG. 19. Cnidoblast with large Nematocyst from the body-wall of *Hydra fusca*. Highly magnified. From Schneider.

- A. Unexploded. B. Exploded. 1. Cnidoblast. 2. Nucleus of cnidoblast. 3. Cnidocil. 4. Muscular sheath. 5. Wall of nematocyst. 6. Thread. 7. Reflexed processes.

one swift lash with its tentacles and the luckless water-flea is seized and at the same time paralysed. If we now remove and examine the prey, we shall find it covered with exploded thread-capsules, the threads of which have entered its body, and exerted a poisonous action on it. It is perfectly easy to induce a *Hydra* which is being observed under the microscope to eject its thread-capsules: we

have only to irrigate it with a little ten per cent. solution of common salt, and from all parts of the skin we shall see first the threads shot out, and then the capsules follow.

In the case of a fluid like salt solution, the stimulating action is no doubt exerted over the whole surface of the animal, but an examination of the tentacle, when it is extended, reveals an arrangement for bringing about the explosion of the thread-capsule. The surface of the tentacle is seen to be covered with little swellings, in which are collections—one might say, batteries—of thread-capsules (8, Fig. 17); and from the surface of the ectoderm, in which they are embedded, delicate hair-like rods project out into the water (3, Fig. 19). If one of these be touched, it transmits a stimulus to the cell containing the thread-capsule, the cnidoblast (Gr. *κνῖδη*, a nettle; *βλαστός*, a sprout), as it is termed; in response to this stimulus the cell contracts, presses on and explodes the capsule. These rods are called cnidocils (Gr. *κνῖδη*, a nettle; Lat. *cilium*, an eyelash) and are the simplest form of sense-hairs met with in the animal kingdom.

In the first chapter it was pointed out that protoplasm, when it effects movements, always does so by contracting. We saw, for instance, that the extrusion of the pseudopodia of *Amoeba* could be accounted for by supposing that part of the outside protoplasm contracted and, so to speak, squeezed out part of the more fluid interior. In the life of *Hydra* the principal movements which occur are the shortening and lengthening of the body and the tentacles (B, Fig. 16). Now it has been found that of these movements, the shortening is effected by the contraction of the ectoderm in a longitudinal direction, and the lengthening by the contraction of the endoderm in a transverse direction, in consequence of which the animal is rendered thinner and longer. It has been further ascertained, by the examination of very carefully prepared transverse longitudinal sections, that each ectoderm cell possesses at its base a tail running vertically, embedded in the thin layer of jelly sometimes called the structureless lamella or mesogloea (Gr. *μέσος*, 'intermediate;' *γλῶϊα*, glue), which separates ectoderm and endoderm (Fig. 20). The endoderm cells similarly possess short tails, embedded in the jelly, but these run transversely. These tails then are instances of the tendency of protoplasm, which contracts regularly in one direction, to be drawn out into fibres in that direction, or, in other words, we have before us the first step in the conversion of an ordinary cell into a muscle cell. Cells

showing this modification are termed myo-epithelial (Gr. muscle): the word epithelial is used to signify the arrangement of cells in a layer to form a pavement or mosaic.

The most important function of the endoderm cells is to digest the prey which is captured by the tentacles and thrust into the coelenteron. For this purpose they secrete a fluid which has a great power of dissolving protoplasm. This fluid, termed digestive juice, is poured forth into the coelenteron and a large portion of the prey is dissolved by it and passes by diffusion into the endoderm cells, from which part is transferred in a similar manner to




FIG. 20. Section through the body-wall of *Hydra fusca*. Highly magnified. After Schneider.

- | | | |
|------------------------------|-------------------------------|--|
| 1. Ectoderm. | 2. Endoderm. | 3. Mesogloea or structureless lamella. |
| 4. Nematocyst. | 5. Cnidocil. | 6. Muscle-fibres of ectoderm cells cut across. |
| 7. Nucleus of ectoderm cell. | 8. Interstitial cells. | |
| 9. Cuticle. | 10. Pigment granule. | 11. Food granule. |
| | 12. Nucleus of endoderm cell. | 13. Flagellum. |
| | | 14. Water vacuole. |

the ectoderm. Certain portions of the prey, consisting of some of the proteids, resist the action of this juice. These are seized by pseudopodia emitted by the endoderm cells and bodily engulfed, and subsequently slowly digested in food vacuoles. Any insoluble parts of the prey, such as cuticle, skeleton, etc., are ejected by the mouth. Some of the endoderm cells also bear flagella, whose movement doubtless aids the circulation of the fluid in the coelenteron.

We have already seen that *Hydra* at certain seasons of the year, viz. the late autumn, produces egg-cells (ova) and male

germs (spermatozoa). The latter are shed out into the water, and eventually some of them reach the egg-cells and unite with them. This process is called fertilization, and the fertilized egg-cells cover themselves with spiny coats and drop off into the mud. Here they remain through the winter; in the spring the hard coat cracks and out issues a minute *Hydra*.




FIG. 21. *Obelia helgolandica* $\times 1$. From Hartlaub. This the hydroid generation, natural size as it appears to the naked eye.

But *Hydra* is by no means limited to this method of sexual reproduction in its power of multiplying itself. All through the spring and summer, if it be well fed, it buds or reproduces itself by Gemmation. A small swelling makes its appearance on the side of the body; this is really a hollow pouch containing a cavity in communication with the coelenteron (4, Fig. 16). The walls of the pouch are merely continuations of the body-wall of the *Hydra*, and hence consist of the same two layers. The pouch rapidly lengthens, and after a while a circle of tentacles sprouts out from its free end, and a mouth is formed in the centre. We thus have a daughter *Hydra* still in close connexion with the parent, the coelentera of the two being in open communication; later, however, this communication becomes closed and the offspring separates from the parent and leads a free existence. A third method of reproduction, which probably rarely occurs except artificially, is Fission. If a *Hydra* be divided into two halves, each half will grow up into a new individual.

A large number of the Coelenterata, called the Hydromedusae, agree with *Hydra* in all essential points of structure; the most important point of difference is that in them the buds do not become separated, but remain permanently in connection with the parent, and thus complicated colonies are built up (Fig. 21). Other differences of less

Hydro-
medusae.

importance are that there is a horny shell, the perisarc (Gr. περί, around; σάρξ, flesh) (6, Fig. 22), shed by the ectoderm on at any rate the lower portion of the body, also that the tentacles are nearly




FIG. 22. Part of a branch of *Obelia* sp. To the left a portion is shown in section. After Parker and Haswell.

1. Ectoderm. 2. Endoderm. 3. Mouth. 4. Coelenteron.
5. Coenosarc. 6. Perisarc. 7. Hydrotheca, prolonged at base of Hydroid as a shelf. 8. Blastostyle, a mouthless hydroid bearing medusa-buds. 9. Medusa-bud. 10. Gonotheca, part of perisarc which protects the medusa-buds.

always solid, containing, instead of tubular outgrowths of the endoderm, a solid cord of cells (Fig. 22) with firm outer membranes and

partially fluid contents, so that the cells have the same kind of stiffness as a well-filled water-pillow. These cords likewise bud off from the endoderm, but, as apparently the animal does not need the tentacle cavity which exists in the *Hydra*, it has disappeared, and the solid axis is essentially a strengthening or skeletal structure. As in *Hydra*, there is an oral cone; and in some species of Hydromedusae, at any rate, there is an additional row of short tentacles at the tip of this. It has been stated above that the buds do not become detached, but there is one kind of bud differing much in shape from the rest which does become detached. In

Medusa.

such a bud, the whole body becomes very much shorter and at the same time much flattened out in its lower portion, so that the main circle of tentacles is widely separated from the oral cone; at the apex of the latter there is sometimes a second circle of small tentacles. The flattened part of the body becomes concave on the side towards the mouth so as to assume the form of a bell or umbrella, and, owing apparently to this circumstance, the part of the coelenteron which it contains becomes so pressed together, that by the adhesion of its upper and lower walls, its cavity for the most part disappearing, it becomes converted into a concave layer, called the endodermal lamella. Along four lines, however, the cavity does not disappear (4, Fig. 23), and it also




FIG. 23. Free-swimming Medusa of *Obelia* sp.

1. Mouth at end of manubrium.
2. Tentacles.
3. Reproductive organs.
4. Radial canals.
5. Auditory organ.

remains open just beneath the circle of larger tentacles at the edge of the bell, so that in this way we have a circular or marginal canal established, communicating by four radial canals with the part of the coelenteron that still persists in the oral cone, and opening to the exterior by the mouth (1, Fig. 23). The upper surface of the bell is styled the exumbrella or aboral surface (Lat. *ab*, away from; *os*, *oris*, the mouth) the lower the subumbrella or oral surface.

The great mass of the bell is composed of the jelly intervening between the outer ectoderm on the convex side and the endoderm. In this jelly solid strings sometimes appear which give it a firmer consistence. The modification of the



FIG. 24. *Bougainvillia fructuosa*, Allman \times about 12. From Allman.

- A. The fixed hydroid form with numerous hydroid polypes and medusae in various stages of development. B. The free swimming sexual Medusa which has broken away from A.

base of the animal into the shape of an umbrella causes the oral cone to resemble the handle, hence the name *manubrium* (Lat. a handle), by which it is usually designated in a bud of this kind (1, Fig. 23). Just above the circular canal in most *Medusae* a fold of the outer skin grows in towards the oral cone, so as to form a broad circular shelf: this structure is called the *velum* (Lat. an awning) (B, Fig. 24; 1, Fig. 25). The bud now breaks loose and swims by contractions of the bell, aided by vibrations of the *velum*. Anyone would now recognise it as a minute jelly-fish, though it really is quite different in many points from the larger and better known animals denoted by that term. Zoologists speak of it as a *Medusa*, and speak of the stock from which it was budded as a colony consisting of medusoid and hydroid persons, the latter term denoting the ordinary buds which resemble *Hydra*. The terms *polyp* and *hydranth* are also often used to denote a hydroid person. A remarkable feature of this differentiation into two structurally different persons is that the *Medusa* is, in many respects, more highly developed than the hydroid person. The ectoderm cells composing the *velum* and those forming the lining of the under side of the bell or sub-umbrella are strongly drawn out into processes which are muscular. In the *velum* these are arranged so as to form two bands running round the edge of the bell or umbrella, one band being in connection with the upper and another with the lower layer of cells composing the fold of ectoderm, of which the *velum* consists. Just, however, where the *velum* is attached to the bell, its cells—upper and lower—undergo another and more interesting modification (4 and 5, Fig. 25). At their bases a tangle of delicate threads of almost inconceivable fineness appear; these threads are outgrowths of the cells, but far more delicate than those which already in *Hydra* we recognised as the forerunners of muscles; the threads we are now considering are, in fact, nervous in nature, and the tangles of them connected with the upper and lower layers, respectively, of the *velum*, constitute an upper and a lower nerve ring. Each thread is to be regarded as the tail of an excessively small ectoderm cell.

In *Hydra* we found the earliest appearance of sense hairs; and the cells of which they are processes, viz. the cnidoblasts, may be called sense cells. In the *Medusa* we meet with definite collections of sense cells aggregated so as to form sense organs. These are found close to the position of the nerve ring, either on the *velum* itself, or immediately outside it at the bases of the tentacles, so

that the stimuli which they receive are easily transmitted to the nerve ring. Two main kinds of sense organs are frequently found, which may be roughly called eyes and ears; never, however, both kinds in one Medusa. The 'eyes' are little coloured patches of skin; some of the cells of which end in clear rods while others secrete a coloured substance or pigment. Both pigment and rods are necessary if there is to be vision, though we do not understand why. The ears are little pits in the base of the velum; they may be open, or their edges may come together, so that the ectoderm lining them is entirely shut off from the outer skin. In either case, some of the




FIG. 25. Radial section through the edge of the umbrella of *Carmarina hastata* showing sense-organ and velum.

1. Velum. 2. Jelly. 3. Circular muscles of velum. 4. Upper nerve ring.
5. Lower nerve ring. 6. Nematocysts. 7. Radial vessel running into circular vessel, both lined by endoderm.
8. Continuation of endoderm along aboral surface. 9. Sense organ, tentaculocyst.
10. Auditory nerve.

cells forming the walls of the pits secrete particles of lime, others close to them develop delicate sense hairs. The result is that vibrations in the water, if they come with a certain frequency, will affect the heavy particles, and their vibrations in turn will affect the sense hairs. There is another kind of information, however, which organs like these give their possessor, and this is probably still more important to the floating Medusa, namely, information as to the position of the animal with regard to the vertical. In other words, the Medusa learns from them whether it is moving upwards or downwards or sideways: for when the animal shifts its position,

the heavy particles in the ear-sacs shift theirs and affect different sense cells.

Through these different sense organs stimuli are continually pouring in from the external world. If the stimuli only affected the contractile cells nearest them irregular movements would result. The function of the nerve ring, as of all nervous systems, is to co-ordinate the stimuli, that is to collect and rearrange and rapidly distribute them to the whole animal so that a definite reaction of the whole contractile tissue results, not a series of local reactions interfering with one another.

The Medusa is very voracious and rapidly increases in size. It feeds on the small organisms of all kinds, both plants and animals, which are found at the surface of the sea. After some time it com-




FIG. 26. The ciliated larva or Planula of a Hydromedusan, *Clava squamata*. Magnified. From Allman.

A & B. Swimming about in the sea. C. Coming to rest on a rock. D. Developing tentacles, oral cone and stolon. 1. Tentacles. 2. Oral cone. 3. Stolon.

mences to give rise either to eggs or to spermatozoa, which usually develop in exactly the same way in which they developed in *Hydra*, i.e. from the interstitial cells of the ectoderm. The accumulations of these cells, called gonads or generative organs, are borne either on the under side of the bell (3, Fig. 23), or on the sides of the manubrium, and it is a curious fact, that those Medusae which have them in the former position usually possess ear-sacs, whereas when the gonad is situated on the oral cone, ear-sacs are never present, but eyes may be. The eggs and spermatozoa are both shed out into the water and coalesce there, and the fertilized egg develops into a little oval larva, termed a Planula (Fig. 26), without

tentacles or mouth, and covered all over with cilia. It consists at first of a hollow vesicle of ectoderm cells, later becoming filled with a solid plug of endoderm. This little creature swims about for a while and then attaches itself by one end to a stone or a piece of sea-weed. The attached end flattens out (C and D, Fig. 26), but the rest of the animal lengthens and a mouth and tentacles appear at the free end, and the endoderm becomes hollowed out; so that the creature takes the form of an unmistakeable hydra-like organism. It then begins to bud out a branch called a stolon which creeps along the substratum. From this other polyps will arise, each of which has only to bud in order to reproduce the colonial stock from which its parent, the Medusa, was separated. The free-swimming young or planulae furnish good examples of what is meant by the term larva. This name is given to the young form of any animal when it is very different to the fully-grown animal and leads a free life.

We have thus learnt that a Medusa gives rise to an egg, which develops into a Hydroid person, which after a time in turn buds off a Medusa; such an alternation of generations is very characteristic of a large number of Coelenterata. The Medusa represents a sexual generation, the Hydroid an asexual generation, and inasmuch as the Medusoid is often only produced as a bud of the third or fourth order (i.e. is budded from a Hydroid person which has produced similarly from another Hydroid person), it will be seen that several asexual generations intervene between two sexual ones. The most probable explanation of this is that the Medusa is only a specially modified Hydroid, which has acquired the power of locomotion, in order to disperse the eggs over a large area, and thus avoid the overcrowding of a limited area with one species. The swimming bell and velum are contrivances to enable the bud which bears the eggs to move about. If, however, this explanation be adopted, it is a most remarkable fact that in many species the Medusae are very imperfectly developed and never become free. Such Medusae are usually more or less degenerate and are termed gonophores. Since the gonophore fails to fulfil the purpose for which we believe the Medusa to have been developed we must assume that conditions have now so far changed that the same wide scattering of the eggs is not now so necessary as formerly, possibly because the species in question are restricted to particular strips of the shore. *Tubularia larynx* found growing on seaweed is a good example of a form with degenerate Medusae, *Bougainvillea* or *Obelia* of forms with free Medusae.

The Sea-Anemones are representatives of a second division of the Coelenterata, which show a decidedly more complicated structure than the animals just considered.

Actinozoa.

Unfortunately it is very difficult to obtain the ordinary sea-anemones in a sufficiently expanded condition to make out their structure, since when irritated they contract so much as to throw their internal structures into great confusion. Another animal belonging to the same group is the 'colonial' species *Alcyonium digitatum*, sometimes called "Dead men's fingers."




FIG. 27. Part of a colony of *Alcyonium digitatum*, showing thirteen polypes in various stages of retraction and expansion $\times 8$.

- | | |
|----------------|---|
| 1. Mouth. | 3. Mesenteries with reproductive cells. |
| 2. Oesophagus. | 4. Feathered tentacles. |

It is comparatively easy to paralyse the members of the colony or polyps by adding cocaine, or some similar reagent, to the water in which the colony is living (Fig. 27). If then an expanded polyp be cut off and examined with a lens, we shall be able to make out most of its structure. We notice to begin with that there is a single circle of eight tentacles, each of which has a double row of short branches, so that it looks like a miniature feather; within the circle of tentacles there is, however, no trace of an oral cone; there is instead a flat disc, slightly sunken in the centre, where we find the slit-like mouth. If we look in at the lower cut end of the

polyp we shall see that the coelenteron, instead of being a simple cylindrical space like that of *Hydra*, is partially divided into compartments by folds stretching in towards the centre, but not meeting. These folds are called mesenteries, and there are eight of them, corresponding in number (but not in position) with the tentacles (Fig. 28). We shall further see that the mouth does not,




FIG. 28. Transverse section through a polyp of *Alcyonium digitatum* below the level of the oesophagus \times about 120. From Hickson.

1. Coelenteron. 2. Mesentery with free edge. 3. Ectoderm. 4. Mesogloea or jelly. 5. Endoderm. 6. Muscles in mesentery.

as in *Hydra*, open directly into the coelenteron, but leads into a flattened tube, which projects into the interior of the body. This tube, the so-called oesophagus or gullet, is really lined by the ectoderm, which is merely tucked in at the mouth. Such a tube is known as a stomodaeum¹. The mesenteries, although they end freely below, are attached to the sides of the stomodaeum above, so that in this region the coelenteron is divided into a number of compartments, each of which is prolonged into one of the hollow tentacles (Fig. 29).

¹ "I have proposed to designate this ingrowth...the stomodaeum (στόμοδαιον, like πυλόδαιον, the road connected with a gateway) and similarly to call another ingrowth which accompanies the formation of the second orifice (the anus) of the enteron, the proctodaeum" (πρωκτός, the anus). Ray Lankester.

A microscopic section of such a polyp shows us several other interesting points. We see that we have to deal with the same layers which we met with in *Hydra*, skin (or ectoderm) and coelenteron lining (or endoderm). Between them, however, there is the jelly, which was present as an exceedingly fine membrane in *Hydra*, and which, greatly thickened, formed the substance of the bell of the Medusa. This jelly is fairly thick in the minute sea-anemone we are examining, and here contains cells, which have wandered into it from the ectoderm. Some of these cells have the




FIG. 29. Transverse section through a polyp of *Alecyonium digitatum*, through the region of the oesophagus \times about 120. From Hickson.

1. Cavity of oesophagus. 2. Siphonoglyph. 3. Ectoderm. 4. Mesogloea or jelly.
5. Endoderm. 6. Muscles in mesenteries. 7. Inter-mesenteric cavity.

power of secreting thorny rods of lime, termed spicules. These spicules are very abundant where the polyp merges into the general surface of the colony, so that they form a kind of stiff protecting crust round the base of the polyp, and over the surface of the colony from which the polyps rise. In the organ-pipe coral, *Tubipora*, the spicules in the lower parts of the polyps are so felted together that they form a set of parallel tubes, suggesting the pipes of an organ; only the upper part of the polyp, where the

spicules are not yet closely aggregated, being capable of movement. We have spoken above of the colony as distinct from the polyps, and this use of the word demands some justification. When we were dealing with the Hydromedusae, we used the word colony in the sense of the whole mass of the polyps which cohered together, and which had arisen by the growth of one original polyp. Now in *Alcyonium* and its allies, budding does not take place in quite the simple manner in which it occurs in *Hydra* and its allies. Instead of one polyp growing directly out of another, the coelenteron of the parent sends out a tube lined only by endoderm. This tube grows, pushing the ectoderm before it; but, as between the ectoderm and endoderm there is a thick jelly interposed, the endodermal tube can branch without the ectoderm becoming indented. Where the free ends of these tubes reach the surface, there fresh polyps are developed, mesenteries and oesophagus making their appearance. Something like these tubes does, in fact, occur amongst Hydromedusae: a complete colony is found to consist of a number of upright branches ending in polyps but connected at their bases by tubes called stolons which creep along the ground: the endodermal tubes of *Alcyonium* may be compared to these stolons, the great difference being that in their case, owing to the thickness of the jelly, the ectoderm is stretched uniformly over a mass of tubes, instead of each tube having its own ectodermal covering as in the Hydromedusae.

Still examining a section of the polyp the next point we notice is the structure of the mesenteries. These end in a free edge below, which is much thickened and folded, and since it stands out in contrast with the rest of the mesentery as if it were an independent structure it has been called a mesenteric filament (Figs. 28 and 30). The cells composing six of these filaments are very tall and secrete a juice which digests the prey: the remaining two filaments are composed of ciliated cells of moderate height which maintain a constant outward current of water. The surface of the mesenteries is covered by cells which become very much folded so as to produce a marked projection from the face of the mesentery. The cells of the folded area are all produced into vertical muscle-tails so that together they give rise to one of the powerful longitudinal muscles (Figs. 28 and 29), by which the sudden retraction of the polyp is brought about. The slow expansion is effected by the reaction of the elastic jelly or mesogloea and perhaps also by the pressure exerted on the fluid contained in

the body by a layer of circular muscles developed as outgrowths from the endoderm cells of the intermesenteric chambers.

A second difference is found in the position of the eggs and sperm cells. These are developed from the endoderm on the face of the mesenteries, very low down in the base of the polyp and nearer the free edge than the longitudinal muscle. The eggs when ripe are cast out into the coelenteron and so out by the mouth, though in many species they come in contact with the male cells whilst in the coelenteron of the parent.

The gullet has at one side a deep indentation or groove which is lined by powerful cilia (2, Fig. 29). The groove is termed a siphonoglyph (Gr. *σίφων*, a tube; *γλύφω*, to hollow out) and its cilia keep up an inward current of water whilst the rest of the gullet is choked with prey, and so fresh supplies of water charged with oxygen are brought in contact with the lining of the coelenteron and enable it to respire. Thus in conjunction with the action of the two ciliated mesenteric filaments a complete circulation of the water in the coelenteron is maintained. The ectoderm of course gets its oxygen directly from the surrounding water.

The ordinary sea-anemones differ from *Alcyonium* in very many points. The tentacles, hollow as before, are never feather-like, but always perfectly simple and round, and there are usually a large number of them, so that they are arranged in several concentric circles. The mesenteries also are numerous, and extend inwards to different lengths, so that we can distinguish primary mesenteries which join the gullet from secondary ones which do not. Both primary and secondary are usually arranged in pairs. Spicules are never developed and in the ordinary anemones of our coasts there is no skeleton whatsoever. The common anemones of our coasts, sometimes, though rarely, bud, but there is another large class of anemones which do form colonies, the buds occasionally arising as in the Hydromedusae from the body of the parent directly. These colonial anemones form the hard stony masses called coral (Fig. 30). If we look at a piece of coral we can see in it cups with partitions radiating inwards, the whole reminding one of the structure of a sea-anemone: and it was a natural mistake to suppose, as the earlier naturalists did, that the hard skeleton was formed inside the body of the polyps, the partitions representing the mesenteries. Of course it is difficult to imagine how the animal could move if it had all that mass of stone inside it. How the corallum or stony skeleton is formed is a matter of dispute. It

has been suggested that it is secreted by the ectoderm as a kind of sweat which hardens, or that the ectoderm cells are calcified and thrown off, or that the ammonium carbonate, secreted by all animals, precipitates the calcium carbonate of the sea water and so forms the skeleton. At any rate a calcareous cup is formed in which the polyp sits and the partitions of the cup indent the base of the animal, pushing before them folds of the body wall, which project into the coelenteron between mesenteries, so that the action of the longitudinal muscles is not interfered with.




FIG. 30. Semi-diagrammatic view of half a simple Coral, partly after G. C. Bourne. On the right side the tissues are represented as transparent to show the arrangement of the theca and septa; on the left side a mesentery is seen.

1. Tentacle. 2. Mouth. 3. Oesophagus. 4. Mesentery. 5. Mesenteric filaments, free edge of mesentery. 6. Ectoderm. 7. Endoderm. 8. Basal plate. 9. Theca. 10. Columella. 11. Septum.

Coral-forming anemones are found all over the world,—one species, *Caryophyllia*, being actually found at low
Coral.

spring tides on the south-west coasts of England: but it is only in the tropics that those species are found which keep on budding and growing with sufficient persistence to build up the great reefs which form the famous coral islands of warmer seas. Of course as soon as the reef is built up to the surface the polyps cease to grow, and the breakers soon pile up broken off pieces in sufficient quantity to raise the reef above the tide-marks.

In all the anemones that have been described so far there has been no trace of individuals modified for swimming, as the medusoid persons in a Hydromedusan colony are modified. There is however a class of animals which seem to be truly anemones modified for a free-swimming life, although zoologists have hitherto hesitated about classing them either with the Hydromedusae or with the Anemones.

The zoological name of these creatures is Acalephae (Gr. ἀκαλήφη, a nettle). They are the larger and better known jelly-fishes. A common British species, *Aurelia aurita*, is in summer often cast by thousands on the southern shores of Great Britain. Viewed from the outside they very much resemble the medusoids. Like them they possess a swimming bell with a circle of tentacles at the margin. There is also a prominent oral cone or manubrium. This however does not bear real tentacles, but the four corners of the rectangular mouth are drawn out into long frilled lips (2, Fig. 31), along the inner sides of which are open grooves leading into the gullet. Perhaps the most marked difference is that the reproductive organs are here, as in the anemones, swellings of the stomach lining: the eggs and spermatozoa are shed into the coelenteron and escape by the mouth. The generative organs have the shape of four semicircular ridges, and along the inner side of each of these there is a row of filaments composed of cells somewhat similar to the cells on the edges of the mesenteries in the anemones (11, Fig. 31). Nothing like these gastric filaments, as they are called, are found in the Hydromedusae. There is, further, no velum in the Acalephae, and there is also no nerve ring. Sense organs however of an exceedingly interesting kind are present.

In *Aurelia*, for instance, there are eight minute tentacles which stick out from the edge of the bell and are covered by special little hoodlike outgrowths of the same (9, Fig. 31). Each of these tentacles contains a hollow outgrowth from the circular canal lined like it by endoderm. The endoderm cells at the tip secrete a mass of calcareous particles: the skin cells at the base of the tentacle have produced nervous fibrillae from their bases and so the tentacle, as it is caused to sway in one direction or another by the weight of its heavy end, affects now some of the nerve fibrillae and now others, and so produces the same effect as the stones in the ear sac of a medusoid, though the construction of the Acalephan organ is quite different. In one division of the Hydromedusae, however,

sense tentacles similar to those of the Acalephae are found. Here the edges of the hood often join so as to form a sac enclosing the organ, whence the name tentaculocyst (9, Fig. 25). It has been proved experimentally that the ordinary stimuli which cause the rhythmical pulses of the bell, proceed from these tentaculocysts, so that they act like minute brains. How the co-ordination of the stimuli proceeding from the eight centres is brought about we do not know, but it is probably due to the presence of a very thin diffuse sheet of nerve fibrillae on the under surface of the bell.




FIG. 31. *Aurelia aurita*. Somewhat reduced.

1. Mouth. 2. Circumoral processes. 3. Tentacles on the edge of the umbrella. 4. One of the branching perradial canals. There are four of these, and four similar interrarial canals; the perradial canals correspond to the primary stomach pouches of the Hydra-tuba, the interrarial alternate with these. 5. One of the unbranched adradial canals. 8. The circular canal. 9. Marginal lappets hiding tentaculocysts. 11. Gastral filaments, just outside these are the genital ridges.

It has been mentioned above that the reproductive organs are swellings of the endoderm. The central space or "stomach" is a wide sac occupying the centre part of the bell and not, as in the Medusoids, confined to a large extent to the oral cone. In *Aurelia*

this space is produced into four lobes, and in the floor of each lobe is one of the reproductive organs. From the edges of the stomach a number of branching canals lead out into the circular canal (4, Fig. 31), all these tubes being, as it were, burrows in a continuous sheet of endoderm cells, which stretches out to the edge of the disc and really represents a part of the coelenteron, the cavity of which has been obliterated. It thus corresponds exactly to the endodermal lamella of the Hydromedusae.

When the eggs fall out of the mouth they are caught in little pockets and there develop into little Planula larvae. These, as usual, become free and swim about, and finally each fixes itself and develops into a little polyp, called a Hydra-tuba, not unlike a *Hydra* in appearance (A, Fig. 32). When examined by microscopic sections, however, it shows important points of difference. Thus




FIG. 32. Strobilization of *Aurelia aurita*. From Sars.

- A. Hydra-tuba on stolon which is creeping on a Laminaria. The stolon is forming new buds at 1 and 2. B. Later stage $\times 4$. Scyphistoma. The strobilization has begun. C. Strobilization further advanced $\times 6$. D. Free swimming Ephyra stage $\times 7.5$, seen from below. E. The same seen in profile $\times 7.5$.

there is no oral cone, but a flat mouth-disc in the centre of which the mouth leads into a gullet like that of the anemone, lined by the ectoderm and projecting into the coelenteron. The latter has four ridges projecting into it, the lower edges of which are free while the upper ones are joined to the gullet (stomodaeum). In fact

the Hydra-tuba is to all intents and purposes a very simple anemone. During a large part of the year it multiplies by budding, just as a *Hydra* does, but at certain seasons it undergoes a very remarkable change (B and C, Fig. 32). The oral disc flattens out very much, and its edges become drawn out into lobes, the tentacles at the same time dropping off. A short oral cone is developed from the centre of the disc, the mesenteries become perforated and finally the whole flattened-out top of the Hydra-tuba breaks off and swims away. This is known as an Ephyra larva (D and E, Fig. 32). It leads a free life and gradually develops into a large jelly-fish. But long before the primary oral disc has become free, the part of the Hydra-tuba next below has been growing out so as to produce a similar disc. This process, called Strobilization (Gr. *στροβιλός*, a whorl), is repeated until the Hydra-tuba resembles a pile of saucers, in which state it is called a Scyphistoma (Gr. *σκύφος*, a saucer).

We can get some idea as to how this extraordinary development may have arisen on the following hypothesis:—The original Acalephan was probably an anemone with a wide top and narrow base. In this top the generative organs were developed, and when the eggs became ripe it broke off and wandered away in order to disperse the species. The lower part of the polyp regenerated the head, exactly as a *Hydra* can do if the head with its ring of tentacles be cut off. Later this process of renewal became hurried on until it commenced before the separation of the head was complete and thus we have the Scyphistoma stage. It is a strong support of this theory that there exists a large coral-forming anemone, *Fungia*, in which there is a flat top and a stalk, and the flat top periodically falls off and is renewed.

A third great division of the Coelenterata is constituted by the animals called Ctenophora (Gk. *κτείς*, *κτενός*, a comb).

Ctenophora.

These are widely different from both Hydromedusae or Actinozoa, even including Acalephae. They never bud and with one doubtful exception have no thread cells. In place of these there are gripping or adhesive cells covered with a secretion by which they adhere to the prey. They are often ripped off in the struggles of the prey. They are each provided with an elastic tail embedded in the jelly which pulls in the object to which they have adhered. The Ctenophora are free swimming but their locomotion is performed not by the agency of muscular bands but by eight bands of cilia which run like meridians of longitude over the

generally oval body from the mouth to the opposite pole (5, Fig. 33). The cilia in each band are arranged in short transverse rows, and the cilia in each row are joined at the base and free at the tip. So each row has the form of a comb, and thus the name comb-bearer, *Ctenophora*, is seen to be appropriate. Further the principal sense organ is situated in the centre of the end of the animal opposite to the mouth at the spot where the bands of thickened ectoderm which carry the combs, converge. These thickened ridges of cells are often termed "ribs." If we compare




FIG. 33. *Hormiphora plumosa*. After Chun. Side view.

1. Mouth leading into stomach.
2. Aboral pole with sense organ.
3. Funnel.
4. Paraesophageal canal running back towards oral pole.
5. One of the eight bands of fused cilia.
6. One of the eight canals running towards 5.
7. A tentacular pouch.
8. A tentacle.
9. Gelatinous tissue.

the animal to a globe, the end at which the mouth is may be called the oral pole, the opposite end the aboral pole (2, Fig. 33).

The sense organ at the aboral pole is a plate of thickened ectoderm, the cells of which have developed nerve tails. Similar nerve tails are developed by the bands of ectoderm which carry the combs. The cells at the edge of the plate carry cilia fused with one another which arch over the plate and cover it like a tent. Inside is a calcareous ball supported on four curved bars, each made of conjoined cilia, borne by some of the inner cells. This ball acts as a balancing sense-organ. If the animal inclines to one side the ball will bear heavily on the support on that side, and stimulate thus the corresponding ribs, which will thus act more vigorously than the rest and tend to restore the vertical position.

Like Actinozoa, Ctenophora have a well-marked stomodaeum, and the true coelenteron is represented by a series of branching canals, the central one being termed the funnel (3, Fig. 33). The funnel and stomodaeum are both flattened but in planes at right angles to one another. The funnel gives off (1) two canals, the so-called excretory canals, which open at the sides of the sense-organ; (2) two canals, paragastric, running back towards the mouth parallel with the stomodaeum (4, Fig. 33); (3) two canals running each to a branched tentacle, which can be retracted within a pouch (7, Fig. 33). This branched tentacle is covered with adhesive cells, there is one on each side of the animal. Each tentacle canal gives off four branches (6, Fig. 33) which lead into the meridional canals running under the ribs, from the cells lining which both ova and spermatozoa are produced, as Ctenophora are hermaphrodite. The commonest British form is *Hormiphora plumosa*.

Phylum COELENTERATA.

The classification of the Coelenterata is as follows :—

Class I. HYDROZOA.

Coelenterata without mesenteries or gullet lined by ectoderm: genital cells derived from ectoderm.

Order 1. **Hydrida.**

Only hydroid persons present, not permanently attached but capable of locomotion, the buds become free.

Order 2. **Hydromedusae.**

Composite fixed colonies of hydroid persons from which medusoid persons are budded off.

Suborder (1) **Gymnoblastea**. Perisarc confined to the base of the hydroids: medusoids have eyes and bear gonads on the manubrium.

Suborder (2) **Calyptriblastea**. Perisarc expanded to form cups called hydrothecae, into which heads of hydroid persons can be retracted: medusoids have ears and bear gonads on under side of umbrella.

Class II. ACTINOZOA.

Solitary or colonial Coelenterata with gullet lined by ectoderm: coelenteron provided with radiating mesenteries: genital cells derived from endoderm.

Order 1. **Alcyonaria**.

Eight fringed tentacles, and eight mesenteries: spicules in the jelly.

Order 2. **Zoantharia**.

Mesenteries usually in pairs, either six pairs or some multiple of six: tentacles conical: no spicules but often an external calcareous skeleton formed by the ectoderm.

Order 3. **Acalephae**.

Forms with alternation of generations: mesenteries present in young, but later become absorbed: oral part breaks loose and becomes developed into a free-swimming organism externally resembling a medusoid: the stalk of the original polyp reproduces the lost parts.

Class III. CTENOPHORA.

Very widely different from the two preceding divisions: free-swimming animals with a sense organ and nervous disc of skin at the pole opposite the mouth: swim not by muscular contractions but by vibrations of eight longitudinal bands of cilia radiating from nervous disc, which bands consist of successive transverse rows of cilia, the cilia of each row fused at base so as to form a comb-like structure: only two tentacles, a gullet lined by ectoderm: stomach represented by a system of branching tubes.

CHAPTER IV.

PHYLUM PORIFERA.

THE group of the sponges or Porifera occupies an almost isolated position in the animal kingdom. Sponges agree, it is true, with Coelenterata in exhibiting cellular structure and having their protoplasm arranged in tissues ; and further in the fact that all the internal cavities of the body are in communication with one another, so that both Coelenterata and Porifera might be described as systems of branched tubes. A closer inspection however reveals the fact that the tissues of the Porifera are very different from those of Coelenterata, and originate in a different way from the larva, so that the opinion is gaining ground, that whereas most, if not all, of the higher groups of animals have descended from ancestors which had we seen them we should have classed as Coelenterata, Porifera on the other hand have been independently derived from Protozoa.

In Coelenterata the colonies can be analysed into persons (medusoids or hydroids) and stolons, and many of the Porifera show a like aggregation of persons. But in many forms it is impossible to suggest how many individuals are contained in the branch system of a single aggregate since all distinctness of individuals is lost. Further analysis shows that the apparent persons or units, even when most clearly demarcated, are of very varying morphological value.

The salient peculiarities of sponges will be best appreciated by a short description of one of the simplest types known, a sponge called *Leucosolenia*, which is common on most clean rocky shores.

In this animal we can recognise a foundation consisting of a network of horizontal stolons, adherent to some foreign object, from which a number of upright tubes spring. Each upright tube

ends in a large opening, the *osculum* (1, Fig. 34), which can be closed if the animal be irritated and which in *Leucosolenia* is partly closed by a perforated membrane. This opening, which at first sight recalls the mouth of *Hydra*, is really used for a quite different purpose. It is an efferent opening (Lat. *effero*, to carry out) and from it the water which has passed through the animal is expelled. Water enters the internal cavity through a multitude of very fine pores in the walls of the tube (Fig. 35, and 1, Fig. 37): it is the universal presence of these pores which gives the name Porifera to the group.



FIG. 34. View of a branch of *Leucosolenia* sp., showing the sieve-like membrane which stretches across the osculum. The lower part of the sponge shows spicules only $\times 10$. From Minchin.

1. Sieve-like membrane.

The wall of the tube is made up of two layers, but we must guard ourselves against rashly comparing these with the layers of the body wall of *Hydra*, and hence it is better to avoid the names ectoderm and endoderm and adopt the terms dermal and gastral layers.

The dermal layer consists of flat cells which cover the external surface and extend for a short distance inside the osculum, and of cells termed amoebocytes from the resemblance of their movements to those of an *Amoeba*: the whole of the rest of the tube and the stolons are lined by a tissue consisting of peculiar cells called choanocytes (Gr. *χῶανος*, a funnel; *κύτος*, a hollow vessel), or

collar cells, which alone constitute the gastral layer (3, Fig. 35 and Fig. 36). Each of these is cylindrical and provided with a funnel-shaped transparent rim called the collar, turned towards the cavity of the tube. The collars of adjacent cells are not




FIG. 35. Vertical section through an osculum with sieve-like membrane, and a tube of *Leucosolenia* sp. Highly magnified. From Minchin.

1. Sieve-like membrane. 2. Outer layer. 3. Flagellated or collar cells (choanocytes). The pointer should have been continued to indicate the cells lining 5. 4. Spicules. 5. Internal cavity

normally in contact, and the outer part of the cell bodies are widely separate, so that here the distinctness of the elements of a cellular tissue is carried to an extreme. From the centre of each collar a long flagellum arises, and it is by the action of these flagella

that water is drawn in through the pores. The sponge lives on the organisms carried in by the current; these appear to be carried within the collars by the minute whirlpools produced by the individual flagella: they adhere to the collars and are swallowed by them and digested by the cells. It will be seen that the collar is a real living structure, not a cuticular tube, such as the hydrotheca of a calyptoblastic hydroid, and this is further illustrated by the fact that it is withdrawn by the collar-cell under certain conditions.

The water after being exhausted of its food is expelled through the osculum, carrying with it all excreta.




FIG. 36. Section of flagellated chamber of *Spongilla lacustris*, showing the flagella and collared cells $\times 1500$. From Vosmaer.

1. Nucleus. 2. Vacuole. 3. Opening into the inner space of the sponge.

The outer layer of the body-wall consists, in the ordinary condition of the sponge, of flattened cells. These however, especially in the region of the osculum, have the power of changing their shape so as to become shorter and thicker; in a word they can contract, although they show no trace of the fibrillae found in all muscle and in the muscle tails of the contractile cells of Coelenterata. The contraction is slow, not quick, as in true muscle.

It has been proved that the pores are formed by specially large cells, the porocytes, which extend from the outer layer and push aside the choanocytes, and then become hollowed out.

Between the two layers is found a certain amount of secretion which may be termed jelly, in which in many sponges a large

number of cells is found. These form a portion of the dermal layer, and are, for the most part, amoeboid. Some of these probably act as carriers of food and possibly of excreta from one layer to the other. Others at first very similar give rise to ova and spermatozoa. A third class called scleroblasts—derived in *Leucosolenia* from the flat cells which cover the surface, but not so derived in all sponges—secrete the rods which form the skeleton and which are termed spicules (Fig. 34, and 6, Fig. 37). In *Leucosolenia* these are calcareous and have three rays, more or less in one plane— a




FIG. 37. Section of a portion of *Grantia extusarticulata*. Highly magnified.
From Dendy.

- | | | |
|---|--|---|
| 1. Openings of the inhalant canals. | 2. Inhalant canal. | 3. Openings of |
| | | inhalant canals into flagellated chamber (prosopyle). |
| 4. Flagellated chamber. | 5. Flagellated or collar-cells, choanocytes. | 6. Spicules. |
| 7. Exhalant opening of flagellated chamber. | | |

shape technically named triradiate. One limb is usually directed parallel with the long axis of the tube, and often bears a fourth ray or spine making a quadriradiate spicule. The spicules although remaining unconnected are numerous enough to form a loose mesh-work.

The larva of sponges at first sight recalls the planula of Coelenterata, inasmuch as it has the form of an oval vesicle containing cells, some of which are amoeboid, and has a single layer of flagellated cells on the external surface.

Larva.

This layer either completely surrounds the larva, as in *Spongilla*, or partially surrounds it, as in *Leucosolenia*. When however this larva changes into a sponge, the inner layer bursts forth and surrounds the ciliated cells and eventually forms the dermal layer of the adult, whereas the ciliated cells form the gastral layer. This extraordinary metamorphosis is the exact opposite of what happens to the planula and renders a comparison of the tissues of Coelenterata and Porifera impossible.

The most important points in which the higher sponges differ from *Leucosolenia* are the folding of the outer and inner layer, the restriction of the choanocytes to small portions of the latter, and the differentiation of the body into distinct regions.

Complex
Sponges.

A common sponge on the British coast, *Sycon* (*Grantia*) *compressum*, will illustrate the first step in this complication. This animal has the form of a series of a flattened thick-walled upright tube. The layer lining the central cavity consists of flattened cells, but from this cavity pouches lined by choanocytes extend out into the substance of the wall. These flagellated chambers, as they are often called, communicate with the exterior by a series of inhalant canals which intervene between them and into which the pores open (Fig. 37). The inhalant or afferent canals are due to foldings of the outer layer.

When a sponge becomes still more complicated the central cavity becomes broken up into a series of branching canals, which are termed exhalant or efferent, and the ciliated chambers become small and rounded (Fig. 36), each often connected only by a single opening or prosopyle (Gr. *πρόσω*, forwards; *πύλη*, a gate) with the afferent system of canals. Numerous oscula are found in one sponge mass, so that no pretence of discriminating the individual can be made.

The majority of sponges have siliceous spicules, and these are often arranged in bands glued together by a horny secretion called spongin. The Bath-sponge is the skeleton of a genus *Euspongia* which has the network of spongin cords without the siliceous spicules. It is found in the Mediterranean and other seas. Two fresh-water species, namely, *Spongilla lacustris* with a bush like appearance and *Ephydatia fluviatilis* with an encrusting form, are often found growing on the side of canals and on the timbers of river-locks or weirs in Great Britain. These two species are bright green when they grow in the light, but they are pale flesh-colour when

they grow in the shade. In Canada similar species adhere to stones in the river St Lawrence.

Porifera then may be defined as animals consisting of branch-systems of tubes, the principal openings of which are exhalant, whereas the inhalant openings are minute perforations of the walls. The wall consists of two layers; some cells of the inner layer have the form of choanocytes, whilst the skeleton consists of siliceous or calcareous needles formed by cells of the outer layer which wander in, or of spongin. There are never any thread-cells, or differentiated muscle or well-marked nerve-cells, nor any such organs as tentacles.

The phylum is divided into three classes:—

Class I. CALCAREA.

Sponges with calcareous spicules and large flagellated chambers.

Ex. *Leucosolenia*, *Grantia*.

Class II. HEXACTINELLIDA.

Sponges with siliceous spicules, having three axes at right angles to one another and with large flagellated chambers.

Ex. *Euplectella*, the Venus flower-basket.

Class III. DEMOSPONGIAE.

Sponges with quadriradiate, triradiate or needle-like siliceous spicules or none, the needle-like spicules arranged in cords and often embedded in spongin, flagellated chambers usually small.

Ex. *Ephydatia*, *Spongilla*, *Euspongia*.

CHAPTER V.

INTRODUCTION TO THE COELOMATA.

THE last two groups of animals studied, although very different from one another in most respects, yet agree in this that the groundwork of their structure is a set of tubes branched in different ways and with walls of varying thickness but consisting always of two layers with an intervening jelly. It would not be straining the truth to assert that in the Coelenterata and the Porifera we find but two tissues, an outer more or less differentiated skin—the ectoderm with the underlying jelly,—and an inner layer mainly digestive in function.

The phyla which are next to be considered, and which may be grouped together under the name Coelomata, differ from the two mentioned above in the possession of an important organ termed the coelom (Gr. κοίλωμα, a thing hollowed out). This is often described as a space intervening between the ectoderm and endoderm, and the term coelomic cavity or body cavity has been used to describe it. In spite of the etymological difficulty we propose in the following pages to deal with this organ under the term *coelom*, and its cavity under the term *coelomic cavity*. In reality it consists of one or more pairs of sacs with perfectly defined walls lying at the sides of the endodermic tube. In the adult these sacs join each other above and below the endoderm, and the adjacent walls entirely or partly break down, and thus one continuous cavity results. The wall of the coelom and the tissues derived from it are known as the mesoderm. To describe the coelom as a split or space is to describe it negatively: with as much justice the endodermic tube might be described as a split. In each case the real object of consideration is the wall.

If we leave out of account cases in which the facts of development have not been fully elucidated and confine our attention to

those instances where the whole history of the coelom has been exhaustively worked out, we find that this important organ arises in one of two ways, either (1) by the formation of pouches of the endodermic tube, which become nipped off (Fig. 38); or (2) by the budding of two large cells, formed themselves by budding from the endoderm (Fig. 39), these cells subsequently growing rapidly and dividing so as to form bands, the so-called germinal bands, which subsequently become hollowed out. These initial cells are termed pole-cells.




FIG. 38. Three transverse sections through a developing *Amphioxus* to show origin of mesoblast from endodermal pouches $\times 435$. From Hatschek.

The ectoderm is deeply shaded, the mesoderm is lightly shaded, the endoderm—alimentary canal and notochord—is unshaded. A. shows the origin of the paired mesodermal pouches from the archenteron; the cavity—coelomic—of the former is still in communication with the cavity of the alimentary canal. The notochord is arising in the middle line from the endoderm, and the tubular nervous system above it is already separated from the ectoderm. B. shows the mesodermal pouches completely shut off; they each enclose a cavity, the coelom, and each consists of an outer wall next the ectoderm, the 'somatopleur,' and an inner wall next the endoderm, the 'splanchnopleur.' C. shows the mesodermal pouches extending ventrally beneath the notochord, now completely separated from the wall of the alimentary canal, and also round the alimentary canal. The coelomic space is larger, and the splanchnopleur is beginning to form muscle-cells.

A sharp controversy has raged round the question which of these two processes gives us the best representation of what occurred in the evolution of Coelomata from simpler Coelenterata-like ancestors.

If however we recall the fact that in the Actinozoa the endodermic sac has the form of a series of pouches ranged round a central cavity, and that the walls of these pouches become converted into muscles and generative cells exactly as in the case of the coelom, and that pores exist in many cases, placing the cavity of these pouches in communication with the outside world, we shall

be induced to conclude that the coelom was probably evolved from lateral pouches of the gut and that the mesoderm is therefore derived from the primitive endoderm. Where pole-cells occur the cavity of the alimentary canal is small in proportion to the thickness of its wall, and the pole-cell might be looked on as a solid pouch.




FIG. 39. Two stages in the early development of a common fresh-water mollusc, *Planorbis*, to show the origin of the mesoderm cells $\times 320$. From Rabl.

The ectoderm cells are deeply shaded, the endoderm cells are unshaded. A. Young stage in which the endoderm has not begun to be invaginated; it is a lateral optical section. B. Older stage, optical section seen in front view; the endoderm cells are invaginating, and the two mesoderm cells are seen on each side. 1. Mesoderm or pole-cells; in B, each has budded off another mesoderm cell.

In most Coelomata the mesoderm forms by far the greatest portion of the body, and it may be roughly stated that the mesoderm gives rise in the fully developed animal to "the muscles, the bones, the connective tissue, both arteries and veins, capillaries and lymphatics, with their appropriate epithelium," and to the excretory and generative organs.

In the Porifera and in the more complex Coelenterata, where the thin structureless lamella of *Hydra* has swollen into a bulky mass of jelly such as we find in a Medusa, cells begin to wander into it from the ectoderm, and thus a kind of tissue is formed to which the name mesoderm has unfortunately been applied. We see that its origin and nature are quite different, although both in Sponges and Coelenterata it may give rise to the skeleton, and in

this respect at least it may be regarded as a forerunner of the true mesoderms.

The endoderm, after the separation from it of the mesoderm, forms the lining epithelium of the digestive tube and of its appendages, which in the higher Vertebrata are the organs known as lungs, liver, pancreas, and bladder. The basis of the skeleton of Vertebrata, the gelatinous rod called the notochord, also arises from it.

In Coelenterata there is one opening only to the digestive sac, which is used both as a mouth to take in food and as anus to cast out indigestible material. In the overwhelming majority of the Coelomata there is a second opening, the anus, the mouth being restricted to the function of taking in food. As a consequence the digestive sac takes the form of a tube open at both ends, and is known in the higher groups as the alimentary canal. Often this endodermic tube is much longer than the ectoderm, and so in order to be contained in the bounds of the ectoderm it has to be bent and looped on itself.

Round both mouth and anus the ectoderm is generally tucked in, so as to form as it were vestibules to the true alimentary canal. Of these, the ectodermic vestibule to the mouth is called the stomodaeum, and is found amongst the Actinozoa, where it has been already described. The proctodaeum is the term applied to the vestibule around the anus. Although not strictly parts of the alimentary canal stomodaeum and proctodaeum are usually included in descriptions of it, and indeed in some cases—Crustacea—they form by far the greatest portion of the apparent digestive tube.

The internal anatomy of the lower animals was first studied by physicians and others who were primarily interested in human anatomy. An unfortunate consequence is that a large number of names are used in the description of simpler animals, which are based on fanciful resemblances between their organs and those of man. As a consequence many of these names are quite misleading. To give some instances: the word stomach in the Lobster denotes part of the stomodaeum, in the Vertebrata it signifies part of the endodermic tube. The pharynx of an earthworm is the stomodaeum, in a fish it includes both stomodaeum and the first part of the endodermic tube. The term liver has also been much abused.

The names taken from the anatomy of the higher animals which are customarily used in the description of the alimentary

canal are as follows: mouth- or buccal-cavity, pharynx, oesophagus, stomach or crop, gizzard, intestine, and rectum. They are applied generally to parts of it succeeding one another in the order above given. The significance of these will be explained in each case: it would perhaps be more logical to sweep away altogether these and a host of similar terms employed to designate other parts of the body, but so deeply are they engrained in zoological literature that such a course would render unintelligible most anatomical descriptions of species that we possess.

Besides forming the outer layer of the skin or epidermis of the animal and the stomodaeum and proctodaeum, the ectoderm gives rise to the brain and nervous system, and to the essential cells of the sensory organs.

In the group Coelenterata a general circular outline of the body predominates, the principal external organs being arranged like the spokes of a wheel around the mouth as a centre. Such an arrangement is spoken of as a radial symmetry, and is in all probability connected with the fixed life so common amongst Coelenterates, a condition of affairs which renders it advantageous to have organs developed so as, to use a familiar phrase, to be on the look-out all round.

The free-swimming Medusae, it is true, move always with the apex of the bell directed forwards, but as has been pointed out (see p. 55) they are to be regarded as specially modified hydroids, and they have not modified the radial symmetry so deeply impressed on them by the habits of ancestral Coelenterata.

In the higher groups of animals there is usually one fixed part of the body which moves first when the animal changes its position; and when such a portion is definitely set aside to move first we can distinguish the front end of an animal from the hind end. It is usual to term the former the head or anterior end and the latter the posterior end, and when an organ such as a man's arm lies nearer the anterior end (head) than another, as for instance his leg, we say the former is anterior to the latter, and that the latter, i.e. the leg, is posterior to the former, i.e. the arm. In describing the parts of an appendage such as the arm it is usual to speak of the part nearest the base of attachment as proximal and the part further away as distal.

Corresponding with the appearance of the head as distinct from the rest of the body, which is in contradistinction termed the

trunk, we find a difference arising between the surfaces of the body. With few exceptions animals, whether creeping, swimming, flying or walking, keep the same surface turned towards the earth. This lower surface is termed the ventral (Lat. *venter*, belly), whilst the upper surface or back is termed the dorsal (Lat. *dorsum*, back). As a rule the difference in their relationship to their surroundings induces a difference in the aspect of these two surfaces, and it is seldom difficult to determine which is the ventral and which the dorsal surface of the body. As a general rule the ventral surface of an animal is much lighter in colour than the dorsal. In most Coelomata the nervous system is for the most part ventral, the chief blood-vessel dorsal, but in the Vertebrata the reverse is the case. In both the alimentary canal lies between the chief blood-vessel and the main nervous system.

The two sides of an animal, the right and left, are, however, exposed to much the same conditions and as a rule resemble each other very closely. When this is the case an animal is termed bilaterally symmetrical, and it may then be divided in one plane—and in *one* plane only—in such a way that each half forms a reflex image of the other, such as we should see if we held half the animal up to a looking-glass. This bilateral symmetry may extend to all the internal organs, as it does in an earthworm or a crayfish, or it may be confined to the external features and some of the internal organs only, as in insects or in most vertebrates, where the coiling of the alimentary canal, etc., interferes with the bilateral symmetry of the internal organs.

In some animals, and these are for the most part such as move sluggishly or have become permanently attached to some substratum and do not move at all, this bilateral symmetry has been lost and the two sides do not resemble one another. Such animals are called asymmetrical. The Snail is a familiar example of such asymmetry. Amongst the Echinodermata (Star-fish and Sea-urchins) this asymmetry is replaced by a radial symmetry.

CHAPTER VI.

PHYLUM ANNELIDA.

THE name Annelida (Lat. *annulus*, a ring) means ringed, and refers to the fact that the bodies of the creatures grouped under this name are built up of a series of parts more or less resembling each other placed one behind another. This division of the body into more or less similar parts is called segmentation; each part is called a segment (or somite), and the animal is said to be segmented. Like the symmetry, the segmentation may be merely external, or may affect both the exterior and

Segmentation. a greater or less number of the internal organs. Sometimes, however, as in the case of the longer half of an earthworm's body, the segmentation affects all the organs, and the likeness of one segment to another is so great that it would be impossible to say what part of the body any given isolated segment was taken from. More often, however, one or another of the organs of the body differs in shape or size in successive segments, and this is the case with the internal organs of the first twenty segments of the earthworm's body, so that if these segments were all separated it would not be very difficult to place them together in their natural order.

If we take an earthworm and kill it by placing it in alcohol for a few minutes and examine it carefully, we shall see that the body is composed of some 150 rings, each of which corresponds with a segment. The rings are separated from one another by slight grooves. At each end of the body there is an opening, the mouth (2, Fig. 40) in front and the anus (3, Fig. 40) behind. Besides these, two slit-like pores with rather swollen lips, situated on the under surface of the fifteenth segment (5, Fig. 40), may be seen. These are the pores through which spermatozoa are discharged, and are consequently known as the male genital openings. The

The
Earthworm.
External
features.

other openings into the body are minute and require the aid of a lens to make them out. There are paired openings on each segment, except the first three and the last, situated latero-ventrally; these are the openings of the tubes known as nephridia (Gr. νεφρίδιον, a little kidney), which act as kidneys; in addition to these a median dorsal pore opening into the body-cavity is situated in each groove behind the tenth segment (11, Fig. 44). The earthworm is hermaphrodite, that is, it contains both male and female organs in its body. Through two slit-like openings in the ventral surface of the fourteenth segment the eggs are discharged: these are called the female generative openings. Two pairs of pouches called spermathecae, which are reservoirs for spermatozoa received from another worm (*v. p.* 99), open, one pair between the ninth and tenth, the other between the tenth and eleventh segments, all on the ventral surface.

If a worm killed in alcohol be drawn through the fingers a certain roughness may be felt along the sides and lower surface. This roughness is due to the presence of a number of small bristles, called chaetae (Gr. χείρη, hair), which project from the body (7, Fig. 40, and Fig. 43). Each segment bears eight of these chaetae arranged in four pairs, one pair on each side being lateral and the other nearer the ventral middle line. It is by means of the chaetae that the worm crawls about; since by protruding the chaetae and implanting them in the soil a fixed point is obtained from which the anterior end of the




FIG. 40. Latero-ventral view of *Lumbricus terrestris*, slightly smaller than life-size. From Hatschek and Cori.

1. Prostomium. 2. Mouth. 3. Anus. 4. Opening of oviduct. 5. Opening of vas deferens. 6. Genital chaetae. 7. Lateral and ventral pairs of chaetae.
- xv. xxxii. and xxxvii. are the 15th, 32nd, and 37th segments. The 32nd to the 37th form the Clitellum.

3
FIG. 40.

body can be pushed forward and to which the hinder end of the body can be drawn up.

The colour and thickness of the body from the thirty-second to the thirty-seventh segment differ in adult worms from those of the segments which lie before and behind this band. This is due to the presence in this region of certain ectodermal glands whose secretion forms the cocoons in which the eggs are laid. This region of the body is called the Clitellum (xxxii—xxxvii, Fig. 40).

The surface of the body of an earthworm is glistening and somewhat slippery. This is due to the cuticle, which is a thin membrane secreted by the ectoderm cells of the skin; if a dead earthworm be soaked in water for a few hours the cuticle can be easily stripped off the body. In the crayfish, insects, etc., a similar cuticle is present, but it is much harder and forms an external protective skeleton; even in the earthworm, where it is soft, it acts as a protection to the underlying cells, and its smooth surface enables the worm to creep into narrow holes, without hindrance. The chaetae are simply large local thickenings of the cuticle: they protrude from pockets called chaeta-sacs, each of which is a portion of the ectoderm tucked in. In the bottom of each sac is a specially large cell which rapidly secretes a column of cuticle and builds up the chaeta.

If we cut through the skin of an earthworm we do not make our way into the cavity of the alimentary canal but into the coelomic cavity, in which not only the alimentary canal but the blood-vessels, kidneys, reproductive organs, apparently lie. The relation of the alimentary canal to the body-cavity might be roughly represented by introducing a piece of glass tubing loosely into an india-rubber pipe. The alimentary canal would be represented by the glass tube and the body-cavity by the space between the glass and the india-rubber.

The coelomic cavity is a very important feature in all the higher animals; it may become very reduced, as in the Arthropods, but it is always present, although it may not at first sight be easy to recognise. There are, however, certain features which it always presents: (i) it always possesses a proper wall, never being a mere slit intervening between various organs, and it is always surrounded by mesoderm; (ii) its walls give rise to the cells which form the reproductive cells; (iii) the kidneys, which are primitively tubes with open ends, open into it.

There is no difficulty in recognising the body-cavity of an

earthworm. It is comparatively spacious, and is divided by a series of partitions into a number of chambers which correspond in number and position with the segments of the body. These partitions or septa (8, Fig. 41) are pierced by the alimentary canal, the nervous system and blood-vessels; they are not complete but are provided with holes so that the space in one segment is not shut off from the spaces in the neighbouring segments. Fundamentally in Annelida the body-cavity consists of a series of pairs of sacs interposed between the skin (ectoderm) and the gut-wall (endoderm); there is in the embryo a pair in each segment, but the walls of these come into contact above and below the alimentary canal and then break down, so that the cavities of the right and left sacs open into one another and a ring-shaped space results. This space has distinct inner and outer walls of its own which are known collectively as the peritoneum (Gr. *περί*, around; *τόνος*, a stretched band).

The septa are formed where the adjacent walls of two sacs, placed one behind the other, come in contact. If this description of the relations has been followed it will be seen that the coelom in the adult consists of a series of ring-shaped spaces, and that the alimentary canal is not truly in the coelom nor, it may be added, is the nervous system or the blood-system.

Like all similar spaces in animals the body-cavity of an earthworm contains a fluid, and in this fluid certain cells float, which change their shape as an *Amoeba* does, and hence are called amoebocytes. As a rule the body-cavity is completely shut off from the outside world, but in the earthworm it opens to the exterior by means of the dorsal pores (11, Fig. 44), and at times the fluid which it contains escapes through these holes and pours over the cuticle. This fluid has a certain poisonous action on bacteria, and helps to keep the outside of the body clean and free from parasites. Somewhat similar pores leading from the exterior to the body-cavity are found in certain fishes.

At the anterior end of the body there is a lobed lip which overhangs the mouth, termed the prostomium (1, Fig. 43); beneath it is a somewhat crescent-shaped mouth leading into an oral cavity, which extends through three segments (Fig. 41). There are no teeth in this cavity, and the food is probably sucked in by the action of the muscular stomodaeum, called the pharynx, which succeeds it and reaches back to the sixth or seventh segment. This is followed by the true endodermic tube. The first part is narrow, and is

ANNELIDA.

teen, and this is separated by a septum from the gizzard, which extends to about the twentieth segment. The exact segment in which the above-

mentioned parts of the alimentary canal lie varies with the amount of food they contain, the septa which are pierced by them being stretched forward or backward according to their state of fullness or emptiness.

Behind the twentieth segment the intestine stretches without change to the anus. It is a thin-walled tube, supported by the septa between each segment and swelling out slightly in each segment, so that it presents an outline like a string of beads. A deep fold, called the typhlosole (Gr. τυφλός, blind; σωλήν, a gutter), runs along the upper surface of the intestine, projecting into its cavity. Its presence causes the wall of the intestine to be pushed in, and thus the internal absorbing portion is increased (7, Fig. 42). The intestine is covered everywhere by a number of cells of a yellow colour. These form the inner wall of the coelomic sac and are actively engaged in excretion.

The exact part that each of the above-mentioned parts of the alimentary canal plays in digestion is not thoroughly understood. The pharynx helps to take food in by a sucking action which is caused by the contraction of the




FIG. 41. Anterior view of the Internal organs of an Earthworm, *Lumbricus terrestris*. Slightly magnified. From Hatschek and Cori.

1. Central ganglion or brain. 2. Muscular pharynx. 3. Oesophagus.
4. Crop. 5. Muscular gizzard.
6. Intestine. 7. Nephridia (the reference lines do not quite reach the nephridia).
8. Septa. 9. Dorsal blood-vessel. 10. Hearts. 11. Spermathecae. 12. Vesiculae seminales.

The Roman figures refer to the number of the segments.

muscles running from it to the body-wall, resulting in an enlargement of the cavity of the pharynx, so that food may pass in by atmospheric pressure. The food passes down the oesophagus, being propelled by a series of contractions of the walls of the alimentary canal which push it along; on its passage it is mixed with the secretions of the calciferous glands. The crop serves as a resting-place in which the food accumulates before passing into the gizzard. The hard, horny walls of the last-named chamber help to grind up the food and render it fit for the action of the juices which digest it. The process of digestion, or the rendering of the food soluble, probably takes place in the intestine, and through the walls of this portion of the alimentary canal the soluble products of digestion soak, and are taken all over the body by the blood-vessels and probably also to some extent by the fluid in the coelom.




FIG. 42. Six segments from the intestinal region of an Earthworm, *terrestris*, dissected to show arrangement of parts. Magnified. From Hatschek and Cori.

1. Septa. 2. Nephridia. 3. Ventral nerve-cord. 4. Sub-neural blood-vessel.
5. Nephrostomes, internal funnel-shaped openings of nephridia. 6. Intestine. 7. Typhlosole. 8. Circular blood vessels.
9. Ventral or sub-intestinal blood-vessel. 10. Dorsal blood-vessel.

The series of contractions which squeeze the food onwards towards the anus are known as peristalsis; they constitute the sole movements of which the alimentary canal is capable and are carried out by muscles developed from the cells of the inner wall of the coelom, which pass round the canal like a series of rings or tight india-rubber bands.

The earthworm eats earth and manages to find sufficient nourishment for its needs in the small amount of organic matter, broken-down *débris* of leaves, etc., which is contained in the earth. The actual minerals of the earth are not digested but are passed out of the body in the form of those coiled and thread-like castings which are so commonly seen on a lawn in the early morning. Earthworms also eat fallen leaves, and to this end they drag the leaf-stalks into their burrows, and on autumn mornings it is a common sight to see lawns studded with the stalks of horse-chestnut leaves or the needles of fir trees, the stalks having been dragged a little way into the burrows by the worms. It is thus clear that the earthworm is of great use as an agricultural agent. The burrows that they make admit both air and rain to the deeper layers of the soil, and the earth which they swallow in their burrows is brought to the surface and spread about in the form of castings. This is carried on to such an extent that the whole surface of the soil soon becomes covered by a layer of earth brought up from below.

The dark streak which runs along the body of the worm from head to tail in the middle line is caused by the dorsal blood-vessel (10, Fig. 42), in which the blood flows forward. A parallel sub-intestinal vessel in which the blood flows backwards underlies the intestine, and a third but smaller vessel, the sub-neural, lies still more ventrally under the nerve-cord. The dorsal vessel receives blood from the yellow cells covering the intestine by two pairs of minute vessels in each segment, and anteriorly it breaks up into a network of small vessels which branch over the pharynx. But by far the larger part of the blood from this vessel passes into the sub-intestinal vessel by means of five pairs of loops, called hearts, situated in the seventh, eighth, ninth, tenth, and eleventh segments (10, Fig. 41). Each pair of these hearts encircles the oesophagus, and contracts at regular intervals from above downwards. Their contractility has suggested the name heart. As they pass from the dorsal vessel into the sub-intestinal the effect of their contractions is to drive the blood which is passed forward on the dorsal side of the animal into the ventral system, whence it passes toward the tail. These contractile hearts thus take a large share in maintaining the circulation of the blood. The sub-intestinal vessel gives off a special vessel in each segment to the nephridia, and the blood which is purified in these organs is returned to the dorsal vessels by another series of vessels. The dorsal vessel and the

sub-neural vessel are put into communication in each segment by two lateral vessels which lie on the outer side of the coelom and which receive numerous small vessels from its substance.

All the blood-vessels are for the most part merely chinks between the coelomic wall on the one hand and the ectoderm and endoderm on the other. Those described are merely the larger channels in a continuous network of spaces. The contractile power which some, like the hearts, dorsal vessel, and sub-intestinal vessel, possess is due to the presence of a special wall of muscular cells derived from that part of the coelomic wall which lies next them.

The earthworm is the first animal that we have studied possessing a distinct and well-marked body-cavity; it is also the first in which we find a distinct blood-system. In the Coelenterata the cavity in which digestion is carried on permeates the body in all directions, and the soluble products of digestion are never far from the tissues or cells which may need them. But in the earthworms the alimentary canal is a straight tube separated from a number of the other systems of organs by a space or coelomic cavity, and hence a vascular system is of great use in conveying the digested products to where they are most needed. Thus the blood serves to take up the nutriment from the intestine and distribute it to all the active cells in the body. The blood is also the medium by which the waste products resulting from katabolism are collected and taken to the appropriate structures whose duty it is to separate them from the blood and cast them out of the body of the animal. Amongst the products which do not contain nitrogen the most important is carbon dioxide, which is carried by the blood to the skin and got rid of through the ectoderm, at the same time as the oxygen needed for respiration is absorbed.

In the Vertebrata the excretion of the waste nitrogenous material is performed by a pair of compact organs, the kidneys. In the earthworm this function is carried out by the nephridia, which fundamentally resemble the tubules composing the kidney of Vertebrates, but are not compacted into a solid organ. They are distributed throughout the body, one pair being situated in each segment, except the last segment and the first three, which have no nephridia (7, Fig. 41, and 2, Fig. 42). Each nephridium is a minute tube, opening at one end on to the surface of the worm near the outer chaeta of the more ventral pair and at the other end into the body-cavity. This inner opening or nephrostome has cilia on its funnel-shaped rim, and these flicker with an untiring

movement. The nephrostome does not lie in the same segment as the rest of the tube but pierces the anterior septum, and projects into the cavity of the segment in front, somewhere near the sub-intestinal vessel. Thus each segment contains a funnel-shaped opening and a tube which opens externally, but they do not belong to the same nephridium. The tube is not straight but is coiled and lies as a white glistening tangle close to the muscular body-wall. Each nephridium is to be regarded as a portion of the coelomic sac into which it opens internally. It is, so to speak, a tail of this sac which projects backwards into the next one—not, of course, piercing it, but indenting, so to speak, its anterior wall.

When we examine a nephridium through a microscope we see that the walls of the tube are very richly supplied with minute blood-vessels, and we may be able to make out that a large part of the tube is lined with well-marked glandular cells. It is these cells which take up the waste nitrogenous matter from the blood and pass it into the tube, and thus out of the body. The part of the nephridium nearest the external opening is swollen so as to form a bladder. It is not lined by glandular cells, but has a muscular wall by the contraction of which the contents are from time to time expelled.

The blood thus takes digested food to the living cells all over the body, and brings from them certain nitrogenous excreta to the nephridia, which cast them out of the body. But the nephridia also exert some action on the other great fluid of the body—the coelomic fluid—which bathes all the organs of the body. It has been mentioned above that the funnel-shaped ciliated openings of the nephridia open into the coelom, so that the fluid of this cavity can pass out of the body not only by the dorsal pores but by the tubular nephridia. This fluid has suspended in it numerous amoebocytes (*v. p.* 85), and these corpuscles act as scavengers, taking up into themselves any foreign bodies, such as bacteria, which have made their way into the coelom, and breaking them up.

The yellow cells (7, Fig. 44), which surround the gut and form the inner wall of the coelom, are also actively engaged in extracting nitrogenous waste from the endoderm cells and the blood-vessels which pass near them. When the excreta have accumulated to a certain extent in a yellow cell it dies, and its remains fall out into the coelomic fluid, where they are eaten by the amoebocytes. These latter then wander to the nephridium and become pressed close against its wall, the cells of which extract the excreta from

the amoebocytes and pass them into the cavity of the nephridial tube. The funnel of the nephridium is too small to admit the amoebocytes—it serves as a flushing apparatus, since its cilia draw in water from the coelom which is swept down the tube and carries the excreta into the terminal bladder whence they are from time to time expelled.

It is probable that the yellow cells represent a primitive mode of excretion, and that originally the whole coelomic wall undertook this function, the products escaping either by simple pores or by being taken up by amoebocytes which forced their way out through the skin, as in Echinodermata. The yellow cells and the nephridia are then to be regarded as portions of the coelom in which the power of storing up excreta is specially developed, and in this limitation of this power to a special area we have the first type of an excretory organ. A localized excretory organ requires some means of bringing to it the products of katabolism of all portions of the body—since poisonous excreta are produced by all living protoplasm—and this means is supplied in the earthworm by the blood-system and the amoebocytes.

The earthworm, although it lives in earth, has a clean, glistening look, and this is partly due to the fact that the coelomic fluid is poured out from the dorsal pores (11, Fig. 44) and keeps the skin moist and lubricated. This fluid is also antiseptic in its action and thus its presence prevents foreign organisms, such as bacteria, which swarm in the mould in which the worm lives, settling upon the skin and growing there. Numerous glandular cells belonging to the ectoderm also pour forth a secretion through minute pores in the cuticle.

The earthworm breathes through its skin. The blood-system sends up into the skin innumerable minute vessels or capillaries which come so near the outer surface of the worm that the oxygen can pass in from the air into the blood. The name capillary (Lat. *capillus*, a hair) was suggested by a comparison of the exceedingly small calibre of these vessels with the diameter of a human hair.

The blood is red, and the red colour is due to the same substance which colours our blood, haemoglobin, but there is this difference, that whereas in Vertebrates the haemoglobin is contained in certain cells which float in an almost colourless fluid, in the earthworm it is dissolved in the fluid itself. This substance has a strong attraction for oxygen which it takes up from the air that comes into the neighbourhood of the skin-capillaries, forming a bright red

compound called oxy-haemoglobin. This compound is unstable, and when the blood in its course round the body encounters a cell hungry for oxygen, the oxy-haemoglobin is decomposed, yielding up its oxygen; at the same time it absorbs carbon dioxide from the cell, forming a compound of a purplish colour called reduced haemoglobin. When the blood again approaches the skin carbon dioxide is displaced by oxygen and got rid of, oxy-haemoglobin being again formed.




FIG. 43. Diagram of the anterior end of *Lumbricus herculeus* to show the arrangement of the nervous system. After Hesse.

I. II. III. IV. The first, second, third, and fourth segments.

1. The prostomium. 2. The cerebral ganglia. 3. The para-oesophageal commissure. 4. The first ventral ganglion. 5. The mouth. 6. The pharynx. 7. The dorsal and ventral pair of chaetae. 8. The tactile dorsal nerves. 9. The anterior, middle and posterior dorsal nerves. 10. The anterior, middle and posterior ventral nerves.

If we cut open an earthworm by a median dorsal incision and attentively examine the upper surface of the pharynx we shall find at its anterior end, tucked away between it and the skin, two little whitish knobs lying close to one another. These are the cerebral or supra-oesophageal ganglia (1, Fig. 41; 2, Fig. 43). At their outer ends the supra-oesophageal ganglia pass into two cords (3, Fig. 43). If we now cut away the pharynx and remove the alimentary canal we can trace these two cords towards the ventral middle line where they unite and form the first sub-oesophageal ganglion (4, Fig. 43);

The Nervous System.

from this a long white cord—the ventral nerve-cord—runs back to the extreme posterior end of the animal. If we examine these structures with a lens we shall be able to see that the supra-oesophageal ganglion gives off small nerves to the sensitive pro-stomium, and that the ventral nerve-cord swells out between each pair of septa, that is in each segment, into a thicker portion which gives off, both dorsally and ventrally, and on each side, three pairs of nerves to the surrounding parts. Each of these swellings is termed a ganglion (Gr. γάγγλιον, a knot¹) (4, Fig. 43). The nature of a ganglion-cell or nerve-cell has already been explained when the Medusae were described. Ganglia are portions of the nervous system containing nerve-cells. In the earthworm such cells are found everywhere on the cord forming the central nervous system, though more abundantly in the swellings called ganglia.

The nervous system of an earthworm thus consists of two supra-oesophageal ganglia situated in the third segment, a pair of connecting cords called commissures, which form a ring round the pharynx, and a ventral cord which swells out into a ganglion in every segment behind the third. The ring round the mouth and the solid nature of the nervous system is common to nearly all the Invertebrata, and in those which have a bilateral symmetry and are segmented there are supra-oesophageal ganglia and a ventral nerve-cord bearing segmentally repeated ganglia.

The earthworm has no specialized sense-organs, it has neither eyes to see, nor nose to smell, nor ears to hear with. Still, although it is apparently deaf, it is not devoid of the power of appreciating those stimuli which in us excite the sensation of sight or smell. A strong light suddenly turned on the anterior end of the body will cause the worm instantaneously to withdraw into its burrow, and worms readily recognise the presence of such favourite food as onions and raw meat. Their sense of touch is well developed and they are very sensible to vibrations, for instance, a stamp of the foot on the ground will cause all those in a certain radius to disappear into their burrows. It is further possible that earthworms possess other senses with which we are totally unacquainted.

The nervous system is one of the most important in the body. It governs and controls the action of every tissue and cell. It receives and registers impressions from the outside world, and

¹ Γάγγλιον was used by the old medical writers to indicate the swelling or "knot" in a muscle caused by cramp.

co-ordinates the movements and activities of every part of the body. It further serves to put each organ and each part of each organ in communication with all the others, and thus this vast accumulation of tissues and cells acts in an orderly way and towards a set end.

A transverse section of an earthworm, such as can be cut by a microtome from a specimen embedded in paraffin wax, is most




FIG. 44. Transverse section through *Lumbricus terrestris* in the region of the intestine, and of a dorsal pore. Magnified.

1. Cuticle. 2. Ectoderm or epidermis. 3. Circular muscles. 4. Dorsal nerve.
5. Longitudinal muscles. 6. Somatic epithelium.
7. Splanchnic epithelium, or yellow cells. 8. Epithelium lining the intestine.
9. Coelom. 10. Nephridium cut in section. 11. Dorsal pore.
12. Dorsal blood-vessel lying along the typhlosole or the groove in the wall of intestine.
13. Sub-intestinal blood-vessel. 14. Ventral nerve-cord.
15. Sub-neural blood-vessel. 16. Ventral nerve.

The dorsal and ventral nerves are added diagrammatically. The other structures are drawn from nature.

instructive, in exhibiting the relation to one another of the various tissues which make up the body of the earthworm. The outermost boundary is constituted by the cuticle (1, Fig. 44), a hardened secretion poured out by the ectoderm (2, Fig. 44). The ectoderm is composed of tall cylindrical cells, amongst which are isolated

“goblet cells”—that is, cells with a round body situated beneath the level of the rest and with a long neck. The name is suggested by the shape. In the body of these cells mucus is secreted, which is poured forth through a hole in the cuticle opposite the end of the cell-neck and helps to keep the surface of the worm moist.

Beneath the ectoderm is a thin and hardly perceptible layer of jelly forming a bed on which the ectoderm cells rest. This foundation is called the dermis, and is included with the ectoderm in the ordinary conception of the “skin.” In contradistinction to the dermis the ectoderm is often spoken of as the epidermis (Gr. *ἐπί*, upon).

Beneath the dermis comes a layer of circular muscles (3, Fig. 44), and beneath these again a much thicker layer of longitudinal muscles. The circular muscles consist of a few layers arranged to form rings round the section. The longitudinal muscles are arranged very regularly, and in the section they have the form of a series of feathers (5, Fig. 44), since the individual fibres appear arranged in oblique rows between which tongues of jelly extend, giving off lateral branches on which the fibres rest.

Both sets of muscles are composed of muscle-cells. These are long fibre-like structures pointed at both ends. Most of the protoplasm is differentiated into fine fibrillae, which indicate (see p. 29) contractile power. In the centre of the cell is a patch of unmodified protoplasm with a nucleus. The whole cell may be compared to a myo-epithelial cell of *Hydra*, in which the epithelial part has diminished in size and the tail increased. Nor is this a fanciful comparison, for the study of development teaches us that the cell is actually derived in this way from the originally simple cells of the wall of the coelomic sac.

The movements of the earthworm can be more easily understood when the arrangement of the muscles is known. The longitudinal muscles serve to shorten the body, and as the coelomic fluid, like water, is practically incompressible, the diameter of the animal must be increased, and thus the chaetae can be driven into the sides of the burrow. On the other hand, the circular muscles diminish the diameter of the coelom, and the contained fluid being forced to move in a longitudinal direction stretches the body out. The holes in the septa equalize the pressure in the various segments by permitting the fluid to escape from one into the next.

Mention has been made above of “jelly” as forming a support for the ectoderm and the longitudinal muscles. It forms also the

main part of the substance of the septa. In the worm and higher animals generally jelly fulfilling this function is known as connective tissue. Its nature will be more fully dealt with in the section relating to *Arthropoda*.

Within the longitudinal muscles there is a layer of cells called the somatic peritoneum (6, Fig. 44) which forms the immediate wall of the coelom. As the coelom in a segment of the worm has a ring-shaped form there is an inner as well as an outer wall of the coelom; the former, since it closely invests the alimentary canal, is called the visceral or splanchnic (Lat. *viscus*; Gr. *σπλάγχνον*, entrail) peritoneum (7, Fig. 44)—the latter the parietal or somatic (Lat. *paries*, an outer wall; Gr. *σῶμα*, body) peritoneum. The parietal peritoneum is composed of flattened cells; the visceral peritoneum, on the other hand, consists of large cubical cells, the yellow cells already described.

Beneath the visceral peritoneum there is a thin layer of circular muscles, the splanchnic muscles derived from the peritoneal layer and forming the agency by which the peristalsis (*v. p.* 87) of the gut is carried out.

The endoderm (8, Fig. 44) consists of a single layer of long cylindrical cells bent in dorsally to form the typhlosole. Within the limbs of this fold the splanchnic peritoneum is very much thickened.

The dorsal blood-vessel can be seen embedded in the yellow cells lying in the typhlosole (12, Fig. 44), whereas the ventral vessel is attached by a membrane to the ventral side of the intestine. This membrane is really a part of the partition which separated the two coelomic sacs which originally existed in the segment.

The nerve-cord, apparently lying loosely in the coelom, is surrounded by a layer of cells similar to those forming the somatic peritoneum of which they once formed a part (14, Fig. 44). Hence the coelom has extended in a ring-shaped manner round the nerve-cord exactly as it has surrounded the gut. At the sides of and below the nerve-cord may be seen sections of vessels, the sub-neural and latero-neural vessels. The mass of the nerve-cord is made up of the sections of nerve-fibres, whilst the nuclei of ganglion-cells can be seen forming a sheath on the outer border of the cord. The fibres are divided into two bundles by a septum of connective tissue. On the dorsal surface of the cord there are seen three apparent tubes, these are sections of the so-called "giant" fibres—colossal nerve-fibres which are outgrowths of equally large ganglion-cells.

Sections of chaeta sacs and nephridia may be seen in favourable sections.

It has been mentioned above that it is one of the characteristics of the coelom that the cells lining it should produce the reproductive cells. This does not mean that any cell lining the coelom can become an ovum or a spermatozöon, but that at certain spots the cells forming part of the coelomic wall turn into either female or male generative cells. In the earthworm the paired ovaries (5, Fig. 45) are situated in the thirteenth segment and may be seen by cutting through the intestine about the region of the gizzard and gradually lifting it up from behind forwards; when it is freed up to the twelfth segment




FIG. 45. View of Reproductive Organs of the Earthworm, *Lumbricus terrestris*. Part of the vesicula seminalis is cut away on the left side to expose the testis and the inner opening of the vas deferens. Slightly magnified. From Hatschek and Cori.

1. Spermathecae. 2. Funnel-shaped internal openings of the vas deferens.
3. Anterior testis. 4. Vesiculæ seminales. 5. Ovary attached to posterior wall of septum separating XII and XIII.
6. Oviduct traversing septum separating XIII and XIV. 7. Vas deferens. 8. Glands in the skin. 9. Ventral nerve-cord. 10. Septum.

The Roman figures indicate the number of the segments.

the ovaries may be seen as minute white, pear-shaped bodies lying one on each side of the nerve-cord. They are attached by their broad end to the posterior wall of the septum separating segment twelve from segment thirteen, and they are formed by the accumulation and growth of some of the cells which cover this septum, that is, from cells lining this portion of the coelom.

If one of the ovaries be removed and examined under a microscope it will be seen that many of the cells composing it are large,

spherical and crowded with granules. The largest lie in the narrow end of the ovary which waves about in the coelomic fluid. These cells are the full-grown eggs or ova, and when ripe they drop off from the ovary into the coelom, but are probably at once taken up by the wide funnel-shaped openings of the oviducts, one of which is situated opposite each ovary. Like the nephridia, the two oviducts pierce a septum, the one between the thirteenth and the fourteenth segments. They are short tubes which open into the coelom by the above-mentioned funnel-shaped opening in the thirteenth segment and to the exterior by a small pore just outside the inner pair of setae on the fourteenth (6, Fig. 45). They bear on their course a diverticulum or sac which is called the receptaculum ovarum, in which the ova collect until the earthworm is ready to make a cocoon to receive them.

The male reproductive cells are formed in the testes, of which there are two pairs situated in a similar position to the ovaries but in the tenth and eleventh segments (3, Fig. 45). They are in many respects similar to the ovaries but are hand-shaped, the broad end of the hand being attached, the fingers free. Their ducts which convey away the spermatozoa are called the vasa deferentia (Lat. *vas*, vessel; *deferens*, carrying away). They have similar funnel-shaped openings to those of the oviducts and they traverse the septum behind the segment in which these openings lie, but they do not at once open to the exterior. The two ducts of each side unite in the twelfth segment, and the common duct thus formed runs back to open by a pore with swollen lips on the fifteenth segment, the one behind that on which the oviducts open (7, Fig. 45).

There is, however, one great difference between the male and female organs. Whereas the ovaries lie freely in the body-cavity and can readily be seen if the intestine be removed, each pair of testes and the corresponding inner funnel-shaped openings of the vasa deferentia are concealed by a certain sac or bag called the vesicula seminalis, and it is only by cutting away the wall of this sac that these structures come into view (4, Fig. 45). Each vesicula seminalis is a flat, oblong bag extending backwards from the front wall of the segment in which it lies and situated beneath the alimentary canal. The angles of the front vesicula seminalis are produced into two long pouches which project upwards at the sides of the alimentary canal, and are often called lateral vesiculae seminales, though they ought to be termed lateral horns of the anterior vesicula seminalis. A similar projection is produced

from the hinder angles of the posterior vesicula seminalis, so that on opening a worm three pairs of greyish white sacs are seen at the sides of the gut. The study of the way in which the vesicula seminalis is formed shows that the space it contains is really part of the coelom which has become cut off from the rest, so that, although at first sight the testes seem to differ from the ovaries and to be exceptions to the general rule that reproductive cells have their origin from the walls of the coelomic cavity, a closer examination shows that this apparent divergence is not real.

Every earthworm has grown up from an egg which has been fertilized by a spermatozoon. As the earthworm is hermaphrodite, that is to say, contains both male and female organs, it might be thought that the spermatozoa of an individual would fertilize its own ova, but this is not the case. Cross fertilization or the fertilization of the ova of one individual by the spermatozoa of another is the rule in Nature, and the earthworm is no exception to the rule. The method by which the spermatozoa reach the ova is not clear in all its details, but it is something like this. The cells which are to form the spermatozoa break off from the testes and whilst lying in the fluid contents of the vesicula seminalis they divide and the products of the division or spermatozoa develop each a long vibratile tail by whose aid they swim actively about. Two earthworms then approach each other and the spermatozoa pass down the funnel-shaped opening and vasa deferentia of each and into the spermathecae of the other. The earthworms then separate, each carrying away the spermatozoa of the other.

The spermathecae in which the earthworm stores up the spermatozoa received from another individual are pockets of the skin (1, Fig. 45). They belong, strictly speaking, to the female reproductive system. Seen from the interior of the animal, they appear as four small white spherical bodies, lying one pair near the hind end of segment nine, and the other pair near the hind end of segment ten, and each pair opens by a very short neck or duct on the grooves between segments nine and ten and ten and eleven, just inside the outer pair of chaetae. It is through these ducts that the spermatozoa from another worm enter.

Earthworms lay their eggs in cocoons, which at one time were mistaken for the eggs themselves. These cocoons are usually brown and horny and vary in size in different species of earthworm; some are about as large as rape seed, others almost equal in bulk to

a small grain of wheat. They are formed from the secretions of the peculiar ectoderm cells found in the clitellum and at first have a ring-like shape. The secretions harden when in contact with the air. The animal begins to wriggle out of the band, which at first surrounds its body in the neighbourhood of the thirty-second to the thirty-seventh segment. As the band passes over the openings of the oviducts in the fourteenth segment it carries away with it a certain number of ova, and as it passes the orifices of the spermathecae between the eleventh and tenth and tenth and ninth segments, some of the spermatozoa which have been received from another individual are squeezed out. Besides ova and spermatozoa the cocoon contains a certain amount of a milky and nutritive fluid in which these cells float; this is probably supplied by certain other glands in the skin of the earthworm. At the moment the last segment, that is, number one, is withdrawn, the anterior end of the cocoon contracts and closes, and as the posterior end of the band-like ring passes over the head it also closes, so that the cocoon lies in the earth as a closed vesicle containing eggs, spermatozoa and a nutritive fluid. The spermatozoa fuse with the ova and from the fertilized ova, by division into a number of cells and by the differentiation of the cells into muscle cells, epithelial cells, digestive cells, nerve cells, etc., a young earthworm is built up. Before being hatched out of the cocoons the young embryos are nourished by the milky nutritive fluid in which they float.

In Great Britain there are several species of earthworm, which are grouped into two genera, viz. *Allolobophora*, with fourteen species, which, with one exception, have the prostomium not dove-tailed into the second segment; and *Lumbricus*, with five species, in which the prostomium is completely dove-tailed into the second segment. The above account has been taken from the anatomy of *L. herculeus*, the largest of our indigenous species, but with the exception of a few minor details the account applies to most British earthworms.

Species of
Earthworm.

Order I. Oligochaeta.

The sub-order to which earthworms belong, the Terricolae, are for the most part inhabitants of the land, and occur widely distributed over the Earth, being as a rule, only absent from sandy and desert soils. Some of them are aquatic, but not many. On the other hand, the allied sub-order the Limicolae

are for the most part denizens of fresh water. Both sub-orders contain numerous genera and families ; together they form the order Oligochaeta, which is characterised by being hermaphrodite, by having the reproductive organs few in number and definite in position, by developing directly from the egg without the intervention of any larval stage, and lastly by the absence of certain structures which are very characteristic of the other great division of the true worms or Chaetopoda.

Order II. Polychaeta.

The Polychaeta differ from the Oligochaeta, as their name implies, by possessing a large number of chaetae on each segment. The sides of each segment are further as a rule drawn out into hollow flaps or lobes called parapodia, which bear the chaetae. Each parapodium may be divided into a dorsal half, the Notopodium, and a ventral half, the Neuropodium (15 and 16, Fig. 47). Both notopodium and neuropodium carry bunches of chaetae, and each has, as a rule, one particularly large chaeta, the aciculum, completely concealed in a very deep chaeta-sac, which is moved by muscles attached to its base and serves as a kind of skeleton for the parapodium. There is usually above the notopodium and beneath the neuropodium a process called a cirrus. The dorsal cirrus may be modified into a gill, and both dorsal and ventral cirri may be absent.

The coelom is often divided into three longitudinal compartments by two muscular partitions (5, Fig. 47) which run from the dorso-lateral line towards the median ventral line near the nerve-cord. The mesenteries which divide the space between each segment are absent in some of the Polychaeta which live in tubes.

As a rule Polychaets have a certain number of the anterior segments modified to form a head, which usually



FIG. 46. *Nereis pelagica*, L. After Oersted.

carries tentacles and organs for absorbing oxygen from the water, called branchiae or gills. They are generally of separate sexes, and the eggs develop into a larva which swims in the sea and gradually changes and grows up into a worm. This group includes a very great variety of forms, almost all of which are marine. With few exceptions they form burrows for themselves, which most




FIG. 47. Transverse section through *Nereis cultrifera*, slightly simplified. The parapodia are shown in perspective. Magnified.

1. Cuticle. 2. Epidermis. 3. Circular muscles. 4. Longitudinal muscles. 5. Oblique muscles forming a partition. 6. Somatic layer of epithelium. 7. Coelom. 8. Splanchnic layer of epithelium. 9. Cavity of intestine. 10. Dorsal blood-vessel. 11. Ventral blood-vessel. 12. Ventral nerve-cord. 13. Nephridium cut in section. 14. Ova. 15. Notopodium. 16. Neuropodium. 17. Dorsal cirrus. 18. Ventral cirrus. 19. Chaetae. 20. Aciculum with muscles at inner end.

of them occasionally desert in order to seek prey and to discharge the reproductive cells. Some however never leave the burrows, which in this case often take the form of tubes composed of a secretion of the ectoderm.

Order III. **Hirudinea.**

Besides the Oligochaeta and Polychaeta the order Hirudinea, the members of which are popularly known as leeches, is included amongst the Chaetopoda. They were for some time regarded as a distinct order of Annelida, since the great majority of species possess no chaetae and have other peculiarities; but the recent discovery of species possessing chaetae, and the close resemblance between the development of all Hirudinea and that of Oligochaeta, renders it evident that they are true Chaetopoda and that the absence of chaetae is a secondary characteristic.

There is little doubt that the
 Leeches. Hirudinea are closely allied
 External to the Oligochaeta;
 features. indeed there are certain

families which it is not easy to assign definitely to either group; but the more typical forms are easily distinguished. Externally leeches may be recognized by the possession of a sucker at each end of the body, the anterior one being formed by the mouth, whilst the posterior one is a special organ. By alternately attaching and releasing these suckers and bending the body the animal crawls along.

With the exception of *Branchelion*, which bears tufted gills, the bodies of leeches are without external processes. There are no parapodia, and no branchiae or tentacles, and only one genus of the family has any chaetae. The body is segmented, and recently it has been shown that the number of segments is always thirty-three. Some however of the segments are fused together; thus for example the




FIG. 48. *Hirudo medicinalis*, about life size.

1. Mouth. 2. Posterior sucker. 3. Sensory papillae on the anterior annulus of each segment. The remaining four annuli which make

up the dorsal surface.

posterior sucker contains traces of six or seven true segments. The best test of the number is to count the ganglia on the ventral nerve-cord. But even this is not decisive, because although there are *twenty-one free ganglia in the centre of the body a certain number*, some say five and some six, are fused into the sub-oesophageal ganglion, and a certain number, some say seven and some say six, coalesce to form the ganglion of the posterior sucker. Whichever view is taken the total number of segments is thirty-three.

The body of the leech is ringed or divided into a number of annuli. These do not, however, represent the segments, but a number, varying in the different genera, make up a segment. In *Hirudo*, the medicinal leech, there are five annuli to a true segment; in *Clepsine*, a common fresh-water leech, the number is three. The real segmentation is, however, to some extent indicated by markings on the skin.

The animal is covered like the earthworm by a thin cuticle secreted by the outermost cells, and the ectoderm contains numerous goblet cells which are especially well-developed over the segments abutting on the generative orifices. Here they form a clitellum, and the secretion the cells pour out forms a cocoon in which the eggs are laid.

The nervous system of a leech does not differ in essentials from that of the earthworm, but the nephridia, of which there are in *Hirudo* seventeen pairs, are peculiar. They are no doubt a modified form of the same organ as the nephridium of the earthworm, and they consist of coiled cellular tubes. The outer end communicates with the exterior through a muscular vesicle. The inner end, or so-called testis lobe, lies near the testis in the genital segments. The whole is traversed by a ramifying network of chambers opening by minute pores on the testis lobe.

The other systems of organs are still more unlike what has been described in the case of the earthworm and deserve a short account. Leeches live by sucking the blood or juices of other animals, usually of Vertebrates. They are divided into two large groups—(a) the *RHYNCHOBDELLIDAE*, which pierce the tissues of their hosts by means of a fine protrusible stomodaeum, the so-called proboscis, and (b) the *GNATHOBDELLIDAE*, which bite their prey by means of horny jaws. The medicinal leech is one that bites, and the tri-radiate little scar which its three teeth make in the skin was well-known to our forefathers in the times of bleeding and cupping.

The three teeth, which are notched like a saw, are really only thickenings of the cuticle borne by the wall of the pharynx, which contains many unicellular glands whose secretion prevents blood from coagulating. Thus the leech when fixed on to its victim by the oral sucker readily obtains a full meal.

From the pharynx a short narrow tube, the oesophagus, leads into an enormous dilatation, the crop. This extends to the fourteenth segment and gives off on each side a series of eleven pouches or caeca (Lat. *caecum*, blind), which increase in size from before backward. The posterior caeca are very large and reach back to the level of the anus, lying one on each side of the intestine. The leech has the habits of a boa-constrictor. It makes a hearty meal, absorbing as much as three times its own weight of blood, and the blood it absorbs is stored up for many months in this enormous crop. It slowly digests the food in a small globular stomach situated just behind where the posterior caeca leave the crop. The stomach opens into a short intestine which ends in the anus, a minute pore situated dorsally between the posterior sucker and the body (Fig. 49).

In one genus at least, *Acanthobdella*, the coelomic cavity is almost as well-developed as in an earthworm, and is divided up by septa as in that animal. In other leeches the cavity tends to disappear, becoming in fact displaced by a great growth of tissue, and is reduced to a few narrow channels. In many leeches it contains a fluid closely resembling the true blood, so that unless very careful microscopic examination be made these channels may be mistaken for true blood-vessels. The capsules in which the ovaries and testes lie are also parts of the coelom.

The medicinal leech, owing to a great growth of this above-mentioned tissue, is almost without a coelomic cavity. When the body is opened a narrow vessel, full of a red fluid, is seen running along the middle dorsal line above the alimentary canal. This is the dorsal sinus, a remnant of the true coelomic cavity; a similar sinus runs along the ventral surface underneath the alimentary canal, which is called the ventral sinus. It communicates with the dorsal sinus by lateral channels which run between the intestine and the posterior caeca of the crop. It surrounds the ventral nerve-cord, which thus seems to float in blood, but really lies in the red coelomic fluid, and it gives off lateral sinuses which surround the inner openings of the nephridia. The true blood-vessels

comprise a vessel running on each side of the body and connected together by transverse branches which run from side to side below the ventral sinus. The lateral vessels further supply capillaries to the nephridia, alimentary canal, reproductive organs, etc., and a very extensive system to the skin where the haemoglobin of the blood takes up oxygen. Except in *Branchellion*, which has special gills, the respiration of leeches is carried on in the skin.

Leeches are, like the earthworm, hermaphrodite, but their reproductive organs differ in some respects from those of that animal.

In *Lumbricus* the testes are repeated in two segments only, but in *Hirudo* there are usually nine pairs of testes. The cavities of both the testis and of the ovary are to be regarded as part of the original coelom; in strictness the testes probably correspond to the vesiculæ seminales in an earthworm, which are part of the coelom, and enclose the true testis. Each testicular sac gives off a short transverse duct which passes into a longitudinal canal termed the vas deferens, of which there are two, one on each side of the body. At its anterior end each vas deferens passes into a convoluted mass of tubes—the so-called epididymis—whose walls secrete a substance which binds




Fig. 49. View of the internal organs of *Hirudo medicinalis*. On the left side the alimentary canal is shown, but the right half of this organ has been removed to show the excretory and reproductive organs.

- | | | | | |
|---------------------------|---|----------------------------------|-----------------------------------|-----------------|
| 1. Head with eye spots. | 2. Muscular pharynx. | 3. 1st diverticulum of the crop. | 4. 11th diverticulum of the crop. | 5. Stomach. |
| 6. Rectum. | 7. Anus. | 8. Cerebral ganglia. | 9. Ventral nerve-cord. | 10. Nephridium. |
| 11. Lateral blood-vessel. | 12. Testis. | 13. Vas deferens. | 14. Prostate. | 15. Penis. |
| 16. Ovary. | 17. Uterus—a dilatation formed by the conjoined oviducts. | | | |

the spermatozoa together into packets called spermatophores. It is to be remembered that the names epididymis, prostate, etc., are given from fanciful resemblances to parts in the anatomy of man by no means homologous with the organs bearing the same name in the leech. From each epididymis a short duct passes towards the middle line, and these two ducts fuse and enter the base of the penis, which is protruded from the segment which contains the sixth distinct post-oral ganglion.

The penis is simply the muscular end of the conjoined male ducts or vasa deferentia; it is the organ by which the spermatophore is deposited in the body of another leech. The spermatozoa in *Clepsine* seem to penetrate the skin at any point and make their way to the ovaries, where they fertilize the eggs. In other species the spermatozoa enter in the usual way into the female genital pore.

As in the earthworm, there are but one pair of ovaries. These are minute filamentous bodies enclosed in a small coelomic sac. From each sac a short oviduct proceeds and uniting with its fellow forms a twisted tube surrounded by many glands. This finally opens by a median pore on the segment behind the one bearing the male opening.

Thus in leeches, unlike what prevails in the earthworm, the genital pores are single and median. The medicinal leech lays its eggs in a cocoon and buries them in holes in the banks of the ponds they inhabit. *Clepsine*, one of the Rhynchobdellidae which is very common in Britain, attaches its eggs to some stone or water-plant, or in some species carries them about on its ventral surface. It has developed a quite maternal habit of brooding over the eggs, and when the young are hatched it carries them about and they feed on some secretion from its body.

Of the Gnathobdellidae, *Hirudo medicinalis* is found in Great Britain, but is commoner in some parts of the Continent. They are cultivated in some districts, but the demand for them is decreasing with the disappearance of blood-letting. They become mature in three years. In the young stages they suck the juices of insects. Another common but small Gnathobdellid leech is the brownish *Nephelis*, which frequents our ponds and pools; it feeds on snails and planarians. A large species of the same genus is common in the shallows of the St Lawrence, in Canada. In warmer climates many leeches take to living on land, and are a source of great annoyance to travellers whose blood they suck. Even water-forms do much damage unless carefully

guarded against. Certain species make their way with drinking water into the throat and back of the mouth, on which they fasten and cause great suffering both to man and cattle.

Phylum ANNELIDA.

This phylum includes segmented animals with, as a rule, a well-developed coelom. The cuticle is always thin and flexible, and the nervous system consists of a pair of supra-oesophageal ganglia, a nerve collar and a ventral nerve-cord which has a ganglionic swelling in each segment.

Class I. CHAETOPODA.

Annelida which possess bristles (chaetae) embedded in pits in the skin and serving as organs of locomotion, or which are believed to have once possessed such organs and to have lost them.

Order 1. Oligochaeta.

Chaetopoda which have the chaetae arranged singly or in pairs and which have neither parapodia nor tentacles: the generative organs are definitely localized, and the sexes are united in the same individual: development is practically entirely embryonic: the group inhabit fresh water or damp earth.

Ex. *Lumbricus*,

Order 2. Polychaeta.

Chaetopoda which have the chaetae arranged in bundles of some size, almost always borne on conspicuous lateral outgrowths of the body termed parapodia: the prostomium has, as a rule, tactile organs, known as tentacles and palps: there are no localized generative organs, ova and spermatozoa being developed from wide stretches of the coelomic wall, but the sexes are separate: in the development a well-marked larval stage occurs: with few exceptions the group is marine.

Ex. *Nereis*.

Order 3. **Hirudinea.**

Chaetopoda in which chaetae and parapodia are absent and which move by means of a muscular sucker developed on the under surface of the posterior segments: there are no tentacles and the mouth acts as an anterior sucker: the coelom is reduced to capsules surrounding the genital cells and to a few narrow channels: the animals are hermaphrodite, and the genital pores single and median: the members of this order live on the juices of other animals, and there are both fresh water and marine species: development is entirely embryonic.

Ex. *Hirudo*, *Nephelis*, *Clepsine*.

CHAPTER VII.

PHYLUM ARTHROPODA.

ONE of the most striking features of the Annelida is the fact that they are segmented, that is to say their body is divided into a number of similar parts placed one behind the other like coaches in a train, each of which to a greater or less extent resembles the part in front of it. The likeness of the parts to one another varies. In some worms we might easily detect from which region of the body any given segment was taken. In the Earthworm, except in the region of the clitellum, there is little external difference; nevertheless if we consider the internal organs we can distinguish any of the first twenty segments from any other behind these and can easily arrange them in their proper order; but no matter how long the worm is, all the segments behind the twentieth resemble one another so closely that it is impossible to assign any to their right place, except the last of all (*v. p.* 82).

The animals included in the group of the Arthropoda are segmented like the Annelida, but with few exceptions the number of segments is small and does not exceed twenty. The segments have also become more highly differentiated from one another in consequence of being modified to perform various functions, and they are more frequently fused together than is the case in the Annelids.

The Arthropoda have jointed outgrowths, called limbs or appendages. These are always arranged in pairs, and at least one pair is modified so as to assist in holding and crushing the food. This character of possessing jointed limbs is what is indicated by the name Arthropoda (Gr. *ἄρθρον* joint; *πὺς* foot).

The Arthropoda may be divided into three classes:—

I. The CRUSTACEA, which includes all the Crabs, Lobsters, Cray-fish, Barnacles, Wood-lice, etc., besides countless small forms such as the Water-flea, Cyclops, and many others which inhabit both salt and fresh water.

II. The ANTENNATA, which include all Arthropoda possessing one pair of feelers—antennae—and breathing by means of air tubes or tracheae. This group is divided into three sub-classes, viz. :

A. The Prototracheata, a group containing the genus *Peripatus*, an animal not found in Europe or in North America, but which must be mentioned because it seems to be a survival of an earlier age, and because its structure has given us a clue to much that was obscure in the anatomy of Arthropods; it is in fact in many respects intermediate between the Annelids and the air-breathing Arthropoda.

B. The Myriapoda or Centipedes, the commonest British examples of which are the chestnut-coloured centipede *Lithobius forficatus* and the black “wire-worm”¹ *Iulus terrestris*.

C. The Insecta, the largest group in the Animal Kingdom. It contains about 250,000 named species, and includes all those creatures such as Beetles, Flies, Dragon-flies, May-flies, Moths, Bees, Ants, and Wasps, etc., which we are accustomed to call insects.


III. The ARACHNIDA, including the Spiders, Harvestmen, Mites, and certain larger forms such as the Scorpion, and *Limulus*, the King-crab.

If we go into an old garden and turn over a stone or look between the bark and the trunk of a decaying tree, or examine the leaves, we may find representatives of each of the four larger classes mentioned above. The Crustacea may be represented by a Wood-louse (Fig. 79), the Myriapoda by a Centipede (Figs. 51 and 84), the Insecta by a Beetle (Fig. 92), and the Arachnida by a Spider (Fig. 53). If we compare these creatures one with another we shall see that they resemble each other in certain particulars.

To begin with they are all clothed in a hard coating consisting largely of the horny substance called Chitin, which
 Exoskeleton. does not form a simple chamber or house in which the body of the animal lies, as a snail lies in its shell, but which is moulded accurately over all the body and even tucked into all the openings, so that it forms an exact cast of the soft parts underneath. This covering is to be regarded as an exaggeration of the cuticle found in Annelids, and it is called an Exoskeleton in order to distinguish it from the internal framework of hard parts found in the Vertebrata.

¹ This is not to be confused with the larva of a beetle, *Elatér lineatus*, which is also called a “wire-worm” by the British agriculturist.


A



B



C



D




FIG. 50.

FIG. 50.

- A. The anterior portion of the body of a Dragon-fly, *Aeschna cyanea*, freed from the larval shell. B. The tail being extricated. C. The whole body extricated. D. The perfect insect, the wings having acquired their full dimensions, resting to dry itself, preparatory to the wings being horizontally extended.

Were this hard exoskeleton of the same consistency all over the body it would be impossible for the animal to bend its body or to move at all, but at certain spots, as may be well seen, between the segments of a Centipede or between the members of a Beetle's legs, the exoskeleton has remained soft, like the leather joints in a suit of mail-armour, and thus a certain amount of flexibility is given to the whole body; for instance the Armadillo wood-louse and the Pill-millepede can roll themselves up into spherical balls.

Not only is a hard exoskeleton a hindrance to unlimited movement but it also interferes with growth. It is impossible to increase in size when shut up in a hard unyielding case. Now growth is one of the common characters of all animals, and the way the obstacle presented by the exoskeleton of Arthropods to growth is overcome is as follows. At certain stated times the outer skin or ectoderm of the animal loosens itself from the inside of the cuticle or investment, which splits or cracks, usually along the middle of the back; through the opening thus formed the body of the animal begins to appear, and gradually withdrawing each limb from its case, it works its way out. The exoskeleton thus cast off, forms a most accurate mould of the animal which has left it, and even includes those portions which are folded in at the mouth and anus, and other openings of the body. A dragon-fly emerging and freeing itself from its cast skin is shown in Figure 50.

The skin of the animal when it steps out of its old casing is quite soft, and it remains so for a varying time, a few hours in the case of some insects, one to three days in a Cray-fish. During this period the animal grows. After a longer or shorter time during which the body remains soft and capable of extension the secretions of the skin commence to harden, and very soon the animal is again enveloped in a hard case which rapidly assumes the colour and appearance appropriate to the species in question.

This moulting of the skin in the Arthropoda is termed the ecdysis. It takes place at more or less regular times in each species, in the Cray-fish three or four times or even oftener during

the first year, the period of most active growth, later but once annually, usually about Midsummer; the Cockroach moults three times during the first year, after which the moults are annual, but it does not become adult till after the seventh ecdysis, when it is four years old.




FIG. 51. A Centipede, *Liethobius forficatus*. Dorsal aspect $\times 12$.

1. Antennae. 2. Poison claws, 5th pair of appendages. 3. 5th pair of appendages. 4. First pair of walking legs.

If we further examine our wood-louse, centipede, beetle, and spider, we shall notice at once that they are all, like the Annelids, bilaterally symmetrical; and it may as well be stated at once that with few exceptions this is true of the internal organs as well as of the exoskeleton. Another feature common to them all is that they possess jointed limbs or appendages. These may occur in all the segments, as in the wood-louse and centipede, or the limbs may be reduced in number and confined to definite regions of the body, as in the beetle and spider, but they always exist and are always jointed.

In the body of the centipede we can recognise but two regions (Fig. 51), a head and a trunk; the trunk consisting of a number of segments, the head apparently of a single rounded one, whose really composite nature is shown by the fact that it carries not one but several pairs of appendages.

The same may be said of the wood-louse (Fig. 79), though here the trunk is divisible into two parts by the character of the appendages. The anterior part or thorax, bears walking legs, the posterior part or abdomen, plate-like appendages which act as respiratory organs. In

neither of these creatures nor in the spider is there any constriction between the head and the trunk, that is to say there is no neck. In the beetle however there is a well-marked neck separating the head from the rest of the body. The three following segments in the beetle are again separated from those which come after, and

form what is called the thorax. This part bears the three pairs of walking limbs and the two pairs of wings. The hindermost segments, often ten in number in insects, constitute the abdomen; this part of the body is devoid of jointed limbs, though doubtless the ancestors of insects once possessed them on all the segments.




FIG. 52. A Male Cockchafer, *Melolontha vulgaris*, seen from above, slightly enlarged. After Vogt and Yung.

- | | | |
|--|--------------------------------|---|
| 1. Head, stretched forward. | 2. Prothorax. | 3. Mesothorax. |
| 4. Metathorax. | 5. Abdomen. | 6. Anterior wing (elytron) of right side, turned forward. |
| 7. Posterior wing of right side, expanded. | 8. Maxillary palps. | 9. Femur of third right leg. |
| 10. Tibia of third right leg. | 11. Tarsus of third right leg. | |

In the Insecta the abdomen may be constricted off from the thorax as it is in wasps (Fig. 95), or there may be no constriction. If we now turn to the spider we shall see that the division of the body into regions has gone along different lines, and we can only recognise two principal parts, a so-called cephalo-thorax or prosoma to which all the appendages are attached, and a stalked abdomen or fused meso- and meta-soma behind, devoid of obvious limbs, though certain little knobs at its hinder end, from the summit of which are spun out the silken threads used in making the web, have been shown to be rudimentary limbs. The abdomen has lost all trace of external segmentation. In the harvestmen—Phalangids—long-legged creatures resembling spiders, found only during the summer months, the constriction between the cephalo-thorax and abdomen is absent, but the latter is distinctly divided into segments (Fig. 103).

Thus in the Arthropods the body is divided into segments, and these segments are not all equal and alike, but they have become variously modified, and some of them have fused together, as in the

head of insects, and the abdomen of spiders, so that certain regions of the body may be distinguished, and this is one of the most characteristic features of the group.

In all Arthropoda certain of the appendages have lost the function of locomotion and are bent round and brought into connexion with the mouth. These mouth or oral appendages assist in catching and holding the food, and to some extent in biting and tearing it into small pieces. With the exception of the Arachnida, in which the arrangement




FIG. 53. The Garden Spider, *Epeira diadema*, sitting in the centre of its web. After Blanchard.

is somewhat different, and of *Peripatus*, which has only one pair of jaw-limbs, the first pair of oral appendages is termed the mandible, the second is the first maxilla, and the third the second maxilla; the last-named however in the Myriapoda retains the appearance of a walking leg, although too short to be used for walking. On the other hand in Crustacea a varying number of the appendages immediately succeeding the second maxilla are often turned forward and assist in the feeding. When this is the case they are termed maxillipedes (Figs. 54 and 56).

The modification which all these appendages undergo is similar in kind. The first stages of it are seen in the Arachnida. Here the first pair of appendages is always a pair of little claws placed in front of the mouth, the last joint shutting down on the next division of the limb like a knife-blade on the handle. After this pair come others, more leg-like, of which sometimes all, and in any case one pair have inwardly directed projections on their lowest joints termed gnathobases, so that when the limbs are brought together they act like a pair of nut-crackers (Fig. 55). Or to take another example, as we pass from the segment of the Cray-fish or of a *Gammarus* which bears the great claws forwards through the maxillae to the mandible we find the outer parts of the limb dwindling in size, and the basal projection growing bigger (Figs. 54 and 56). In the mandible only a minute rudiment of the other joints remains, and is called the palp. In the mandible of the insect even this has disappeared. Limbs which have undergone these characteristic changes are called gnathites (Gr. γνάθος, a jaw).

If we cut open the body of an Earthworm, a Starfish or a Vertebrate, we lay open a chamber in which the alimentary canal and many other organs apparently lie. This chamber is the coelom

or primary body cavity, which has no connexion with the blood system, though amoebocytes float in the fluid it contains. If we cut open the body of an Arthropod or of a Mollusc we also open up a chamber which may be spacious, as in an Insect or a Snail, or which may be much reduced and filled up by the various organs of the body and by muscles, as in a Cray-fish or a Mussel. This cavity however, as development shows, is not similar in its nature to the coelom of an Earthworm or a Vertebrate, and it further differs




FIG. 54. The mouth appendages of *Gammarus neglectus*. From Leuckart and Nitsche, after G. O. Sars.

1. The left mandible.
2. Its palp.
3. 1st maxilla of left side.
4. 2nd maxilla of left side.
5. Maxillipede of each side together forming an under lip.

in that it contains blood and is continuous with the cavity of the heart and large blood-vessels. A special name has been given to this cavity and it is termed the *Haemocoel* (blood-cavity). The presence of this secondary body cavity or *Haemocoel* instead of a *Coelom* introduces at once a peculiarity in the physiology of the circulation of the *Arthropoda* and *Molluscs*. Instead of the oxygen-bearing and food-carrying blood being conveyed all over the body in minute capillaries which ramify in every part of every tissue, in the animals in question the tissues are floating in and bathed by the blood, which surrounds the organs on all sides, and is kept in action by the contraction of a muscular tube—the heart—which opens freely into the body-cavity or *Haemocoel*.




FIG. 55. Pedipalp of *Tegenaria guyonii*, the large house-spider.

1. Coxa. 2. Maxilla, the gnathobase.
3. Trochanter. 4. Femur. 5. Patella.
6. Tibia. 7. Tarsus. 8. Palpal organ.

A true coelomic cavity (as is proved both by its origin and its relation to the excretory and reproductive organs) is however found in *Arthropods* in the cavities of the reproductive organs (Fig. 67) and in certain vesicles connected with the inner ends of some of the excretory organs, such as are found in the coxal glands of *Arachnids*. It is however obviously much reduced and takes a smaller part in the economy of these

animals than it does for instance in the *Annelida* or *Echinodermata*.

The skin of an *Arthropod* like that of an *Earthworm* includes not only the ectoderm, but a firm support for the same called the dermis. The dermis in this case is formed of well-developed connective tissue, and this tissue also forms an investment for every organ in the body, so that as Huxley remarks, if all the organs were dissolved away there would remain a complete cast of them in connective tissue. The same statement is true of *Mollusca* and *Vertebrata*: it is therefore important to obtain a clear idea what connective tissue is.

Its groundwork is a jelly-like secretion intervening between ectoderm and mesoderm, or mesoderm and endoderm, and therefore

to some extent comparable with the structureless lamella of *Hydra* or the jelly of a Medusa. Into this substance cells are budded from the adjacent layers, chiefly from the mesoderm. These cells add to the secretion, in which fibres soon make their appearance, crossing each other at various angles. These fibres are to be looked on as more or less solid precipitates. The cells are found often flattened against them and connected with neighbouring cells




FIG. 56. Left mouth appendages of *Astacus fluviatilis*, slightly magnified. The other appendages are shown in Fig. 60.

- I. Mandible. II. First maxilla. III. Second maxilla. IV. First maxilliped. V. Second maxilliped. VI. Third maxilliped. *en.* Endopodite. *ex.* Exopodite. *ep.* Epipodite. *ex & ep* in III form the Scaphognathite. *l.* Gills.


by delicate protoplasmic threads. The connective tissue round the ends of a muscle is modified to form tendon. Here the fibres all pursue a parallel course and great tensile strength is the result.

Observation of development shows that connective tissue, haemocoel, and blood-vessels all generally arise from the same

rudiment in the embryo, which may be compared to the jelly of Coelenterata. Blood is a portion of it where the jelly is fluid, the fibres are not developed and the amoebocytes remain mobile. In connective tissue the jelly becomes more solid, fibres are developed and the amoebocytes become stationary, being converted into the so-called connective-tissue corpuscles. It is interesting to note that under the abnormal circumstances of a wound the blood of many animals can develop fibres; this property causes what is known as clotting.

FIG. 57. *Asellus aquaticus*. Male viewed from above. From Leuckart and Nitsche, after G. O. Sars.

1. Anterior antennae. 2. Posterior antennae. 3—9. Thoracic limbs. 10. The last pair of abdominal limbs. 11. Testes with their efferent canals. The nervous system is shown black.



The muscular system of the Arthropoda is highly modified as compared with the primitive arrangement found in the Annelida. Instead of a continuous sheath of muscle there are special bundles of muscular fibres for the purpose

The Muscular System.

of moving the various hard parts on one another. Each joint of each limb, for instance, is provided with a pair of muscles which move it on the next joint. One of these is called the *flexor*, or bender, and the other the *extensor*, or straightener. Here as in *Annelida* the muscles are derived from epithelial cells, but all trace of this origin is lost in the adult. In the muscle-cell in many cases the nucleus has divided, giving rise to several nuclei which are surrounded by unmodified protoplasm. All the rest of the protoplasm is converted into fibrillae which consist of alternately dark and light stretches. Such muscles are said to be *striped*, and they have the power of contracting with much greater rapidity than muscles of the type found in *Annelida*. Muscles of the latter kind are called smooth muscles, and in *Arthropoda* exist in the wall of the gut and some other places.

The nervous system of the *Arthropoda* is built upon the same plan as that of the *Annelids*. It consists in its least modified form of a pair of closely approximated supra-oesophageal ganglia forming a brain situated in front of the mouth, in the head in *Insects*, and in the anterior part of the body in those *Arthropods* which have no distinct head. This brain supplies nerves to certain sense organs, and gives off two stout cords, one of which passes to the

left, and the other to the right of the oesophagus. These para-oesophageal (Gr. *παρά*, alongside) cords unite together behind the oesophagus, and where they unite they form a pair of sub-oesophageal ganglia which send nerves to some or all of the mouth appendages (Figs. 57 and 58). Behind this comes a chain of ganglia, normally one pair for each segment, which supply nerves to the organs and appendages of the segment in which they lie; each pair being




FIG. 58. View of nervous system of the Cockchafer, *Melolontha vulgaris*. After Vogt and Yung.

1. Cerebrum.
2. Sub-oesophageal ganglion.
3. 1st thoracic ganglion.
4. 2nd thoracic ganglion.
5. 3rd thoracic ganglion.
6. Fused abdominal ganglia.
7. Nerves to antennae.
8. Optic nerves.
9. Origin of sympathetic nerves.
10. Abdominal nerves, a pair to each segment, which split into an anterior and posterior branch.

connected with their successors by a double nerve-cord. These ganglia do not always remain distinct, but show a tendency to fuse together. Thus in the Cray-fish for instance the supra-oesophageal ganglion (Fig. 60) is shown by its development to be formed by the fusion of several pairs of ganglia; and the mandibles and both pairs of maxillae are supplied from a single ganglionic mass, the sub-oesophageal ganglion, which is the result of the fusion of three primitive ganglia; again in some Flies and in Spiders all the ganglia behind the mouth have fused into one large nervous mass situated in the thorax. This fusion takes place to a less extent in some beetles; for instance in the Cockchafer, *Melolontha vulgaris*, the thoracic ganglia remain distinct, but the abdominal have fused into one mass which has been drawn up into the thorax (6, Fig. 58).

The Crustacea are normally provided with two pairs of long feelers or antennae (though occasionally, as in the case of the Woodlouse, one pair may be entirely lost) and the Insects and Centipedes have a single pair, very conspicuous in some Butterflies and Beetles. These are organs of touch and frequently of smell; and in some cases, such as the Lobster, they also act as hearing organs. They are supplied with nerves from the brain. No such antennae exist in the Spiders or Mites, and this serves at once to distinguish the Arachnids from the other two classes.

The eyes of Arthropoda are peculiarly modified areas of the ectoderm. Over a certain area some of the ectoderm cells become modified into visual sense-cells.

Eyes.

In these there is a gelatinous rod developed from the outer end of the cell, and situated on the one side of it (Fig. 59 A); whilst from the base of the cell a nerve-fibre is developed. Usually several visual cells are pressed together in such a way that their rods cohere, and in this way a fluted spindle-shaped rod termed the rhabdome is built up (Fig. 59 E). Other cells of the visual area remain as supporting cells, being longer than the surrounding ectoderm cells but otherwise unmodified. Pigment—without which no vision can take place—is secreted either by these cells (4, Fig. 59 A) or by amoebocytes which have wandered out from the underlying dermis (8, Fig. 59 B). The cuticle covering the visual area becomes transparent and greatly thickened, and so acts as a condensing apparatus or lens. In the larger eyes each group of visual cells secreting a rhabdome is sharply marked off from the rest and covered by a separate lens or thickening of the cuticle. Such a group is termed a retinula: and as it is surrounded by a sheath of pigment,

it can only be affected by light coming from an object directly in front of it and propagated parallel to its axis. Hence to an Arthropod possessing an eye with many retinulae the outer world will be presented as a mosaic of light and shade, each retinula giving an impression depending on the intensity of light in the field of view directly in front of it. Such a mosaic is an image, and this image




FIG. 59.

- A. Vertical section through a lateral eye of a Scorpion, *Euscorpium italicus*. B. Diagram of retinula of a Scorpion's central eye. C. D. E. Transverse section of B taken at different levels. From Lankester and Bourne.

1. Cuticular lens. 2. Epidermis of the general body-surface. 3. Basement membrane. 4. Epidermal cells which contain pigment. 5. Nerve end cells with nuclei. 6. Rhabdome. 7. Fibres of optic nerve. 8. Pigment contained in connective tissue cells.

will be obviously the more detailed and definite the greater the number of retinulae. Hence in some Arthropods of acute vision, such as the common Fly, the eyes cover the greater part of the head. Eyes with numerous well-defined retinulae are known as compound eyes: and they usually present the appearance of numerous facets of hexagonal outline, owing to the fact that there is a lens corresponding to each retinula. In many cases the retinula




FIG. 60.

FIG. 60. Semi-diagrammatic view of internal organs, and some limbs of right side of a Male Crayfish, *Astacus fluviatilis* $\times 1$. Partly from Howes.

1. Antennule. 2. Antenna. 3. Mandible. 4. Mouth. 5. Scale or squama of antenna, exopodite. 6. Anus. 7. Telson. 8. Opening of vas deferens. 9. Chela. 10. 1st walking leg. 11. 2nd walking leg. 12. 3rd walking leg. 13. 4th walking leg. 14. 1st abdominal leg, modified. 15. 2nd abdominal leg, slightly modified. 16. 3rd abdominal leg. 17. 4th abdominal leg. 18. 5th abdominal leg. 19. 6th abdominal leg, forming with telson the swimming paddle. 20. Oesophagus. 21. Stomach. 22. Mesenteron, mid-gut. 23. Cervical groove. 24. Intestine. 25. Cerebral ganglion. 26. Para-oesophageal cords. 27. Ventral nerve-cord. 28. Eye. 29. Heart. 30. Sternal artery. 31. Supra-intestinal artery. 32. Sub-intestinal artery in abdomen. 33. Sub-intestinal artery in thorax. 34. Ophthalmic artery. 35. Antennary artery. 36. Hepatic artery. 37. Testis. 38. Vas deferens. 39. Internal skeleton. 40. Green gland. 41. Bladder. 42. External opening of green gland.

is depressed beneath the general surface, and the adjacent ectoderm cells meet above it. These cells secrete clear glassy rods which cohere to form a crystalline cone. This also happens in some simple eyes, such as the central eyes of the Spider; here the clear rods remain unconnected, and the whole upper layer of ectoderm cells is known as the vitreous layer. In the Cray-fish the compound eyes are carried on the ends of moveable eye-stalks; and in Spiders the eyes, which in these animals are always simple, are sometimes elevated on a little prominence, like a lighthouse, borne on the head and thorax. The number and position of the eyes in the Spiders are points of great use in identifying the various species.

As a rule the alimentary canal of the Arthropods is about as long as the body, so that it is straight; the Insects however form an exception to this rule, since in their case the canal is longer than the body, and consequently has to be coiled or twisted in order to tuck it away in the limited space. It was mentioned above that the chitinous exoskeleton of Arthropods is tucked in at both the mouth (stomodaeum or fore-gut) and anus (proctodaeum or hind-gut), and in many this lining extends so far in as to leave but a small part of the alimentary canal free from it. In some species the hinder end of the stomodaeum secretes deposits of chitin, as in the cockroach, or is hardened by calcareous deposits, as in the lobster or cray-fish, and thus teeth are formed which lie inside what has been termed the stomach or gizzard. When the moult or ecdysis of the shell takes place the linings of the fore- and hind-gut are also cast off.

The presence of chitin lining parts of the alimentary canal serves to discriminate those parts of the canal which are to be

looked on as merely parts of the skin—the stomodaeum and proctodaeum—from the true endoderm. The stomodaeum is usually divided into a narrow portion leading from the mouth, called the oesophagus (20, Fig. 60), and an expanded portion containing teeth, called the stomach (21, Fig. 60). The proctodaeum is usually a straight cylindrical tube, called the intestine (24, Fig. 60). The small piece intervening between them is called the Mid-gut or Mesenteron; it alone corresponds to the human gullet, stomach, and intestine, and to the whole alimentary canal of a worm behind the pharynx. In it digestion is carried on, and into it opens the so-called liver, one pair—rarely more—of glands consisting of great tufts of branching tubes lined by yellowish-brown cells. These secrete a fluid that assists in digestion. The food passes in part into these glands and some of it is there digested.

In most animals the heart is a muscular sac which opens into a
 Circulatory system of tubes with muscular walls, called arteries,
 apparatus. through which blood is driven to all parts of the body, finally passing into narrow tortuous passages, the so-called capillaries, whence it reaches the thin-walled veins through which it returns to the heart. Thus, excepting such fluid as soaks through the thin walls of the capillaries, the blood is entirely confined within definite channels which do not open into the body cavity. But in the Arthropods the state of things is different; the heart (Figs. 60 and 101), which lies in the middle line just below the skin of the back, opens by a series of slits called ostia into the body-cavity (haemocoel), and when the heart expands the blood which is in the body cavity enters these slits, but cannot pass out again through them when the heart contracts, as each slit has a valvular arrangement which prevents this. When the heart contracts the blood is therefore forced forwards and leaves the heart by a vessel—the aorta—, or by vessels with various names, which sooner or later open again into the haemocoel, and so the circuit is complete. The part of the haemocoel in which the heart lies and into which the ostia open is called the pericardium, and is separated from the remainder of the haemocoel by a horizontal septum called the pericardial septum, in which however there are perforations. The pericardium of Arthropoda thus contains blood, and is consequently widely different from the pericardium of Mollusca or Vertebrata, which is in both cases part of the coelom.

In those Arthropods which have a localised respiratory system, and where the blood takes part in respiration, there is a more

definite course for the blood than that sketched above. The extent to which blood-vessels with definite walls are developed varies in the different members of the group; thus the Scorpion and King-crab have a much more specialized circulatory system than




FIG. 61.

- A. Left side of a Larva of the Prawn, *Penaeus*, to show the origin of the gills. Slightly magnified. From Claus. L₁ to L₅. The first to fifth ambulatory limbs. M₁ to M₃. The first to third maxillipeds. 1a, 2a, 3a, 7a. Podobranchs. 1b, 5b. Anterior arthrobranchs. 1c, 2c, 7c. Posterior arthrobranchs. 1d, 5d, 7d. Pleurobranchs. Of these rudiments of gills only nineteen develop. B. Left side of a fully-grown Prawn, *Penaeus semiculcatus*, to show fully-grown gills. Slightly magnified. 8. Exopodite of second maxilla, which flaps to and fro and so causes a current over the gills. 9. Exopodite of fourth ambulatory limb.

have the Spider and Mites. The blood is very rarely red, but is usually slightly tinged with a greenish or bluish colour.

In the lower and more simply organized Crustacea, such as the water-fleas, there are no special breathing organs, but the blood is able to absorb its oxygen and give off its

Respiratory
apparatus.

carbonic acid as it courses under the thin skin. But in the larger and more complicated Crustacea, such as the shrimp and lobster, a special apparatus is present in the form of gills. These gills are thin-walled extensions of the skin which project from the surface of the body near the base of the limb or on the side of the thorax, into the surrounding water; inside them the blood flows to and fro,




Fig. 62. View of male Cockchafer, *Melolontha vulgaris*, from which the dorsal integument is

moved to show the internal organs. After Vogt and Yung.

1. Cerebral ganglion. 2. 1st thoracic ganglion. 3. 2nd and 3rd thoracic ganglia fused.
4. Fused abdominal ganglia. 5. Oesophagus. 6. Mid-gut.
7. Small intestine. 8. Colon. 9. Rectum. 10. Malpighian tubules, brown portion, with caeca. 11. Malpighian tubules, distal end. 12. Trachea with vesicles. 13. Testes, opening into coiled vasa deferentia. 14. Penis. 15. Single vas deferens.

sides of the cephalo-thorax, as the fused head and thorax is called. There are twenty on each side, and they are protected from injury by a broad flap called the branchiostegite, which has grown down from the back and formed a chamber between itself and the side of the body; in this cavity the gills lie concealed. At the front end of this chamber lies a small paddle or scaphognathite, a part of the second maxilla (Fig. 56 III), which throws out the water from the front end of the gill chamber two or three times every second and thus keeps a current of fresh water passing into this space behind. This may be easily demonstrated by adding some coloured granules, such as carmine or indian-ink, to the water in which lobsters are living.

Many of the Arthropoda breathe air, and their respiratory mechanism is very peculiar and unlike anything else in the animal kingdom. Instead of the blood being taken to a gill or lung and

and a current of water washes them on the outside. The gills are classified according to their point of origin, being termed podobranchs (1a, Fig. 61) when they arise from the proximal joint of the limb, arthrobranchs (1b, Fig. 61) when they are outgrowths of the thin membrane forming the articulation between the appendages and the body, and pleurobranchs (1d, Fig. 61) when they arise from the side of the body above the insertion of the appendage. In order to increase the surface of the gill, it is usually much folded or produced into a number of small processes.

there purified and then driven with its oxygen all over the body to every organ and tissue, the air itself is introduced into the body and is carried by minute tubules to every tissue and cell (12, Fig. 62). Thus in these animals the blood has lost one of its main functions—the respiratory—and remains simply a nutritive fluid. The fine tubules through which the air travels are termed tracheae (Gr. *τραχὺς*, *τραχέια*, rough, corrugated), and the three groups of Myriapods, Arachnids, and Insects are sometimes collectively termed the Tracheata, in contradistinction to the Crustacea, though there is reason to believe that the tracheae in Arachnida have arisen in a different way to those in the other two groups. The tracheae open to the exterior at certain definitely arranged pores termed stigmata, usually found at the sides of the body. From these pores the tracheae pass inwards, dividing into smaller and smaller branches which ultimately end in the various tissues. Each trachea is really a pouch of skin tucked into the body, and hence is lined by chitin continuous with the exoskeleton covering the rest of the body. The tracheae are kept from collapsing by a thickened ridge of the chitinous lining which coils round inside the tube like a spiral of wire inside a water hose. Oxygen is thus absorbed by all the parts of the body directly from the air, and not from the blood. This peculiar mode of respiration has had a profound influence on Insect structure.




FIG. 63. Horizontal section through the abdomen of a Spider, *Argyroneta*. After MacLeod. Magnified.

1. Opening to exterior, tracheal stigma.
2. Terminal tracheae. 3. Lateral tracheae. 4. Lung books.

A very primitive Arachnid, *Limulus*, the King-crab, which lives in the sea, breathes by means of what are called gill-books; these are piles of delicate leaf-like plates placed one over the other like the leaves of a book, and attached to the posterior surface of the appendages of the hinder part of the body, which are flattened (Figs. 64 and 107). When these plates are moved up and down the leaves of the gill-books fly apart and the water gets in between them, and oxygen passes from it into the blood which circulates in

the substance of the leaves. In the Scorpions, which are geologically the oldest and most primitive group of the Arachnids that live on




FIG. 64. Section through the operculum and gills of a King-crab, *Limulus*. \times about 16. The normal number of gills in a *Limulus* is five, the section from which this drawing is made showed only four.

1. Operculum. 2. 2nd gill-book. 3. Muscle which moves gills up and down.
4. Blood-vessels. 5. Muscle which raises the operculum.




FIG. 65. Longitudinal section through the lung book of a Spider. Magnified. From MacLeod.

1. Opening to the exterior or stigma.
2. Free edge of the pulmonary leaves.
3. Space in which the air circulates.
4. Space in which the blood circulates.

land, the arrangement is the same, only the gill-books and the plate-like appendages which carry them are smaller, and the books are packed away into pits on the under side of the body, whilst the highly modified appendages extend horizontally below so as to floor in the pits, leaving only a slit, through which air enters. This arrangement prevents the gill-books—now called lung-books—from drying up. In other Arachnids the gill or lung-book has been lost, and only the pit remains, and this is enlarged and burrows into the body, forming tracheae which may assume all the appearance of Insect tracheae. The Spiders form an interesting link, for some

of their lung-books have been thus replaced by tracheae and others remain as in the Scorpion (Fig. 63).

The excretion of the nitrogenous products of katabolism from an animal's body is a function of fundamental importance.

Nitrogenous excretion. We have seen in the Earthworm that this is performed in a series of little tubes called nephridia, one pair in each segment, and the same is roughly true of Peripatus. But in the other Arthropods, with few exceptions, where the primitive segmentation is much changed and modified, such structures do not exist in each segment, but a single pair of excretory organs suffices for the whole body. In the simpler Crustacea each of these is a tube with glandular walls (i.e. walls composed of cells which are filled with excreta), and each tube opens at the base of the second maxilla, on each side. They are termed the maxillary or shell-glands (Figs. 69 and 70). In the larger and more complex forms corresponding organs open on the second antenna (40, Fig. 60). Here the organ consists of a network of parallel glandular tubes joining each other at intervals and opening into a thin bladder which communicates with the outside. The whole is called the antennary, or green-gland. In a few cases both antennary and maxillary glands co-exist, at least for some time of the animal's life. It must not be forgotten, however, that the chitinous or calcareous exoskeleton is of the nature of an excretion, and an excretion which is not simply expelled from the body but is of use to the animal excreting.

A typical nephridium has been already defined as a tube which opens at its inner end into the coelom. Since the excretory glands of Crustacea have in some cases at their inner ends thin-walled dilatations which are by most zoologists regarded as portions of the true coelom, the Arthropoda may be said to possess modified nephridia.

In Insects and Myriapods the excretory system, like the breathing apparatus, is peculiar; the waste nitrogenous matter is taken up by certain tubules called Malpighian tubules, after a celebrated Italian anatomist named Malpighi (Figs. 62 and 83). These lie in the body cavity surrounded by the blood; they do not open directly into the exterior but into the front end of the proctodaeum, and through this their excreta leave the body.

In the Arachnids the excretory apparatus is of two kinds, which may coexist. In Scorpions and Spiders there are Malpighian tubules superficially resembling those of Insects, only shorter and

less numerous, but they open into the endodermic tube or mesenteron and are therefore endodermic, not ectodermic structures. There are also organs which, like the green- and shell-glands of the Crustacea, are to be regarded as modified nephridia, which open at the one end into a space which is a remnant of the coelom and at the other to the exterior; they are termed coxal glands, since they lie mainly in the coxal or proximal joints of the legs.




FIG. 66.




FIG. 67.

FIG. 66. Male reproductive organs of *Astacus fluviatilis* \times about $2\frac{1}{2}$. From Howes. 1. Right anterior lobe of testis. 2. Median posterior lobe of testis. 3. Vas deferens. 4. External opening of vas deferens. 5. Right fourth ambulatory leg in which the vas deferens opens.

FIG. 67. Female reproductive organs of *Astacus fluviatilis* \times about 2. From Howes. 1. Right oviduct. The left oviduct is shown partly opened. 2. Right lobe of ovary. 3. Left lobe of ovary with the upper half removed to show the cavity of ovary or coelom into which the ripe ova drop. 4. External opening of oviduct. 5. Right second ambulatory leg on which the oviduct opens.

With few exceptions Arthropods are bisexual. The reproductive organs are comparatively simple. Both the ovary (Fig. 67) and the testis (Fig. 66) are continuous with their ducts, which, in the Crustacea, Arachnids, and some Myriapods, usually open to the exterior on the under surface of the middle region of the body, and at the posterior end of the body in Insects and one division of the Myriapods. The space

Reproductive
Organs.

inside these glands, lined by the reproductive cells, is regarded as part of the coelomic cavity.

The foregoing account of the Arthropoda enables us to give the following definition of the group:—The Arthropods are bilateral animals with segmented bodies. The segments are not all alike, and frequently fuse one with another; some at least bear a pair of jointed limbs, of which those in the region of the mouth are modified to catch and bite the food. The nervous system consists of a supra-oesophageal mass or brain, a nervous ring round the oesophagus, and a ventral chain of ganglia sometimes fused into a single mass. A heart is usually present above the alimentary canal, and blood enters it through a series of paired valvular slits from the haemocoel or blood-cavity. The sexes are usually distinct. The coelom is much reduced.

This definition is in the main true of all Arthropods, whether insect, spider, centipede, or crab. We must now consider however how the various subdivisions of this great group may be distinguished one from another.

Class I. CRUSTACEA.

The Crustacea are with few exceptions, such as the wood-louse, inhabitants of the water, and they breathe either through the general surface of the body or by means of gills. They have as a rule two pairs of antennae, and these as well as their other jointed limbs are typically biramous, that is they consist of a basal portion bearing two prolongations. They have at least three pairs of appendages converted into jaws.

The Crustacea are usually divided into two groups, the Entomostraca (Gr. *ἐντομος*, cut in pieces; *ὄστρακον*, a shell) and the Malacostraca (Gr. *μαλακός*, supple); and each of these is again divided into four and three Orders respectively.

Sub-class A. ENTOMOSTRACA.

This group may be regarded as a lumber-room for all Crustacea which are not included in the well-defined division Malacostraca, and the only character which can be attributed to all the members is that of not possessing the marks of Malacostraca.

For the most part they are small Crustacea of simple structure.

The number of their segments varies within wide limits ; some Ostracoda having only seven pairs of limbs, whilst in *Apus* there are sixty-eight pairs. The dorsal part of their head has, in many cases, grown backwards and downwards like a mantle to form a large hood or shell, termed the carapace, which may cover a large part of the body, and in some cases this becomes divided into two lateral halves hinged together like a mussel's shell. In many descriptions of Entomostraca the words "thorax" and "abdomen" are used to describe regions of the body. Such terms are in strictness only applicable to the higher Crustacea, where the trunk is sharply differentiated into two regions distinguished by the character of their appendages. Amongst the Entomostraca however the appendages of the trunk form a uniform series : often it is true the last segments are devoid of appendages, and to these the term abdomen (16, Fig. 68) is often applied, but to us this seems an unjustifiable and misleading use of a term which has an exact significance only amongst Malacostraca.

Entomostraca have no internal teeth in their stomach. As a rule the young are not like their parents but are larvae of a special kind called Nauplii; these after a number of ecdyses, during which the number of segments increases, grow up into adults.

The Nauplius possesses an oval, unsegmented body, a median, simple eye, three pairs of appendages, and a large upper lip. The first pair of limbs representing the first antennae of the adult are simple and unjointed, the other two pairs have a basal piece and two branches. The inner branch of one or both pairs has a hook for masticatory purposes. These two pairs of appendages become the second antennae and mandibles of the adult ; both are at first placed behind the mouth.

The Entomostraca consists of the following Orders :—

Order I. Phyllopoda.

As the name implies the Phyllopoda (Gr. φύλλον, a leaf ; πούς, a foot) are characterized by possessing flattened leaf-like swimming limbs. Of these there are at least four pairs, but there may be many more. The larger Phyllopods are not uncommon in Britain ; one genus, *Artemia*, taken at Lymington, flourishes in salt-pans in which the salt is so concentrated as to be fatal to other animals. *Branchipus* (Fig. 68) is devoid of the carapace, and has an elongated heart extending throughout the body. It occurs in stagnant water, and has been recorded in several localities in the south of England.

It is often found in the vicinity of Montreal, in Canada, in the pools of rain water which have accumulated in disused quarries. *Apus* is another of the larger forms which was formerly found in Britain but has not been met with for some years and is possibly extinct in this country. It has a large carapace, and its flattened leaf-like appendages are regarded as primitive types of the Crustacean limb, from which all the numerous modifications of the higher forms may be derived. Of these eleven pairs are situated in front of the genital opening and are often termed "thoracic," one pair being attached to each of the pre-genital segments of the trunk. Behind the genital opening there are fifty-two so-called "abdominal" pairs of legs, of which several pairs are attached to each post-genital segment except the last two or three.

The genus *Daphnia*, common in ponds and ditches, both in England and America, differs from the foregoing in having fewer segments and a very large bivalved carapace which completely encloses the body. The first antennae, or, as they are generally called, the antennules, are small and simple, but the second antennae are very large and forked and project from the shell, and by their lashing movement carry the animal through the water (Figs. 69 and 70). The carapace is to a certain extent transparent, and through it the beating of the heart, the circulation of the blood, and the movements of the thoracic leaf-like appendages may be made out. Within the substance of each valve of the carapace a coiled glandular tube may be detected ; this is the shell-




FIG. 68. Dorsal view of female, *Branchipus* sp. found in a pond in Sussex \times about 10.

1. Antennae. 2. Head. 3. Eyes.
4-14. The eleven "thoracic" limbs. 15. The caudal forks.
16. The fifth "abdominal" segment.

gland or typical excretory organ of the Entomostraca which opens on to the exterior in the region of the second maxilla. The male *Daphnia* (Fig. 69) is usually smaller than the female (Fig. 70), and is certainly very much rarer. The females lay two kinds of




FIG. 69.

FIG. 70.

FIG. 69. Side view of male *Daphnia similis*. Highly magnified. After Claus. 1. Antennules. 2. Antennae. 3. Testis. 4. Vas deferens. 5. Intestine. 8. Liver, consisting of a single pouch. 9. Heart. 11. Shell or maxillary gland.

FIG. 70. Side view of female of *Daphnia similis*, magnified to the same extent as Fig. 69. After Claus. 1. Antennules. 2. Antennae. 3. 1st pair of legs. 4. 2nd pair of legs. 5. 3rd pair of legs. 6. 4th pair of legs. 7. 5th pair of legs. 8. Hepatic diverticulum. 9. Heart. 10. Brood pouch. 11. Shell or maxillary gland. Th.3 and Th.5. 3rd and 5th thoracic segments. A.1, A.2, A.3. 1st to 3rd abdominal segments.

eggs, (i) summer eggs, which develop in the space intervening between the dorsal side of the body and the shell which acts as a brood-pouch, and (ii) winter eggs, which are larger and become surrounded by a special modification of the brood-pouch called the ephippium. Sheltered by this case the eggs lie at the bottom of the pond, etc., throughout the winter, when the severity of the weather has killed the adults, and with returning spring a young *Daphnia* hatches out from each winter egg to continue the cycle of life.

The Phyllopoda are divided into two Sub-orders, viz. :—

Sub-order 1. **Cladocera.**

Short-bodied Phyllopoda with a dorsal brood-pouch and long second antennae.

Ex. Daphnia.

ο

Sub-order 2. **Branchipoda.**

Long-bodied forms devoid of a brood-pouch and not using the second antennae as swimming organs.

Ex. Apus, Artemia, Branchipus.

The Branchipoda live in fresh-water and as a rule in the standing water of pools and ponds; they are more rarely found in brackish or salt water. They swim actively about by means of the vibrations of their flattened limbs. As a rule aquatic animals swim with the upper surface towards the surface of the water, but the Branchipoda seem very indifferent to this rule, and are quite frequently seen swimming upside down. The Cladocera almost invariably swim upside down, since otherwise the eggs might drop out of the brood-pouch.

Order II. **Ostracoda.**

This Order (Gr. *ὀστρακώδης*, shell-like) contains a great number of species which do not differ greatly from one another. In form they resemble *Daphnia*, but the head does not protrude from between the valves of the carapace, and some of the internal organs of the body, the ovary or testis and branches of the liver, are prolonged into the valves of the carapace. This latter is a very characteristic structure, consisting, like the shell of the Mussel, of two valves. It opens by an elastic ligament which tends to pull

the valves apart, and it closes by the contraction of a muscle which runs across the body from one valve to another. The whole body is included in the carapace, antennae and all.

Ostracoda have fewer appendages than any other group of Crustacea; besides the antennules, antennae, mandibles, and two pairs of maxillae, they possess only two pairs of limbs, and these are stout and cylindrical, in marked contrast to the appendages of the Phyllopoda. The hinder part of the body is rudimentary.




FIG. 71. Lateral view of *Cypris canidida*. After Zenker.

- | | |
|----------------------|----------------------|
| 1. Antennules. | 2. Antennae. |
| 3. Mandibles. | 4. 1st maxillae. |
| 5. 2nd maxillae. | 6. 1st pair of legs. |
| 7. 2nd pair of legs. | 8. Tail. |
| | 9. Eye. |

Both pairs of antennae are jointed, unbranched appendages, and are used in swimming, another most important distinction from *Daphnia* and its allies.

The males differ from the females, which either (*Cypris*) lay their eggs in water-plants or (*Cypridina*) carry them about within their shells. The majority of species are found in the sea, but others occur in fresh-water. They are flesh eaters, and as they exist in great numbers they fulfil the important duty of scavenging on a small scale, and prevent the accumulation of dead organic matter in the water.

Order III. Copepoda.

This Order (Gr. *κώπη*, oar; *πούς*, foot) is also a large one and its free swimming members exhibit a very characteristic structure and appearance. The body is of an elongated pear shape, and consists of a large round head and a tapering trunk of comparatively few segments. The carapace so characteristic of the preceding order is entirely absent. The head bears a single median eye in front, the lateral compound eyes so conspicuous in most Crustacea being absent. Attached to the head are five pairs of appendages, two pairs of unbranched antennae, a pair of mandibles, and two pairs of maxillae. The first thoracic limb (maxilliped) is also borne on the head, near the second maxilla (Fig. 72). The head is not separated from the trunk by any constriction.

masked and difficult to recognise. When both forks are conspicuously developed the limb is said to be biramous. The four or five last segments of the Copepod's body bear no appendages.




FIG. 73. Dorsal view of female *Cyclops* sp. Magnified. Partly after Hartog.

2. Antenna. 1. Antennules. 3. Eye. 4. Ovary. 5. Uterus.
 6. Oviduct. 7. Spermatheca or pouch for receiving the spermatozoa
 of the male. 8. Egg-sacs. 9. Caudal forks. 10. Position of anus.
 11. Compound segment, consisting of the last thoracic (bearing the genital
 opening) and the first abdominal.

The last is produced into two processes, forming a caudal- or tail-fork.

The sexes in the free-living species are not markedly different, but if we examine specimens of such a genus as *Cyclops*, which is common in our fresh-water pools, we shall find that in the breeding season the female carries about with her two egg-sacs (Fig. 73). These are attached to her body just behind the last pair of appendages and project freely at the side. Each egg-sac may contain four or five dozen eggs, which are glued together by a cement-substance. Such egg-sacs are very characteristic of the Copepoda and are even found in the parasitic members of the order. Most of the latter live on fish, and some have acquired the name of "fish-lice." Their mouth appendages have lost their biting function, and have become adapted for piercing the tissues of the host on which they live. Their segmentation is suppressed and their appendages are reduced, and the body has grown out into all sorts of curious processes. The male is often much smaller than the female, and as a rule retains more crustacean characters than she does. Occasionally they are found on the skin of a fish, but more often they occur in the mouth and on the gills, sometimes half and sometimes almost wholly embedded in the flesh of their host.

Order IV. Cirripedia.

Some of the Copepods have become so modified by their parasitic habits, that unless we were able to trace their development, including the larval forms through which they pass before becoming adult, we should have difficulty in assigning them to their proper place amongst the Crustacea. A somewhat similar modification occurs in the Cirripedia (Lat. *cirrus*, a tuft of hair; *pes*, a foot) and is associated with a fixed or sessile habit of life. After passing through a variety of free-swimming larval forms, the animal comes to rest and attaches itself by the anterior end of the body to a stone or rock, the bottom of a ship, or some other object submerged in the sea, and becomes adult.

Like that of the Ostracods the body of a Cirripede is enclosed in a carapace consisting of two valve-like folds which have grown out from the region of the head, but these are usually strengthened by five calcareous plates, a right and left scutum, a right and left tergum, and a median carina, and in *Balanus*, the common acorn-barnacle of our sea-shores, a further armour of triangular plates develops in an additional outer fold of skin which encircles

the body. In *Lepas*, the barnacle usually found in clusters on the bottom of ships and often seriously impeding their progress, this ring is absent, but the anterior end of the head bearing the first antennae at its end has grown out into a long stalk which lodges




FIG. 74. A view of *Lepas anatifera*, cut open longitudinally to show the disposition of the organs. From Leuckart and Nitsche, partly after Claus.

1. Stalk. 2. Carina. 3. Tergum. 4. Scutum. 5. 1st antennae.
6. Mandible with "palp" in front. 7. 1st maxilla. 8. 2nd maxilla.
9. The six pairs of biramous thoracic limbs. 10. Labrum. 11. Mouth.
12. Oesophagus. 13. Liver. 14. Intestine. 15. Anus. 16. Ovary.
17. Oviduct. 18. Testes. 19. Vas deferens. 20. Penis.
21. Cement gland and duct. 22. Adductor scutorum muscle, which closes the carapace.
23. Mantle cavity, i.e. the space intervening between the carapace and the body.

some of the internal organs of the body. The second antennae though present in the larvae are lost in the adult. The rest of the body is enclosed within the carapace. Around the mouth are a pair of mandibles and two pairs of maxillae, and the thorax carries six

pairs of biramous many-jointed limbs beset with numerous hair-like spines, the lashing of which kicks food particles towards the mouth (Fig. 74). These limbs are slender and flexible and thus differ from the corresponding limbs of Copepods.

Like some Copepods the Cirripedes are without a heart, and the existence of special respiratory organs is doubtful. Unlike other Crustacea they are, as a rule, hermaphrodite, the male and female reproductive organs being united in one individual. A few species are parasitic, chiefly on other Crustacea, and these have reached a very extreme stage of degeneration.

Sub-class B. MALACOSTRACA.

The second of the two large groups into which the Crustacea are divided contains most of the more familiar forms, such as Crabs, Lobsters, Shrimps, Wood-lice, etc. For the most part the Malacostraca are larger than the Entomostraca, and the number of their segments is a fixed one. With the exception of the first Order, Leptostraca, which is really a connecting-link between true Malacostraca and the lower forms, this number is nineteen, and there are nineteen pairs of appendages. One of the most marked characters in the Malacostraca is the differentiation of the trunk into two distinct regions, the thorax and the abdomen. It is true, as is mentioned above, that many authors speak of an abdomen in the Entomostraca, but by this they mean, with a few exceptions, the hindermost segments which are devoid of limbs. In any Entomostracan if we examine the series of limbs behind the jaws we shall find that they constitute a continuous series without any sudden change in their character. In a Malacostracan, on the other hand, we find an abrupt change at one point in the character of the limbs. The hinder limbs or swimmerets (pleopods) are markedly different from the front limbs, for whereas in the swimmeret both forks of the limb, endopodite and exopodite, are equally developed, in the last five limbs or the thorax (peraeopods) the endopodite is large and the exopodite is small or absent. It is this difference in character which defines the abdomen.

Although the division between the head and thorax is not always apparent, as a rule, we may assign five segments to the head, eight to the thorax, and six to the abdomen, which ends in an unsegmented flap, called the telson. The reason for this want of a

definite boundary between head and thorax in the Malacostraca, is that the carapace, which as we have seen is an outgrowth of the head, has become fused with the dorsal surface of the thoracic segments, whilst at the sides it forms freely projecting flaps, which since they cover the gills are known as branchiostegites (Gr. *στέγω*, to cover).

The excretory organ of the Malacostraca opens at the base of the second antennae and not as in the Entomostraca, on the second maxilla. As a rule the typical larva—the Nauplius—of the last-named group is not present in the life-history of the Malacostraca, which may hatch out from the egg in a practically adult condition, or may pass through several larval stages, the first of which is the Zoea, a larva with many appendages, possessing eyes, and in all ways more differentiated than the Nauplius.

Order I. **Leptostraca.**

The order Leptostraca (Gr. *λεπτός*, slight, small) contains but three genera, which are interesting because they form an intermediate stage between the Malacostraca and the Entomostraca. Like many of the latter they are provided with a bi-valve carapace which, unlike that of all other Malacostraca, is not fused with the thoracic segments. Behind the six appendage-bearing segments of the abdomen there come two more segments without limbs, and the hindermost bears two diverging filaments constituting a “caudal fork,” such as is commonly found amongst the Entomostraca. The thoracic limbs are flattened and leaf-like, as in *Apus*, but the mandible bears a three-jointed feeler or palp, and the eyes are stalked,—both, on the whole, Malacostracan characters. The excretory organ opens on the second antenna, but in the larva the shell-gland or maxillary excretory organ is found and traces of it exist in the adult.

The order is marine, and very widely distributed throughout the ocean. Its members are capable of living and thriving in very foul water, so foul as to be fatal to most other animals. *Nebalia* is the best known genus.

Order II. **Thoracostraca.**

The Thoracostraca (Gr. *θώραξ*, a breast-plate) form a large group and contain many very different forms. They are placed together because the carapace has become fused with several of the

thoracic segments, so as to form a region known as the cephalothorax, the exoskeleton covering which is not jointed and is not bivalved as in *Nebalia*. The eyes of the Thoracostraca are compound and almost always are borne on moveable stalks. The order is divided in four sub-orders.

Sub-order 1. Schizopoda.

This order is the lowest of the Thoracostraca. The name is suggested by the circumstance that all the eight pairs of thoracic limbs are biramous; the first and sometimes the second pair are reduced in size and provided with gnathobases; they assist the mandibles and maxillae and hence are termed maxillipedes. It will occur to most observers that the thoracic feet of the Schizopod resemble the ordinary form of swimmeret or abdominal appendages




FIG. 75. *Nyctiphanes norvegica*. Slightly magnified. From Watasé. The black dots indicate the phosphorescent organs. The gills are seen between the cephalothoracic and the abdominal appendages.

in the more familiar Lobster or Crayfish. This is so; the swimmerets of a Schizopod are however sharply distinguished from the thoracic limbs by their smaller size. It appears probable that the first step in the evolution of an abdomen was the reduction in size of the appendages, so as to transform the hinder part of the body into a powerful swimming fin, and many Schizopods only use the abdomen in this way, since most of the swimmerets are very small and appear to be practically functionless. The last one however is broad and assists the tail in its vigorous strokes. Some Schizopods have a series of phosphorescent organs which under certain conditions emit a pale but very perceptible light

like that of a glow-worm. This light seems to be controlled by the animal but its use is not very clear.

There are very interesting differences amongst the genera composing the Schizopoda. The genus *Euphausia* for instance has long feathery gills attached to the basal joints of the thoracic legs, and the eggs are not borne about by the mother but hatch out into Nauplii, which pass through a series of metamorphoses before becoming adult. In *Mysis* on the other hand the gills are few and simple and the eggs are borne under the thorax on flat plates termed oostegites, which project inwards from the hinder thoracic appendages. In these two genera we see the beginning of two tendencies which have led the descendants of primitive Schizopoda to differentiate themselves in two different directions. One group have taken to carrying the embryos about until they are fully developed; at the same time the gills are reduced and the carapace, which is essentially a gill-cover, tends to disappear. This group includes the Stomatopoda, Cumaceae and Arthrostraca.

In the other group the gills and carapace are retained, and though the eggs are for a time carried about attached to the swimmerets, the young one passes through a larval stage before becoming adult. This group includes the Decapoda.

Sub-order 2. Decapoda.

The Decapoda (Gr. δέκα, ten) derive their name from the circumstance that the first three pairs of thoracic appendages have become maxillipedes, that is to say have been modified so as to assist in mastication, leaving five pairs of large conspicuous limbs, which have lost all trace of an exopodite, for prehension and locomotion.

This group includes the lobsters, cray-fish, shrimps, prawns, hermit-crabs and crabs, etc. In the division of the crabs, the *Brachyura* (Gr. βραχύς, short; οὐρά, tail), the abdomen is reduced in size and turned up and closely applied to the under surface of the thorax, except when the animal is "in berry" and then the masses of eggs force the abdomen away from the thorax. As a rule crabs are broader than they are long, and the breadth is partly due to the large gill chambers on each side of the body. The gills are really outside the body, but are in a special chamber bounded by the branchiostegite, or free edge of the carapace.

In the lobsters, shrimps, etc., which form the division *Macrura* (Gr. μακρός, long; οὐρά, tail), the tail is relatively large and is not

folded up against the thorax. Some species—the hermit-crabs—shelter themselves in the empty shells of molluscs. In these cases the abdomen does not develop a hard covering as the animal is




FIG. 76. *Carcinus maenas*, ventral aspect. The abdomen or tail is bent back. A little less than life-size.
1. Antenna. 2. Antennules. 3. Left eye reclining in its socket. 4. Right eye, erected.
5. Right 3rd maxilliped in natural, closed condition, its fellow is bent back to expose 6. 6. The
mandible. 7. 1st maxilliped. 8. 2nd maxilliped. 9. Chelae or great claws. 10, 11, 12 and
13. 1st, 2nd, 3rd and 4th ambulatory limbs. 14 and 15. 1st and 2nd abdominal legs which are
modified in connexion with reproduction. 16. Position of anus.

sufficiently protected by its lodging. It remains soft, and acquires a spiral twist as it moulds itself to the interior of its borrowed shell.

Some Decapods have left the sea and taken to live on land, and this has in some cases involved a change of structure, the gills which breathe water being supplemented by the soft vascular lining to the gill-cavity covered by the branchiostegite which, like a lung, breathes air.

The group is for the most part marine, though the well-known fresh-water cray-fishes, *Astacus* in Europe and *Cambarus* in North America, form striking exceptions.

Sub-order 3. Stomatopoda.

The Stomatopoda (Gr. *στόμα*, a mouth) are a sharply defined group with few genera, and must be regarded as an offshoot from the primitive Schizopoda peculiarly specialized. The members attain a considerable size, some eight inches or more in length. The carapace is small and only covers the anterior five thoracic segments; the appendages of these segments are turned forward towards the mouth and take part in feeding, and so are termed maxillipeds. They end in a claw, the last joint shutting down on the penultimate one like a knife blade into its handle. They are thus very different from the maxillipeds of Schizopoda or Decapoda, which are really limbs on the way to become jaws, and have developed gnathobases. The maxillipeds of Stomatopoda are grasping, not chewing organs, and have undergone the same modification as the great claw of the lobster, which might just as reasonably be called a maxilliped. A fertile source of confusion in the study of the Arthropoda is the use of names like maxillipede, thorax, abdomen, etc., to denote different things in different groups. The last three thoracic limbs are for walking, they are very feeble and retain a rudiment of the outer fork or exopodite. The abdomen is large and bears six pairs of flattened swimming limbs, each of which carries a gill in its outer branch.

Unlike most other Crustacea, *Squilla* and the other members of the group do not carry their eggs about with them, but lay them in the burrows in which they live, and by sitting over them and moving their abdominal limbs they keep up a current of water which aerates the eggs. They are exclusively marine, and live buried in the sand or hidden in crevices of the rock. They move actively and are difficult to catch.

Sub-order 4. Cumacea.

The members of the sub-order Cumacea (Gr. κύμα, a wave, or billow) are mostly small, they live in the sea on sandy bottoms at considerable depths, but come to the surface at night. They are especially interesting because to a certain extent they are intermediate in character between the Thoracostraca and the Arthrostraca. Thus their paired eyes are not stalked and are sometimes fused together to form a single eye; the carapace is reduced so as to leave several segments of the thorax uncovered (Fig. 77) and on some of the thoracic legs there is a small exopodite. They




FIG. 77. Female *Diastylis stygia* $\times 6$. After Sars. The carapace is represented as transparent to show the gill.

1. Carapace. 2. First antenna. 3. First leg. 4. Gill borne on first maxilliped. 5, 6, 7 and 8, second to fifth leg. 9. Free part of thorax. 10. Abdomen. 11. Appendage of the last segment of the abdomen.

have a single pair of gills borne by the first thoracic limb. In the female the abdomen, which is long, has lost all the limbs except the last pair.

Order III. Arthrostraca.

The members of the Arthrostraca (Gr. ἄρθρον, a joint; ὄστρακον, a shell) have sessile eyes, i.e. without stalks. The carapace, which in most of the above-mentioned groups covers the segments of the thorax, has disappeared, and consequently seven of the latter are usually freely moveable on one another, the first and in rare cases the second thoracic segment remaining immovably fused with the

head. They thus represent a further stage in the same process which we found going on in Cumacea and Stomatopoda. Only one of the thoracic appendages is modified so as to form a maxilliped; there are consequently seven pairs of walking legs attached to the thorax. In the female these legs bear inwardly directed processes which together form a brood pouch in which the eggs develop.




FIG. 78. *Gammarus neglectus*. Female bearing eggs seen in profile. From Leuckart and Nitsche, after G. O. Sars.

I-VI. Cephalothorax. VII-XIII. Free thoracic segments. XIV-XIX. The six abdominal segments. 1. Anterior antennae. 2. Posterior antennae. 3. Mandibles. 4. 1st maxillae. 5. 2nd maxillae. 6. Maxilliped. 7-13. Thoracic limbs. 14-16. Three anterior abdominal limbs for swimming. 17-19. Three posterior abdominal limbs for jumping. 20. Heart with six pairs of ostia. 21. Ovary. 22. Hepatic diverticula. 23. Posterior diverticula of the alimentary canal. 24. Median dorsal diverticulum. 25. Alimentary canal. 26. Nervous system. 27. Ova in egg pouch, formed from lamellae on the coxae of the second, third and fourth thoracic limbs.

The Arthrostraca are mostly small animals, living in either salt or fresh water; they assume very different forms, some of them with a rudimentary abdomen. They are divided into the sub-orders Amphipoda (Gr. ἀμφί, on both sides; πόδα, feet), which are for the most part compressed or flattened from side to side

(Fig. 78) and carry their gills on their thoracic appendages, and the Isopoda (Gr. *ἴσος*, equal; *πόδα*, feet), which are depressed or flattened from above downwards (Figs. 57 and 79), and whose gills are the modified endopodites of the appendages of the abdomen. A typical example of the last named sub-order is the Hog-water Louse, *Asellus aquaticus* (Fig. 57), common in our ponds and streams, but many of the groups are parasitic and lose most of their characteristic Crustacean features. As in the case of the Decapods some genera of Isopoda have forsaken the sea for a life on land, amongst which the wood-lice, *Oniscus* and *Porcellio*, exhibit certain peculiarities usually associated with Insects; thus the mandible has no palp, one pair of antennae is usually lost, and there are certain tubular air passages believed to be respiratory burrowed in the abdominal endopodites which recall by their structure the tracheae of air-breathing Arthropods. This is another proof that any attempt to group together all animals possessing tracheae leads to absurdities.




FIG. 79. A Wood-louse, *Porcellio scaber* \times about 2. From Cuvier.

Class II. ANTENNATA.

Sub-class A. PROTOTRACHEATA.

A short account of the genus *Peripatus* must be given, as this animal is of a very primitive nature and both its adult structure and the mode of its development throws much light upon the origin and anatomy of Myriapods and Insects and indeed on the Arthropods generally.

The different species of *Peripatus* are differently coloured, but they mostly possess a beautiful, velvety coat. In shape they resemble caterpillars but carry two large antennae on their heads, and at the base of each antenna is an eye. On the under surface of the head is the mouth, and tucked into it on each side is a toothed jaw. This is an appendage which has been modified so as to form a true gnathite. At each side of the mouth is a third pair of appendages, the oral papillae, from the tips of which a sticky slime can be ejected which entangles the insects and spiders on

which the animal lives. The other appendages, which vary in number in the different species from seventeen pairs to over forty, have the form of soft cylindrical papillae ending in two claws, and function as walking legs (Fig. 80). The anus is posterior, and at the base of each leg is a slit-like pore, the opening of a nephridium. The genital pore is in front of the anus.



FIG. 80. *Peripatus capensis* \times very slightly. From Sedgwick.

The body cavity is a spacious haemocoel divided into three longitudinal compartments by two bands of muscles which run from its outer upper angle towards the middle ventral line. The lateral compartments are continuous with the cavities of the limbs and lodge the nephridia, the salivary-glands and the nervous system. The alimentary canal, slime-glands and generative organs lie in the middle compartment.

The mouth leads into a large muscular pharynx, such as is found in many Chaetopods. The salivary glands open near this. They are interesting structures, as development has shown that in origin they are derived from nephridia, a state of things which recalls the fact that in certain Oligochaets some of the nephridia open into the oesophagus. The pharynx leads by a short oesophagus into a roomy, endodermic stomach which reaches back nearly to the anus, a short proctodaeum only being interposed (Fig. 81).

The structure of the heart and pericardium closely resembles that of the same organs in Myriapods and Insects.

The animal breathes by bunches of tracheae or short tubes which pass from the exterior into the tissues and convey air. Their external openings or stigmata are partly in two rows above and between the legs and partly scattered irregularly.

At the base of each leg is a nephridium which ends internally in a vesicle. Embryological research has shown that this vesicle is a remnant of the true coelom which is spacious in the embryo, but becomes displaced as development proceeds by the haemocoel. Enclosed in the proximal part of the leg there is a gland called the crural gland.

Peripatus is bisexual, and again embryology has demonstrated

that the cavity of the sexual organs is coelomic. The male deposits its spermatozoa in packets in the body of the female. It is not known how they reach the ova but they are usually found in the ovary and possibly bore their way through the tissues, as they do in some leeches. The ducts of the reproductive organs are believed to be modified nephridia.

The nervous system consists of a brain and two ventral cords, which however do not approach one another but lie wide apart. They are connected by nine or ten transverse commissures in each segment (Fig. 81). Posteriorly the two ventral nerve-cords fuse above the proctodaeum, an arrangement which recalls what occurs in certain primitive Mollusca.

There are many species of *Peripatus*, which are by some authorities grouped into three or four genera. They are found in widely separated parts of the world and afford, as is often the case with archaic animals, an excellent example of "discontinuous distribution." They have been found in South America and the West Indies, in South Africa, in Australia, New Zealand and in some of the Islands of the Malay Archipelago and in Lower Siam.




FIG. 81. *Peripatus capensis*, male, dissected to show the internal organs $\times 2$. After Balfour.

1. Antennae, showing antennary nerve.
2. Oral papilla. 3, 3', 3¹⁰. 1st, 2nd and 10th leg of right side. 4. Brain and eyes. 5. Circum-oesophageal cord. 6. Ventral nerve-cord of right side, showing the transverse commissures. 7. Pharynx. 8. Stomach. 9. Anus. 10. Male generative opening. 11. Salivary glands. 12. Slime glands and reservoir. 13. Enlarged crural gland of the 17th leg. 14, 14¹⁰. 4th and 10th nephridia of right side.

The development of *Peripatus* first definitely solved the problem of the nature of the various spaces in the Arthropod body, and has also thrown much light on some of the peculiarities of insect embryology. Some species lay eggs and some produce living young, and thus the genus affords favourable opportunities for checking theories as to the effect of development within the body of the parent on the embryology of the offspring.

That the animal is a most interesting "missing link" becomes evident if we attempt to sum up the Annelidan and the Arthropodan features of its anatomy. Thus *Peripatus* resembles Annelida in the nervous system, the muscular pharynx, the structure of the eyes, the serially repeated nephridia, the shortness of the stomodaeum and of the proctodaeum, the thinness of the cuticle and the hollow nature of the paired appendages; but in the indications of joints in the appendages, the reduction in size of the coelomic spaces, the presence of a wide haemocoel and of tracheae, the nature of the antennae and of the heart and pericardium, the position of the genital pore and the presence of true gnathites, *Peripatus* approaches the Myriapods and Insects.

In habits these animals are shy and inconspicuous, hiding under bark or stones, and preferring a moist surrounding. They avoid the light and move with deliberation, testing the ground as they advance with their antennae.

Sub-class B. MYRIAPODA.

The Myriapoda (Gr. *μυρίος*, countless) are characterised by the possession of a head distinct from the rest of the body, bearing antennae, mandibles, and one pair of maxillae, followed by a large number of segments bearing simple leg-like appendages.

Compared with the Crustacea or Insecta the group is a small one, yet it contains some thousands of species which, if we except a few small families, fall readily into two subdivisions (I) *Chilopoda*, and (II) *Diplopoda*.

Order I. Chilopoda.

The very active, lithe, chestnut-brown, rather fierce-looking little centipede, *Lithobius forficatus*, which is very common during the summer months under the bark of old trees, under leaves and other rubbish, is a good example of the *Chilopoda* (Gr. *χίλιοι*, a

thousand) or Centipedes. In the winter it buries itself in the soil. The female lays her eggs from June till August and hastens to cover each with a thin layer of earth; otherwise the egg is seized and devoured by her mate.

If we examine a little more closely one of these Centipedes, we shall see that the body is divided into a head, followed

External
features.

by a very narrow segment and then by fifteen other segments of varying size. The head bears a pair of long antennae, the first appendages, which are constantly waving about. Close behind the point of origin of these antennae lie the eyes. If we turn the animal over and observe the under surface of the head we shall at once see a pair of large vicious-looking claws—the poison claws or fifth pair of appendages. The tip of each of these is pierced and, as it strikes the prey, a drop of poison is squeezed out, which soon kills any insect or larva the Centipede wishes to eat. Although the tips of the poison claws are turned forwards beneath the head, yet these appendages really spring from the first segment of the trunk, which is enlarged, and is known as the basilar segment. If we separate with a pair of mounted needles these poison claws we shall see attached to the head the fourth pair of appendages, sometimes called the second maxillae, though they resemble legs and have undergone little modification. They are reduced in size and each has a blunt, functionless gnathobase. In front of these the third pair of appendages or first maxillae take the form of a lobed plate, being united with one another in the middle line. These cover in their turn the second pair of appendages or mandibles which, like those of Insects and unlike those of Crustacea, consist simply of the blade, having no palp or feeler.

The fifteen segments which succeed the one carrying the poison




FIG. 82. A Centipede, *Lithobius forficatus*. Dorsal aspect $\times 12$.

1. Antennae. 2. Poison claws, 5th pair of appendages. 3. Second maxillae, 4th pair of appendages. 4. First pair of walking legs.

claws each bear a pair of seven-jointed running legs ending in a pair of claws.

Near the base of some of the legs—not of all—in the soft skin uniting the hard dorsal and ventral plates of chitin, is an oval opening. This leads into a chamber from which the tracheae pass off. These tubes divide and subdivide into smaller tubes, which run all over the body and traverse all the tissues, even entering the smallest cell. They are lined with a cuticle of chitin, and are kept from collapsing by the presence of a fine spiral thickening of this cuticle which gives them a very characteristic appearance when seen through a microscope. They are full of air and constitute the respiratory apparatus of the Centipedes.

The existence of such a breathing apparatus, which is confined to Peripatus, the Myriapods, the Insects, and certain of the Arachnids, is associated with certain striking features in the internal anatomy of the body. In most animals the oxygen of the air is taken up by the blood, and carbon dioxide is given out, at certain fixed points called gills or lungs, and the vascular system is arranged so as to drive the blood through these specialized respiratory organs. The blood takes the oxygen to the various tissues and takes from them the carbon dioxide which is removed from the body at the same centres. In the Tracheata however the air is itself conveyed by means of the tracheae to all the cells of the body, and the gaseous exchange takes place on the spot. Associated with this remarkable method of breathing is the fact that the body cavity of all the Arthropoda is really a blood-space, and the study of embryology shows that the real coelom is almost obliterated though portions of it probably persist as the cavities of the reproductive organs. The blood has in the Tracheata lost one of its chief functions, the respiratory one, and exists chiefly as a nutritive fluid, bathing the alimentary canal and taking up from it the soluble food which it conveys to the other tissues. It is kept in circulation by a contractile heart which lies along the middle dorsal line of the animal. In *Lithobius* this heart has a pair of ostia or openings in each segment, into which the blood from the pericardium pours, only to be sent out of the heart again at its anterior end into the general cavity of the body, for here the heart has an opening and there is no system of smaller vessels or capillaries.

Another peculiarity associated with the above-mentioned method of breathing is the nature of the excretory organs which rid the

body of its nitrogenous waste. In *Peripatus* we find more or less typical nephridia, and we meet with modifications of these in the coxal-glands of some Arachnids, but in the Myriapoda and in the Insecta these organs are wanting and their place is taken by certain outgrowths from the proctodaeum, called after an Italian anatomist Malpighian tubules. In *Lithobius* there are two such tubules, blind at their free end, and at the other opening near the hind end of the alimentary canal (6, Fig. 83). Their walls contain traces of uric acids and urates which they have taken up from the blood, and which they presumably excrete through the alimentary canal.

The last-named organ is a straight tube which runs from one end of the body to the other. A pair of salivary glands pour their secretion into it near the mouth, but no other digestive glands exist. *Lithobius* is carnivorous, living chiefly upon insects, their larvae, and on earthworms.

A large part of the space in the head is occupied by the bilobed brain which supplies the antennae and the mouth appendages. This brain is connected by means of para-oesophageal commissures with a long ganglionated ventral cord which supplies nerves to the legs and the rest of the body (Fig. 83).

Myriapods are bisexual, the ovary and testis are continuous with




FIG. 83. *Lithobius forficatus*, dissected to show internal organs \times about 2. After Vogt and Yung.

- | | |
|---------------------------|---------------------------|
| 1. Antenna. | 2. Poison claw. |
| 3. Salivary gland. | 4. Walking legs. |
| 5. Ventral nerve-cord. | 6. Malpighian tubule. |
| 7. Vesicula seminalis. | 8. Small accessory gland. |
| 9. Large accessory gland. | 10. Unpaired testis. |
| 11. Alimentary canal. | |

their ducts which open to the exterior on the ventral surface of the last segment.

Order II. Diplopoda.

The second large subdivision of the Myriapoda is well illustrated by the black wire-worm, *Iulus terrestris*, very commonly found in Great Britain curled up under stones or burrowing in the soil, where it is said to do much damage by gnawing the tender roots of plants, for all Diplopods (Gr. διπλός, double) are vegetarians.

The wire-worm is a black, shiny, cylindrical animal with an enormous number of legs, in spite of which its movements are much slower than are those of *Lithobius*. The terga or dorsal shields are in this sub-group very much enlarged, whilst the sterna or ventral shields are very much reduced, and thus it comes about that the bases of each pair of legs, instead of being separated by the width of the body, are close together. Another peculiarity in this subdivision is that each tergum corresponds with two segments, and that each apparent segment bears two pairs of legs and has the internal organs also duplicated. This double arrangement however only begins at the fifth segment behind the head.




FIG. 84. *Iulus terrestris*, sometimes called the "Wire-worm." From Koch
x about $3\frac{1}{2}$.

1. Antennae. 2. Eyes. 3. Legs. 4. Pores for the escape of the excretion of the stink-glands.

The appendages on the head are :—(i) Short, usually clubbed-shaped antennae ; (ii) mandibles ; and (iii) a single pair of maxillae fused into a lobed plate.

Both the first two segments behind the head bear but one pair of legs, the third has no legs but carries the opening of the generative ducts. The fourth free segment has one pair of legs, the remainder two pairs.

The female *Iulus* lays its eggs, some 60 to 100, in an earthen receptacle she has prepared beneath the surface of the ground.

on the ventral surface a pair of legs, and the two hindermost of which bear on the dorsal surface a pair of wings. The abdomen consists of a varying number of segments, ten being perhaps the usual number but fewer often occur. The abdomen bears no appendages except at the posterior end, where a pair of rod-like outgrowths—the anal cerci—are often found.

Owing to the similarity of Insects to one another and their great number the study of them has become a very special branch of Zoology, which is termed Entomology. The necessity of extremely detailed study is due to the same cause and a great number of technical terms are in use for describing the numerous structures which build up the body of the Insect.

In this short book it will only be possible to indicate a few points about the anatomy of Insects, and we will take as a type the common Cockroach because it is both a generalized form and not too small for dissection.

The common Cockroach of the British kitchen is *Periplaneta orientalis*, but a larger form, *Periplaneta americana*, is often met with on ships and from them makes its way to the docks; it is also often found in Zoological Gardens, etc. *P. germanica*, a small species, is becoming increasingly common in England.

The whole body of the Cockroach is covered by a chitinous covering which varies in thickness, from the black, hard head to the thin, whitish areas which exist at the joints and which permit movement of the harder parts on one another. Except in the head the segments of the body can be detected externally, and as in other members of the Arthropoda the segmentation affects some only of the internal structures, such as the heart, the tracheae, the muscles, and the nervous system, the other organs of the body not being influenced by it.

The head of a Cockroach is a flattened structure placed at right angles to the axis of the body. It is oval in outline, its upper edge being considerably broader than the lower. It is loosely jointed to the thorax by a neck which permits considerable movement (Fig. 85). This neck enters the head near its upper edge and below it the head hangs free. On the upper and outer edge of the head are a pair of kidney-shaped eyes of a shining black colour, on the inner curve of which the antennae or feelers have their origin. These are long whip structures, often as long or longer than the body; they are made up of many joints, and during life are in active movement, now stretched downward as if trying the ground




FIG. 85. *Periplaneta orientalis*, male $\times 2$. A. Dorsal view. B. Side view.
From Kükenthal.

- A. 1. Antenna. 2. Palp of first maxilla. 3. Prothorax. 4. Anterior wings. 5. Femur of second leg. 6. Tibia. 7. Tarsus. 8. Cerci anales. 9. Styles.
- B. 1. Antenna. 2. Head. 3. Prothorax. 4. Anterior wing. 5. Soft skin between terga and sterna. 6. Sixth abdominal tergum. 7. Split portion of tenth abdominal tergum. 8. Cerci anales. 9. Styles. 10. Coxa of third leg. 11. Trochanter. 12. Femur. 13. Tibia. 14. Tarsus. 15. Claws.

on which the creature moves, and now waving aloft as if testing the air.

The mouth is on the lower edge of the head and is covered in front by a small, moveable flap called the labrum or upper lip. At the sides it is protected by the first and the second pairs of appendages, and behind the fusion of the right and left third pair forms a plate called the labium, which completes the boundaries of the mouth behind (Fig. 86).

If the first pair of mouth-appendages or mandibles be removed from the head and examined through a lens, each is seen to be a single-jointed stout jaw with a toothed inner edge which bites against the corresponding part of its fellow. It is characteristic of the mandibles of Insecta to have no palp or remnant of the distal joints of the limb, such as is almost universally present in Crustacea.

Behind the mandibles, and like them situated on each side of the mouth, are the first maxillae. Each consists of a number of joints, and each joint has a special name. Like the typical gnathite of other Arthropods we may regard them as consisting of a limb-like appendage with out-growths from the basal joints biting against corresponding processes—gnathobases—of the fellow appendage. There are two of these gnathobases, the hard, pointed lacinia and an outer portion, the softer galea (B, Fig. 86). The lowest joints form an L-shaped hinge which, when opened out, protrudes the jaw. The outer portion of the first maxilla is many-jointed, and is sensory in function, constantly touching and testing the ground as the animal moves about. It is called the maxillary palp.

The second maxillae are united across the median line and thus constitute a fold or plate called the labium, which bounds the mouth behind as the labrum bounds it in front (C, Fig. 86). Each half may be resolved into elements similar to those of the first maxillae, the fused basal joints of the pair of appendages form the mentum and sub-mentum, the galea being represented by the paraglossa, whilst the inner gnathobase corresponds with the lacinia and is termed the ligula. As in the case of the first maxilla the outer joints of the appendage which have a tactile function are termed the labial palp.

The thorax is built up of three segments, the pro-, meso-, and meta-thorax. The skeleton of each segment consists of a dorsal hard piece, the tergum, united

with a corresponding ventral piece, the sternum, by a soft intervening pleural membrane. The tergum of the first thoracic segment is clearly visible, but the meso- and meta- terga are concealed by the wings. The two pairs of wings are formed by folds of the skin arising from the terga of the meso- and meta-thorax respectively, and in a state of rest conceal the dorsal surface of the animal behind the prothorax. The front pair are termed elytra; they are hard and horny, one overlaps the other, and they probably serve more as protectors to the delicate hind wings than




FIG. 86. Mouth-appendages of *Periplaneta*. Magnified.

- A. Mandible. B. 1st maxilla. 1. Cardo. 2. Stipes. 3. Lacinia.
 4. Galea. 5. Palp. C. Right and left 2nd maxillae fused to form
 the labium. 1. Submentum. 2. Mentum. 3. Ligula, corresponding
 to the lacinia. 4. Paraglossa, corresponding to the galea. 5. Palp.

as organs of flight. The posterior wings are thin and membranous, and are of greater area than the elytra, and they constitute the effective organs in the rare flight of the Cockroach. At rest they are folded like a fan and concealed by the elytra. In *Periplaneta orientalis* the wings—as is not uncommon amongst Insects—are rudimentary in the female.

The ventral plate or sternum of each thoracic segment bears a pair of legs by means of which the Cockroach scuttles rapidly about.

Each leg consists of a number of joints, viz. a thick flat coxa, applied to and articulating with the sternum; a minute triangular joint, the trochanter; a stout joint called the femur; a more slender one termed the tibia, armed with spines; then a piece consisting of six short joints called the tarsus, with a whitish hairy patch under each joint which acts as a sole; and finally a pair of

terminal claws (Fig. 85). These names, as is too often the case in Zoology, were suggested by fanciful and misleading comparisons with the parts of the vertebrate limb.

The abdomen consists of ten segments, and here the terga and sterna can be easily seen, as they are not obscured by the insertion of the wings and legs. The eighth and ninth terga are however both tucked under the seventh and are not readily seen until the animal is artificially stretched. The tergum of the tenth or last segment stands out from the hind end of the animal and is cleft into two lobes. The sterna are equally distinct, but the first is small. The abdomen is broader in the female than in the male, and the seventh sternum is shaped like the bow of a boat and projects backwards, hiding the posterior sterna and supporting the lower surface of a roomy pouch or cavity in which the egg-case is formed. In the male the seventh sternum conceals the eighth and ninth.

The stigmata leading to the tracheae are placed in the soft pleural membrane connecting terga and sterna.

The abdomen is usually regarded as being without appendages, but a pair of jointed cerci anales emerge below the edge of the tenth tergum in each sex, and in the male the ninth sternum bears a pair of anal styles. The claim of these structures to be reckoned as appendages of the same rank as the antennae, the gnathites and the legs, was at one time not generally conceded, but appears to be now fairly established for the cerci anales.

In the soft tissue between the tenth tergum and the last visible sternum, at the hind end of the body, is placed the anus, below it the single genital pore is situated. The anus is supported by certain thickened plates in the skin, known as podical plates, and around the genital orifices are arranged certain rods and bars, symmetrical in the female but asymmetrical in the male, whose functions and meaning are obscure, but which are connected with the processes of conjugation and of egg-laying. As we have seen, this region is in the female enlarged into a genital sac by the growth and modification of the seventh sternum, and the tucking into the space so formed of the skin carrying the eighth and ninth sterna. The opening of the oviduct is on the eighth sternum, and on the ninth is the single opening of the receptaculum seminis or spermatheca, which consists of two pouches of unequal size composed of inturned ectoderm; these are always found full of spermatozoa in the fertilized female. The spermatozoa apparently leave the

spermathecae when the eggs are being laid and fertilize the ova whilst they are in the genital sac. Two glands, consisting of branching tubes,—called colleterial glands—open separately behind the spermatheca. They secrete a fluid which hardens to form the egg-capsule in which the eggs are laid. This is moulded in the genital sac and may often be seen half-protruding between the distended seventh sternum of the mature female.

When the skin is removed from the dorsal surface of the Cockroach the cavity laid open is not a coelom but a haemocoel, and it is largely filled by a loose white tissue, known as the fat-body, which surrounds the various internal organs. If the alimentary canal be disentangled from this it is at once evident that in Insects, unlike other Arthropods, the intestine is longer than the body and the larger portion of it which lies in the abdomen is coiled in order to stow it away. Like the digestive tube of other Arthropods a large part of its length consists of the stomodaeum and proctodaeum. The former consists of an oesophagus which quickly passes into a large crop in which the food is stored during digestion. The lining of both these regions bears hairs and the muscles in their walls are striped. The crop is followed by a gizzard, which bears internally six hard chitinous teeth, and behind them are fine hairs which act as strainers, so that only finely divided food can pass on into the mesenteron or chylific ventricle, as the part of the alimentary canal is called which alone is lined by endoderm and is capable of absorbing nourishment. This tube is produced in front into seven or eight pouches, the so-called hepatic diverticula. The mesenteron, the limit of which is marked by the insertion of the Malpighian tubules, is succeeded by the intestine or proctodaeum, a long coiled tube which enlarges posteriorly and opens by the anus. The enlarged portion is called the rectum (Fig. 87), the anterior coiled portion the colon.

Lying along the crop on each side is a pair of branched glands—the salivary glands—and a bladder termed the salivary reservoir. All three are provided with long ducts. Those of the two glands on each side unite to form a single tube which then receives the duct of the reservoir, and the common ducts of the two sides open behind the mouth but in front of the second maxillae. The saliva converts starch into sugar. The secretion of the hepatic diverticula emulsifies fats and turns insoluble proteids into the soluble forms (peptones). This secretion seems to pass forward into

the crop and there the true digestion is effected. The digested and soluble food then passes through the filter of the gizzard into the mesenteron, where absorption of the nutritious parts is effected, the undigested portions passing on to the intestine and so out of the body. The cells of the mesenteron undoubtedly exert some action on the products they absorb, though we are ignorant of its precise nature, but in the end they pass on the products of digestion—altered no doubt—to the blood which everywhere bathes the alimentary canal, and by this the new material is conveyed all over the body.




FIG. 87. A Female Cockroach, *Periplaneta*, with the dorsal exoskeleton removed and dissected to show the viscera. Magnified about 2.

1. Head. 2. Labrum. 3. Antenna, cut short. 4. Eye. 5. Crop.
6. Nervous system of crop. 7. Gizzard. 8. Hepatic caeca. 9. Mid-gut or mesenteron.
10. Malpighian tubules. 11. Colon. 12. Rectum. 13. Salivary glands.
14. Salivary receptacle. 15. Brain. 16. Ventral nerve-cord with ganglia.
17. Ovary. 18. Spermatheca. 19. Oviduct. 20. Genital pouch in which the egg-cocoon is found.
21. Colleterial glands. 22. Anal cercus.

The blood is kept in circulation by the heart which lies in the middle dorsal line close under the skin; in fact it can be seen through the skin in the region of the abdomen. It is a long vessel

made up of thirteen chambers corresponding with the three thoracic and ten abdominal segments, each chamber opening into the one in front and the whole somewhat resembling a row of funnels fitted one into another. At the broader hinder end of each chamber is a pair of ostia or holes, through which the blood enters from the pericardium, and there are valves which prevent the blood being forced out of the ostia or forced backward when the heart contracts, so that its only course is to flow forward. The pericardium is separated from the rest of the haemocoel by the pericardial septum, in which however there are certain holes which permit an interchange of contents between the two cavities. *When at rest the pericardial septum is arched upwards, but it is pulled outwards and flattened by the periodic contraction of certain muscles attached to its sides called the alary muscles, thus enlarging the pericardium and causing an inflow of blood into it from the rest of the haemocoel.* This blood enters the heart when it is relaxed and the ostia are open, and hence by the alternate contractions of the alary muscles and the muscular wall of the heart the circulation is maintained.

The anterior end of the heart, called the aorta, opens by a trumpet-shaped orifice into the haemocoel and the blood pours out of this and bathes all the organs of the body. It thus takes up the soluble food which has left the alimentary canal and conveys it to those parts of the body where it is needed, and in a similar way it gives up its superfluous fat to be stored up in the fat bodies and its urates or waste nitrogenous material to the Malpighian tubules, whence they are passed out of the body. It is noticeable that just as water-plants are as a rule not of a compact shape, but finely subdivided so as to expose as large a surface as possible to the surrounding medium, so in the body of the Cockroach, the various organs are long, tubular, or diffuse structures offering a large surface to the nourishing and purifying blood.

The heart contracts almost as frequently as the normal human heart, i.e. about seventy-two times a minute when the Cockroach is at rest, but at other times its rate of contracting varies a good deal. The blood is colourless and contains amoeboid corpuscles. It is slightly alkaline.

It is obvious from the above account that in the Cockroach the blood is mainly a means of conveying nutriment to the organs and taking certain waste matter from them, and that unlike what is usual in other animals, its respiratory function is at a minimum. Owing to the nature of the tracheae, the air with its oxygen is

The tracheae being full of air present a glistening silvery appearance, which is unmistakable. They are prevented from collapsing by the presence of a spiral thickening of the chitinous lining which runs round the interior of the tube just as the wire spiral strengthens the india-rubber tube of some kinds of garden hose. Respiration is effected by the alternate arching up and flattening of the abdomen, resulting in an alternate increase and diminution of its volume, which, since the blood is incompressible, results in an alternate inrush and expulsion of air from the tracheae. In all probability only the contents of the larger tracheae are affected by this process; by diffusion the oxygen from this "tidal air" is handed on to the finer tracheae and thence to the blood.

In Insects the tracheal mode of respiration reaches its highest development, and it is accompanied by a correlative diminution and simplification of the circulatory apparatus, the oxygen of the air being conveyed directly to, and the carbon dioxide removed directly from, the cells to the outer air, whilst the blood loses its respiratory function. It is doubtful how far this state of things is connected with the peculiar disappearance of the coelom—which presumably only exists in the cavity of the reproductive organs—because a similar replacement of the coelom by a haemocoel is found in Crustacea and Mollusca, where the blood is respiratory and the gills are compact and active organs; but it probably is correlated with

body being haemocoelic. Crustacea probably retain nephridia, those of the fourth segment—shell glands—being persistent in the Entomostraca, whilst those of the second segment—green glands—persist in the Malacostraca. It is not absolutely proved, but it seems probable, that the inner ends of these glands represent coelomic spaces. But even amongst Crustacea in certain Amphipods, for instance, we find the transference of the function of the nephridia to outgrowths of the alimentary canal. In Arachnids the nephridia or coxal-glands show very varying degrees of development, but on the whole they are tending to die out and to be replaced by Malpighian tubules or diverticula of the intestine. Finally in Myriapods and Insects, where the true coelom is reduced to its minimum and where the tracheal mode of respiration attains a very high degree of development, all traces of nephridia have disappeared and the waste nitrogenous matter is excreted solely by the Malpighian tubules.

These are very fine long caecal diverticula,—so fine as to be but just visible to the unaided eye, 60—80 in number, arranged in six bundles which open into the beginning of the narrow part of the proctodaeum. They float in the blood, winding about amongst the abdominal viscera (Fig. 87). They contain crystals, probably of urate of soda, which are taken up from the blood and which leave the body through the intestine.

The nervous system of the Cockroach is constructed on the same plan as that of the other segmented Invertebrates with which we have had to do. There is a large supra-oesophageal ganglion or brain connected by commissures, which encircle the oesophagus and unite below in a sub-oesophageal ganglion. Together these occupy a considerable portion of the cavity of the head. The supra-oesophageal ganglion supplies paired nerves to the eyes and to the antennae, and is thus the sensory centre. The sub-oesophageal ganglion supplies the mandibles and both pairs of maxillae. From

The only specialized sense organs are the eyes and the antennae. The eyes have fundamentally the same structure as those of the Crustacea; the antennae are the seat of the senses of smell and taste, and are, in addition, very delicate tactile organs. The maxillary palps are also tactile, and are constantly touching and testing the ground on which the Cockroach is moving.

Cockroaches are bisexual. The ovaries in the female consist of two sets of eight tubes, uniting at their anterior end into two cords which pass to the dorsal wall of the thorax and become attached to the pericardial septum, and at their posterior end fusing into two short oviducts which join to form a small uterus (Fig. 87). Each of the sixteen tubes contains cells, some of which become ova, and as they approach the oviduct the ova become arranged in a single row. At the same time they increase greatly in size by the deposition of yolk in the egg, so that an ovum just before it leaves the body is of considerable size.

The eggs are apparently fertilized after leaving the uterus by spermatozoa, which emerge from the spermatheca (in which they have been deposited by the male) situated behind the opening of the uterus. Whilst still in the genital pouch the fertilized eggs are surrounded by the secretion of the colleterial glands which open behind the spermatheca, and this secretion hardens into the egg-capsule or cocoon.

The paired testes of the male are only functional during youth and, as they diminish in size after they cease to function, they are only to be found with difficulty. They lie concealed by the fat body below the terga in the region of the fourth, fifth, and sixth abdominal segments. They look somewhat like elongated bunches of cherries, their translucent colour strongly contrasting with the opaque white of the fat body. Two vasa deferentia lead from the testes to a pair of large reservoirs called vesiculae seminales, which together form the mushroom-shaped gland. Into these, at an early age, the cells destined to form spermatozoa pass from the testes and there they undergo their further development. The mushroom-shaped gland opens to the exterior by means of a short muscular

tube, the ductus ejaculatorius, which has its orifice just below the anus. The name of the gland is derived from its form ; it has a thick stalk surrounded by a crown of branches. Fertilization and oviposition take place during the summer.

Sixteen eggs are laid in each egg-capsule, and for some seven or eight days, until the mother finds some warm and secluded hiding-place to deposit her load, she carries about the capsule, half-protruding from the genital pouch. When the embryos in the eggs are fully formed, which takes about twelve months, it is said that they secrete some fluid, probably saliva, which dissolves the upper part of the capsule and so permits of their escape. In *P. germanica* the mother is said to take a part in freeing her offspring from their temporary imprisonment. When they first appear they are white, with dark eyes, but the integument soon thickens and darkens. They have no wings but in other respects they resemble their parents, and thus there is no metamorphosis such as occurs in the Butterflies and many other Insects. They run actively about, devouring any starchy food they can find, and when in time they grow too large for their coat of mail, it splits and a soft Cockroach extricates itself from it. The integument soon hardens again. This casting of its skin or ecdysis takes place seven times, and after the seventh moult, when the insect is four years old, it is adult.

The Insects are usually subdivided into eight Orders, which are mainly based (i) on the structure of the gnathites ; (ii) on the nature of the wings ; and (iii) on the amount of Metamorphosis which the life-history of the Insect presents. A short account of each of the criteria is therefore subjoined.

The Mouth-Parts (Gnathites) of Insects.

The mouth-parts of Insects can in almost all cases be resolved into a pair of mandibles which never bear palps, and two pairs of maxillae which are usually provided with palps. In the different orders of Insects and in different members of the orders, these mouth-appendages show many modifications and are put to a very great variety of uses. One or other part may be suppressed and disappear, others may coalesce, as is the case with the right and left second maxillae of the Cockroach, but as a rule traces of all the gnathites may be found, though often much altered. The mouth-parts of insects have been grouped as follows: (i) *BITING*. This kind

much elongated, and takes the form of a fleshy protuberance which to some extent ensheaths the other parts. In the house-fly, *Musca domestica*, the piercing organs are fused to the labium and act only as supporting rods for it, but in the Gnat or Mosquito they are free and reach a high degree of development. These parts are overlaid by a somewhat enlarged labrum, and between this and within the grooved labium the pointed stylets lie. Amongst these a sharp style called the hypopharynx situated behind the mouth may be distinguished. Two pairs of lateral stylets, identified by some as the modified mandibles and first maxillae, also exist and the maxillary palp acts as a sensory organ. The Hemiptera or Bugs have a very similar set of gnathites in correspondence with their habits of boring into animals or plants to feed on their juices. In this Order the mouth-parts when not in use are bent under the body and lie along the under surface of the thorax. The labium is jointed and its edges are curved round to form a deep groove,

the slit of which is only partly covered by the labrum. Within this groove four sharply pointed styles—the mandibles and first maxillae—work. They are as a rule finely toothed like little saws and are well adapted for piercing the skin. There are no palps. (iv) *BITING AND SUCKING*. The Hymenoptera or Bees and Wasps have mandibles not unlike those of a Cockroach and use them for biting and moulding their food of pollen and the wax they secrete from their bodies. The laciniae of the maxillae form blade-like structures and their palps have much diminished in size. The labial palps however are large, and the conjoined median outgrowths from the labium (corresponding to the ligula of the Cockroach, 3, Fig. 86 c) form a kind of grooved tongue along which the nectar in the flowers is sucked up.

It thus appears that although the mouth-parts of Insects are highly modified in connexion with the kind of food they live on and the modes in which they obtain it, nevertheless the various mouth-parts have a common ground plan, and although the authorities differ as to details, a fundamental similarity runs through these appendages in the different Orders.

Wings of Insects.

The wings of Insects are folds of the integument, flattened so that the two sides are in contact on their inner surfaces. At certain places however slits are left and through these tracheae pass taking air to the wings. The ectoderm of both upper and under layers is also thickened along certain lines, and the presence of these thickenings divides the wing up into a number of areas. These lines are usually called wing-veins or wing-nerves, but as they are neither veins nor nerves it is better to call them nervures. The presence and disposition of the nervures is of the highest importance in classification. Wings may be thin, membranous, and transparent, as in the Grasshopper (Fig. 88) or Dragon-fly (Fig. 50), where there is an enormous number of nervures, or in the Flies and Bees, where there are few nervures, or they may be thickened and strongly chitinised as in the front wings of Beetles. In this last group the anterior wings are called elytra (Gr. ἐλῦτρον, a cover) and they always meet together in a median longitudinal line, so that when they are closed the insect appears to be wingless (Fig. 92); in some few cases they have fused together so that the posterior or flying wings are rendered useless. In one great

division of the Hemiptera, one half of the anterior wing is horny and strongly chitinous, the other and posterior half is membranous. In the Cockroach, as we have seen, the anterior wings tend to become horny and are of little use in flight (Fig. 85). The posterior wings of the same insect when at rest are folded together something




FIG. 88. *Pachytylus migratorius*. A Grasshopper. Natural size.

like the leaves of a shut fan and many species in several of the orders fold up their hind wings when not in use. The tucking away of these wings under the small elytra is a complicated affair in some Insects such as the Earwig, where the nipper at the end of the body are said to aid in the process. Many Insects however, such as the Dragon-flies, Plant-lice, Butterflies and Moths, Flies

and Bees and numerous others, do not fold up their wings but either bear them erect or lying depressed on the body. In some cases the wings are quite transparent, but in the Moths and Butterflies they are covered with a dense fur of flattened scales which can readily be brushed off as a fine powder or dust (Fig. 91). It is these scales which give rise to the beautiful and in some cases gorgeous colouring of the Lepidoptera.

Two pairs of wings are present as a rule, but the order Diptera has only the anterior pair, the hind-wings being replaced by certain stalked structures called balancers or halteres. In the Hymenoptera, the two wings of each side are clamped together by means of hooks on the hind wing which fit into a ridge on the hinder edge of the front wing (Figs. 93, 94, and 96). The two wings of each side thus move as one. It is not uncommon to find isolated species in which the wings are not developed, for instance, the females of many Plant-lice and some Moths; whilst Fleas, which are sometimes placed amongst or near the Order Diptera, never possess wings, though their absence is compensated for by a special development of the powers of jumping.

Metamorphosis.

A very large number of animals that live in the water, whether in the sea or fresh water, hatch out from the egg in a larval condition. That is to say, the being which leaves the egg is very unlike the adult in structure and habits, but by growth and a series of accompanying changes in time passes over into the adult which is capable of reproducing. These changes are what is known as metamorphosis. In the life-history of land animals such larval stages are very rare and indeed hardly exist outside the Sub-class Insecta. As we have seen, the egg of a Cockroach gives rise to a young Cockroach which differs but little from the adult and gradually grows into it by a series of small changes, but which never at any time undergoes a long period of profound rest. But if we consider the case of a Moth or Butterfly we shall find that the egg does not give rise to an animal resembling a minute Butterfly but to a worm-like larva or caterpillar, which has no wings and in other respects is very unlike the Insect which produced the egg. This caterpillar as a rule eats voraciously and grows rapidly with little change in form until its fourth ecdysis, when a sudden change occurs, and the so-called pupal stage supervenes. In this stage

with a few exceptions the animal now called a pupa (Lat. *pupa*, a puppet) is motionless and ceases to feed. It may be uncovered and




FIG. 89. Larva of *Bombyx mori*, the Silkworm. Life size

protected only by the hardened integument or it may be enclosed in a casing or cocoon. In the case of the Silkworm Moth and some others, this is constructed of silk. During the pupal stage, the animal undergoes a profound change, many of its organs and tissues being broken up and new ones recon-

stituted. When this process is completed the pupa casts its skin, makes its way out of the cocoon and emerges as an imago (Lat. *imago*, an image) or perfect insect.



FIG. 90. Cocoon of *Bombyx mori*, from which silk is spun. About life size.

The various orders of Insect differ in the degree in which metamorphosis occurs. In the Aptera there is no metamorphosis and the development is said to be direct. In Orthoptera and Hemiptera there is no quiescent pupa stage and the chief difference between the larva and adult is the absence of wings. Here the metamorphosis is said to be incomplete. The same is true of most of the Neuroptera, a very varied assembly of Insects, in some forms of which however, e.g. the Caddis-flies, a pupal stage exists. Amongst the Lepidoptera, Coleoptera, Hymenoptera and Diptera there is a well-marked pupal stage, and these orders are said to have complete metamorphosis.

Various names have been given to the larvae of Insects without very precise definitions. Those of the Lepidoptera are usually called Caterpillars. They are often gaudily coloured and bear tufts and bunches of hair. Besides the three pairs of legs which are found on the three segments following the head and which correspond with the legs of the imago, certain of the abdominal segments bear fleshy stumps called abdominal legs. The larvae of some of the Saw-flies (Hymenoptera) have a similar bright colouring and resemble Caterpillars, and like them feed exposed on leaves, etc.

The larvae of Beetles and most Hymenoptera are as a rule hidden underground or in galls or wax-comb. They are whitish in colour and unattractive, and are often termed grubs, whilst the footless




FIG. 91. Silk-worm moth, *Bombyx mori*.

A. Female. B. Male.

white larvae of the Diptera, which are for the most part deposited in some organic substance—whether alive or not—are usually termed maggots.

In the following account of Insect Classification we can only indicate the chief characters of each Order and mention the names of one or two common members of each.

Order I. Aptera.

Wingless Insects, with scales and hairs covering the body. The mouth-parts are adapted for biting. They move by running or by springing by aid of a caudal style which is kept bent forwards under the abdomen and retained in this position by a ventral hook. When released from this hook the recoil of this style hurls the insect into the air. The segments of the thorax are not fused together and they have no metamorphosis.

Not all wingless Insects belong to this order. The name Aptera (Gr. ἀπτερος, wingless) refers to the belief that the ancestors of these Insects never had wings and that thus they represent a lower stage of evolution than the rest of the sub-class.

For the most part the Aptera are minute Insects living in retired spots under leaves or rubbish, in roof-gutters, etc., but they are widely distributed over the world. One of the best known is the Silver-fish *Lepisma*, which hides in disused cupboards, old chests of drawers, sugar barrels, etc. It runs with great rapidity.

Order II. Orthoptera.

The Orthoptera (Gr. ὀρθός, straight; πτερόν, a wing) have mouth-parts adapted for biting. The anterior wings are as a rule stiff and when the Insect is at rest one overlaps the other, and both usually cover and conceal the large membranous hinder wings with which the creature flies. There is an incomplete metamorphosis, the young being at first without wings.

This Order is a very varied one and doubts exist as to whether it is a natural one. It includes the Cockroach, whose anatomy has already been described; the Earwig, *Forficula*; the *Mantis*; the leaf and stick insects, *Phyllium* and *Phasma*; the Grasshopper (Fig. 88) *Acridium*; the Locust, *Locusta*; the Cricket, *Gryllus*; and many others.

Order III. Neuroptera.

The Neuroptera (Gr. νῆρον, a tendon and hence a nervure) have biting mouth-parts. Both pairs of wings are membranous and used in flight, and the "veins" of the wings form a more or less close network. Metamorphosis complete or incomplete.

This Order, like the preceding, contains many families which, except as regards the structure of the wings, have little resemblance to one another. The following are a few of the more widely known species: the White-ant, *Termes*; the May-fly, *Ephemera*; the Dragon-fly, *Libellula* or *Aeschna* (Fig. 50); the Ant-lion, *Myrmeleo*; the Aphis-lion, *Hemerobius*; the Caddis-fly, *Phryganea*, which in some respects approaches the Lepidoptera; and the *Thrips*, an insect which injures corn crops and certain flowers and is sometimes elevated to the position of a distinct order.

Order IV. Coleoptera.

The Coleoptera (Gk. κολεός, a sheath) have mouth-parts adapted for biting. The anterior wings are hard and horny and fit together in the middle line with a straight suture. The hind wings are membranous and folded. The metamorphosis is complete, that is, there is an active larval stage (Fig. 92), followed by a quiescent stage, during which extensive changes in the internal anatomy take place.

Unlike the preceding, this order is clearly defined and its members are on the whole very like one another. It has always been a favourite order with the Entomologists, and the number of species named and described is far greater than in any other order. It includes all the Beetles. For the most part these Insects are dull in colour but their firm exoskeleton gives them a very definite outline and renders their preservation and identification comparatively easy, which may to some extent account for their popularity with collectors.




FIG. 92. In the centre *Coccinella septempunctata*, the Lady-bird \times about $2\frac{1}{2}$, with the larva to the left \times about $2\frac{1}{2}$, and the beetle, natural size, to the right.

Order V. *Hymenoptera*.

The Hymenoptera (Gr. *ὑμένω-πτερος*, membrane-winged) have mouth-parts adapted for biting and sucking. The "ligula" of the labium is long and grooved, whilst the paraglossae are small.




FIG. 93. *Formica rufa*, the Wood-ant.

1. Female. 2. Male. 3. Neuter.

The mandibles are well-developed and the laciniae of the first maxillae large. The four wings are alike, membranous in texture, and the hind wings are hooked on to the anterior in such a




FIG. 94. *Apis mellifica*, the Honey-bee.

way that the two wings of each side move together. They differ from the wings of the Neuroptera in possessing fewer veins. The metamorphosis is complete.

This group comprises the Ants, Bees and Wasps. Many of them live in highly complex communities and in their social habits and general intelligence they reach a level which is only surpassed by man himself. The group includes the Wood-wasp, *Sirex*; the




FIG. 95. *Polistes tepidus* and nest.

Saw-fly, *Tenthredo*; the "Gall-fly," *Cynips*; the *Ichneumon*; the Ant, *Formica*; the Wasp and Hornet, *Vespa*; the Humble-bee, *Bombus*; and the Honey-bee, *Apis*.

Order VI. Hemiptera.

The Hemiptera (Gr. ἡμι, half) have mouth-parts arranged for piercing and sucking. The basal part of the labium is elongated and tubular, the mandible and first maxilla form sharp pointed styles. The two pairs of wings may be alike or may differ, and the anterior pair are in some cases half horny and half membranous. The metamorphosis is incomplete, there being no quiescent stage.

The members of this order present very great divergence both of form and of size; they are colloquially known as Bugs and Lice. Amongst the commoner forms are the Water-boatman, *Notonecta*; the Water-scorpion, *Nepa*; the Bed-bug, *Acanthia*; the *Cicada*, remarkable for its chirping noise; the Frog-hoppers, including the Cuckoo-spit, *Aphrophora*; the Plant-louse, *Aphis*; the *Phylloxera*, which destroys vines; scale Insects and lice.

Order VII. Diptera.

The Diptera (Gr. δι-πτερά, two wings) have mouth-parts arranged for piercing and sucking. The only difference in this respect from the Hemiptera consists in the fact that the sucking tube is partly formed by the labrum and that the first maxillae retain palps. Only one pair of wings, the anterior, are present; the posterior are represented by a pair of short knobs called balancers or halteres (Fig. 97). The metamorphosis is complete.

The Diptera or Flies form one of the largest of the Insect Orders, probably as large as the Coleoptera, although at present the number of species of Beetles named and described is far greater than that of Flies. Amongst the commoner genera are the Gnats and Mosquitoes, *Culex*; the Daddy-long-legs, *Tipula*; the "Gall-fly," *Cecidomyia* (Fig. 97); the Horse-fly, *Tabanus*; the Bot-fly, *Oestrus*; the common House-fly and Blue-bottle, *Musca*, and many others. The Flea, *Pulex irritans*, which is wingless but endowed with considerable powers of jumping, is sometimes placed in a Sub-order of the Diptera, and sometimes in a separate Order.




FIG. 96. *Glossinia morsitans*, the Tsetse-fly.




FIG. 97. *Cecidomyia destructor*, the Hessian-fly.

1. Insect. 2. Larva. 3. Pupa or "flax seed." All magnified.

Order VIII. Lepidoptera.

The Lepidoptera (Gk. λεπίδωτός, covered with scales) have mouth-parts adapted for sucking only. The two pairs of wings are similar in appearance and covered with scales (flattened spines) which give rise to the beautiful pattern on the wings but are easily rubbed off. None of the wings fold up, and when not in use are either held erect or are depressed on each side of the body. The metamorphosis is complete.

This Order is very clearly defined and the members show a marked resemblance one to another. It includes the Butterflies

and Moths, and all of them exhibit a very definite and complete metamorphosis. The eggs give rise to worm-like larvae known as caterpillars, which consume much food, generally of a vegetable nature (Fig. 89). After a considerable time, varying from a few weeks to three years, the caterpillar comes to rest, and in such cases as the Silk-worm Moth, *Bombyx mori*, surrounds itself by a case or cocoon spun by itself, which furnishes the material silk (Fig. 90). Within this cocoon, or in some species without forming a cocoon, the caterpillar forms a pupa, and whilst in this state it undergoes a very thorough reorganization and gradually the mature Insect is built up; after a certain time this emerges and occupies its comparatively short life in the propagation of its species (Fig. 91). The female usually deposits its eggs on or near the plants which serve as food for its offspring.

Class III. ARACHNIDA.

The third large group of the Arthropoda is a very varied one and contains many animals which differ markedly in their structure one from another. Perhaps the most distinctive features of the

External features.	Arachnida (Gk. ἀράχνης, a spider; εἶδος, shape) are (i) There are no true gnathites. No appendage loses all other functions and becomes exclusively a jaw, although the proximal joints of several are prolonged inwards towards the mouth and help to take up food; in a word some of the limbs have developed gnathobases; (ii) The most anterior appendages are never antennae but always a pair of nippers, termed chelicerae; (iii) The active catching and walking legs of the fore part of the body or prosoma are strongly contrasted with the plate-like modi- fied limbs of the middle part of the body, or mesosoma when the latter exist, but in many cases these have disappeared and in others have become so modified that they are no longer recognisable as limbs. Nearly all Arachnids moreover agree in having the anterior end of the body, the prosoma ¹ as it is called, marked off from the rest and covered by a single piece, the carapace. The rest of the
-----------------------	---

¹ The name cephalothorax is often applied to this region, but the term is too misleading to be used. The cephalothorax of Decapod Crustacea includes the first fourteen segments of the body: the prosoma of Arachnida only includes six, and therefore corresponds roughly to the "head" of the higher Crustacea. Similar criticism might be launched against the use of the word "abdomen," but here the error is too deep-rooted for correction since the term is used in describing both Crustacea and Insecta, and in each case in a different sense.

body or abdomen is in some forms differentiated into two regions, the mesosoma and metasoma, but in other cases this distinction does not exist; it may be segmented or it may not. The prosoma bears six pairs of appendages, and of these the last four are usually walking legs. The appendages of the abdomen are connected with the respiratory function and are much modified, often—in the terrestrial forms—forming floors for the respiratory chambers. The breathing apparatus may be tracheal, or in a few marine forms branchial, or may take the form of respiratory chambers, the last named and the gills have a peculiar form found only amongst Arachnida. They consist of “books” of thin superposed lamellae attached to the posterior aspect of an appendage. When modified for breathing air these “books” are called lung-books. When, as is the case in *Limulus*, they breathe oxygen dissolved in water they are called gill-books. The genital orifice is usually on the anterior end of the abdomen, ventral; and the group is bisexual. Many different Orders are included in the Arachnida, the best known being perhaps those which include the Spiders, the Harvestmen, the Mites and the Scorpions. The last named are only found in warm climates, and Mites are too small for investigation with the naked eye, so that we will take the Spider as an example of Arachnid structure.

Order I. Araneida.

Spiders belong to the Order Araneida (Lat. *arana*, a spider), in which the abdomen is unsegmented and soft. The second pair of appendages called the pedipalpi are leg-like and modified in the male in connexion with the fertilization of the female. The abdomen bears certain modified appendages called spinnerets, on which open the glands, the secretion of which produces the Spider's web. If we examine such a Spider as *Epeira diademata*, which is common enough in English gardens, sitting on or near its wheel-shaped web (Fig. 98), we notice that behind the prosoma there is a slender waist and that this is followed by a large swollen abdomen with no outward trace of division into segments, or into meso- and meta-soma.

There are six pairs of appendages, and it is at once noticeable that there are no antennae or feelers to act as sensory organs. Their function is to some extent taken over by the long walking legs. The first pair of limbs are called chelicerae; in *Epeira* these are two-jointed, the terminal joint

External
structure.

being pointed and folded down against the basal joint except being used (Fig. 99). This pair of appendages contains poison glands and the poison escapes through an opening at the point




FIG. 98. The Garden Spider, *Epeira diadema*, sitting in the centre of its web. After Blanchard.




FIG. 99. Front view of the head of a Spider, *Tetrrix denticulata*. Magnified. From Warburton.

1. Head. 2. Eyes.
3. Basal joint of chelicerae.
4. Claw of chelicerae.

of the second joint. By means of it the Spider can kill insects and seriously hurt larger animals.

The second pair of appendages in the Arachnida are called pedipalpi (Fig. 100). In *Epeira* they resemble the walking legs, but in the male at the final moult the last joint becomes altered and forms a hollow sac—the palpal organ—which plays an important part in fertilizing the female.

Then follow four pairs of walking legs, each with seven joints and terminated with two or three claws; in some species they are provided with a pad of short hairs called a scopula, which helps the animal to run on walls and ceilings.

The mouth is very minute, for the Spider does not swallow solid food but sucks the juices of its prey. It lies between the bases of the pedipalps, and the basal joint of each of these appendages has a cutting blade termed the "maxilla" (2, Fig. 100). It is a common feature of the Arachnids that the basal joints of one or more of the pairs of appendages are produced inwards towards the mouth and act as jaws, but the modification never goes so far as to obscure the limb-like form of the appendage and so produce a true gnathite.

On the ventral surface of the abdomen, just behind the waist, is situated the genital opening, protected by a plate which is the result of the fusion of a pair of appendages, and on each side of this is the slit-like orifice of a lung-book. The lung-books are very remarkable structures. Each opens to the exterior by a pore through which the air enters, and consists of a sac, the cavity of which is largely occupied by a number of thin plates in the substance of which the blood circulates and is thus

brought into close relationship with the air which passes in and out between the neighbouring plates; the sac is floored in by a special plate which is a modified appendage (Figs. 63 and 65). Such a breathing apparatus is peculiar to the Arachnida. In some Spiders we find a second pair of lung-books placed behind the others, and in other species this second pair is replaced by a pair of tracheae recalling the respiratory mechanism of the Myriapods or the Insects (Fig. 63). They have however been independently developed, and probably owe their origin to the sac of a lung-book from which the lamellae have disappeared.

Near the hinder end of the abdomen are four tubercles or spinnerets, and if these be pushed aside, two more, shorter in length, come into view. These are the organs which form the web. They are very mobile and are




FIG. 100. Pedipalp of *Tegenaria guyonii*, the large house-spider.

1. Coxa. 2. Gnathobase, the so-called "maxilla." 3. Trochanter. 4. Femur.
5. Patella. 6. Tibia. 7. Tarsus. 8. Palpal organ.

pierced at their ends by hundreds of minute pores through which the silk exudes as a fluid, hardening on exposure to the air (18, Fig. 101).

The silk is secreted by a large number of glands which have their exit at the above-mentioned pores. Of these in *E. diademata* there are five different sorts and each secretes a special kind of thread; for the various lines in a Spider's web differ considerably one from another, in accordance with the use they are put to. The circular lines are sticky and help to catch insects for the Spider's food, the radial lines are stout and form a framework for




FIG. 101. Diagram of a Spider, *Epeira diademata*, showing the arrangement of the internal organs \times about 8. From Warburton.

1. Mouth. 2. Sucking stomach. 3. Ducts of liver. 4. Malpighian tubules. 5. Stercoral pocket. 6. Anus. 7. Dorsal muscle of sucking stomach. 8. Caecal prolongation of stomach. 9. Cerebral ganglion giving off nerves to eyes. 10. Sub-oesophageal ganglionic mass. 11. Heart with three lateral openings or ostia. 12. Lung sac. 13. Ovary. 14. Acinate and pyriform silk glands. 15. Tubuliform silk gland. 16. Ampulliform silk gland. 17. Aggregate or dendriform silk glands. 18. Spinnerets or mammillae. 19. Distal joint of chelicera. 20. Poison gland. 21. Eye. 22. Pericardium. 23. Vessel bringing blood from lung sac to pericardium. 24. Artery.

the support of circular lines; the threads with which the Spider binds up his captured prey differ from these, and there is still another kind of thread with which it constructs its cocoons, and each kind of line is supplied from different sets of glands.

The spinnerets have been shown to be the vestiges of appendages.

The dissection of a Spider requires much care, since the organs almost fill the body and are completely embedded in the large masses of the digestive and reproductive glands. The oesophagus, which leads from the mouth, opens into a strong sucking

"stomach," which is really like the stomach of the Cray-fish, a stomodaeum. This is attached by muscles to the chitinous exoskeleton, and when the muscles contract its cavity is enlarged and thus a sucking action is induced at the mouth (Fig. 101). Behind this is an endodermic portion of the alimentary canal which gives off certain caeca or blind tubes, followed by an intestine which traverses the abdomen and is further provided with a number of ducts which collect the products of a very capacious digestive gland or "liver." The intestine, which is also lined by endoderm, is followed by a short proctodaeum, the proximal portion of which is swollen up into a pouch called the stercoral pocket. It ends in an anus situated close behind the spinnerets.

Spiders possess two kinds of organs which excrete waste nitrogenous material: (i) the Coxal glands, which are true nephridia, i.e., glandular tubes running between a reduced coelom and the exterior, and (ii) Malpighian tubes, a pair of simple pouches opening into the endodermal intestine. The coxal glands are better developed in some species, such as the common House-spider, *Tegenaria derhamii*, than is the case in *E. diademata*, where they are very degenerate and where their functions seem to have largely passed to the Malpighian tubules. In fact these structures are an interesting example of a set of organs degenerating in consequence of their functions having been assumed by another set.

The heart of the Spider is of the same general type as that of Myriapods; it is a tube with paired slit-like openings—ostia—at the sides through which the blood enters, to be driven out again through certain rather ill-defined vessels, to circulate in the spaces between the various organs.

The nervous system is concentrated; there is a bi-lobed ganglion above the oesophagus which gives off nerves to the eyes and the chelicerae; this is connected by two lateral cords, which pass one on each side of the oesophagus, with a large nervous mass situated in the thorax. From this, nerves pass off to supply the remaining five pairs of limbs, and two nerves arise which pass backward and supply the abdomen. The only conspicuous sense organs of Spiders are the eyes; of these in *E. diademata* there are four large eyes arranged in a square on the top of the head and two small ones on each side of the square. This number, eight, is not uncommon in Spiders, where both number of eyes and their disposition are much used in systematic classification.

The male, as is not uncommon amongst the Araneida, is

smaller than the female. The ovaries and testes lie in the abdomen and have the form of a network of tubes, a form characteristic of Arachnida; the spermatozoa are conveyed to the palpal organs of the pedipalpi of the male and by them introduced into pouches, the spermathecae of the female. The eggs are fertilized before




FIG. 102. Diagrammatic view of Palpal Organ.

1. Tarsus. 2. Bulb. 3. Vesicula seminalis. 4. Opening of vesicula seminalis. 5. Conductor. 6. Haematodocha. 7. Alveolus.

they are laid, which usually takes place in October, and they are then enclosed in cocoons of yellowish silk. The young are hatched out in the following spring and at once begin spinning. By means of the minute threads they secrete they weave a kind of nest about the size of a cherry-stone which hangs suspended from some twig or leaf. At the least disturbance the hundreds of young Spiders in the nest begin to disperse; the spherical nest breaks up as into dust, but when the disturbance is at an end the minute Spiders, so small as to be almost invisible, re-assemble and again form their spherical little nursery.

The number of species of Spiders is very great, and their habits are very diverse and well worthy of study.

Order II. Phalangida.

The Phalangids (Gr. *φάλαγγιον*, a venomous kind of spider) or Harvestmen are in common talk usually classed with Spiders, but they differ from the latter in having no waist, that is, the abdomen is not separated from the prosoma by a constriction, and they breathe entirely by tracheae. They have four long and very

slender pairs of legs, which easily break, and their eyes are sometimes elevated above the surface of the head on a tubercle like a look-out tower. The abdomen is distinctly divided into segments.




FIG. 103. A Phalangid or Harvestman, *Oligolophus spinosus*, adult male $\times 2$.

1. Chelicerae. 2. Pedipalps. 3, 4, 5 and 6. First, second, third, and fourth legs.

As a rule these creatures are nocturnal, and are usually met with in dark corners or amongst the stalks of hay or grass. Their long legs enable them to steal with a gliding spring upon their prey, for the most part insects or spiders, for they are carnivorous. They are dull in colour, grey, brown or blackish, as becomes an animal that loves the dusk. About twenty-four species have been recorded in Great Britain. Phalangids die down as winter sets in, but the eggs last through the cold weather and give rise to a new generation in the spring.

Order III. Acarina.

The Acarids (Gk. ἀκῆρῆς, a morsel) or Mites form an enormous order whose function in life is to a large extent to play the scavenger, and the terrestrial forms confer the same benefits on the dwellers on the Earth that the Ostracods and many of the smaller Crustacea do on the aquatic fauna. Many of them however have adopted parasitic habits and cause disease amongst larger animals, and induce the formation of galls and other deformities amongst plants. Most of the Mites, as their name indicates, are of minute




FIG. 104. *Tyroglyphus siro*, seen from the ventral side. A. Female. B. Male. Magnified. From Leuckart and Nitsche.

1. Pedipalpi. 2. Chelicerae. 3, 4, 5, 6. First, second, third and fourth walking legs.
7. Chitinous thickenings supporting legs. 8. Furrow round body.
9. Reproductive opening, flanked by two suckers on each side. 10. Anus. 11. Suckers at side of anus.

size; but the female Ticks, belonging to the family Ixodidae, which live amongst the undergrowth of forests, on the look-out for some vertebrate prey, can when they become attached to their hosts—man, cattle, or even snakes—by distending their bodies with the blood they suck, swell out to the size of hazel-nuts.

Anatomically they are difficult to characterize. Like the Phalangids, they have no waist, and when special breathing organs are present they take the form of tracheae; they differ however

from the Phalangids in never showing signs of segmentation. The chelicerae may be clawed or chelate, like a lobster's claws (Fig. 104), but they often take the form of piercing stylets and the pedipalpi may form a sheath to protect them.

The number of species is very great; amongst the commoner forms may be mentioned, *Tetranychus telarius*, often known as the Red Spider, which spins webs under leaves in which whole colonies shelter. This species is believed to do great damage in hot-houses. *Tyroglyphus siro*, the Cheese-mite, which burrows in decaying cheese, and the genus *Phytoptus*, which causes the conical galls on lime-trees, maples, etc., are also familiar.

Order IV. Scorpionida.

Scorpions are not found in Great Britain, though they are common on the Continent of Europe around the Mediterranean basin and generally in warm climates. They retain a more marked segmentation than is the case with the other Arachnids we have considered. The abdomen is very long, distinctly segmented and differentiated into two portions; (a) the mesosoma, consisting of seven segments of the same diameter as the prosoma, bearing the respiratory appendages; (b) the metasoma, a much narrower part, consisting of five segments and a curved spine like a tail at the apex of which is the opening of a poison gland. The mesosoma has six pairs of appendages. The first of these forms the genital operculum, a plate bearing on its posterior aspect the genital pore in both sexes; the second are "pectines," curious comb-shaped structures, whose exact function is not yet determined, but which are morphologically reduced and thickened gill-books. The third, fourth, fifth and sixth segments bear each a pair of lung-books, and it has already been explained that the floors of these are formed of highly modified plate-like appendages which have, in the adult, lost all trace of their origin from limbs. The seventh segment of the mesosoma shows no traces of limbs, and tapers to join the first segment of the metasoma. At the posterior end of the fifth metasomatic segment, on the ventral surface, is situated the anus, and behind this is a conical pointed joint which contains the poison glands and which forms a very efficient and powerful sting. The whole of this tail is very mobile and the sting can readily be directed to any point. In life the tail is usually borne turned forward over the body so that the sting threatens the head.




FIG. 105. A. Dorsal view of an Indian scorpion, *Scorpio swammerdami* $\times \frac{3}{2}$.
B. Ventral view of the same $\times \frac{3}{2}$.

- A. 1. Chelicera. 2. Pedipalp. 3, 4, 5, 6. 3rd to 6th appendages, or walking legs. 7. Lateral eyes. 8. Median eyes. 9. Soft tissue at side of body, pleura. 10. The poison sting or telson.
- B. 1—6 as in A. 7. The genital operculum. 8. The pectines. 9, 10, 11, 12. The four right stigmata leading to the four lung-books. 13. The last segment of the mesosoma. 14. The third segment of metasoma. 15. The telson. In each case the metasoma, which is usually carried bent forward over the meso- and pro-soma, has been straightened out.

Both the *chelicerae* which are small and short, and the *pedipalpi*, which are long and six-jointed, end in *nippers*, the latter recalling the appearance of the claws of a lobster. The four pairs of walking legs end in claws.

The mouth is very minute, for like the Spiders, Scorpions only suck the juices of their prey. They feed for the most part on Insects and Spiders. The basal joints of the first two pairs of appendages, like those of the pedipalps in Spiders, are all produced towards the mouth, forming *gnathobases* which probably help to hold their food.

Scorpions usually hide under rocks and stones during the day, being often very intolerant of heat, but they creep out as dusk comes on and run actively about. The Scorpion is viviparous, the young being born in a condition resembling their parents.

Order V. Xiphosura. C

A very peculiar aquatic Arachnid called *Limulus*, or popularly the King-crab, inhabits the warmer seas on both sides of the Pacific Ocean and along the shores of the Western Atlantic. It is a littoral form, that is to say, it lives not far from the shore; it burrows in sand or mud at a depth of from two to six fathoms, often lying with only its eyes, which are on the top of the body, exposed.

The shape of the body is something like a half-sphere with a piece cut out and a long spine is attached to the truncated side. This spine has given the name Xiphosura (Gr. *ξίφος*, a sword; *οὐρά*, a tail) to the order. The half-sphere is hinged, and the part in front of the hinge is the *prosoma*, the rest is the abdomen or meso- and meta-soma. On the upper surface of the half-sphere are a pair of simple eyes near the middle line, and there is a pair of compound eyes situated further back, nearer the edge. The under surface of the half-sphere is partially hollowed out, and concealed in this hollow on each side of the middle line of the *prosoma* are six pairs of appendages. The most anterior of these are typical nipper-like *chelicerae*, the next is not specially modified to form a *pedipalp*, but it and the remaining four pairs are walking legs. All of them send inwards a spiny *gnathobase*, which helps to form the border of the mouth. The sixth pair of limbs end in some flattened blade-like structures which assist in digging and burrowing in the sand and in extracting the worms which form the principal item of the diet of the King-crab. The seventh appendages, or the first on the




FIG. 106. Dorsal view of the King-crab, *Limulus polyphemus* $\times \frac{1}{2}$.

1. Carapace covering prosoma. 2. Meso- and meta-soma. 3. Telson.
4. Median eye. 5. Lateral eye.

its posterior surface a gill-book. There is a striking similarity between these organs and the "lung-books" of the Scorpion; the latter, however, do not project, but are sunk in pits. The metasoma terminates at the anus, but behind it a long sword-like tail projects. This post-anal tail corresponds with the swollen,

stinging tail of the Scorpion. It is used by the animal to right itself when it is upset by the motion of the waves.

A curious plate of fibro-cartilage to which muscles are attached lies inside the body near the ventral surface. It is formed of modified connective tissue in which a cheesy material termed chondrin




FIG. 107. Ventral view of the King-crab, *Limulus polydora*.

1. Carapace covering prosoma. 2. Meso- and meta-soma. 3. Telson.
 4. Chelicera. 5. Pedipalp. 6, 7, 8, 9. 3rd to 6th appendages,
 ambulatory limbs. 10. Genital operculum turned forward to show the
 genital aperture. 11, 12, 13, 14, 15. Appendages bearing gill-hooks.
 16. Anus. 17. Mouth. 18. Chilidia.

has been deposited in the ground substance, and is largely built up of interlacing tendons of muscles so that it acts as an internal supporting structure or endoskeleton. It is called the endosternite.

CHAPTER VIII.

PHYLUM MOLLUSCA.

MOLLUSCA (Lat. *mollis*, soft) is the name which is given to one of the largest and most important phyla of the animal kingdom. In it are included not only our terrestrial snails and slugs and many fresh-water species but also the oysters, mussels, periwinkles, whelks, and countless other species of "shell-fish," bivalve and univalve, which crowd the rocks laid bare at low-water around our coasts: and in addition to these, the extraordinary Octopuses, Squids, and other forms of Cuttle-fish belong to the same great phylum. The name Mollusca seems to have been suggested by the fact that the members of the phylum do not possess any internal hard parts such as are found in Man and other vertebrates. This softness of internal constitution is shared by other classes with no relation to the Mollusca, as for instance the great group of the Arthropoda. The Arthropods however possess a horny covering which closely invests them, following every irregularity of their outlines, so that it seems a real part of themselves. This is the exoskeleton or cuticle, and constitutes one of the great differences between them and the Mollusca. The latter, it is true, possess also an exoskeleton composed principally of calcareous matter, but this adheres only to a part of the surface. It is usually very thick and easily detached, and so it is frequently looked on as a separate thing from the animal and is known as the shell. The shell is to be looked on as a secretion, produced by a part of the skin only: this part of the skin, which almost always projects from the rest of the body as a flap, is called the mantle. The space between the mantle-flap and the rest of the body is known as the mantle-cavity. The mantle-cavity shelters the gills or organs of respiration, and into it open the kidney or kidneys and the anus, and usually also the genital ducts.

General
description.

CLASS I. GASTEROPODA.

In order to fix our ideas we may take the common English garden snail, *Helix aspersa*, which has also established itself throughout North America from Nova Scotia to New Orleans, or, if procurable, the larger *Helix pomatia*, which on account of its size is easier to dissect, as a type of the Mollusca. In Lower Canada the genus *Helix* is not very

Description
of Snail.




FIG. 108. *Helix pomatia*. Side view of shell and animal expanded. From Hatschek and Cori.

1. Mouth. 2. Anterior tentacles. 3. Eye tentacles. 4. Edge of mantle.
5. Respiratory pore. 6. Anus. 7. Apex of shell. 8. Foot.
9. Reproductive aperture.

abundant, and the largest species, *Helix albolabrus*, is too small for convenient dissection. *Limnaea stagnalis*, the large river-snail, is however common and easy to obtain, and its structure is similar in the main outlines to that of *Helix*.

The shell is coiled into a spiral form; the body contained in it consists of a visceral hump, coiled like the shell and closely adhering to it, and of a portion which we call the head, neck, and foot, which can be drawn within the opening of the shell if the animal is alarmed, but which under ordinary circumstances is quite outside it. The snail is devoid of anything in the nature of legs,—an important character of the Mollusca as contrasted with the Arthropoda,—but the part of the body next the ground is a flat muscular surface, called the foot. By means of wave-like contractions of the longitudinal muscular fibres of this organ the snail moves along, always preparing the ground for itself by depositing a layer of slime on it. This slime is poured forth from a gland which opens in front of the foot, just beneath the mouth

(14, Fig. 111). The foot is one of the most important organs of the Mollusca; it takes different shapes in the different groups but always assists locomotion. In the pond-mussel, for instance, it is shaped like a wedge, in order to force a path through the soft mud at the bottom of the ponds in which the animal lives. The different shapes which the foot assumes afford the chief basis for the classification of Mollusca.

The head of the snail bears two pairs of feelers, or tentacles, which are hollow outgrowths of the body-wall (2, 3, Fig. 108): these when irritated are protected by being pulled outside in, and so are brought into the interior of the body. The first or shorter pair are supposed to be the chief seat of the sense of smell: the second and longer pair have at their tip a small pair of black eyes. These eyes are merely minute sacs, the walls of which are made of light-perceiving cells, connected at their bases with a nerve which leads to the brain; in the cavity of the vesicle is a horny lens which nearly fills it up. The eyes of nearly all the Mollusca are constructed on the same plan, but in the Cuttle-fish, not only is the vesicle large and spacious and the lens proportionately smaller, but there is in addition a series of folds of skin surrounding the place where the eye comes to the surface, which constitute an outer chamber, and outside this, eyelids, so that the whole organ acquires a superficial similarity to the human eye.

If we carefully pick away the shell of the animal and lay bare the visceral hump, brushing away any mucus which may adhere to the body, we shall see on the right side of the animal a round hole (5, Fig. 108). A bristle passed through this reaches into a large cavity separated from the outside by an exceedingly thin wall. This space is nothing but the mantle-cavity, which, as explained above, is the space comprised between the projecting mantle flap and the rest of the body. The peculiarity about the snail is that the mantle edge has become fused to the back of the neck so as to shut the mantle-cavity off from the exterior, leaving only this little hole of communication. The mantle-cavities of the marine allies of the snail, such as the whelk and periwinkle, are not so completely shut off, inasmuch as in them the mantle flap merely lies against the neck but is not fused to it, and inside the mantle-cavity there is a gill. This gill consists of a hollow axis bearing on one or both sides a close set row of thin plates inside which the blood circulates and receives oxygen from the water by diffusion. Fresh supplies of water are drawn into the mantle-cavity by the action of myriads of

cilia which cover the gill. A gill of this nature is called a ctenidium, owing to its comb-like appearance (Gr. κτενίδιον, a small comb). Now, since the snail breathes air, not water, it has lost the gill, but to compensate for the loss it has changed the whole mantle-cavity into a lung. The floor of the mantle-cavity, really the back of the neck, is arched and composed of muscles: when these contract the floor flattens, and thus the mantle-cavity is enlarged and air is drawn in.




FIG. 109. *Helix pomatia*. The animal seen from the dorsal side after removal of the shell. From Hatschek and Cori.

1. Auricle of the heart receiving pulmonary vein. 2. Anterior tentacles.
3. Eye tentacles. 4. Edge of mantle.
5. Nephridium. 6. Liver. 7. Albumen gland. 8. Pulmonary vein.
9. Foot.

The blood is contained in large vessels running in the thin roof of the mantle-cavity: these are clearly seen when the mantle flap is clipped away from the neck and turned over to the right (8, Fig. 109. and Fig. 110). These vessels are seen to all converge to the heart, which consists of two small oval sacs placed end to end. That into which the vein enters is thin-walled and is called the auricle: the other thicker one is called the ventricle (Fig. 110); it is the more muscular of the two and drives the blood through two arteries to the body. One of these passes up to the visceral hump, and the other forward to the head and neck. In Molluscs which have gills the auricle always receives the blood from the gill: when there is one gill, as is the case with nearly all the uni-valves, there is only one auricle: but where, as in the bivalves and cuttle-fish, there are two or even four gills (as in *Nautilus*)

there are likewise two or four auricles. The heart is surrounded by a space called the pericardium, which really corresponds to the body-cavity or coelom of Vertebrates, Annelids, and Echino-

derms, for into it the excretory organ opens and in the embryo the genital cells are budded from its wall. Other large spaces existing in the head and neck have no connexion with the coelom but are really parts of the blood system. Since there are no regular veins, except those which run in the mantle-roof, the arteries open into irregular spaces. It will be remembered that the space called pericardium amongst the Arthropods is really a blood space and that the heart opens into it by openings called ostia: the coelomic character of the pericardium of Mollusca is then another distinguishing

Internal
structure.

feature of the group. It opens by a narrow ciliated passage, the reno-pericardial canal, into the kidney, which is seen in the mantle-roof beside the pericardium (5, Fig. 109). The kidney looks like a solid yellow organ; but in reality it is a vesicle into the cavity of which numerous folds project, covered by the peculiar cells which have the power of extracting waste products from the blood, which flows in spaces in the kidney wall. The kidney communicates with the exterior by a narrow thin-walled tube, the ureter, which runs along the right side of the body and opens on the lip of the respiratory opening, just above the opening of the anus (10, Fig. 112).

The kidney in Mollusca varies a good deal in structure, but is always built on the same funda-




FIG. 110. *Helix pomatia*, with the upper wall of the pulmonary chamber cut open and folded back. From Hatschek and Cori.

1. Ventricle. 2. Anterior tentacles. 3. Eye tentacles. 4. Cut edge of mantle.
5. Respiratory pore. 6. Anus. 7. Opening of ureter. 8. Foot. 9. Auricle receiving pulmonary vein. 10. Rectum.
11. Nephridium. 12. Upper wall of pulmonary chamber.

mental type as that of the Snail. Where there are two gills there are likewise two kidneys. Often there is no ureter, but the kidney opens directly to the exterior, as in the cuttle-fish, the whelk (*Buccinum*), the limpet (*Patella*). In the cuttle-fish instead of irregular spaces there are regular veins in its walls, and the folds covered with special cells are only developed over the course of these veins.

Turning now to the digestive system of the snail we notice several very interesting peculiarities. The mouth is situated in front, beneath the small pair of tentacles, and there is a curved horny bar, the jaw, in the roof of the mouth. Against the jaw works a rasp-like tongue, called the radula, the surface of which is a horny membrane covered with myriads of minute, recurved teeth. Underneath this membrane there are certain small pieces of cartilage to which muscles are attached, which pull the cartilages and the membrane covering them alternately downwards and forwards, and upwards and backwards, so that the tongue is worked against the jaw. Thus the snail is enabled to tear pieces out of




FIG. 111. Inner view of right half of head of *Helix*, to show the arrangement of the Radula $\times 2$.

1. Mouth. 2. Horny jaw. 3. Radula. 4. Cartilaginous piece supporting radula. 5. Radula sac from which radula grows. 6. Muscle which retracts the buccal mass. 7. Intrinsic muscles which rotate the radula. 8. Cerebral ganglion. 9. Pedal and visceral ganglia. 10. Oesophagus. 11. Anterior tentacle. 12. Eye tentacle. 13. Orifice of duct of salivary gland. 14. Mucous gland which runs along foot and opens just under the mouth.

the leaves on which it feeds (Fig. 111). A similar organ is found in all Mollusca, except the Bivalves or Lamellibranchiata, and the number, shape, and arrangement of the teeth are an important help in classification. The horny membrane is continued backward into

a little blind pouch, called the radula sac: here is its growing-point, where new teeth are continually being formed as the old ones wear away. In the limpet (*Patella*), this radula sac is extra-




FIG. 112. *Helix pomatia*, opened and the viscera exposed.
From Hatschek and Cori.

- | | | |
|---|------------------------------------|---|
| Pharynx. | 2. Oesophagus. | 3. Salivary glands, with duct. |
| 4. Stomach. | 5. Liver. | 6. Rectum. |
| 7. Anus. | 8. Kidney. | |
| 9. Inflated commencement of ureter. | 10. Opening of ureter to exterior. | |
| 11. Ventricle. | 12. Auricle. | 13. Pulmonary vein. |
| 14. Opening of nephridium into pericardium. | 15. Ovo-testis. | 16. Common duct of ovo-testis. |
| 17. Albumen gland. | 18. Female duct. | 19. Male duct. |
| 20. Spermatheca. | 21. Flagellum. | 22. Accessory glands. |
| 23. Penis. | 24. Dart sac. | 25. Vagina. |
| 26. Eye tentacle, retracted. | 27. Anterior tentacle, retracted. | 28. Muscles which retract the head, pharynx, tentacle, etc. |

ordinarily long, attaining a length two or three times greater than that of the body. In the cuttle-fish the radula is present and the jaw is developed into upper and lower beaks, like those of a parrot, with which the animal tears its prey to pieces. The Bivalves have lost all trace of both jaws and radula: they live on the microscopic organisms which the currents of water which they produce may bring to them, and so they do not need to masticate their food.

The radula sac, and the muscles and cartilages belonging to the radula, form a swelling which is called the buccal mass. Behind this comes the oesophagus or gullet, which appears narrow by comparison, but its cavity is really as large as the space inside the buccal mass. The gullet soon widens out into the first stomach or crop, which is used for storing the food. On the outside or surface of this two branching whitish structures are seen, the salivary glands. They secrete a juice which runs forwards through two tubes, the salivary ducts opening into the buccal mass. The saliva mingles with the food as it is being masticated. The crop is situated in the hinder part of the neck, and behind it the alimentary canal passes under the mantle-cavity and up into the visceral hump. The great mass of this hump is occupied by a brownish looking organ, called the liver. This, like the similarly named organ in the Arthropoda, is a great mass of tubes, lined by cells of a deep brown colour: the tubes join together and eventually open by two main tubes, one above and one below, into a dilatation of the alimentary canal. This swelling is the true digestive stomach. It is probable that the "liver" assists digestion by preparing a fluid which is poured into the stomach: its function is thus not the same as that of the human liver. In fact it must be confessed that the name liver has been recklessly given by the older naturalists to any brown-coloured organ found near the stomach of an Invertebrate. The part of the alimentary canal behind the true stomach is called the intestine. It takes a turn in the liver substance and then runs out of the visceral hump along the right side of the body, to open by the anus, which, as we have seen, is placed just behind the respiratory opening.

The central nervous system resembles that of the Annelida in being made up of ganglia, each of which might be compared to a miniature brain, connected together by means of commissures, that is, bands of nerve fibres. The two largest ganglia, which are placed above the oesophagus, one at each side, and connected by a commissure, are called the supra-oesophageal or cerebral ganglia,

or sometimes the brain (1, Fig. 113); but there is no reason to think that they are any more important to the animal than the others. Underneath the oesophagus there is what at first sight seems to be a compact nervous mass, connected with the supra-oesophageal ganglia by a commissure on each side forming a nerve collar (Fig. 113). Closer inspection shows that this mass is perforated by a hole through which passes the great anterior artery from the ventricle, and that from both the lower and upper halves a separate nerve comes off to go to the cerebral ganglia. Thus the apparently simple nerve collar consists of two commissures on each side, united in a common sheath. Between them a minute nerve passes down, to end finally in a minute membranous sac, lined by ciliated cells and cells with sense hairs, and containing fluid in which a little ball of carbonate of lime floats. This sac, the otocyst, is the only other important sense-organ, besides the eyes, which the snail possesses. It is difficult to dissect, but if the small bivalve *Cyclas* be taken, the shell opened and the foot cut off and slightly compressed, or if one of the transparent Molluscs, such as *Pterotrachea*, which float at the surface of the sea, be examined, it is perfectly easy to see both otocysts with the microscope. It used to be supposed that the function of this organ was to perceive sound, but whilst it is probable that some vibrations of the air affect it, it is nearly certain that, like the otocysts of Medusae and Arthropoda, its main function is to enable the Mollusc to keep its balance by allowing it to perceive whether it is leaning on one side or not. As the snail changes its position the little ball inside rolls about and affects different parts of the wall of the vesicle, and hence probably different fibres in the nerve which supplies it.

Not all Mollusca possess eyes, but all, except perhaps the Oyster, which never moves, possess otocysts. The experiment has




FIG. 113. View of nervous system of *Helix pomatia*.

1. Cerebral ganglion. 2. Pedal and visceral ganglia. 3. Buccal ganglia. 4. Nerve to lips. 5. Olfactory nerve. 6. Optic nerve. 7. Pleuro-cerebral commissure. 8. Pedo-cerebral commissure. 9. Genital nerve. 10. Nerve to mantle. 11. Nerve to viscera.

been made in the Cuttle-fish of cutting them out, and it is then found that the animal loses its power of keeping its balance in the water and tumbles about.




FIG. 114. Optical section through the auditory vesicle or ear of *Pterotrachea friederici*, a transparent, pelagic Mollusc \times about 150. After Claus.

1. Auditory nerve.
2. Ciliated cells.
3. Auditory cells.
4. Large central auditory cell.
5. Supporting cells.
6. Otolith.




FIG. 115. Nervous system of *Limnaea*. After Lacaze Duthiers.

1. Cerebral ganglion.
2. Pedal ganglion.
3. Oesophageal ganglion.
4. Pleural ganglion.
5. Abdominal ganglion.
6. Visceral ganglion.

To return to the central nervous system. In the pond-snail, *Limnaea*, the hinder part of the sub-oesophageal nervous masses consists of no less than five ganglia, strung together on a short loop of nervous fibres, which is called the visceral loop. Of these a pair nearest the head are called the pleural ganglia, the next are called the visceral ganglia, and the one at the end the abdominal ganglion (Fig. 115). The front and lower part of the sub-oesophageal nervous mass consists of the pedal ganglia, which sends nerves exclusively

to the foot. Pleural and visceral ganglia can be recognised in the young snail, but they become indistinguishably joined in the older one. In other Molluscs, such as the Sea-hare (*Aplysia*), or the Ear-shell (*Haliotis*), the visceral loop is long and the ganglia widely separated. In these animals it can be seen that the pleural ganglia send nerves to the sides of the body, and that from the visceral ganglia nerves come off which go to the base of the gill or gills. At the base of each gill

there is a patch of thickened skin, called an osphradium (Gr. *ὀσφραίνομαι*, to smell), provided with numerous sense-cells, which enables the animal to test the water which enters its mantle-cavity. Of course no such organ exists in the snail. The muscles of the radula are supplied by nerves from a special pair of small ganglia placed on the buccal mass—the buccal ganglia—connected with the supra-oesophageal ganglia.

We thus see that the nervous system of the snail consists of a pair of supra-oesophageal ganglia connected by commissures with (a) a pair of pedal ganglia supplying the muscles of the foot with nerves, (b) an extremely short visceral loop, the ganglia on which are so closely placed as to become practically confluent with each other, whence nerves go to all parts of the body, and (c) a small pair of buccal ganglia supplying the buccal mass. The nervous systems of all Mollusca are built on this plan: in the bivalves, however, where there is no radula, not only are the buccal ganglia absent, but the pleural and cerebral are fused with one another, and, as the visceral loop is long, we find three widely separated pairs of ganglia,—cerebro-pleural, pedal and visceral—the last named often termed parieto-splanchnic, in different parts of the body. The Cuttle-fish have a closely massed nervous system, like the snail, which is protected in a kind of rudimentary skull, made of cartilage.




FIG. 116. Nervous system, osphradium (olfactory organ) and gills of *Haliotis*. After Lacaze-Duthiers.

- | | |
|-------------------------|----------------------|
| 1. Cerebral ganglion. | 2. Pedal ganglion. |
| 3. Osphradial ganglion. | 4. Pleural ganglion. |
| 5. Abdominal ganglion. | |
| 7. Nerves to mantle. | 8. Gills. |
| | 9. Pedal nerves. |

The only organs of the snail which remain to be mentioned are the reproductive organs. These are exceedingly complicated in the snail, both sexes being united in the same individual, a condition of affairs which is known as hermaphroditism. The essential genital organ is the ovotestis, a small yellowish patch of delicate tubes spread out on the surface of the liver, on the inner side of the uppermost coil of the spire (Fig. 112). This organ produces both eggs and spermatozoa, and both travel down a single tube. Before the duct reaches the neck it receives the secretion of a large organ, called the albumen gland. This secretion consists of a fluid which has proteids in solution and is of high nourishing value. Beyond the albumen gland, although externally simple, the duct is divided by a septum into two passages, one for the eggs and one for the spermatozoa, and still further on it becomes completely divided into two separate tubes. The female portion opens to the exterior by a thick-walled muscular part, the vagina, into which a tuft of tubes—the mucous glands—open. The vagina also receives the opening of an organ, called the spermatheca, which is a round sac at the end of a long duct, in which the spermatozoa received from another individual are stored up. In addition to this, a thick-walled sac, called the dart-sac, also communicates with the vagina. In this sac is found a calcareous rod which is thrown out into the body of another individual about the time of fertilization. The male duct opens also into a muscular organ, called the penis, which can be partly everted, that is, turned inside out, and so protruded. The function of this organ is to transfer the spermatozoa to another individual; it has a blind pouch projecting inward beyond the place where the male duct enters it, called the flagellum; in this the spermatozoa are massed together into bundles, called spermatophores. Both penis and vagina have a common genital opening far forward on the right side of the neck (Fig. 108).

Few Mollusca have such complicated generative organs as the snail. One large group of marine snails, the Opisthobranchiata, resemble *Helix* in being hermaphrodite, but none possess the dart-sac, and in many the generative opening is placed further back and connected with the opening of the penis by a groove, called the seminal groove. Hence the penis is obviously derived from a muscular pit on the side of the head into which the spermatozoa trickled, and was at first unconnected with the generative opening.

In another group of marine snails, the Prosobranchiata, there is

a separation of the sexes, and there is no albumen gland. The penis is not a sac which can be turned inside out, but a projecting lobe of the body, often of great size. In the most primitive Mollusca—the Solenogastres—the genital organ remains throughout like a thickening of the wall of the pericardium or coelom; the eggs and spermatozoa drop into the pericardium and find their way out by the nephridia, just as is the case with Annelida.

This is the case also in Cephalopods, where, however, there were originally four kidneys, and the one or two which serve as generative ducts are specialized for this purpose; thus the duct is in the male prolonged into a papilla, which serves as the penis. A commoner case is for the generative organ to be closely connected with one kidney and to burst directly into it. This is found in the simpler Prosobranchiata, such as the Limpet (*Patella*), the Ear-shell (*Haliotis*), and their allies. In *Nucula* and the simplest bivalves there are two generative organs, and they open into both kidneys; in the Pond-mussels, *Anodonta* and *Unio*, and the more modified forms, they open independently close to the kidney opening. There is little doubt that in all Mollusca the tube conveying away the generative products was originally a kidney or a part of one.

Having got some idea of the arrangement of the organs of the snail, we must proceed to consider some points about the form of the body considered as a whole. If we except the genital opening, the head and neck of the snail are exactly bilaterally symmetrical in their outer form; on each side there is a taste-tentacle and an eye-tentacle, and the mouth and the opening of the slime gland are exactly in the middle line. Most of the ordinary animals we see—birds, quadrupeds, fishes, insects, worms, etc.—are bilaterally symmetrical with regard to the exterior, and many with regard to the whole body. The peculiarity of the snail is that, whilst it follows the ordinary rule as far as the head, neck and foot are concerned, it departs from it with respect to the visceral hump and the included organs. The shell is, as we all know, spiral, but this shape is due to the shape of the visceral hump contained within it, by the activity of the skin of which the shell is produced. This spiral shape again is simply due to one side being longer than the other, and it is connected with the shortness of the right side, that we find the opening of the vent on the right side. In all bilaterally symmetrical animals this opening is situated in the middle line, but in some of the marine allies of the snail—the whelk, limpet, and others forming the group

Asymmetry
of body.

snail is generally small or has quite disappeared, and since where this has taken place there seems to have been a tendency to undo the twisting, the anus becomes pushed back to nearly the middle line, and the visceral loop becomes straightened out and shortened. There is reason to believe that this last process has gone on in the snail, although it has kept its shell. It appears then that the curious spiral form of part of the body and the inequality of the sides, has something to do with the possession of a large shell by a crawling animal. We do not understand very clearly how the one thing has brought about the other, but we can understand that there would be a tendency in a tall visceral hump to topple over to the one side or the other, and thus exercise a greater strain on one side than on the other. Certain it is, at any rate, that the only existing Mollusca which possess large coiled shells and yet are bilaterally symmetrical, are the pearly *Nautilus* and another rare Cuttle-fish (*Spirula*), which do not crawl but swim.

The class or primary division of the Mollusca to which the snail belongs is called the Gasteropoda, on account of the flat smooth foot or crawling surface which they all possess (Gr. γαστήρ, the belly; πούς, πούς, foot). The shell is typically composed of a single piece, never of paired pieces; and from this circumstance is derived the common term univalve often applied to the Gasteropoda by collectors; in one small division of the class (the Isopleura) the shell is represented by eight pieces placed one behind the other in the middle line.

Class II. LAMELLIBRANCHIATA OR PELECYPODA.

The characters mentioned at the end of the last section sharply separate the Gasteropoda from another class of Mollusca, the Lamellibranchiata or Pelecypoda, to which the common mussel and innumerable marine forms, such as the oyster, clam, cockle, etc., belong. The Molluscs belonging to this class have a shell composed of two similar pieces, the right and left valves, united by a horny flexible piece, the hinge (Fig. 117). The foot is typically formed like a wedge or axe-head,

Fresh-water
Mussel.




FIG. 117. Shell containing *Anodonta mutabilis*, and behind it the inner face of an empty left shell.

1. Points of insertion of the anterior retractor, above, and protractor muscles, below. 2. Point of insertion of the anterior adductor muscle. 3. Point of insertion of the posterior retractor. 4. Point of insertion of the posterior adductor muscle. 5. Lines formed by successive attachments of the mantle. 6. Umbo. 7. Dorsal siphon. 8. Ventral siphon. 9. Foot protruded. 10. Lines of growth.

whence the name Pelecypoda (Gr. πέλεκυς, a hatchet), and is used as a plough to force a way through the mud in which the creatures live. There are a great number of pond- or river-mussels, some 500 species at least in North America: *Anodonta anatina* is perhaps the commonest in England, but in places *Unio pictorum* is abundant; *A. anatina* occurs in Canada and the United States, and in these countries *Unio complanatus* is also common. Any one of these

forms will serve our purpose. The shell is about four inches long


The Shell. and two inches high, and is covered with a black horny layer, the so-called periostracum. The shell is apt in places to be eroded by the action of the carbonic acid in the water. Underneath it is a thick, slightly translucent layer of crystals of limestone, called the prismatic layer. The inner part next the mantle is composed of thin layers placed one above the other. This is the mother-of-pearl, or nacreous layer, which in many Molluscs has an iridescent sheen, owing to its action on light. These three layers are also present in the shell of the snail and in all other Molluscan shells, but they are very easily made out in the shell of the pond-mussel. To the periostracum the colour of the Molluscan shell is mainly due. The periostracum and prismatic layers are formed by the edge of the mantle, and if destroyed they cannot be replaced. The nacreous layer is deposited by the whole surface of the mantle. If by chance a grain of sand gets wedged in between the mantle and the shell, it is apt to become covered with layers of mother-of-pearl, and in this way a pearl is formed. The shell is marked by a series of curved lines running parallel to one another. These lines mark the limits of growth attained in each year, the amount intervening between two lines being the amount of growth accomplished in a year. It will be seen that the common focus around which the curves run is not in the centre of the hinge line, but decidedly nearer one end. This common focus is called the umbo, and it represents the shell with which the *Unio* started life (6, Fig. 117). The end of the shell nearer which it is placed is the anterior end.

As might be expected from the shape of the shell, the mantle has the form of two great flaps hanging down at the sides of the body. The flaps have a free edge in front, below, and behind, but pass into the general wall of the body, with which they fuse, above. The edges of the mantle flaps are very much thickened and closely adherent to the shell; as stated above, it is by these edges alone that the periostracum and the prismatic layer are formed.

The hinge is, strictly speaking, part of the shell; it is secreted by the ectoderm of the back of the animal between the two mantle lobes. When the valves of the shell are pressed closely together the hinge is bent out of shape, and by its elasticity it tends to throw the valves apart, and hence when a mussel is dead the valves always gape.

The two valves in *Unio* articulate with one another by means

of teeth. There are a pair of stout teeth a little in front of the umbo, on the left valve, working on either side of one tooth on the right valve; these are called the cardinal teeth. A long ridge on the right valve, working between two ridges on the left valve, is called the lateral tooth. Anodonta derives its name (Gr. ἀν-, not; ὀδούς, ὀδόντος, a tooth) from the circumstance that the shell is devoid of teeth.



6. 118. Right side of *Anodonta mutabilis* with the mantle cut away and the right gills folded back \times about 1. From Hatschek and Cori.

1. Mouth. 2. Anus. 3. Cerebro-pleural ganglion. 4. Anterior adductor muscle. 5. Anterior retractor muscle. 6. Protractor muscle. 7. Dorsal siphon. 8. Inner labial palp. 9. Foot. 10. External opening of nephridium or organ of Bojanus. 11. Opening of genital duct. 12. Outer right gill-plate. 13. Inner right gill-plate. 14. Ventral siphon. 15. Epibranchial chamber, the inner lamellae of the right and left inner gills having been slit apart. 16. Posterior retractor muscle.

When the shell is removed from the animal the cut ends of the fibres of two large muscles are seen. These muscles, which run

The Body. transversely from the one valve to the other, are called

the anterior and posterior adductors, respectively, and it is by means of them that, when danger threatens, the animal closes the valves and shelters foot, gills, and body, within. Just behind the anterior adductor are a pair of small muscles, running into the foot, and these are the anterior retractors. A similar pair, the posterior retractors, are found just in front of the posterior adductor, and by the combined action of the four the foot is drawn back within the valves (Figs. 118, 121): The foot is thrust forth by the forcing of blood into it, through the contraction of the muscles which underlie the skin in various parts of the body, aided by the action of a pair of small muscles called protractors,

the fibres of which are attached to the shell low down, close to the foot, and from thence run upwards and backwards. The animal moves by forcing out the foot and wedging it in the mud in front and then drawing the body after it.

At the sides of the body on each side we find the branchia or gill, or ctenidium, which as in the Gasteropoda consists of a hollow axis bearing two rows of plates. The ctenidium is, however, highly




FIG. 119. A. Diagrammatic section through *Anodonta* to show the circulation of the blood. B. Section through *Anodonta* near the posterior edge of the foot. From Howes.

- A. 1. Right auricle. 2. Ventricle. 3. Keber's organ. 4. Vena cava. 5. Efferent branchial trunk. 6. Efferent pallial vessel. 7. Efferent branchial vessel. 8. Branchiae. 9. Afferent branchial vessel. 10. Efferent renal vessel. 11. Afferent branchial trunk. 12. Afferent renal vessel. 13. Rectum.
- B. 1. Right auricle. 2. Epibranchial chamber. 3. Ventricle. 4. Vena cava. 5. Non-glandular part of the kidney. 6. Glandular part of the kidney. 7. Intestine in foot. 8. Pericardium. 9. Shell. 10. Ligament of shell.

modified in *Unio*. The axis is attached high up to the side of the body in front, but projects freely into the mantle cavity behind. The plates have become narrowed so as to form long filaments, and the ends of each row are bent up and are, in the case of the outer row, fused to the mantle lobe. The bent-up ends of the inner row are joined to the foot in front, and to the corresponding parts of the ctenidium of the other side behind, but in the middle

they are free, at least in some species (Fig. 119). Successive filaments of one row are welded together into a plate, called a lamella, by the fusion of their adjacent edges, leaving only occasional holes for the percolation of the water, so that individual filaments appear like ridges on a ploughed field (Figs. 118, 120). The descending and bent-up ends of the same filament are tied together by cords or narrow plates of tissue traversing the space between them. These cords and plates are called interlamellar junctions, since they unite two lamellae. The pieces of tissue uniting the filaments are called interfilamentar junctions, or collectively, subfilamentar tissue. Gill-plate is the name given to the whole mass composed of one row of V-shaped filaments: there is thus an outer and an inner gill-plate on each side, and each gill-plate has two lamellae formed from the descending and ascending limbs of the filaments, respectively (Fig. 119). It is this peculiar modification of the ctenidia which has suggested the name *Lamellibranchiata* for the class.

Each V-shaped filament is clothed on its outside, that is, the side looking away from the concavity of the V, with high ectoderm cells carrying powerful cilia. By the action of these a strong indraught of water is produced, the current entering between the posterior borders of the mantle lobes, which normally gape slightly. On this current the animal depends both for respiration and for nutrition, since the food consists entirely of the minute animals and plants swept in with the water. The normal position of the Mussel is to have the anterior end deeply embedded in the sand or mud and the posterior end protruding; the animal moves only when for some cause the water becomes unsuitable for its purposes.

Since the upturned ends of the inner rows of filaments of both ctenidia are united behind the foot, a bridge is formed dividing the mantle cavity into an upper or epibranchial division and a lower or hypobranchial. The gaping opening between the mantle lobes at the posterior end is similarly divided into an upper portion, the dorsal siphon, and a lower, the ventral siphon. Since it is the outer lower surfaces of the filaments which are clothed with cilia, it is into the ventral siphon and hypobranchial chamber that the current passes. The lips of both siphons—especially the ventral siphon—are plentifully beset with small papillae, which are sensitive to light and shade. If the shadow of the hand be allowed to pass over them the mantle edges are instantly drawn together and the siphons thus closed. In the scallop (*Pecten*) similar papillae are

developed into well-formed eyes. Part of the water passes through the small holes left between the gill-filaments and so into the epibranchial chamber and escapes by the dorsal siphon, carrying with it the matter cast out from the kidneys and the anus. As it percolates through the gills the blood which circulates in these organs receives oxygen and gets rid of its carbonic acid.

A large part of the water, however, pursues a different course. In front of the gills there are situated two organs called labial palps, on each side of the anterior part of the animal (8, Fig. 118).




FIG. 120. Right side of *Anodonta mutabilis*, dissected to show the viscera \times about 1. From Hatschek and Cori.

1. Cerebro-pleural ganglion. 2. Cerebro-pedal commissure. 3. Oesophagus.
4. Anterior retractor muscle. 5. Liver. 6. Stomach. 7. Aorta.
8. External opening of organ of Bojanus or nephridium. 9. Nephrostome or internal opening of the same. 10. Pericardium. 11. Right auricle.
12. Posterior end of ventricle passing into posterior aorta.
13. Rectum. 14. Glandular part of nephridium. 15. Anus.
16. Opening of epibranchial chamber. 17. Ventral siphon. 18. Edge of shell.
19. Cerebro-visceral commissure. 20. Intestine. 21. Foot.
22. Reproductive organs. 23. Pedal ganglion of right side. 24. Mouth.
25. Opening of the reproductive organ.

These are triangular flaps, an upper and lower on each side, the surfaces of which are covered with grooves clothed with abundant cilia on the sides turned towards one another. The two superior labial palps are connected by a narrow ridge crossing above the mouth; the two inferior labial palps by a similar ridge beneath it. The mouth thus lies at the bottom of a trough,—the lips of which are formed by the superior and inferior labial palps respectively.

The mouth is situated beneath the great anterior adductor muscle which projects beyond it like a forehead. The action of the labial palps is to direct a large portion of the incoming current into the mouth, and so the animal obtains its food.

The alimentary canal shows a considerable resemblance to that of the snail. No trace, however, of radula, buccal mass, crop, or salivary glands, is to be seen. A short oesophagus leads at once into the stomach, which is a wide sac receiving right and left the ducts of the two lobes of the liver. The intestine runs vertically down into the foot, makes several loops there, and then turns back and reaches nearly to the point from which it started, i.e. the hinder end of the stomach. Thence it pursues a straight course through the pericardium and over the posterior adductor muscle, to end in an anal papilla which projects into the epibranchial mantle-cavity. For part of its course the ventral wall is infolded towards the cavity so as to produce a ventral typhlosole comparable to the dorsal typhlosole in the worm. The straight concluding portion of the intestine is called the rectum. The pericardium is situated in the mid-dorsal line posterior to the stomach. The fact that it surrounds the rectum is the consequence of its origin as a pair of sacs in the embryo lying to the right and left of the intestine, which later meet above and below this organ.

There are, as mentioned above, two kidneys or nephridia in the mussel. These, frequently termed the organs of Bojanus, are dark coloured bodies, situated beneath the floor of the pericardium, on either side of the vena cava. Each consists of a U-shaped tube placed horizontally, with one limb placed vertically above the other and the bend directed backwards. The deeper limb is the active part; it has numerous folds projecting into it which are covered with dark cells. It opens into the pericardium in front by a curved slit lined with powerful cilia, which produce an outward current. This of course is the reno-pericardial duct such as has been already described in the snail. The outer and upper limb is wide and smooth-walled, and opens into the deeper limb beneath the posterior adductor. In front it opens to the exterior through a pore with thick lips placed just above the place where the upturned ends of the inner row of filaments are attached to the foot (Fig. 120).

The kidney, since it is a tube lined with excretory cells and communicating internally with the body-cavity, is a nephridium comparable to that of the worm, *Lumbricus*. In the worm the

function of the internal opening is to convey to the exterior the fluid in the body-cavity, which contains excretory matter thrown

out by the cells lining the coelom.

The anterior end of the pericardium of the Mussel has a brownish red colour and is produced into numerous little pockets lined by peculiar cells, which are excretory in function (Fig. 119). This portion of the pericardial wall is called Keber's organ, and the excreta thrown out by it pass down the reno-pericardial canal.

The heart consists of a ventricle which surrounds the rectum, and two flat triangular auricles, the broad bases of which are inserted into the wall of the pericardium just over the place where the bent-up ends of the outer filaments of the ctenidium are attached to the mantle. From the ventricle blood is driven forwards by an anterior aorta dorsal to the rectum, and backwards by a posterior aorta ventral to the rectum. From these arteries it finds its way into a multitude of irregular spaces in the foot and the other portions of the body, and eventually reaches a vessel, called the vena cava, lying under the floor of the pericardium in the middle line, between the right and left upper limbs of the two kidneys. From the vena cava the blood streams out through many channels in the wall of the kidney and reaches the axis of the ctenidium, whence it makes its way into the

filaments, especially those of the outer row. From the upturned edges of these last it reaches the mantle and from this the auricle.




FIG. 121. Dorsal view of *Anodonta mutabilis*, with the upper wall of the pericardium removed to show the heart \times about 1. After Hatschek and Cori.

1. Foot. 2. Anterior adductor muscle. 3. Protractor muscle.
4. Anterior retractor muscle. 5. Posterior retractor muscle.
6. Posterior adductor muscle. 7. Dorsal siphon. 8. Ventral siphon.
9. Anus. 10. Split between left and right mantle lobes through which larvae leave the epibranchial chamber.
11. Keber's organ. 12. Rectum traversing ventricle. 13. Nephrostome or internal opening of organ of Bojanus. 14. Ventricle.
15. Left auricle. 16. Anterior retractor muscle.

Some blood is sent to the lobes of the mantle, as in the snail, and through the thin skin absorbs oxygen; this blood is returned direct to the auricle without passing through the gill; from this fact it appears that the mantle lobe, as well as the gill, is a respiratory organ.

In the nervous system the cerebral and pleural ganglia on each side have coalesced, so that only one cord proceeds from them to the pedal ganglion. There is a long visceral loop, ending in two closely conjoined visceral ganglia, placed beneath the posterior adductor (Fig. 120). On either side of these, just where the axis of the ctenidium becomes free from the body, is a thickened patch of yellow ectoderm—the osphradium. This is a peculiar sense-organ, the function of which, it is believed, is to test the water passing over the gill as to suitability for respiration. There are a pair of large otocysts in the foot.

Mussels are male and female, and their reproductive organs are paired, and consist on each side of a bunch of tubes spreading through the foot. The ducts are continuous with the walls of the ovary or of the testis. They open by slit-like orifices just in front of the opening of the nephridia on each side of the foot. The spermatozoa are swept out by the water passing through the dorsal siphon and are sucked in by the inhalent currents of female individuals. The eggs when cast out are detained between the two lamellae of the outer gill-plate and there fertilized. They develop into peculiar larvae called Glochidia, in which the bivalve shell is developed, but not the foot. When a fish passes by, the mother expels the Glochidia from the gills, and they seize hold of the tail or fins of the fish and embed themselves therein. They develop there for some weeks and change gradually into the adult form. They show a remarkable sensitiveness to the presence of fish, but if they fail to attach themselves to one they fall to the bottom of the water and perish.

Lamellibranchiata as a group have very uniform habits; the principal points in which they differ from one another are (1) the degree of finish which that all-important organ the ctenidium has attained, and (2) the extent to which the animal is able to burrow.

The simplest forms, such as *Nucula*, have ctenidia like those of a Gastropod, a fact which suggests the view now generally held, that the Lamellibranchs are descended from some primitive type of Gastropod.

In others, such as the Sea-mussel (*Mytilus*) the ctenidia have

the same external appearance as those of *Unio*, but the filaments are very loosely united with one another and their upturned ends are not fused to the mantle. The foot is small and tongue-shaped,

the animal never burrows and rarely moves, being fixed by a cord of mucus called the byssus, secreted by a gland in the hinder part of the foot.

In the Oyster (*Ostrea*) the foot has disappeared and the animal passes its life resting on one side. In the Scallop (*Pecten*) the foot has also atrophied, but the animal is able to swim through the water by flapping the valves of the shell. The Cockle (*Cardium*) has a large and powerful foot, by which it is enabled to execute leaps.

Mya (sometimes known as the Clam, though this term is applied to many Bivalves) and its allies burrow deeply in the sand and have the edges of the mantle behind drawn out into two long tubes closely apposed to one another, termed the dorsal and ventral siphons. By means of these tubes they keep up a connexion with the surface, so that the currents of water are not interrupted. Similar tubular funnels, though not so much drawn out, are seen in the Razor-shell (*Solen*) (Fig. 122). *Pholas* and some others are able to burrow in rock; this is said in some cases to be effected by an acid secretion poured out by the flat disc-like end of the cylindrical foot. *Teredo*, the ship-worm, burrows in timber; the siphons are very long and covered with a shelly deposit; the




FIG. 122. *Solen vagina*, the Razor-shell, the shell is opened and the posterior part of the mantle is torn to admit of this.

1. Shell. 2. Foot. 3. Labial palps.
4. Gills. 5. Torn portion of mantle.
6. Bristle in ventral siphon.
7. Bristle in dorsal siphon.

original valves of the shell are very small compared to this secondary shelly tube. This animal is very destructive to submerged wooden structures; a wooden pile supporting a pier in

Vancouver was in eighteen months reduced to a mere spongework of wood by its ravages.

Class III. CEPHALOPODA.

A third class of the Mollusca, very differently constituted from the Lamellibranchiata, is that of the Cuttle-fish, or Cephalopoda. This paradoxical name, literally "head-footed" (Gr. κεφαλή, head; πούς, ποδός, a foot), is suggested by the circumstance that the foot has grown forward and upwards at each side of the head, and that these two extensions have met and coalesced, so to speak, on the back of the neck. The edges of this part of the foot, which may be called the fore-foot, are drawn out into strap-like processes, which are the arms by which the animal seizes its prey. The edges of the hinder part of the foot, on the other hand, have become bent round and joined beneath the animal, so as to form a tube, the funnel, through which water is ejected from the mantle-cavity.

The commonest example of the
Sepia. Cephalopoda




FIG. 123. Diagrams of a series of Molluscs to show the form of the foot and its regions and the relations of the visceral hump to the antero-posterior and dorso-ventral axes. After Lankester.

- I. A Prosobranch Gastropod. II. Lamellibranch. III. A Cephalopod.
A. Anterior surface. P. Posterior surface. D. Dorsal surface. V. Ventral surface. 1. Mouth. 2. Anus. 3. Mantle-cavity. 4. Foot.

is the Squid, *Sepia officinalis*, often caught round the British shores by trawlers. It is also found in the Mediterranean, where it is a favourite article of food. A cuttle-fish of about the same size but of a narrower and more elongated shape, *Ommastrephes illecebrosa*,




FIG. 124. Posterior view of male of *Sepia officinalis* $\times 1$. The mantle-cavity has been opened to expose its contents.

1. Long arm half protruded.
2. A short arm; this one is hecto-cotyized.
3. Lips surrounding horny jaws; mouth.
4. External opening of funnel.
5. Eye.
6. Cartilaginous knob on mantle which fits into the hollow 8.
7. Gill.
8. Socket for 6.
9. Anus.
10. Depressor muscle of the funnel.
11. Reproductive pore.
12. Right kidney papilla.
13. Visceral mass.
14. Fin.

is common in the Gulf of St Lawrence. The body of *Sepia* appears to be composed of a swollen head, separated by a neck from a tapering trunk. When closely examined, however, the body is seen to be nothing but a long, pointed, visceral hump, like that of the snail, but it is not twisted, and is unprotected by an external shell. The mantle, as in the snail, is a skirt-like fringe of skin, the space between its inner surface and the visceral hump forming the large mantle-cavity. In order to compare the animal with the snail it must be placed with the point of the hump projecting upwards and backwards (Fig. 123). The so-called head includes the true head, with two enormous eyes of almost human aspect, surrounded by the fore-foot. The fore-foot is drawn out into eight short pointed arms, thickly covered on their inner sides with stalked suckers (Fig. 124), and two very long arms bearing suckers only at their expanded ends. These latter can be pulled back into two large pits situated at their bases, and when so retracted they are completely hidden from view.

The sucker is a cup with a horny rim which keeps the opening from collapsing. In its base there is a swelling, which is the end of a muscle running into the stalk, and by the contraction of this, when the cup is applied to any object, a partial vacuum is produced. By means of the suckers the Squid can take a firm hold of its prey.

The hind-foot is the tube, known as the funnel (Figs. 124 and 127). The posterior end of this is overlapped by the hind end of the mantle; in other words, it projects into the mantle-cavity. The mantle is very muscular; by the contraction of longitudinal muscles running towards the apex of the hump the mantle-cavity is widened; by the contraction of circular muscles it is narrowed, and by the alternate action of these two sets of muscles, water is sucked in and forced out of the mantle-cavity.

When, however, the mantle-cavity is contracted, two projecting pegs on the inner side of the mantle fit into sockets on the outer side of the funnel (6 and 8, Fig. 124). No water can then escape over the free edge of the mantle, and all is ejected in a narrow and forcible stream through the funnel. The funnel itself is muscular and by contraction aids the process; there is a valve-like projection inside it which prevents water from being driven back into the mantle-cavity (Fig. 127).

Since water is sucked in gently and ejected forcibly the animal is propelled in the opposite direction, that is backwards, by the

reaction of the stream against the surrounding water. *Sepia* can however also swim gently forward by wave-like undulations of the two lateral fins. These fins are flaps of skin projecting from the sides of the visceral hump (14, Fig. 124).

It has been said that the visceral hump is unprotected by an external shell. This is not strictly true. On the anterior surface of the hump there is an oval plate-like shell completely hidden in




FIG. 125. A diagram showing the relation of the kidneys to the pericardium in *Sepia*.

1. External opening of the kidney into mantle-cavity. 2. Internal opening of the kidney into the pericardial coelom. 3. Opening of the right kidney into the dorsal sac and hence into the left kidney. 4. Left kidney, ventral portion. 5. Reno-pericardial canal. 6. Pericardium, part of the coelom. 7. Branchial heart. 8. Dorsal sac common to both kidneys.
- A. Arrow passing into left kidney by external opening from mantle cavity. B. Arrow passing into right kidney through external opening into median lobe. C. Arrow passing into external opening and then into internal opening, and so into pericardial coelom.

a sac formed by the meeting over it of upturned flaps of skin (14, Fig. 127). From its upper surface project an innumerable number of delicate calcareous plates parallel to one another, the spaces between them being filled with gas so as to give lightness.

In one or two living Cephalopoda, as for instance the Pearly Nautilus (*Nautilus pompilius*), and in very numerous extinct forms, there was a large tubular external shell which might be straight or

coiled, but which always had the peculiarity of having a large number of septa, or transverse plates, dividing up its cavity into chambers, only the last of which contained the visceral hump, the rest being filled with gas (Fig. 130). In *Sepia* it is supposed that the chambers have become so small and shallow that the last one simply appears as a plate situated on part of the surface of the hump. The other chambers contain gas as in *Nautilus*.

Sepia possess two well-formed ctenidia, each consisting of an axis bearing two rows of thin plates. The axis is suspended from the body by a membrane, and the ctenidia project forwards and downwards instead of backwards as in the Lamellibranchiata (7, Fig. 124).

As in Lamellibranchiata, there are two kidneys which open by little papillae placed just in front of the bases of the ctenidia (12, Fig. 124). Just inside the papilla is a narrow opening, the lips of which are folded so as to make it appear like a rosette. This is the internal opening of the kidney: it leads into a lateral prolongation of the pericardium, which is the reno-pericardial canal (Fig. 125). The kidney has the form of a wide sac and may perhaps be compared to a U-shaped kidney, like that of *Unio*, in which the two limbs have become merged in one another.

The wall of the kidney is smooth, except over the course of the large veins which run beneath its upper and inner wall. Here the epithelium is folded and consists of tall cells which are actively engaged in extracting excreta from the blood, as may be seen by the rows of granules with which they are filled. From the anterior ends of the kidney two outgrowths project which immediately fuse into one and constitute a great pouch called the dorsal sac (8, Fig. 125) stretching upwards and backwards just underneath the shell. This peculiar extension gives to the two kidneys the form of **M**, between the median **V** and outer limbs of which lies the pericardium. Posteriorly the cavities of the right and left kidneys also communicate with one another.

The pericardium is a wide sac lying between the dorsal pouch of the kidneys and their ventral parts. At the sides it gives off the reno-pericardial canals, whilst the stomach and intestine project into its roof.

The ventricle of the heart is a spindle-shaped sac lying transversely (Fig. 126). Into its two ends open the tubular thin-walled auricles which receive the blood from the ctenidia. From its anterior wall a powerful artery, the anterior aorta, is given off

running forward above the oesophagus to the head, and a smaller artery or posterior aorta goes backwards and upwards to supply the stomach and genital organ. These arteries have regularly formed branches from which the blood enters definite veins. This formation of well-defined channels for the blood is characteristic of the Cephalopoda. Of these veins the most important are: (1) the anterior vena cava; this is a channel in the mid-ventral line in front of the




FIG. 126. View of heart and chief blood-vessels of *Sepia cultrata*.
Partly after Parker and Haswell.

- | | | | | |
|---------------------------|---------------------------|------------------|--------------------|----------------------|
| 1. Ventricle. | 2. Auricle. | 3. Ctenidium. | 4. Anterior aorta. | 5. Posterior aorta. |
| 6. Anterior vena cava. | 7. Vein from ink-sac. | 8. Genital vein. | 9. Branchial vein. | 10. Branchial heart. |
| 11. Right abdominal vein. | 12. Vein from the mantle. | | | |

kidneys, which forks and sends a branchial vein over each kidney to the base of each gill; (2) the abdominal veins; these are a pair of large channels which come from the mantle, especially the upper part of it, and join the forks of the vena cava just before they enter the gills; (3) the genital vein; this is a trunk draining the genital organ, it runs along the ventral wall of the dorsal pouch of the kidney and joins the right fork of the vena cava; (4) a vein from the ink-sac joins the same fork, and (5) on each side a smaller vein from the mantle joins the main venous system at the branchial hearts




FIG. 127. Left half of a *Sepia*, showing the relation to one another of some of the principal viscera, about 1. Diagrammatic.

1. Ovary. 2. Genital part of the coelom. 3. Pericardial part of the coelom; the reference line touches the heart. 4. Mantle-cavity. 5. Section of intestine. 6. Incomplete septum between genital and pericardial coelom. 7. Ventral limb of kidney. 8. Glandular tissue of kidney. 9. Dorsal limb of kidney. 10. Stomach. 11. Liver duct. 12. "Pancreatic" caeca. 13. Liver. 14. Shell. 15. Shell sac. 16. Dorsal horny jaw. 17. Anterior opening of funnel. 18. Valve in funnel. 19. Radula. 20. Lips. 21. Ventral horny jaw.

(Fig. 126). Where these veins come in contact with the kidney wall the special excretory tissue mentioned above is developed.

A peculiar feature in the circulatory system is the presence of a pair of muscular swellings of the forks of the vena cava just before they enter the gills. These are the branchial hearts, the function of which is to drive the blood into the gills, whereas the auricles drain it out of them. Each branchial heart projects on the one side into the kidney and on the other side into the renopericardial canal, and the epithelium of the latter where it covers the heart is greatly thickened so as to form a cushion, the function of which is excretory. This, like Keber's organ in the river-mussel, is a remnant of the primitive excretory function which probably all the cells of the coelom once possessed.




FIG. 128. Lateral view of the central nervous system of *Sepia officinalis*. Magnified. From Cheron.

1. Upper buccal ganglion.
2. Nerves connecting buccal ganglion with cerebral ganglion.
3. Brachial ganglion.
4. Pedal ganglion.
5. Pleural ganglion.
6. Supra-oesophageal ganglion.
7. Cut end of optic nerve.
8. Superior ophthalmic nerve.
9. Pallial nerves.
10. Visceral nerve.
11. Anterior nerve to the funnel.
12. Auditory nerve.
13. Inferior ophthalmic nerve.
14. Nerves to the arm.
15. The dotted outline represents the buccal mass and the oesophagus.

The alimentary canal of *Sepia* is constructed on very much the same plan as that of the snail. The mouth is situated in the centre of the arms and surrounded with a frilled lip (Fig. 127). There is a large buccal mass containing the radula, and there are a pair of powerful jaws shaped like a parrot's beak, moveable on one another, of which the ventral is the larger. There are two salivary glands and a long narrow oesophagus but no crop. The oesophagus widens behind into the stomach, which receives, as is usual in Mollusca, the ducts of the liver. With the stomach is connected a side pouch

spirally coiled. The liver is enormous, occupying all the anterior portion of the visceral hump; the ducts traverse the dorsal extension of the kidneys, and are in this position covered externally with excretory tissue which by the older naturalists was termed "pancreatic caeca" (12, Fig. 127) from a mistaken comparison with the human pancreas. The intestine is slightly bent on itself and ends in an oval papilla. A peculiar sac, the ink-bag, the cells lining which secrete the pigment known as Indian ink or Sepia, opens by a long duct on this papilla (Fig. 129). When the Cuttlefish is alarmed it ejects this ink and darkens the water so much as completely to escape from view.

The nervous system consists of ganglia even more closely massed than in the case of the snail. The supra-oesophageal ganglia form one rounded mass; they are produced at the sides into the very much larger optic ganglia which are in close relation to the eyes (Fig. 128). The pedal ganglion is divided into an anterior ganglion called the brachial, and a posterior ganglion sometimes called the infundibular. The brachial ganglion supplies a stout nerve to each arm, and each nerve swells out into a small ganglion just where it enters the arm (Fig. 129). The infundibular ganglion supplies the funnel.

Posterior to the infundibular ganglion are the two pleural ganglia fused together. These give rise to a visceral loop which supplies the various internal organs and the gills. From the same ganglion two short nerves run to the mantle and terminate in the two large stellate ganglia, which underlie the skin and supply nerves to all the muscles of the mantle (Fig. 129). This ganglion and the common trunk of the two visceral nerves represent the pleural ganglia, the visceral loop and its associated ganglia, of other Mollusca. The buccal mass is supplied by two ganglia, superior and inferior, each representing a pair joined by a minor nerve collar running round the oesophagus. The inferior ganglion corresponds to the buccal pair in the snail, the superior is a separated part of the cerebral.

It has been already stated that *Sepia* possesses complicated eyes. In the embryo these are like the eyes of the snail, merely sacs lined by visual cells and containing a transparent horny secretion which serves as a lens. In fact, in the embryo, the sac is at first a pit which gradually closes up. Immediately over the spot where the first pit closed a second pit is formed in which a second horny lens is formed just over the first one, so that the lens consists

of two pieces, and as in the eye of the Vertebrate, there is an anterior and a posterior chamber to the eye separated from one another by the lens.




FIG. 129. *Sepia officinalis* dissected to show the nervous system, ventral view.
From Cheron.

1. Three nerves to the arms dissected out. 2. Auditory nerve. 3. Anterior nerve to the funnel. 4. Nerve to vena cava. 5. Posterior nerve to funnel. 6. Continuation of this nerve. 7. Accessory nerve to mantle. 8. Left nerve to mantle. 9. Stellate ganglion. 10. Common trunk of the visceral loop. 11. Left branch of the visceral loop. 12. Nerve to muscles. 13. Nerve to viscera. 14. Ganglion on branchial heart. 15. Nerve of ctenidium. 16. Ink-bag. 17. Duct of ink-bag. 18. Left nidamental gland. 19. Branchial heart. 20. Position of anus. 21. External opening of kidneys.

Into the anterior chamber a circular fold projects called the iris, fulfilling exactly the same function as the iris of the human eye

or the diaphragm in a photographic camera. Outside and around the eye a circular fold acts as an eyelid.

The cerebral, pedal and pleural ganglia are surrounded by very tough connective tissue, in which the fibres, although still visible, have a cheesy consistence, the tissue being called fibro-cartilage. In this way a kind of skull is formed, which sends a scoop-like extension on either side over the back of the eye, covering the optic ganglia. The edges of the scoop pass into ordinary connective tissue round the rest of the eye. This tissue forms the wall of the eyeball.

The otocysts are branched and embedded in the ventral wall of the skull. They receive nerves from the cerebral ganglia, but as the nerve fibrils traverse the pedal ganglia they appear to arise from the latter.

The genital organ in *Sepia* occupies the apex of the visceral hump. It is, as examination of young specimens shows, a thickening of the wall of the coelom, behind the pericardial coelom. The space into which the eggs and spermatozoa are shed is only shut off from the pericardium by an incomplete partition, so that in *Sepia* a state of things persists throughout life which is only found in the embryos of the snail and its allies (Fig. 127).

The genital duct is present only on one side, the left, and is produced into a prominent papilla which in the male is used as a penis (Fig. 124). The outermost part of the duct in the male is a wide pouch in which the spermatozoa are welded into masses and enveloped in cylindrical cases called spermatophores. Just beyond this the duct receives the excretion of two glands termed prostate glands, and then narrows into a very fine tube which opens internally into the coelom. Since in some cuttle-fish the genital duct is paired and in *Nautilus* there are two pairs of kidneys, and the genital ducts of that animal appear to be modified kidney ducts, it has been suggested that the genital duct of *Sepia* is all that is left of a missing pair of kidneys.

The oviduct is simple, but in the female there are four glands, the nidamental glands, situated on the wall of the mantle cavity just outside the kidneys (18, Fig. 129). From the secretion of these glands tough egg-shells resembling india-rubber cases are made. The egg is about the size of a pea, and when the young cuttle-fish emerges it is already like the adult.

Modern cuttle-fish have a fairly uniform structure. The two long tentacular arms are absent in the Octopoda. In *Loligo* the

shell is horny, in *Octopus* it is entirely absent. In *Ommastrephes*, the common cuttle-fish of the Gulf of St Lawrence, the anterior chamber of the eye is open and the lens bathed with seawater.

Nautilus is a remarkably interesting cuttle-fish, widely different from *Sepia* and the others, but closely allied to most of the extinct forms. The arms are short, broad, ill-defined lobes, the suckers being represented by tentacles with raised ridges round their bases. There is a large external shell coiled forwards in the median plane over the animal's head, so to speak (Fig. 130). The visceral hump is enclosed in the last chamber, and




FIG. 130. Side view of *Nautilus pompilius* $\times \frac{1}{2}$. After Graham Kerr. Half the shell has been removed to expose the animal and the chambers of the shell.

1. Last completed chamber of the shell. 2. Hood part of foot. 3. Shell muscle.
4. Mantle cut away to expose (5) the pin-hole eye. 6. Outer wall of shell, some of which is cut away to show the chambers. 7. Siphon.
8. Tentaculiferous lobes of the foot. 9. Funnel.

from the apex of the hump a membraneous tube called the siphuncle is given off, which runs through all the other chambers, piercing the septa. There is a fold of the mantle turned back over the anterior edge of the shell, the first foreshadowing of the shell sac of *Sepia*.

There are four gills, and four kidneys, and four auricles to the heart. Thus *Nautilus* shows traces of segmentation. The papillae of the posterior kidneys are split, one half leading directly to the reno-pericardial canal, the other into the sac-like kidney. The

reno-pericardial canals thus open directly to the exterior, and the genital ducts are in such a relation to the anterior kidneys as to make it probable that they are the reno-pericardial canals belonging to these, which have acquired independent communication with the exterior.

Cuttle-fish feed chiefly on crabs, shrimps and other Arthropoda, using their beaks to break the hard shell. Some are large enough to attack men, and this circumstance has given rise to many legends. Gigantic species are sometimes cast dead on the shores of Nova Scotia, the length of body being ten feet, and of the arms over fifty feet. The phylum Mollusca finds its climax in the cuttle-fishes.

Phylum MOLLUSCA.

Mollusca are classified as follows :

Class I. GASTEROPODA.

Mollusca with a flat foot adapted for crawling. There is a buccal mass and radula ; distinct pleural ganglia are present and the shell is never composed of paired pieces.

Sub-class I. ISOPLEURA.

Bilaterally symmetrical forms with a shell composed of eight median plates situated in a longitudinal series. Numerous pairs of ctenidia.

Ex. *Chiton*.

Sub-class II. ANISOPLEURA.

Asymmetrical forms, with the left side of the visceral hump long in comparison to the right, the anus, kidneys and ctenidia being shifted forwards.

Division I. STREPTONEURA.

The arms and ctenidia shifted so far forward that the visceral loop is pulled into the shape of an eight and the gill is anterior to the heart.

Order 1. Aspidobranchiata.

Usually two kidneys, two auricles, two ctenidia. The axis of the ctenidia free and both rows of plates present.

Ex. *Haliotis*, *Patella*.

Order 2. Pectinibranchiata.

One kidney, one auricle, one ctenidium in which the axis is adherent to the mantle and only provided with one row of plates.

Ex. *Buccinum*, the Whelk.

Division II. EUTHYNEURA.

The visceral loop is untwisted and the gill is posterior to the heart.

Order 1. Opisthobranchiata.

Marine forms with a ctenidium and mantle.

Ex. *Aplysia*.

Order 2. Pulmonata.

Land and fresh water forms breathing air, having the mantle cavity converted into a lung.

Ex. *Helix*.

Class II. SOLENOGASTRES.

Degenerate worm-like Mollusca devoid of shell and foot and with a ventral ciliated groove. There is a rudimentary radula and the genital organs burst into the pericardium, the nephridia serving as genital ducts.

Ex. *Proneomenia*, *Neomenia*.

Class III. SCAPHOPODA.

Mollusca with a tubular shell and mantle and a long cylindrical foot ending in three processes. A buccal mass and pleural ganglia are present. The genital organ opens into the left nephridium.

Ex. *Dentalium*.

Class IV. LAMELLIBRANCHIATA.

Mollusca with a shell composed of two valves united by a hinge, and a mantle of two lobes. The foot is usually wedge-shaped and the plates of the ctenidia are fused to form gill-plates. No buccal mass. Pleural ganglia fused with the cerebral.

Sub-class I. PROTOBRANCHIATA.

Small Lamellibranchiata with a simple ctenidium like that of Gasteropoda, and large labial palps.

Ex. *Nucula*.

Class V. CEPHALOPODA.

Mollusca in which the front part of the foot surrounds the head and is drawn out into sucker-bearing arms whilst the hind portion of the foot forms a muscular tube. The ganglia are massed together and protected by a skull: there is a buccal mass with a radula and two jaws.

Sub-class I. TETRABRANCHIATA.

Cephalopoda with four ctenidia, four kidneys, four auricles, a large external shell, no suckers and very short arms.

Ex. *Nautilus*.

Sub-class II. DIBRANCHIATA.

Cephalopoda with two ctenidia, two kidneys and two auricles. The shell enveloped in the mantle and the arms are long and provided with suckers.

Order I. Decapoda.

Dibranchiata with two long and eight short arms.

Ex. *Ommastrephes*, *Sepia*.

Order II. Octopoda.

Dibranchiata with eight arms of equal length.

Ex. *Octopus*.

CHAPTER IX.

PHYLUM ECHINODERMATA.

THE class of animals known as the Echinodermata comprises the well-known Star-fish or Five-fingers, the equally well-known Sea-urchins, the less familiar Sea-cucumbers and Brittle-stars, lastly the graceful Feather-stars. The name is derived from two Greek words, *ἐχῖνος*, which means hedgehog (and was also used for the sea-urchin), and *δέρμα*, the skin. The prickles and spines with which many members of this Phylum are covered constitute a very prominent feature in their appearance. Spines, it is true, are sometimes absent, but in every case, whether this is so or not, the skin contains a skeleton consisting either of plates or of rods, and the spines are merely rods belonging to this skeleton, projecting outwards, still covered by the skin which they push before them.

Class I. ASTEROIDEA.

The most familiar of all the British Echinoderms is probably the common star-fish, *Asterias rubens*, which may be found at low water on almost any part of the coast where shell-fish, its favourite food, abound. Very similar species, *Asterias vulgaris* and *Asterias polaris*, abound on the American coast, the first-named on the New England coast, the second further north in the Gulf of St Lawrence. The species represented in Fig. 131 belongs to a different genus, *Echinaster*, but in all essential features of its anatomy it agrees with *Asterias*. *Echinaster sentus* is common on the N. American coast. The name star-fish denotes the shape. The body is produced into five arms or lobes which are arranged like the spokes of a wheel round the centre of the body or disk, where on the under side the mouth is situated. These arms are termed radii, and the re-entrant angles between them interradii.

The star-fish creeps about with its mouth downwards: its motion is effected by means of hundreds of delicate semi-transparent tentacles. These are situated in five grooves running along the under side of the arms and converging towards the mouth. They merge into a depression

Skeleton.



FIG. 131. Oral view of *Echinaster sentus* with tube-feet extended \times about 1.
From Agassiz.

surrounding that opening. These grooves are termed the ambulacral grooves: the tentacles situated in them are called the tube-feet, and the depressed space round the mouth in which all the grooves unite is called the buccal membrane (Lat. *bucca*, the cheek) or the peristome (Gr. περί, around, and στόμα, mouth).

generative cells, and cells which give rise to the skeleton. Between the outer wall of the body-cavity and the true external skin which corresponds to the ectoderm, there is a mass of more or less gelatinous substance exactly corresponding to the jelly of a Medusa or the connective tissue of an Arthropod, which constitutes the substance of the body-wall. Into this material cells budded from the body-cavity wall wander : these cells from their power of movement and appearance can be recognised as amoebocytes. It is from these cells that the skeleton is formed in the way we have described above : some of them, however, retain their primitive character and wander about, probably carrying food to the various

parts of the body-wall or perhaps carrying away waste matter. A third section again secrete the fibres which bind the various rods constituting the skeleton together, and form a simple and primitive variety of connective tissue.




FIG. 132. The common Star-fish, *Asterias rubens*, dissected to show motor, digestive and reproductive systems. After Rolleston and Jackson.

- 1—5. The five arms. 6. Madreporic plate and canal. 7. Arborescent “hepatic” caeca, two in each arm. 8. Generative glands. 9. Ampullae of tube-feet. 10. Ambulacral plates, inner surface. 11. Pyloric sac. 12. Duct leading from pyloric sac to pyloric caeca. 13. Stomach bulging into arm. 14. Anus.

The alimentary canal can most easily be examined by carefully cutting away all the upper parts of the five arms in one piece, cutting along both sides of each arm, then raising the upper part of the animal and clipping through the intestine near the anus. By this means the animal is separated into an upper and lower half and all the internal organs are displayed in one piece or the other. The alimentary canal is then seen to consist of several regions clearly distinguished from one another. It begins with an exceedingly short gullet which passes at the lips into the buccal membrane already mentioned: the gullet widens out above into an exceedingly loose baggy stomach produced into ten short pouches, two situated in the beginning of each arm. Above the stomach and communicating with it by a wide aperture lies a flattened pentagonal bag, called the pyloric sac, and from each of the five angles of this sac there is a tube given off which runs into each arm, where it is soon divided into two parallel sacs, each produced into a multitude of little, short pouches. These sacs are called the pyloric caeca: caecum, Latin "blind," being a convenient zoological term for a blind pouch. The pyloric caeca are tied to the upper side of the arm, each by two bands of transparent membrane called mesenteries. From the centre of the pyloric sac a short straight tube runs to the upper surface of the animal where it opens by a minute anus: this tube is called the rectum, a name, as we have seen, commonly given to the last portion of the digestive tube. The rectum has attached to it two branched tubes of a brown colour which open into it, called the rectal glands.

The reason of the division of the digestive sac into various parts is of course the different uses to which they are put in the life of the animal; and we may stop for a moment to enquire what these uses are.

Star-fish feed chiefly on bivalve shell-fish, such as mussels, cockles and clams, though they will attack almost any animal, and their mode of seizing their prey is very curious. If they are attacking a bivalve, they bend all their five arms down round it, thus arching up the central portion of the body. Then the stomach is pushed out,—this being rendered possible by the turning inside out of its edges, which as we saw above, were loose and baggy—and wrapped around the fated mollusc. The pushing out is effected by the contraction of some muscle fibres in the body-wall; these tend to diminish the space which the coelom occupies, and as this is

filled with incompressible fluid, the stomach must be pressed out. After some time has elapsed the star-fish relaxes its hold and it is then seen that the shell of the mollusc is completely empty and as clean as if it had been scraped with a knife. Now it is obvious that the stomach must pour out some strong chemical solvent, which is able in the first instance to kill, then disintegrate, and finally entirely dissolve the prey; and if thin sections of the wall of the stomach be examined, we see that many of the cells of which it is composed are what are called goblet-cells, that is, they are swollen out by large clear drops of fluid, which are probably of a




FIG. 133. Star-fish, *Echinaster sentus*, in the act of devouring a Mussel.

1. Madreporic plate.

poisonous nature. The cells of the pyloric sac, on the other hand, present a different appearance; they are full of minute granules and thus recall the appearance of the cells in other animals, which contain the active digestive principle. Hence it seems reasonable to suppose that the mussel is killed by the action of the juice secreted by the stomach, and its flesh digested by the secretion of the pyloric sac and its appendages which flows downwards into the stomach. Any portion remaining undigested is expelled through the rectum; no food ever penetrates into the pyloric caeca.

The locomotion of the star-fish is effected in the following manner. The tube-feet which crowd the ambulacral grooves are

during life continually extended and retracted. At their ends are flat circular disks, and these disks are pushed against the stone or rock or whatever else the star-fish is clinging to. Then by the contraction of their muscles the centre of the disk is pulled upwards, and so it is made to adhere in exactly the same way in which a boy makes a leather "sucker" adhere to a stone. When once the disk is firmly fixed the contraction of the tube-foot draws the animal after it.




FIG. 134. Diagram of a transverse section of the arm of a Star-fish.

- | | | |
|--|---|---|
| 1. Ectoderm. | 2. Jelly. | 3. Peribranchial space in the skin. |
| 4. Peritoneal lining of body-cavity. | 5. A branchia. | 6. Pyloric caecum. |
| 7. Mesentery supporting a caecum. | 8. Spine. | 9. Ossicle in skin. |
| 10. Pedicellaria. | 11. Ambulacral ossicle. | 12. Adambulacral ossicle. |
| 13. Radial trunk of water-vascular system. | 14. Radial septum separating the two periaermal spaces. | 15. Radial nerve-cord, a thickened band of ectoderm with a plexus of nerve-fibrils underlying it. |
| 16. Ampulla of tube-foot. | 17. Tube-foot. | 18. Periaermal space. |
| 19. Coelom. | | |

We found that in order to examine the alimentary canal it was advisable to divide the star-fish into an upper and a lower half. If we now cut away the tube-feet and look at the roof of the ambulacral groove from which they project, it will be seen that the groove is roofed in by a double series of calcareous rods, meeting each other at an angle like the beams of a church-roof (11, Fig. 134). These are called the ambulacral ossicles. They can be drawn together by muscle fibres running from one of a pair to its fellow just under the spot where they meet. By this action the ambulacral groove is narrowed; and at the same time, inwardly

projecting spines lining its edges are made to meet, so that the tube-feet are entirely protected by a trelliswork of spines. These spines are attached to rods, called the adambulacral ossicles, firmly bound to the outer edges of the ambulacral ossicles (12, Fig. 134). Inside the animal, between the ambulacral plates, a series of pear-shaped transparent bladders tensely filled with fluid project into the coelom (Figs. 132 and 134). These are really the swollen upper ends of the tube-feet, and are termed ampullae. They act as reservoirs into which the fluid contents of the lower part of the foot are driven when the longitudinal muscles of the tube-foot contract. The bladder-like upper end of the foot has only circular muscles, and when these contract the fluid is driven back into the lower part of the tube-foot and it is expanded. The tube-feet, though from the above description it would seem as if each was capable of acting without the others, are really all parts of one system: they are connected by short transverse tubes, with a canal running along the whole length of the arm immediately under the ambulacral ossicles, called the radial water-vessel (13, Fig. 134). This canal and its branches can easily be seen in microscopic sections of the arms of young star-fish, or they can readily be demonstrated by cutting off the tip of the arm of a fully-grown specimen and finding the end of the radial tube on the cut surface, and injecting it with coloured fluid by means of a fine pipette. The five radial tubes are connected with each other by a ring-shaped canal lying just within the peristome, which is called the water-vascular ring. There are nine small pouches called Tiedemann's bodies projecting inwards from the ring canal. In these are formed the amoebocytes which are found floating in the fluid of the canal, and which arise by budding from the wall of each pouch. From the ring canal also in one interradius, where the tenth Tiedemann's body if it existed would be found, a tube is given off which leads to the upper surface of the disk, where it opens by a sieve-like plate, pierced by numerous minute pores, called the madreporite (Figs. 132 and 133). This vertical tube receives the awkward name of the stone-canal because its walls are stiffened by calcareous deposit; its cavity is reduced to a mere slit by the projection into it of an outgrowth of its wall shaped in section like a T with coiled ends, which is likewise strengthened by lime. Although, as we have said, the cavity of the stone-canal is a mere slit, yet it is lined by long narrow cells carrying most powerful cilia. In many species of star-fish, although not in *Asterias*, stalked

sacs resembling greatly enlarged ampullae are attached to the water-vascular ring. These appear to act as reservoirs of fluid for it: they are known as Polian vesicles after Poli, the naturalist, who first described them.

Now since all the movements of a tube-foot can be accounted for by the action of the longitudinal muscles of its lower part and the circular muscles of the ampulla, the question arises as to what is the purpose of this apparatus of radial and circular tubes, stone-canal, and madreporite? There is one interesting little mechanism which supplies a valuable clue to the answer to this question. This is a pair of valves, placed in the tube-foot at the entrance of the transverse canal, which unites it with the radial tube. These valves swing open into the tube-foot when the pressure in the radial tube is greater than the pressure in the tube-foot, but when the pressure in the latter is the higher, they close, so that under no circumstances can water escape from the tube-foot into the radial canal. So it appears that there is an arrangement which allows fluid to pass into the tube-foot but which prevents its return, and this implies that under ordinary circumstances there must be a loss of fluid. We must in fact suppose that when the tube-foot is driven out by the contraction of the ampulla, the contained fluid slowly transudes through its thin walls and the loss is supplied from the radial canal. The pressure in the radial and circular canals is kept up by the action of the cilia in the stone-canal, by means of which a slow but steady current is produced, setting in from the outside through the madreporite.

The function of the whole system of tubes therefore is to keep the tube-feet full of fluid and thus tense and rigid, so that they can perform their functions properly.

The nervous system of the star-fish is one of the most interesting features in its anatomy. The ectoderm consists of long delicate cells bearing flagella, interspersed with goblet-cells similar in appearance to those lining the stomach. The slime which these cells manufacture covers the surface of the animal and no doubt protects it from the attacks of bacteria and microscopic fungi. But the chief point of interest is that at the bases of the long delicate cells there is an indescribably fine tangle of delicate nerve-fibres which are doubtless outgrowths of some of the cells. Here and there a nucleus is seen amongst them, which belongs to a ganglion cell—that is an ectoderm cell which has lost its connection with the rest, and has become pushed down into the

fibrillar layer. The ectoderm all over the body is therefore underlain by a nervous sheath and is very sensitive, but there are certain places where the nervous sheath becomes very much thickened and it is these areas which constitute the true sense-organs and the central nervous system.

Isolated sense-cells,—that is, cells having a stiff protruding hair, are scattered all over the surface: but the only spot where they are collected in groups so as to form true sense-organs, is on the tips of the tube-feet. The tube-feet are then practically the only sense-organs, and since the radial water-tube ends at the tip of an arm in a freely projecting tentacle, we might regard the whole radial tube as a huge branched, sensitive tentacle. There is the more justification for doing this when it is found that the radial tube with its freely projecting tip is in the young star-fish quite independent of the outgrowth of the body called the arm, and only secondarily becomes applied to it. At the base of the end-tentacle there is a thick cushion of nervous matter in which are excavated a number of ectodermal pits lined by cells containing orange pigment. These pits are organs of vision: and it has been experimentally shown that a star-fish deprived of these organs is insensible to light.

The central nervous system consists of five thick bands of nervous skin running along the bottom of the ambulacral groove underneath the radial water-tubes (Fig. 134). They are termed the radial nerve-cords, and are joined by a circular band of a similar nature, called the nerve-ring, lying under the water-vascular ring. Bands of nervous matter run out along the side of each tube-foot to the tip. It is a frequent occurrence in animals of low organization to find the central nervous system taking the form of bands connecting sense-organs. Everything suggests that its great function is the co-ordination of stimuli. Intervening between the radial nerve-cord and the radial water-tube there are two canals lined by flattened cells and separated from one another by an imperfect septum (14, Fig. 134). They are called the radial periaermal canals and are outgrowths from the coelom. From their upper walls are derived the muscles which move the ambulacral ossicles on one another: from their lower walls a layer of ganglion cells and nerve-fibres, which may be termed the coelomic nervous system in order to distinguish them from the main mass of ganglion cells and fibres which are derived from the ectoderm. This coelomic nervous system, which is very thin in the star-fish, seems to serve as the channel by which stimuli from the radial nerve-cord reach the

ambulacral muscles. The five pairs of radial periaermal canals are connected with one another by a circular canal lying above the nerve-ring called the outer periaermal ring. Inside this is another circular canal called the inner periaermal ring, which is an expansion of the foot of the axial sinus (see p. 247).

The upper or aboral surface of the star-fish is provided with two most interesting groups of organs, pedicellariae and dermal branchiae. The former are minute pincers, composed of two or rarely three blades moving on a basal piece.




FIG. 135. Pedicellariae from *Asterias glacialis*. From Cuénot.

- A. Crossed form $\times 100$. 1. Ectoderm. 2. Base of left "jaw." 3. Muscle closing the "jaws." 4. Basal ossicle. 5. Muscle opening the "jaws." 6. Fibrous band connecting the basal ossicle with one of the rods of the skeleton. 7. Fibres of peduncle.
- B. Straight form. 1. Basal ossicle. 2. "Jaws." 3. Adductor muscle. 4. Muscle closing the "jaws." 5. Muscle opening the "jaws."

These close when the skin of the back is irritated; their main purpose appears to be to keep the surface of the animal clear from zoophytes and other small encrusting organisms, and possibly also of removing any matter cast out by the anus. They cover the thickened bases of the blunt spines with which the back is beset. Larger pedicellariae are scattered in the inter-spaces between the spines and are distinguished from the smaller by the fact that the blades do not cross as is the case with these. The larger kind are also found on the adambulacral spines.

The pedicellariae are probably little spines of the second order. In the small blunt-armed star-fish, *Asterina gibbosa*, there are no

true pedicellariae, but the plates on the back bear small spines arranged in twos or threes, which act when the skin is irritated somewhat like pedicellariae.

The dermal branchiae (5, Fig. 134) are conspicuous in a star-fish when alive; they are very difficult, on the other hand, to detect in preserved specimens. They are in fact thin spots on the body-wall, where it consists only of the ectoderm and the wall of the coelom—closely apposed, the jelly, fibres and skeletal rods being absent. These spots project like little finger-shaped processes, and their purpose is to facilitate respiration. The fluid in the coelom or body cavity being separated from the external water by a very thin membrane, the dissolved oxygen is able to pass from the one fluid to the other with great ease.

There is no localized excretory organ in the star-fish or indeed in any Echinoderm. Throughout the phylum so far as is known this function is performed by the amoebocytes which float in the coelomic fluid and have been produced by the budding of the cells forming the wall of the coelom. When charged with excreta the amoebocytes endeavour to make their way out. This in the star-fish they effect by accumulating at the base of the dermal branchiae and working their way through the thin body-wall and so escaping into the ocean.

The organs of sex in the star-fish are very simple. Both kinds of germ cell are aggregated in great feather-shaped glands situated in pairs in the bases of the arms and opening in the angles between the arms or in the inter-radii. The ten ovaries in the female and ten testes in the male are connected by a circular cord of immature germ cells called the genital rachis running round the disc just dorsal to the coelom. The rachis is in turn connected with a pillar of similar cells running alongside the stone-canal which used to be termed the heart, under a mistaken idea of its function, but which we shall term the genital stolon. The genital rachis is formed as an outgrowth from the genital stolon, and the latter is an outgrowth from the coelomic wall, so that the genital cells are derived from the coelomic cells as in other Coelomata. The genital stolon is interposed between the general coelomic cavity of the animal and a special division of the same which is called the axial sinus, and which runs parallel to the stone-canal. The axial sinus is derived in development from the anterior portion of the coelom in the larva. Underneath the

madreporite there is still another division of the coelom completely shut off from the rest, which may be termed the madreporic vesicle. It apparently represents a rudimentary second water-vascular system, since in exceptional cases it may develop the rudiments of radial canals. The genital stolon projects into the axial sinus; it has a brown colour which no doubt suggested the connection with the blood-system to the earlier anatomists, but true blood-vessels do not exist in Echinodermata. The ova and spermatozoa are thrown out into the water by pores situated on the under or oral surface at the base of the arms, and unite with each other there. The young lead a free-swimming existence, and are so unlike the star-fish that no one would ever dream of suspecting that the two had anything to do with each other. As however these peculiarities are fundamentally the same in each of the groups of the Echinoderms they will be dealt with later when the characters of these other groups have been studied.

The other species of star-fish, which are all grouped together in the Class Asteroidea (Gr. ἀστὴρ, a star, εἶδος, shape), differ but little in really fundamental points from *Asterias rubens*. Pedicellariae may, as we have seen, be absent; the arms may be short so that the shape almost becomes that of a pentagon and the arrangement of the plates and spines constituting the skeleton may vary very much. In one family, the Astropectinidae, there is no anus, the rectum ending blindly, and the tube-feet have pointed ends. These star-fish do not climb but run over the surface of the sand.

The number of arms is most often five, but not only do individual variations from this rule occur in species where five is the normal number, but species, and even genera and families are characterised by having a larger number: the common Sun-star, *Solaster papposa*, for instance, has from eleven to thirteen arms.

Class II. OPHIUROIDEA.

The next order of Echinoderms is termed the Ophiuroidea (Gr. ὄφις, a serpent, εἶδος, shape), or the Brittle-stars. These like the star-fish have a body with five arms diverging from a central disk on all sides like the conventional representation of a star. The arms are, however, sharply marked off from the central disk, and they do not, as in the true star-fish, insensibly merge into it, but are continued along grooves on the under surface to the immediate neighbourhood of the mouth: further they are exceedingly long

and flexible and totally unlike the stiff arms of *Asterias* or its allies.

The habits of the animal too are very different from those of the star-fish. Instead of creeping slowly along by the action of the tube-feet it springs along by muscular jerks of the arms, sometimes




FIG. 136. Dorsal, upper or aboral view of *Ophioglypha bullata* \times about $2\frac{1}{2}$.
From Wyville Thompson.

pushing with four arms and seizing hold in front with one, sometimes pushing with three and hauling itself on with two. The name Brittle-star is derived from the readiness with which, if irritated, the animal will snap off an arm.

As might naturally be expected, the most striking differences from the star-fish are shown in the arms. No ambulacral groove is

apparent: the arm being encased in a cuirass consisting of four series of plates, an upper row, two lateral rows each bearing a row of spines on its edge, and an under row (Fig. 137). On close inspection the short pointed tube-feet may be seen protruding from minute pores at the sides of the under row of plates. A thin section of the arm reveals the fact that there really is a space corresponding to the ambulacral groove of the star-fish, but that by the approximation of its edges it has become closed off from the outer world so that it forms a canal, the so-called epineural canal (4, Fig. 137). Above this canal, at the spot one would term the apex of the ambulacral




FIG. 137. Section through an arm of an *Ophiuroid*. Diagrammatic, magnified.

- | | | |
|-----------------------|------------------------------------|---------------------------------|
| 1. Radial nerve-cord. | 2. Radial perihaemal canal. | 3. Radial water-vascular canal. |
| 4. Epineural canal. | 5. Ventral plate. | 6. Tube-foot. |
| 7. Pedal ganglion. | 8. Lateral plate. | 9. Spine. |
| 10. Dorsal plate. | 11. Coelom. | 12. Longitudinal muscle. |
| 13. Vertebra. | 14. Soft tissue supporting plates. | |

groove in a star-fish, there is a ridge of nervous matter covered on the lower side by cells exactly resembling the skin cells covering the nerve ridges in *Asterias*. This is the radial nerve, and above this again is a large rounded disk of calcareous matter, the so-called vertebra. This really corresponds to a pair of ambulacral plates which have become fused together. So much might be inferred from the fact that the radial water-tube runs in a groove on its under surface, and it is clearly proved by examining young specimens. Each vertebra is very short, and it not only has rounded knobs and cups in order to enable it to slide on its successor and predecessor, but is connected to each of them by four great muscles,

by the contraction of which the arm is moved in any direction (Fig. 137). If the two side muscles contract the arm is moved toward that side, if the two upper, upwards, and so on. These muscles are the seat of the chief activities of the animal, and it is not surprising to find that a pair of large nerves comes off between each two vertebrae to supply them, and that where these nerves are given off the nerve-cord is thickened and the nerve-cells increased, so that a string of ganglia is produced strongly recalling the ventral nerve-cord of the Earthworm. Between the vertebrae and the radial nerve-cord there is a single canal (2, Fig. 137), representing the pair of radial perihaemal canals in a similar position in




FIG. 138. A diagrammatic vertical section of an *Ophiuroid*. After Ludwig. The circumoral systems of organs are seen to the left, cut across, their radial prolongations cut longitudinally, to the right.

1. Body-wall. 2. Mouth. 3. Coelom. 3¹. Coelom of the arm.
4. Mouth papillae. 5. Torus angularis. 6. Oral plate. 7¹. 1st ambulacral ossicle. 7², 7³, 7⁴. 2nd to 4th ambulacral ossicle, or vertebrae.
- 8¹, 8², 8³. 1st to 3rd ventral plate. 9. 1st oral foot. 10. Transverse muscle of the 2nd joint. 10¹. External interrarial muscle.
- 10². Internal interrarial muscle. (The line should point to the dotted tissue.) 11. Water-vascular system: to the left the circumoral ring, to the right the radial vessel. 12. Polian vesicle. 13. Nerve-ring and radial nerve. 14. Genital rachis. 15. Radial perihaemal canal.

Astroidea. From the ventral wall of the canal the coelomic nervous system is formed: and it is by the greater development of this system where the nerves to the ambulacral muscles are given off that the ganglionic swellings of the nerve-cord are produced. The vertebrae and these muscles nearly completely fill the arm, leaving only a small canal above the vertebrae (11, Fig. 137): this is an outgrowth of the body cavity or coelom, but there is no branch of the alimentary canal continued into it, as was the case with the star-fish.

The digestive sac is here a simple flattened bag lined by cells somewhat like those lining the pyloric sac of the star-fish. There

is no anus, and the edges of the stomach cannot be pushed out. How then, it may be asked, does the Brittle-star eat, and of what does its food consist?

It must be confessed, that in spite of its quick movements and highly developed nervous system, the Brittle-star belongs to the great army of mud-eaters and scavengers. Where they live—usually at the bottom of sea pools and at such depths of the ocean as to be in still water—the mud or sand is impregnated with decaying animal and vegetable matter, and the Brittle-stars shovel this material into their mouths by means of the two pairs of tube-feet of each arm which lie nearest the mouth and are called the




FIG. 139. Oral view of part of the disk and arms of *Ophioglypha bullata* $\times 4\frac{1}{2}$. From Wyville Thompson.

oral tube-feet. The interradii between the arms project inwards over the mouth, as the mouth-angles; these are lined along their edges and at their tips with broad blunt spines called teeth and mouth papillae, so that they form an efficient strainer and prevent coarse particles entering the stomach (Figs. 138 and 139). The calcareous plate at the apex of each mouth-angle which bears these spines is called the *Torus angularis* (5, Fig. 138).

We saw that in the star-fish the whole surface is covered with a sensitive skin, but that the tube-feet act as sense organs

as well as being locomotor in function. In the Brittle-stars the sole purpose of the tube-feet is to serve as sense-organs; they are often covered with little warts consisting mainly of sense-cells with their delicate hairs sticking out all round, just like the batteries of cnidoblasts in *Hydra*, and in all cases there is a special nervous swelling surrounding the base of each tube-foot called the pedal ganglion (7, Fig. 137). As, however, these tube-feet have lost their power of attaching themselves by a sucking action to objects and hence are of no use for locomotion, the ampullae have disappeared; and as the action of the ampullae is probably the chief cause of the loss of fluid in the tube-feet of the star-fish, in the Brittle-star, where the loss must be very small, the stone-canal is excessively narrow and the madreporite, instead of being a regular sieve, has two pores only, rarely more. It is very curious to find that the madreporite is on the under side of the animal; in the young Brittle-star it is on the edge of the disc, but in each interradius the upper surface grows more rapidly than the ventral, and so it is forced round on to the under side. To the water-vascular ring are attached four large Polian vesicles, the interradius occupied by the stone-canal alone being without one. The tube-feet are the only sense-organs, in a sense still more real than is the case with star-fish, for in the Ophiuroids the rest of the ectoderm, after having given rise to a cuticle, has disappeared, the solid mail of plates which the animal possesses appears to render it impervious to sensations of contact.

The organs of sex are very simple; they are situated in the disk in the interradii and consist, in each interradius, of several short pouches. These open into ten sacs, called the genital bursae; one pair being placed in each interradius. These sacs are merely invaginations of the ectoderm which does not here disappear as over the rest of the body; they are lined by ciliated cells, which keep up a constant current of fresh water pouring into them, and thus they fulfil the same function as the "dermal branchiae" of star-fish.

Class III. ECHINOIDEA.

The general appearance of the dried skeleton of a Sea-urchin, or Echinoid, is familiar to most people, but many would fail to recognize any resemblance to a star-fish in the slightly flattened sphere, covered with spines. If, however, we are fortunate enough to see one living, we at once perceive that along five meridians the sphere is beset with beautiful semi-transparent tube-feet, ending in suckers,

exactly like those of the star-fish. In fact, the Sea-urchin might be described as a star-fish in which the upper surface had shrunk to insignificant proportions, being represented by a small patch of leathery skin at the upper pole: or, if we regard the whole radial tube with its tube-feet as an immense branched tentacle, and the arm as its support, we should say that the arm had been again




FIG. 140. *Strongylocentrus dröbachiensis*. From Agassiz $\times 1$. Aboral surface.

1. Expanded tube-feet.

2. Spines.

merged in the body, so that the radial tube was bent back in a curved course. As a matter of fact, the end of the radial tube projects very slightly beyond the general surface and bears at its tip, as is the case in the star-fish, a rudimentary eye, which is situated near the upper end of the body, just outside the small area of leathery skin mentioned above.

The skeleton of the Sea-urchin is a cuirass of plates, fitting edge

to edge, with two openings. Of these the upper (already referred to) is covered with leathery skin and has the small anus in the centre of it and is called the periproct (Fig. 147); it is this area which corresponds to the whole back of the star-fish. The other opening is in the centre of the lower surface and is likewise covered by flexible skin; it surrounds the mouth and is called the peristome (Fig. 146).




FIG. 141. Aboral view of the dried shell of *Echinus esculentus* $\times 1$. The spines, pedicellariae, and tube-feet have been removed.

1. Anus. 2. Leathery skin round anus, periproct. 3. Madreporic plate.
4. Genital plate with genital pore. 5. Ocular plate with eye.
6. Line of junction of ambulacral and interambulacral plates. 7. Ambulacrum. 8. Pores through which tube-feet protrude. 9. Bosses which bear the spines.

The cuirass itself is called the corona and consists of twenty strips, each made up of a row of plates. Corresponding to each tube-foot area or radius there are two rows of so-called ambulacral plates, and each intervening area or interradius is similarly covered by two rows of large plates. As in Ophiuroids, there is no ambulacral groove visible from the outside: it is represented by the epineural canal, immediately inside which there is the radial nerve-cord.

kind have short stumpy jaws, each with a poison bag at its base and a stiff stalk; these are doubtless weapons of defence and enable the Urchin to give any unwelcome visitor which might come too close a warm reception. Such pedicellariae are called gemmiform (Fig. 142). Another kind, termed tridactyle, have long jaws, and a flexible stalk. It was supposed that these helped the animal to climb by seizing hold of waving fronds of sea-weed till the tube-feet could get a hold, but this is proved not to be the case. All we positively




FIG. 144. Diagrammatic vertical section of a Sea-Urchin. From Leuckart, after Hamann.

1. Mouth. 2. Intestine cut short. 3. Siphon. 4. Rectum. 5. Anus.
6. Ventral "blood"-vessel on intestine. 7. Dorsal "blood"-vessel on intestine.
8. Stone-canal. 9. Madreporic plate. 10. Genital rudis.
11. Water-vascular ring. 12. Nerve-ring. 13. Tube-foot with ampulla.
14. Radial nerve. 15. Radial water-vessel. 16. Polian vesicle.
17. Muscles; those on the left pull Aristotle's lantern outwards, those on the right retract it. 18. Ocular plate.

know is, that they have been seen catching hold of particles ejected by the vent and passing them on, from one to the other, so that they do not rest on the skin. It has been shown that a gentle movement in the water excites the tridactyle pedicellariae, and a stronger movement calls the gemmiform into activity.

The Urchin is provided with five white chisel-like teeth, each of which slides on a pair of grooved pieces called alveoli, meeting in a point below. Each pair of alveoli meet in a point where they clasp the tooth. Above they are united by two pieces called

epiphyses (13, Fig. 143) which meet in an arch. A pair of alveoli with their epiphyses are often spoken of as a jaw, and adjacent jaws are joined by stout, inwardly projecting rods called *rotulae*. The whole apparatus of five jaws has received the name of 'Aristotle's lantern.' This can be pushed out or pulled in by muscles attached to arches, called *auriculæ*, rising from the inner side of the skeleton (Fig. 143). Through the *auriculæ* the radial water-tube and nerve pass, and they thus correspond in position to the ambulacral plates of star-fish.

The food of the Urchin ordinarily consists of seaweed, which it gnaws with its teeth. No doubt the little worms and molluscs always found in abundance on the surface of the weed add a flavour to the repast. The alimentary canal is exceedingly unlike those of the Echinoderms so far studied. The gullet ascends vertically between the teeth and passes into the intestinal tube which runs in a spiral right round the body and then turns sharply back and describes one turn of a spiral in the opposite direction; after which it bends inwards and runs straight up to the anus (Fig. 146). For the first part of its course a small tube, the so-called siphon, runs parallel to it, opening into it at both ends.

The water-vascular ring is situated above the masticatory apparatus, and is thus widely separated from the nerve-ring, which is situated below it: the radial tubes, in consequence, run downwards along the "lantern" before bending outwards under the *auriculæ* (see Fig. 144). The water-vascular ring bears small pouches termed Polian vesicles; which seem, however, to correspond to Tiedemann's bodies in an Asteroid. The first pair of tube-feet in each radius are different to the rest, in that they are short and not capable of extension, and that their disks are oval. These tube-feet protrude through the peristome and are called the buccal tube-feet; they function as tasting organs, and are thrown into violent excitement if a piece of eatable matter is put near them (Fig. 147).

In describing the Asteroidea it was mentioned that the genital stolon or "dorsal organ" had been mistaken by former authors for a heart: and that true blood-vessels were unknown amongst Echinodermata. If by blood-vessel is meant a tube with well-defined walls in which there is a definite circulation of fluid this is strictly true.

It must be remembered, as was pointed out in the chapter on Arthropoda, that blood-vessels and connective tissue have both been derived from the same rudiment, which may be compared to the jelly of Coelenterata. Now Echinodermata really represent a stage before




FIG. 145. Sections through parts of *Echinus esculentus*.

- A. A section at right angles to the plane of the Madreporic plate. From Chadwick $\times 16$. 1. Madreporic plate. 2. Pores in the same. 3. Madreporic vesicle. 4. Ampulla of madreporic plate or dilatation of stone-canal into which the pores open. 5. Madreporic tube. 6. Genital stolon. 7. Axial sinus.
- B. A section at right angles to an ambulacral area. 1. Radial nerve-cord. 2. Radial perihaemal canal. 3. Radial water-canal. 4. Epineural canal. 5. Ampulla. 6. Cavity of tube-foot. 7. Ambulacral plate. 8. Boss for articulation of spine. 9. Spine. 10. Muscles which move the spine. 11. Ectoderm.

the evolution of either blood-vessels or proper connective tissue. Apart from the plates of the skeleton the substance of the body-wall has little more consistence than the jelly of an *Aurelia*, and readily degenerates into slime. The ground substance has remained so fluid that it is still traversed by amoebocytes which carry excreta to the exterior. In Echinoidea along two tracts, one situated on the same side of the oesophagus as the stone-canal and the other on the opposite side, the jelly intervening between the inner wall of the coelom and the oesophagus has undergone the first stage in the change to




FIG. 146. View of Sea-Urchin, with part of the shell removed to show the course of the alimentary canal. From Leuckart, after Cuvier.

- | | |
|--|---|
| 1. Mouth surrounded by five teeth (displaced). | 2. Lantern of Aristotle. |
| 3. Oesophagus, coiled intestine, and rectum. | 4. Ovaries with oviducts. |
| 5. The siphon. | 6. "Blood-ring." |
| 7. Fold of peritoneum supporting genital rachis. | 8. "Blood-vessel" accompanying intestine. |
| 9. Ampullae at base of tube-feet. | |

a blood-vessel. The fibres are scantily developed and the amoebocytes are present in immense numbers, whilst the ground substance has become more fluid and probably contains proteids since it stains with carmine, like protoplasm. These tracts are termed dorsal and ventral "blood"-vessels. The dorsal vessel being on the side next the stone-canal. These tracts have not the form of tubes, but are networks of irregular passages devoid of proper walls. These

passages accompany the alimentary canal throughout most of its course and it seems as if the products of digestion were accumulated in them. A so-called "blood-ring" of similar character surrounds the oesophagus just above the water-vascular ring and into this the two "vessels" open. A similar ring has been described in Asteroidea and Ophiuroidea: in some species of the former class a tract of similar substance appears to run down the arm just above the nerve-cord in the septum separating the two periaermal canals, and the name of these canals (Gr. περί, around; αἷμα, blood) has been suggested by this circumstance.




FIG. 147. Oral field of *Echinus esculentus*. Magnified. From Kükenthal.

1. Ambulacrum with tube-feet and spines.
2. Gill.
3. Teeth of Aristotle's lantern.
4. Buccal tube-feet.
5. Soft membrane around mouth.

Breathing, as one might expect, is carried out wherever the body-wall is thin enough to allow the oxygen to diffuse through, that is to say by the tube-feet and by the peristomal membrane. The tube-feet, as in the star-fish, are provided with large ampullae which project freely into the great spacious body cavity. Oxygen

thus taken into the fluid filling the tube-feet can be passed into the body cavity through the ampullae, and there is a curious arrangement to facilitate this. Where the tube-foot passes through the skeleton it is split into two parallel tubes which reunite below (B, Fig. 145): so that on the dried shell we see on the ambulacral plate several pairs of pores, each pair corresponding to a single tube-foot. As the cells lining the inside of the latter are ciliated, the splitting of the tube is apparently to facilitate the separation of the upward and downward currents of water.

The peristome has ten branched pouches, situated one pair in each interradius and projecting outwards. These are the gills, but it is unreasonable to suppose that all the breathing is done by them. They communicate not with the general body cavity, but with a part of it, called the lantern coelom, shut off from the rest by a septum stretched between the teeth and jaws. Embedded in the upper wall of this are certain rods called radii, which are connected with each other and the auriculæ by muscles, and by means of these the upper wall of the lantern coelom can be raised or depressed and so the pressure inside is altered. When these rods are depressed water is driven out into the gills and there absorbs oxygen. When they are raised the water is sucked back into the lantern coelom and the oxygen passes through the thin wall of the latter into the general coelom.

The organs of sex are alike in external appearance in both sexes (Fig. 146). They have the form of five great bunches of tubes hanging down into the body cavity and opening by five small holes, placed in plates called the genital plates, forming the summit of the interambulacral series on the corona and situated just outside the periproct (Fig. 141 and 148). In the young Sea-urchin there is a genital rachis connecting them together, and throughout life there is a genital stolon alongside the stone-canal. The genital stolon is relatively much larger in Echinoidea than in Asteroidea, and surrounds the axial sinus in the lower part of its course, so that this space appears like a cavity excavated in the stolon. Hence by one author the axial sinus and stolon were mistakenly described as a nephridium with glandular walls, and the madreporic vesicle, which is here much enlarged and extends parallel with the axial sinus, was called by the same author the accessory kidney.

The ordinary Sea-urchins, such as we have described, live chiefly on rocky and stony ground: there are, however, two distinct orders which live in sand or mud and have undergone singular

modifications in order to fit them for this kind of life. These are termed the Irregular or Exocyclic Sea-urchins, because whereas the anus has become shifted from the upper pole of the body down one side to the edge, or even to the under surface of the more or less




FIG. 148. Aboral system of plates of *Echinus esculentus*. From Chadwick $\times 4$.

1. Basal plate. 2. Radial plates. 3. Madreporite. 4. Periproct, region around anus. 5. Anus. 6. Genital pore.

flattened body, the madreporite and genital plates still retain their position. In both orders the tube-feet of the upper part of the ambulacra are the main breathing organs, and are immensely flattened and expanded at the base, and the pores through which they pass are arranged in two converging curves on each ambulacrum, the figure produced being compared to the petal of a flower, hence the name applied to them, viz. petaloid ambulacra. The family CLYPEASTERIDÆ or Cake-urchins represents one of the orders. They live at or near the surface of the sand. They still retain their teeth, which are placed almost horizontally, and they use them as spades to shovel the sand into the mouth. There are calcareous pillars stretching from the upper to the lower surface of the shell or test, apparently to enable them to withstand rough usage, since the Clypeasteridæ in many cases live within reach of the breakers. The best known British species is *Echinocyamus pusillus*, a little oval Sea-urchin about the size of a pea, whence the common name

applied to it, viz. Pea-urchin. On the east coast of North America one species, *Echinarachnius parma*, the Sand-dollar, is very common; this is an extremely flattened Urchin of circular outline, the shape and size of which have suggested a comparison with the famous silver-dollar of the United States currency.

The other order is represented by the Heart-urchins or SPATANGIDAE. They live buried at depths of a few inches to a foot beneath the surface of the mud, and the body is more or less oval or egg-shaped, slightly flattened underneath. The mouth is no longer in the centre of the under-surface but is nearer one end, and is usually crescentic and always without any trace of jaws. These Urchins have usually only four of the ambulacra "petaloid"; the fifth has a few long tube-feet with expanded, fringed disks. In the case of the familiar British species *Echinocardium cordatum* it is known that the Urchin extends these from its burrow right up to the surface of the sand and collects with them decaying organic matter lying on the surface. This is pushed within reach of the buccal tube-feet and so gets into the mouth.

The animal does not use its tube-feet to walk with, but moves by means of its spines, which are provided with flattened tips. Besides these spines it possesses peculiar lines of very small spines covered with cilia, which cause a current to pass over the gill-like tube-feet. Such rows of ciliated spines are termed fascioles.

Class IV. HOLOTHUROIDEA.

The fourth group of the Echinoderms is termed the Holothuroidea or Sea-cucumbers, and consists of animals of a more or less sausage-shaped form, with the mouth at one end and the large anus at the other.

These animals have undergone the same essential modification as the Sea-urchins, the arms having been re-absorbed into the body, so that the radial tubes run down the side of the body and end near the vent. The nervous system also is situated beneath the surface, the ambulacral groove being represented by the epineural canal. The skin, as in Echinoidea, retains its well-marked ectoderm with nervous sheath.

They are however distinguished by some most marked characteristics:—1. The skeleton has almost entirely disappeared, being represented only by grains and prickles of various shapes completely




FIG. 149. View of *Holothurta tubulosa* somewhat diminished. The animal is opened along the left dorsal interradius and the viscera are exposed. After Ludwig.

- | | | |
|--|---------------------------|---------------------------|
| 1. Tentacles. | 2. Ampullae of tentacles. | 3. Water-vascular ring. |
| 4. Polian vesicle. | 5. Stone-canals. | 6. Radial water-vessel. |
| 7. Radial longitudinal muscle partly cut away. | 8. Reproductive organ. | 9. Alimentary canal. |
| 10. Cloaca. | 11. Respiratory trees. | 12. Ventral blood-vessel. |
| 13. Dorsal blood-plexus. | | |

buried in the skin. 2. The muscular system of the body-wall is most powerfully developed: there is a pair of strong longitudinal muscles running inside each radial tube, and transverse muscles run across each interradius. 3. The buccal tube-feet are highly modified and are the means by which the animal feeds itself. 4. The anus is wide and the concluding portion of the intestine strongly muscular, and is used as a breathing organ; water being sucked in at the anus and thrown out again. 5. The stone-canal does not reach the exterior, but terminates in a sieve plate hanging down into the interior of the body.

The breathing by means of the anus is carried out by certain organs called gill-trees. These are two great branched tree-like outgrowths of the hinder part of the intestine, reaching right through the body cavity to near the mouth (Fig. 149). Water is taken in by the anus and forced up into the finest branches of these and no doubt diffuses through into the body cavity under the pressure set up by the contraction of the muscles of the anus. Hence it is that the animal is able to dispense with an external madreporite, and also to obtain the fluid necessary to keep its tube-feet tense from its own body cavity. From the water-vascular ring one or more long-stalked Polian vesicles hang down into the body cavity.

The muscular body-wall has a very curious effect on the economy of the animal. When it is irritated it contracts the muscles, and since the fluid in the body cavity is practically incompressible, the effect is to set up a tremendous pressure. As a result of this the wall of the intestine near the anus tears, and a portion or the whole of the intestine is pushed out. The gill-trees are the first to go, and in some species the lower branches of these are covered with a substance which swells up in sea-water into a mass of tough white threads in which the enemies of the animal are entangled. A lobster has been seen rendered perfectly helpless as a consequence of rashly interfering with a Sea-cucumber. These special branches are termed Cuvierian organs.

A Holothuroid is only temporarily inconvenienced by the loss of its internal organs. After a period of quiescence it is again furnished with the intestine and its appendages. Some species, which are able to pull in the mouth end of the body with their tentacles, when strongly irritated snap off even this, and yet are able to repair the loss.

The intestine is a simple looped tube which has three limbs.

One limb runs down towards the anus, the next turns up again towards the mouth and then bends back into the final limb which goes towards the anus. These limbs are attached by mesenteries to different interradii of the body, the first to that which in the ordinary position of the animal is mid-dorsal, the next to the left ventral, and the third to the right ventral (Fig. 149).

Accompanying the alimentary canal are so-called dorsal and ventral "vessels" similar to those of the Echinoidea, and there is also a "blood-ring" like that described in the same class. In Holothuroidea the ventral vessel is close to the alimentary canal but the dorsal vessel is borne on a little ridge projecting from the intestine. The alimentary canal is enswathed by minor branches of the network of which the dorsal and ventral vessels form merely the large trunks. The whole system thus assumes a very complicated appearance, but even here it has been shown that there is no circulation nor even a proper wall to the spaces. The longitudinal vessels indeed often do not appear to communicate with the blood-ring.

The buccal tube-feet form a crown of from ten to twenty-five great branched tentacles, and their different shapes are used to classify the various families of the Sea-cucumbers. Most species feed on sand or mud, but one family can only be described as anglers. In them the tentacles are long and delicately branched so that they resemble pieces of sea-weed. The animal stretches them out, and they become the resting-place of numbers of the minute animals which swarm in sea-water. When one tentacle has got a sufficient freight it is bent round and pushed into the mouth which is closed on it. It is then forcibly drawn out through the closed lips so that all the living cargo is swept off.

The organs of sex are similar in nature to those of the Urchins, but are represented by only one mass of tubes which all unite in a common opening near the tentacle region, and it is in this region that the stone-canal opens in the one or two rare cases where it still opens to the exterior. Hence it appears that whereas in the irregular Sea-urchins the genital openings and madreporite have remained fixed whilst the anus has been shifted, here the anus has remained in its original position whilst the genital opening has been shifted towards the mouth.

The Holothuroidea are divided into the following five Orders.

1. *Elasipoda*: Sea-cucumbers whose tentacles have shield-shaped ends drawn out into short processes, devoid of gill-trees,

with the tube-feet of the upper surface of the body modified into stiff respiratory processes. Live only at great depths in the ocean.

2. *Aspidochirotae*: Sea-cucumbers with shield-shaped ends to the tentacles,—these have also large ampullae so that they can be individually retracted. With gill-trees and often Cuvierian organs.

3. *Dendrochirotae*: Sea-cucumbers with long delicately-branched tentacles without ampullae. The whole front end of the body can be pulled in by means of special muscles. Gill-trees present.

4. *Molpadidae*: Sea-cucumbers with tentacles unbranched or with two or four small lateral branches, and no other tube-feet. Gill-trees present.

5. *Synaptidae*: Sea-cucumbers in which the tentacles have two rows of short branches. No tube-feet except these, the radial canals having also disappeared. No gill-trees.

Class V. CRINOIDEA.

The last group of the Echinoderms is termed the Crinoidea (Gr. *κρίνον*, a lily), animals long familiar to collectors of fossils under the name of Lily-encrinites. They differ from other Echinoderms in that from the centre of what corresponds to the upper or aboral surface of other orders, there springs a jointed stalk by which the animal is moored to the substratum.

Animals of this type were much more common in past times than now. Large masses of limestone are actually made up of their skeletons. The modern order of Crinoidea includes a few species surviving at great depths in the ocean, and about the mode of life of these we know nothing. There are, however, besides these a number of species not sharply marked off from each other assigned




FIG. 150. *Antedon acoela*, Car.
A young individual $\times 1\frac{1}{2}$. After
Carpenter.

to two genera, *Antedon* and *Actinometra*, which live at moderate depths in the ocean and which have been thoroughly studied. These however are exceptional in that they break off from the stalk when they are mature and swim about by muscular movements of the long arms. The stump of the lost stalk forms a knob called the centro-dorsal ossicle, which is provided with




FIG. 151. Transverse section through the disk and base of an arm of *Antedon rosaceus*. After Ludwig.

1. Mouth. 2. Various sections of alimentary canal. 3. Epithelium of ambulacral groove. 4. Nervous layer of ambulacral groove. 5. Radial water-canal. 6. Circumoral water-vascular ring. 7. Stone-canal. 8. Pore-canal. 9. Trabeculae traversing the coelom. 10. Axial coelom communicating with 11. 11. Coelom of arm. 12. Cirri. 13. Genital stolon giving off 14. 14. Branches of genital stolon in cirri. 15. Radial nerve of dorsal nervous system. 16. "Chambered organ" in centre of dorsal nervous system. 17. Calcareous rods developing into trabeculae. 18. Muscles connecting radial and brachial plates. CD. Centro-dorsal piece. R¹, R², R³. First, second and third radial plate. Br.¹, Br.² First and second brachial plate.

grasping processes called cirri, by means of which the animal can temporarily attach itself.

We may select for our type the common *Antedon rosaceus*, which can easily be captured by the dredge at moderate depths.

This animal has a small disk and ten extremely long arms. It reminds one of a star-fish, in the fact that on the oral sides of these arms there are open grooves converging to the mouth, and that the skin lining these grooves is modified to form nervous bands uniting in a ring round the mouth. These ambulacral grooves are further lined by powerful cilia which cause currents of water carrying small animals to flow towards the mouth, and thus the animal is fed. The tube-feet are small, without disks, and apparently of use only as gills, those springing from the grooves on the disk alone retaining their sensory function. The real sensory organs are the tips of the branches of the arms, called the pinnules, which are arranged in a row down each side of each arm.

The skeleton is peculiar. The ventral side of the body is covered by a leathery skin, but on the aboral side there is first the centro-dorsal ossicle, a round knob representing the uppermost joint of the stem, and then five rows of plates, called radials, radiating from it. These five rows show us that here, as in most other Echinoderms, we have to do with five primitive arms or radii; these radii, however, bifurcate the moment they become free from the disk, and so there are ten arms: the uppermost plate in each of the five rows having a double facet, on to which fit the lowest of the rows of plates supporting the arms.

The arms really bifurcate again and again, but in each case one of the forks does not develop further and forms a pinnule. If in the case of any of the bifurcations both forks were to develop we should have an increase in the number of arms, and indeed species of *Antedon* with twenty, forty and even one hundred arms are known.

There is no madreporite, but the whole of the upper soft integument is riddled with isolated pores which lead into the body cavity and are lined by ciliated cells. The water-vascular ring has hanging down from it a large number of stone-canals, which also open freely into the body cavity. Only one pore and one stone-canal exist in the stalked young, but their position, comparatively near the mouth, is utterly different from that in any other Echinoderm. In the adult the cavity of the coelom is traversed in every direction by cellular cords called trabeculae.

The anus is situated on the ventral side of the body in an interradius, the alimentary canal being coiled in a simple spire in the disk. We have spoken above of the ambulacral grooves being lined by nervous cells, like those forming the radial nerve in





FIG. 152. *Rhizocrinus*, Sars
× about $2\frac{1}{2}$.

star-fish. This is indeed so, but the Crinoid possesses another and much more important nervous system. From the body cavity five canals are given off which penetrate the stalk. These canals swell up in the substance of the centro-dorsal ossicle into chambers, and in the permanently stalked forms like *Rhizocrinus* or *Pentacrinus* they form similar chambers wherever the stalk bears cirri. The coelomic cells which form the walls of these canals develop great masses of nervous fibrillae. In *Antedon* of course only the five uppermost chambers remain when the stalk disappears—they are termed collectively the chambered organ—and the nervous lining of these constitutes a kind of brain (Fig. 151). From this brain cords go off to the cirri, and five great cords run upwards perforating the radial rows of plates, and bifurcating eventually pass into the arms perforating the plates which form the skeleton of the latter. It has been experimentally proved that it is this nervous system which controls the muscles moving the arms, and that if the whole soft part of the disk including the ambulacral nervous system be removed the animal swims just as well as before.

The organs of sex are rounded masses found in the pinnules and are really, as in *Asteroidea*, *Ophiuroidea* and *Echinoidea*, swellings on branches of a genital rachis. There is also a genital stolon, which however has no connection with any of the stone-canals, but rises from the rachis to the centre of the dorsal wall of the coelom. The young are carried on the pinnules for some time, and have a very short free swimming life, very soon settling down

and developing into little pentacrinoids with a jointed stalk. The name "pentacrinoid" is suggested by their resemblance to *Pentacrinus*. These stalked young present interesting features in the skeleton found in many living and fossil Crinoidea but absent in the adult Antedon. Thus the mouth is guarded by five inter-radial valves each supported by an oral plate, and dorsal to the radials is a circle of five interradial ossicles.

Leaving aside the Crinoidea, the development of which is known only in one case and is there evidently much modified, the eggs of the other four groups of Echinoderms develop into free swimming animals which for periods varying from a fortnight to six weeks lead a free life at the surface of the ocean. These young are called Dipleurula larvae and they are, as mentioned, utterly different to adult Echinoderms: unlike these, but like most other animals, they are bilaterally symmetrical (Fig. 153). They swim by means of a powerful longitudinal ciliated ring, drawn out into a number of arms or processes. They possess a complete alimentary canal, consisting of oesophagus, stomach and rectum, and the coelom is




FIG. 153. Ventral view of a Larva of a Holothurian taken at Marseilles \times about 100. From Joh. Müller.

- | | |
|---------------------------------------|-------------------|
| 1. Mouth. | 2. Oesophagus. |
| 3. Stomach. | 4. Rectum. |
| 5. Anus. | 6. Coelomic sac. |
| 7. Rudiment of water-vascular system. | 8. Ciliated band. |

represented by two sacs lying one at each side of the digestive tube. These sacs are, as a study of the early development teaches, portions of the alimentary canal budded off from the rest. As development proceeds, the radial tubes and water-vascular ring are formed on the left side from a portion of the coelomic sac which is cut off from the rest. On the right side the first trace of the skeleton appears, and this side becomes the upper or aboral, whilst the left forms the lower or oral side of the Echinoderm.

This development is not only interesting on account of the extraordinary metamorphosis which the young undergo, but also on account of the fact that whilst the adult is utterly unlike any of the other Coelomata, the structure of the young is reconcilable with the

fundamental structure of Annelida and Mollusca, etc. The only plausible explanation of this is to be found in the hypothesis that the young represent in a rough sort of way the ancestor from which the Echinoderms were derived.

The Phylum Echinodermata is classified as follows:

Sub-Phylum A. **Pelmatozoa.**

Echinodermata which are fixed to some foreign object during the whole or part of their existence by a jointed stalk springing from the centre of the aboral surface.

Class I. CRINOIDEA.

Pelmatozoa with five long arms which repeatedly fork. The genital organs are borne in the tips of the branches.

Sub-Phylum B. **Eleutherozoa.**

Echinodermata which are free during the whole of their adult existence and rarely fixed even during the larval condition. When the immature form is fixed the stalk springs from the oral surface near the mouth and is not jointed.

Class I. ASTEROIDEA.

Eleutherozoa with arms (free radii) containing outgrowths of the alimentary canal and open ambulacral grooves. The arms have feebly developed muscles and locomotion is effected entirely by the tube-feet.

Ex. *Asterias*, *Echinaster*.

Class II. OPHIUROIDEA.

Eleutherozoa with arms sharply marked off from the central disk. The arms do not contain outgrowths of the alimentary canal and have closed ambulacral grooves. They have highly developed muscles, and locomotion is entirely effected by the arms, the tube-feet being purely tactile.

Ex. *Ophioglypha*.

Class III. ECHINOIDEA.

Eleutherozoa in which the arms have coalesced with the body, the radii being arranged like meridians on a sphere. The ambulacral

grooves are closed. The body has a complete armour of closely adjusted plates and the spines are moveably articulate with these and assist in locomotion.

Order 1. **Endocyclica.**

Echinoidea in which the anus is in the centre of the aboral pole and teeth are present.

Ex. *Echinus*.

Order 2. **Clypeastridea.**

Echinoidea in which the anus is excentric, the dorsal tube-feet are flattened and teeth are present.

Ex. *Clypeastra*, *Echinocyamus*, *Echinarachnius*.

Order 3. **Spatangidae.**

Echinoidea with an excentric anus and flattened dorsal tube-feet but without teeth.

Ex. *Spatangus*.

Class IV. **HOLOTHUROIDEA.**

Eleutherozoa resembling Echinoidea in the anus and ambulacral grooves; but with rudimentary skeleton and highly developed muscular body-wall and greatly enlarged buccal tube-feet by means of which all the food is obtained.

Ex. *Holothuria*.

CHAPTER X.

PHYLUM BRACHIOPODA.

BRACHIOPODS (Gr. *βράχιον*, the arm; *πούς*, *ποδός*, the foot) are true Coelomata and retain the coelom in a primitive and typical condition. Like the Mollusca, they are not segmented, and the only trace of a repetition of parts in the group is in a genus called *Rhynchonella* in which the nephridia are repeated, so that we find two pairs. A similar repetition of the same organs occurs amongst the Mollusca in *Nautilus*.

Brachiopods are exclusively marine. They have a shell consisting of two valves, so that at first sight they appear to resemble the Pelecypoda, but in Brachiopods the shells are placed ventrally and dorsally, and not on the two sides of the animal as in Mussels. In a few cases such as that of the primitive genus *Lingula* the two valves of the shell are nearly alike in size and shape and consist largely of horny matter or chitin. In most cases however the shell is calcareous, and since in Brachiopoda, as in most bilaterally symmetrical animals, the two sides resemble one another whilst the back and front are unlike, each valve of the shell is symmetrically shaped, but the dorsal valve differs from the ventral, the latter being usually the larger. In a few cases, such as that of *Crania*, a British form, common in certain localities, the ventral valve is flat and attached by its whole surface to the substratum; all that is then seen is the arched dorsal valve. Since in the overwhelming majority of Pelecypoda the two valves of the shell are similar in appearance, whilst each is asymmetrical in shape, the umbo being situated near the anterior end, it is easy to distinguish at a glance the shells of the Pelecypoda from those of the Brachiopoda.

The posterior end of the body terminates in a stalk which in *Lingula* helps to keep the animal in the holes of the sand in which it lives. In other forms the stalk is shorter and it is firmly glued

to a rock so that when it has once fixed itself a Brachiopod cannot change its place of residence (Fig. 157). Each valve of the shell is lined by the body-wall of the animal, but the body does not occupy the whole of the space between the two valves; it is produced into two folds or flaps called the mantle-flaps, which are each hollow and contain extensions of the coelom. These secrete the larger part of the valves of the shell. In *Lingula* and some others the free edge of these mantle-folds, lying parallel with the free edges of the shells, bear a number of chaetae which recall those of the Chaetopoda. It is by no means certain that the shell of Brachiopods is an external secretion like that of Mollusca: it seems possible that it is really deposited in the connective tissue under the ectoderm.

In most of the thick-shelled forms the shell is traversed by processes of the mantle, which nourish it, so that in dried Brachiopods the shell seems perforated with a number of pores.

If we slightly open the valves of the shell of a living Brachiopod (so as to avoid tearing the tissues) and look in, we shall see between the ventral and dorsal mantle-folds the anterior body-wall of the creature. This sometimes runs almost horizontally across between the space within the valves, but often slopes obliquely from the ventral to the dorsal valve of the shell.

Part of this wall is modified to form two long ridges, the ends of which project freely and are called the arms; they are coiled and are beset with tentacles (Fig. 156). Running close to the origin of the tentacles is a little lip or flange so placed that the two form a groove or gutter. The groove is




FIG. 154. *Terebratulata obesa*, a fossil Brachiopod shell $\times \frac{3}{4}$.

- A. Dorsal view. B. Lateral view.
a. posterior, b. anterior end. The line between a and b is called the length, it traverses the aperture through which the stalk projects. The line between c and d is the breadth, and between e and f the thickness, and between g and h is the hinge-line.




FIG. 155. A section through the shell of *Walthheimia flavescens*. Magnified.

- a. Prismatic layer formed in connective tissue. b. Epidermal layer. c. Outer calcareous layer. d & e. The expanded outer ends of the tubes which traverse the shell.

lined with cilia and so is the inner face of each tentacle. The whole of this apparatus is called the Lophophore. It might be described as a ring of tentacles, the ends of which were drawn out so as to form the arms. It is never quite so simple as the above account would lead one to suppose, but the ring is often produced into two minor lobes forming the lesser arms situated between the main ones, and in many genera the two main arms are raised up from the level of the body-wall and each is twisted into a spiral. The dorsal shell may be prolonged into a series of plates and even into elaborate bands and loops which serve to support such lophophores.




FIG. 156. View of the inner side of the right half of *Waldheimia australis*. From a dissection by J. J. Lister.

1. Mouth. 2. Lophophore. 3. Stomach. 4. Liver tubes. 5. Median ridge on dorsal shell. 6. Heart. 7. Intestine, ending blindly. 8. Muscle from dorsal valve of shell to stalk. 9. Internal funnel-shaped opening of nephridium. 10. Stalk. 11. Body-wall. 12. Tentacles. 13. Coil of lip. 14. Terminal tentacles.

The mouth lies in the middle line at the bottom of the gutter between the lip in front and the tentacles behind. The lophophore is thus an organ for catching food and passing it into the mouth. The cilia which cover the inner surface of the tentacles and line the gutter set up small whirlpools in the water. Minute animals and algae becoming involved in these are swept into the mouth. In many species the

Internal
structure.

tentacles can be protruded between the valves of the shell, and thus the area they affect is enlarged.

The mouth leads into a simple stomach which ends in a short intestine. Both stomach and intestine are ciliated. A digestive gland called the liver consisting of a number of branching tubes opens on each side into the stomach, and as is the case in the Crustacea much of the digestion takes place inside these glands. In the genera of Brachiopoda which have a hinged shell the intestine ends blindly, but in those which have no hinge there is an anus which may open in the middle line as in *Crania*, or on the right side of the body as in *Lingula*.

On the dorsal surface of the stomach is a small, muscular, contractile vesicle, the heart (Fig. 156). This gives off a number of vessels, amongst others one which passes to each tentacle, which therefore possibly act as respiratory organs.

The chief part of the nervous system retains its primitive relation to the ectoderm. Just in front and just behind the mouth there are thickenings of the ectoderm forming a supra- and sub-oesophageal ganglion respectively. The latter contrary to the usual rule being much the larger (Fig. 157). They are connected by two lateral cords and give off a

number of nerves, one of which runs to each tentacle. No sense organs, such as ears or eyes, are known; and indeed the fixed




FIG. 157. A longitudinal vertical median section through *Argiope neapolitana*.

1. Ventral shell. 2. Canal containing blood-vessel. 3. Sub-oesophageal nerve ganglion. 4. Mouth. 5. Stomach. 6. Stalk. 7. Plexus of blood-vessels. 8. Median crest on dorsal shell. 9. Membrane which has separated from shell during the process of decalcification.

Brachiopod, whose "strength is to sit still" and sweep little particles of food towards its mouth, has but little need of specialized sense-organs.

The cavity of the coelom is reduced by the presence of the alimentary canal, the digestive gland and the heart, but it is still spacious. It is partially divided up by certain mesenteries which support the alimentary canal, and it is traversed by several pairs of muscles. Some of these muscles run from valve to valve, and when they contract close the shell, others being situated behind the hinge, so that when they contract the valves slightly open. Others again run from the valves to the inner surface of the stalk and their contraction bends the body one way or another and may even serve to slightly rotate it.

There is—except in one genus—but one pair of nephridia. These are short tubes which open by large trumpet-shaped openings (9, Fig. 156) into the coelom; whilst their external openings are situated at the sides of the body behind the lophophore. The cells lining the nephridia are some of them ciliated, whilst others are crowded with coloured granules. As already mentioned the genus *Rhynchonella* possess two pairs of nephridia.

As a rule, in Brachiopods the sexes are separated. The cells destined to form ova or spermatozoa are derived from those lining the body cavity. At certain places, usually four in number, the coelomic cells multiply and build themselves up into ovaries or testes according to the sex. When they are ripe they fall off into the coelom and make their way to the exterior through the nephridia. The spermatozoa are cast into the water by the male, and the female must bring them within the valves of her shell by the action of the current set up by the cilia, because the eggs are almost certainly fertilized as soon as they leave the nephridia. The eggs develop in certain brood-pouches situated at the sides of the animal which are formed by a bulging in of the body-wall. A larva is ultimately formed which leaves the body of the mother and swims about in the sea by means of a band of cilia. As it is extremely minute, although it swims quickly it does not get very far, and this probably accounts for the fact that Brachiopods are usually found in large numbers in one place.

Brachiopods are found in all seas. About eleven genera have been dredged around the British Isles, most of them in comparatively shallow water. *Lingula* is usually found between tide-marks or in shallow water; it lives

in a tube in the sand, and the bristles round the mouth of the shell doubtless serve to keep out particles of sand which might otherwise injure the animal. It is found along the East coast of America, in the Pacific and other places. One species of Brachiopod, *Terebratula wyvillei*, has been dredged from a depth of close upon 3000 fathoms.

Perhaps the chief interest of the group is that it includes an enormous number of fossil forms which had a very wide distribution. The extinct forms far surpass both in variety and number the existing forms. Some species have lived on,—as far as we can judge from the shell,—unchanged from the time when the earliest fossil-bearing rocks were laid down. They may thus claim to be one of the oldest groups with which we are acquainted.

The Brachiopoda are classified as follows :—

Class I. ECARDINES.

Shell with no hinge and no internal skeleton. The alimentary canal has an anus.

Ex. *Lingula*, *Crania*.

Class II. TESTICARDINES.

Shell with hinge and internal prolongations ; chiefly calcareous. No anus.

Ex. *Terebratula*, *Argiope*, *Waldheimia*, *Rhynchonella*.

CHAPTER XI.

PHYLUM POLYZOA.

THIS group includes a great number of species, the individuals of which are so small as to be barely visible to the naked eye, but they are with hardly an exception colonial in their habits, and the colonies usually attain a fair size. These colonies take many shapes, some branching like a tree, others being flattened like a leaf, whilst others again are discoidal; often they are encrusting, that is to say they form a layer on some sea-weed or rock, for the majority of them are marine.




FIG. 158. Portions of two Polyzoan colonies. Magnified.

- A. *Smittia landsborovii*. a. Avicularium.
 m. Orifice of cell. o. Oocidium or
 pouch in which the egg develops.
 B. *Tubulipora plumosa*. After Hincks.

If one of these colonies be dried, so that the organic matter shrivels up, a hard skeleton remains, and this is then seen to consist of a number of chambers or "cells," each of which opens to the exterior by an orifice, and, as a rule, communicates with its neighbours. The skeleton may be calcareous, or chitinous, or the colony may be gelatinous in consistency. The dried cell may be open or closed by a lid termed the operculum.

During life each of these cells lodges part of the body of a person of the colony, the "cell" being indeed the cuticle; part however of the person is not clothed with cuticle and is normally stretched out above the cell—the opening in the dried cell is in fact the place where the flexible part of the person begins. At the end of this flexible part is the mouth surrounded by a ring of ciliated

The body cavity is regarded as truly coelomic. It contains a fluid in which cells float; it is traversed by the funicle and by numerous strands of mesodermic tissue. The funicle may be the remains of a median mesentery which once separated the coelomic sacs of the two sides. Some of the cells of its walls give rise to reproductive cells, and the body cavity may open to the exterior in certain individuals which possess an ovary by a short tubular duct, the so-called inter-tentacular organ. This functions as an oviduct and has been regarded by some authors as a modified nephridium. A portion of the body cavity is separated from the rest by a horizontal septum, and forms a space at the base of the tentacles. This may open into the other part or may be completely shut off from it.

No heart or blood-vessels are present. It is possible that some of the nitrogenous waste matter may be got rid of by means of the inter-tentacular organ, but it has also been suggested that these waste products are stored up in certain cells on the funicle. From time to time the tentacles, alimentary canal and nervous system of an individual undergo degeneration and form a brown mass, called the brown-body, which forms a conspicuous feature in the colony. After a time the body-wall, which has not disintegrated, forms a new set of organs and the brown-body may come to lie in the stomach of the reconstituted individual. Thence it passes to the exterior through the anus. It is thought that much of the waste matter which has accumulated in the body of the animal is, in this way, eliminated. In certain *Phylactolaemata* there are a pair of small nephridia opening between the mouth and the anus.

A nerve-ganglion lies between the mouth and anus, situated in that part of the body cavity which runs round the base of the lophophore.

Polyzoon colonies are usually hermaphrodite. The testes are as a rule formed by the multiplication of the coelomic cells which lie at the side of the body-wall, while the ovary originates from the funicle or from the body-wall. They may be found in the same individual or in different individuals of the same colony. As a rule, the eggs develop in connection with the colony, but they may be laid, escaping from the body cavity through the inter-tentacular canal, and then they pass at once into the sea-water. More usually the early stages of development are passed through in the tentacle-sheath or in a special pouch called an oöecium (Fig. 158), or in certain "cells" which contain rudimentary individuals. A free

swimming larval form is usually found, which after a time comes to rest and by budding forms a new colony.

Just as in the colonies of Hydrozoa we found different individuals set apart to perform different functions, so in Polyzoa we find a similar specialization. Certain individuals may be modified to accommodate and protect the developing egg, but perhaps the most remarkable modifications are the Vibracula and Avicularia of the Cheilostome Polyzoa. The vibracula are long hair-like processes which sweep through the water; the avicularia are two snapping jaws provided with powerful muscles, like the claws of a lobster, or the beak of a parrot (Fig. 160). They are modifications of a "cell" and its operculum. The avicularia occasionally catch worms, crustacea and other animals whose presence might interfere with the colony, but the exact part which they otherwise play in the economy of the animals is still obscure.

Besides the sexual method of reproduction just mentioned certain internal buds termed stato-

blasts are formed in the group Phylactolaemata. Masses of cells arise from the funicle and become enclosed between two watchglass shaped chitinous shells whose edges are kept together by a special ring of cells. As a rule, the Phylactolaemata die down during the winter, but the statoblasts persist and when spring recurs give rise to new colonies. A somewhat analogous process ensures the perpetuation of the species in certain fresh-water Ctenostomata.

Polyzoa are widely distributed throughout the sea, many occurring in comparatively shallow water, but others have been dredged at great depths. The Phylactolaemata and a few genera from other subdivisions are fresh-water. Fossil forms are numerous and the Coralline crag, a tertiary deposit, takes its name from the large number of coral-like calcareous forms, sometimes described as "corallines," which are found in it.




FIG. 160. An Avicularium of *Bugula*. Magnified.

b. Beak. c. Chamber representing the body-cavity of the modified individual. dm. Muscle which opens, om. muscle which closes, the mandible on the beak. md. Mandible, the operculum of the modified cell. p. Stalk.

There is a small class of animals with a solid body, i.e. no coelomic space, and with both ends of the alimentary canal included in the ring of tentacles, termed the **Endoprocta**. Their relationship with the Polyzoa is sometimes questioned. All the others are grouped together as **Ectoprocta**, and these are subdivided into

Order I. **Phylactolaemata**.

Fresh-water forms with a horseshoe shaped lophophore, an epistome (except *Fredericella*), and statoblasts.

Order II. **Gymnolaemata**.

With a few exceptions marine, and having a circular lophophore. Devoid of an epistome.

Suborder (1), **Cheilostomata**. An operculum covers the orifice of the cell. Avicularia and vibracula often present.

Suborder (2), **Cyclostomata**. Cells tubular ending in circular mouths. No operculum. Calcareous skeleton.

Suborder (3), **Ctenostomata**. Body-wall soft. The orifice of the cell is closed by the coming together of a fringed membrane.

CHAPTER XII.

PHYLUM CHAETOGNATHA.

THE Chaetognatha (χαίτη, hair; γνάθος, jaw) are small cylindrical animals which swim at the surface of the sea. The name is suggested by the circumstance that at the sides of the mouth are two rows of curved moveable bristles by means of which they seize their prey (*e*, Fig. 161).

The body has a small rounded head in front and tapers to a tail posteriorly; it is provided with one or two pairs of flat, lateral expansions termed fins; the general shape resembles that of a torpedo, if we leave the head out of account. The head is surrounded by a fold of the skin forming a hood which is most prominent at the sides and dorsal surface. Within the hood the head bears a row of sickle-like hooks whose points when at rest converge around the mouth, but are capable of being widely divaricated. The head also bears one or more rows of stout spines whose number and arrangement are of importance for the system of classification (*f*, Fig. 161).

The coelom is well developed and contains a fluid in which cells float. In strictness there are three pairs of coelomic sacs separated from one another by transverse and longitudinal partitions. In the head the coelomic space is practically obliterated by the great development from its walls of the muscles which move the hooks. The coelom of the trunk and tail is further divided into right and left halves by a vertical mesentery, which in the trunk region supports the alimentary canal (Fig. 162). This mesentery is pierced by numerous small holes.

The skin is covered by an epithelium more than one layer thick, some of the cells of which are modified to form sense-organs, while others project from the surface of the body and are known as adhesive cells (Fig. 162). Beneath the epithelium is a thin layer




FIG. 161. A ventral view of *Sagitta hexaptera* $\times 3\frac{1}{2}$.
From O. Hertweg.

- a. Mouth. b. Intestine.
c. Anus. d. Ventral
ganglion. e. Moveable
bristles on the head.
f. Spines on the head.
g. Ovary. h. Oviduct.
i. Vas deferens. j. Testis.
k. Vesicula seminalis.

of jelly called the basement membrane, and beneath this a layer of muscles. Anteriorly the muscles are broken up into numerous bundles which fill the cavity of the head, but in the trunk and tail the muscles form four distinct bundles, bilaterally arranged, two dorsal and two ventral.

The nervous system consists of a dorsally placed ganglion in the head which gives off two lateral nerves; these pass round the alimentary canal and end in a ventral ganglion situated (Figs. 161 and 162) near the centre of the body. The cerebral ganglion gives off nerves to the eyes, the olfactory organ, muscles, etc., and both it and the ventral ganglion are connected with a tangle of nerve-fibrils lying at the base of the ectoderm. A pair of eyes exist on the upper part of the head, and behind the eyes an organ to which an olfactory function has been assigned. This consists of a ring of modified ciliated epithelium. Clumps of isolated tactile cells with long hairs surrounded by supporting cells are scattered over the body and fins (Fig. 162).

The alimentary canal is simple and straight. The mouth—with one exception—is ventral and it leads into a pharynx which traverses the head; this passes into an intestine lined by a single layer of ciliated epithelium, amongst which are some glandular cells. The anus is situated at the junction of the trunk and the tail—and with one possible exception—is ventral.

In *Spadella marioni*, the exception mentioned in the preceding paragraph, there is a glandular structure in the head which may be connected with the excre-

tion of waste nitrogenous material, but no other excretory organ is known and no special respiratory or circulatory organs exist.

The Chaetognatha are hermaphrodite. The paired ovaries (Figs. 161 and 162) lie in the trunk region of the body cavity supported by a lateral mesentery. When mature they almost fill the cavity. The oviduct traverses the ovary. It is not known how the ova make their way into it, but spermatozoa are sometimes found inside it, so that it acts as a receptaculum seminis. The oviducts open to the exterior at the upper surface of the lateral fin, just where the trunk passes into the tail.




Fig. 162. A. Transverse section through a *Spadellia cephaloptera* in the region of the ventral ganglion \times about 200. B. Transverse section through a *Sagitta bipunctata* in the region of the ovary \times about 120.

a. Intestine. b. in A. Ventral ganglion. b. in B. Ovary. c. in A. A ciliated sense-organ. c. in B. Base of the left fin which has been cut off. d. in A. Adhesive cells. d. in B. Left ventral muscle. e. in A. Ectoderm. e. in B. Ventral mesentery. f. Dorsal mesentery. g. Right fin.

The median mesentery of the trunk region is continued through the tail, dividing its cavity into two; and in each of these lateral cavities the cells lining the body-wall are heaped up and form a testis (j, Fig. 161). The cells divide up into spermatozoa, which float in the coelomic fluid and are kept in motion by some of the ciliated cells lining the body cavity. The spermatozoa escape through a pair of short vasa deferentia which open on the one hand into the coelom and on the other to the exterior on the tail. Each has on its course a well-marked vesicula seminalis (Fig. 161).

The ova are transparent and pelagic. The cells destined to form the reproductive organs of the adult are early set apart and distinguishable. The development is entirely embryonic, no larval form being recognizable.

The Chaetognatha consist of three genera, *Sagitta*, *Spadella*, and *Krohnia*, amongst which some twenty-three species are divided. The genera differ from one another chiefly in the arrangement of the armature on the head and in the disposition of the fins, which are always horizontally placed and supported by fine skeletal rods. A caudal fin exists in addition to one (*Spadella* and *Krohnia*) or two (*Sagitta*) pairs of lateral fins.

The Chaetognatha are with hardly an exception pelagic, that is they live near the surface of the sea, and as is usually the case with animals which frequent the surface of the ocean they are transparent. At certain times of the year they are found in incredible numbers swimming on the surface by the muscular contraction of their bodies, their fins acting as balancers and having no movement of their own. At other seasons they descend and are taken at depths varying from 100 to over 1000 fathoms. The cause of their descent is unknown. Their food consists of Infusoria, small larvae, and small Crustacea.

The zoological position of the Chaetognatha is obscure. They show no relationship with any of the larger groups; possibly their nearest existing allies are to be found amongst certain aberrant Nematoda, such as *Chaetosoma*, but at present too little is known to make any close comparison possible.

CHAPTER XIII.

INTRODUCTION TO THE PHYLUM VERTEBRATA, SUB-PHYLA
HEMICHORDATA, CEPHALOCHORDATA, AND UROCHORDATA.

THE Vertebrata comprise almost all the larger animals, including Man. The name simply means jointed (Lat. *vertebra*, a joint, and especially a bone of the spinal column), and refers to the possession of a jointed internal axis as the main part of the skeleton. In the lowest forms this axis is not developed, but in place thereof there is a smooth elastic rod, which has received the name of *notochord*, literally back-string (Gr. *νωτον*, back; *χορδή*, string). In all the members of the phylum this notochord is present at some stage of development, although in the higher forms it subsequently becomes surrounded and obliterated by the jointed rod or vertebral column. Hence the name *Chordata*, which has been proposed for the group, is really more appropriate; but as the term *Vertebrata* has been sanctioned by long usage it is inadvisable to depart from it.

Besides the possession of the notochord there are two other features by which the Vertebrata are distinguished. They all possess at some period of their lives slits in the wall of the front part of the alimentary canal. These slits in the lower forms allow the water which is taken in at the mouth for purposes of respiration to escape, and hence they are called gill-slits. Further, the nervous system takes on the form of a dorsal strip of sensitive skin—the medullary plate, which becomes wholly or partly enrolled to form a tube, the neural canal or spinal cord.

There are in all about 32,000 known species of Vertebrata, including all the more familiar animals—fish, frogs, reptiles, birds, and mammals; so that the word animal to the ordinary mind generally calls up the idea of a vertebrate. Nevertheless the number of species is not much more than half that of the Mollusca, and is not a tenth that of the described species of Arthropoda.

Sub-Phylum I. HEMICHORDATA.

The most primitive members of the phylum are certain worm-like forms, in which it has taken special research to discover traces




FIG. 163. A Balanoglossus, *Ptychodera kowalevskii* $\times \frac{1}{4}$. From Spengel.
1. Proboscis. 2. Collar. 3. Trunk. 4. Mouth. 5. Gill-slits.

of Vertebrate structure. They are marine and live in mud, passing it through their intestines and extracting nutriment from the organic matter it contains: thus they feed and move forwards by the same process. These animals are termed Hemichordata (Gr ἡμι, half) on account of the short rudimentary notochord which they possess. Sometimes they are called Enteropneusta (Gr. πνεῦμα,

breath) because, like all Vertebrata, they use the anterior portion of the gut for breathing. There are several genera, *Ptychodera*, *Chlamydothorax* and others; the name *Balanoglossus* is used as a semi-popular name for any species of Hemichordata.

The body of the animal is divided into three portions: (1) a conical anterior part in front of the mouth, the proboscis; (2) a swollen cylindrical portion immediately behind the mouth, the collar; and (3) a long trunk, at the end of which is the anus.

The proboscis contains one, and the collar and trunk each a pair of special sections of the coelom or body cavity. The coelomic sacs of the proboscis and collar communicate with the exterior by ciliated tubes, the proboscis and collar pores (Figs. 164 and 165). The cilia produce currents setting inwards, and thus the collar and proboscis are kept swollen up and tense with water, and form efficient burrowing instruments. If a *Balanoglossus* be removed from the water and laid upon damp sand it is incapable of burrowing and wriggles helplessly about. As soon however as it is covered by water the proboscis and collar are seen to dilate and become stiff, and the proboscis is then inserted into the sand, soon followed by the collar, whilst the trunk is dragged passively after them. As the walls of both proboscis and collar are highly muscular the water can be expelled through the pores, and the volume of these regions of the body diminished, but the action of the cilia soon swells them up again. On the hinder wall of the proboscis cavity there is a puckered membrane richly supplied with blood-vessels, which is called the glomerulus and appears to act as a kidney. When the water in the cavity has become impregnated with excretory products it is expelled as explained above by a muscular contraction.

The alimentary canal runs straight from the mouth on the anterior surface of the collar region to the posterior end of the trunk; there is neither stomodaeum nor proctodaeum. In most species in the anterior part of the trunk the canal has an 8-shape in section, being partially constricted into two tubes, an upper or branchial into which the gill-slits open, and a lower or oesophageal along which the mud is passed which the animal has swallowed for food. The notochord is a hollow tube of cells surrounded by a tough membrane much thickened beneath (Fig. 164). This tube opens into the alimentary canal in the collar region and projects forward into the proboscis as a support for this organ, which is attached by a very narrow neck to the collar. The whole skin is sensitive, since there is everywhere a layer of nerve-fibrils under-

lying the ectoderm cells, but this fibrillar layer is especially thickened along the mid-dorsal and mid-ventral lines of the trunk, these two regions being connected by a ring of nervous tissue immediately behind the collar. The dorsal thickening alone is continued into the collar region, and here it becomes rolled up so as to constitute a short neural tube (Fig. 164) which becomes detached from the




FIG. 164. Longitudinal vertical section through the middle line of *Ptychodera*. Diagrammatic.

1. Proboscis. 2. Collar. 3. Trunk. 4. Proboscis cavity. 5. Glomerulus.
6. Pericardium. 7. Heart. 8. Proboscis pore. 9. Collar cavity.
10. Mouth. 11. Notochord. 12. Dorsal blood-vessel. 13. Oesophageal portion of alimentary canal. 14. Branchial region of alimentary canal.
15. Ventral blood-vessel. 16. Gill-slits showing external and internal openings; the outlines of the external openings are dotted.
17. Central nervous system. 18. Dorsal roots of nervous system.
19. Ventral pocket of proboscis cavity.

ectoderm and assumes a deeper position, retaining however a connection with the ectoderm through three strings of cells with a fibrillar sheath, known as dorsal roots (18, Fig. 164).

There are very numerous gill-slits opening into the alimentary canal, in the front part of the trunk region; they ought rather to be called pouches with a small outer and a large inner opening. The inner opening of each pouch is divided almost into two by a tongue projecting down from its dorsal edge, the so-called tongue-bar. This tongue-bar is specially richly supplied with blood-vessels and so may be regarded as the principal respiratory organ. The blood-vessels are destitute in most cases of any proper wall: they are as it were mere chinks between the epithelial walls of the gut, coelom and skin. There is however a well-defined dorsal channel, running forward into the kidney, which is contractile, the contractility being confined to the front end of the collar where there is a closed sac with muscular walls, which pulsate rhythmically, situated beneath the blood-vessel. The sac is termed the pericardium, and the

dilated part of the blood-vessel above it, the heart. This dorsal vessel communicates with a ventral vessel in the trunk region by two descending curved vessels at the sides of the collar. Each of the coelomic cavities of the trunk sends forwards into the collar region a narrow tongue lying at the side of the blood-vessel. These tubes from their relation to the vessel are called *perihæmal tubes* (Gr. *περί*, around; *αἷμα*, blood).

The sexual organs or gonads are mere packets of cells in the gill region and behind it, developed from the wall of the trunk coelom (Fig. 165). Each when ripe forms its own opening through the body-wall.

One point of great interest attaching to the Hemichordata is that they commence life as free-swimming larvae, resembling the larvae of the Echinodermata, and suggesting the thought that perhaps two such different groups as the Vertebrata and Echinodermata may have descended by different paths from the same simple free-swimming ancestors.




FIG. 165. Longitudinal horizontal section through *Ptychodera*. Diagrammatic.

1. Proboscis. 2. Collar. 3. Trunk.
4. Proboscis cavity. 5. Glomerulus. 6. Pericardium.
7. Heart. 8. Proboscis pore.
9. Collar cavity. 10. Perihæmal cavity. 11. Collar pore.
12. Dorsal blood-vessel. 13. Alimentary canal.
14. Branchial sac with external opening. 15. Reproductive organs.



Sub-Phylum II. CEPHALOCHORDATA.

Leaving the Hemichordata we next come to some small fish-like animals, the Cephalochordata, which were formerly all included under the name *Amphioxus*, and indeed there is no very strong reason for breaking up this old genus. The name *Amphioxus* (*ἀμφί*, at both ends; *ὀξύς*, sharp) refers to the shape of the body, which is long, flattened and pointed at both ends. It is remarkable that we here meet for the first time with a shape very common among Vertebrates, but almost absolutely unknown elsewhere in the animal kingdom, viz. a laterally compressed form with narrow ventral and

dorsal regions and deep sides. It is common to find animals with broad backs and bellies and narrow sides, but only Vertebrates show



FIG. 166. *Amphioxus lanceolatus* from the left side, about twice natural size. After Lankester. The gonadic pouches are seen by transparency through the body-wall; the atrium is expanded so that its floor projects below the metapleural fold; the fin-rays of the ventral fin are indicated between the atrial pore and anus. The dark spot at the base of the fifty-second myotome represents the anus.



B
FIG. 167.

- A. Velum of *Amphioxus* seen from the inside of the pharynx. After Lankester.
v.sp. sphincter muscle of velum.
v.t. velar tentacles lying across the oral opening.
- B. Oral cartilages of *Amphioxus*. After J. Müller. The basal pieces lie end to end in the margin of oral hood, and each basal piece sends up an axial process into the corresponding oral cirrus.

the reverse condition. In consequence of this peculiar shape *Amphioxus* falls on its side when it ceases moving. It burrows in the sand, lying with its mouth just protruding, and as its lips are fringed with ciliated rods (Fig. 167) a current is produced which brings new water to the gills and with it small swimming organisms which serve as food. At night *Amphioxus* often leaves its burrow and swims about, returning instantly to the sand if alarmed. It can burrow with either the head or tail.

The notochord is a smooth cylindrical rod lying above the gut and running from end to end of the animal. It consists of cells, much of whose body is changed into a gelatinous substance, and which are surrounded by an exceedingly firm membrane termed the chordal sheath. In the embryo the notochord

first appears as a groove in the dorsal wall of the gut, so that we may say that the notochord of the Hemichordata retains a form which is passed through in development by that of *Amphioxus*.

In the very young embryo also an indication is seen of the division of the body into the same three regions as we found in the Hemichordata. Just as in the embryo of *Balanoglossus* so here, the embryonic gut gives rise to five outgrowths from which the coelom of




FIG. 168. Diagrammatic longitudinal section of an embryo of *Amphioxus*.

- | | | |
|-----------------------|---------------------------------------|---|
| 1. Neuropore— | anterior opening of the neural canal. | 2. Neural canal. |
| 3. Neurenteric canal. | 4. Coelomic groove. | 5. Somite divided off from coelomic groove. |
| 6. Collar-cavity. | 7. Head-cavity. | 8. Alimentary canal. |

the adult is derived. These outgrowths are (1) a median anterior unpaired pouch, the so-called head-cavity corresponding to the proboscis-cavity of *Balanoglossus*; (2) an anterior pair of pouches, "the collar-cavities," corresponding to the similarly named sections of the coelom of *Balanoglossus*; and finally (3) a pair of groove-like extensions of the dorso-lateral angles of the gut-cavity, called the coelomic grooves, developed only at the hinder end of the gut. From the last-named the coelom of most of the body arises, and they correspond to the trunk-coelom of *Balanoglossus* (Fig. 168). The proboscis or prae-oral region is however very small and bent down ventrally, its cavity becomes practically entirely obliterated in the adult. Dorsally the collar region is narrow from before backwards, but it extends obliquely downwards and backwards, causing a slight ridge to appear at the side of the body. This ridge grows out on each side into a flap, which meets its fellow beneath the ventral wall of the body and thus they enclose a space, the so-called atrial cavity (Figs. 170, 171). This still communicates with the exterior behind through the atrial pore. The gill-slits, which occur in the front part of the trunk region, open into

this atrial cavity. The atrial flaps, enclosing the atrial cavity, are an obvious arrangement by which the slits are saved from being choked with the sand in which the creature lives. In the Hemichordata the hinder end of the collar region may extend over one or two gill-slits; the arrangement in *Amphioxus* may be regarded as a further development of this state of affairs. As in the case of Hemichordata, the slits of *Amphioxus* are divided into two, by a tongue-bar reaching from the upper margin almost to the bottom of the slit. Each slit thus becomes U-shaped (Figs. 169, 172).




FIG. 169. Anterior region of young *Amphioxus* from left side. After Willey; the renal tubules inserted after Boveri.

at. Atrial cavity. ci. Oral cirri. ch. Notochord. df. Dorsal fin-chambers.
e. Eye-spot. end. Endostyle. hep. Outgrowing liver; the index
line passes through one of J. Müller's renal papillae. met. Metapleural
fold. nph. Nephridia. nt. Spinal cord. olf. Olfactory pit.
ph.b. Peripharyngeal ciliated band. tb. Tongue-bars. vel. Velum.

The upper and anterior portion of the collar-cavity becomes separated from the rest: its inner walls thicken and develop into a powerful longitudinal muscle which forms the first myotome (Gr. *μῦς*, mouse, muscle; *τόμος*, a division).

The trunk coelomic cavity breaks up from the beginning into a series of pouches called somites, each of which subsequently divides into an upper and an under part. The inner walls of the upper parts undergo a similar change to that experienced by the corresponding part of the collar-cavity forming a series of myotomes. The name myotome is given to each of the metamerically arranged bundles of muscle-fibres. Each myotome is separated from the next by a connective-tissue partition. In *Amphioxus* the myotomes of the right side alternate with those of the left, so that the centre of a myotome on one side is opposite the connective-tissue partition on the other. Each is V-shaped, and they are arranged so \llcorner . Hence in a transverse section several myotomes are seen on each

side of the body. Thus we have two great series of longitudinal muscles broken up into myotomes, one on each side of the animal, by the alternate contraction of which powerful side-strokes of the




FIG. 170. Diagrammatic transverse section through pharyngeal region of female *Amphioxus*. After Lankester and Boveri, from R. Hertwig.

- at. Atrial cavity. c. Dorsal coelom, separated from atrial cavity by the double-layered membrane known as the *ligamentum denticulatum*. ch. Notochord. dn. Sensory nerve. e. Endostyle, below which is the endostylar coelom containing the ventral aorta. f. Fin-ray of dorsal fin. g. Gonadic pouch containing ova. hv. Hepatic vein lying in the narrow coelomic space which surrounds l, the liver or hepatic coecum. la. Left aorta separated from the right aorta by the hyperpharyngeal (epibranchial) groove. ly. Lymph-space. mp. Metapleural fold. my. Longitudinal muscles of myotomes; over against the dorsal coelom these muscles are arranged vertically, and form the rectus abdominis of Schneider. nt. Spinal cord. p. Pharynx. r. Nephridium. t.m. Transverse or subatrial muscles. vn. Motor spinal nerve, the fibres of which have the appearance of passing directly into the muscle-fibres. N.B. The connective tissue (cutis, notochordal sheath, etc.) and the coelomic epithelium are indicated by the black lines.

flat body propel the animal forwards.




FIG. 171. Transverse section through post-pharyngeal region of young *Amphioxus*, to show groups of renal cells in floor of atrium. After Lankester and Willey.

ao. Aorta. *at.* Atrial cavity. *b.c.* Body-cavity (coelom). *c.c.* Central canal of nerve-cord (*n.c.*). *ch.* Notochord. *d.f.c.* Fin-cavity. *i.m.* Intercoelic membrane. *int.* Intestine. *l.m.* and *r.m.* Left and right metapleural folds. *r.p.* One of J. Müller's renal papillae. *s.i.v.* Sub-intestinal vein.

The elasticity of the notochord acts like a fly-wheel in storing the force during the latter part of each stroke, and re-inforcing each stroke at its commencement. The cavity of the upper division of the somite persists throughout life, and is known as the myocoel (15, Fig. 179), the fold separating it from the cavity of the lower division being termed the intercoelic membrane (*i.m.* Figs. 171 and 177).

The lower portions of the somites fuse with one another and form a continuous body cavity round the hinder part of the alimentary canal (*b.c.* Fig. 171). In front, owing to the presence of gill-slits, there are formed a right and a left dorsal coelomic canal, and a ventral coelomic tube, or endostylar coelom, the dorsal and ventral portions communicating with one another by spaces in the gill-bars, that is, in the pieces of body-wall intervening between the gill-slits. These spaces are termed branchial coelomic canals.

Although at first formed from backward prolongations of the collar region, the atrial flaps soon become invaded by the lower ends of the trunk myotomes; the ventral muscle however running across the under surface of the atrial cavity (Fig. 170), and which by contracting diminishes its size and thus expels water, originates from the walls of the lower portions of the collar cavity.

The mouth is originally some distance behind the anterior end,

so that there is a prae-oral portion of the body which in the embryo is occupied by an anterior division of the coelom corresponding to




FIG. 172. Anterior portion of body of young transparent *Amphioxus*. After J. Müller, slightly altered.

ch. Notochord. *ci.* Oral cirri. *e.* Eye-spot. *end.* Endostyle. *fr.* Fin-rays. *g.s.* Gill-slits: the skeletal rods of the gill-bars are indicated by black lines. *nt.* Spinal cord, with pigment granules near its base. *ra.* Downgrowth from right aorta lying to the right of *vel.* the velum; with velar tentacles projecting back into pharynx. *w.o.* Ciliated epithelial tracts on inner surface of oral hood.

the proboscis cavity of the Hemichordata. Subsequently however the atrial flaps extend right to the anterior end, so that a new terminal mouth is formed leading into a chamber which is clothed by ectoderm and which is therefore to be regarded as the stomodaeum. The opening of the stomodaeum now forms the apparent mouth, and the lips of this secondary mouth grow out into rods supported by gelatinous material and covered with cilia, the so-called oral cirri, the function of which has been already explained (Fig. 167). The walls of the stomodaeum are known collectively as the oral hood. The position of the primary mouth is still marked by a projecting lip, the velum which is produced into ten or twelve delicate tentacles. These form a filter to prevent coarse material from reaching the alimentary canal.




FIG. 173. Anterior portion of spinal cord of *Amphioxus*; seen from above. After Schneider.

Between the first pair of cranial nerves is seen the eye-spot; one of the branches of the second pair of cranial nerves sometimes arises directly from the spinal cord as shown on the right; farther back are seen the pigment spots of the nerve-cord.

The nervous system is a simple tube with thick walls and very narrow cavity. It is almost as extended as the notochord, and lies above it. It does not however quite reach the front end of the body. Its extreme front tip is called the cerebral vesicle; it has a wide cavity with thin walls, so that the total diameter is not increased. There is a pit reaching down to it from the external




FIG. 174. Median vertical section through the cerebral vesicle of *Amphioxus*. After Kupffer.

c.v. Cavity of cerebral vesicle. e. Eye-spot. g.c. Dorsal group of ganglion-cells. inf. Infundibulum. l.o. Olfactory lobe. tp. Tuberculum posterius.

skin, possibly a rudimentary olfactory organ (Fig. 174), and in the wall of the vesicle itself is a mass of pigmented cells forming an eye-spot. In the young larval *Amphioxus* this part of the nerve-tube remains for a considerable time as an uncovered medullary plate, and one is inclined to imagine that it corresponds to the sensitive nervous surface of the proboscis in the Hemichordata, since in the larvae of these animals there is a sensitive plate with two eye-spots at the apex of the prae-oral lobe. In the wall of the nerve-tube are to be found two kinds of nerve-cells, viz. (a) ordinary small nerve-cells, the processes of which soon pass outwards into the peripheral nerves, and (b) very large nerve-cells, the processes of which extend almost throughout the entire length of the nerve-tube. The processes of the latter kind of cell are called "giant fibres" (gf^1 and gf^2 , Fig. 175): they appear to have to do with regulating

the concerted muscular movements of the animal. Besides the nerve-cells, as in all nervous systems, there are a certain number of supporting cells (*s.f.*, Fig. 175). In the embryo of *Amphioxus* the whole wall of the nerve-tube consists of a single layer of cells, all of which abut on the cavity of the tube; many of these cells become




FIG. 175. Transverse section through the spinal cord of *Amphioxus* in the middle region of the body. After Rohde.

- a.* Giant fibre. *c.c.* Central canal. *g.f.*¹. Giant nerve-fibres, which traverse the spinal cord from before backwards. *g.f.*². Giant nerve-fibres, which traverse the spinal cord from behind forwards. *m.p.* Muscle-plates, i.e. terminations of the nerve-fibres on the muscles. *m.r.* Motor nerve-fibres. *n.f.* Longitudinal nerve-fibres cut across. *s.f.* Supporting cells. *sh.* Sheath of nerve-cord.

afterwards transformed into small round nerve-cells, and recede from the cavity, assuming a more peripheral position: but others retain their connection with the cavity and become drawn out into fibre-like supporting cells. From the nerve-cord are given off two kinds of nerves, but not at the same level, so that in a transverse section one kind only is seen. These are:—(1) sensory nerves, going directly to the skin and having a dorsal origin; (2) motor nerves, going to the myotomes. The nervous tube and the alimentary canal at first both reach to the extreme posterior end of the body and here are connected by a vertical tube, the neurenteric canal. On the course of this tube the anus is formed. As development proceeds the anus slowly shifts forwards and the neurenteric canal

becomes a solid string of cells and disappears. Thus is initiated the formation of a tail, by which term is denoted a portion of the body devoted entirely to locomotion and freed from all part of the gut, being filled only with muscles. The tail of *Amphioxus* only acquires a very limited development, but it soon becomes surrounded by a tail-fin, at first merely made up of the enlarged skin cells, but soon becoming a flap containing gelatinous material. A similar fold along




FIG. 176. Nephridium of the left side, with the neighbouring portion of the pharyngeal wall, as seen in the living condition. The round bodies in the wall of the tubule represent carmine granules. Highly magnified. After Boveri.

the middle line of the back forms the dorsal fin, in which, in the larva, there are a series of metamERICALLY arranged cavities lined by distinct epithelium, probably derivatives of the myocoelic cavities (*d.f.c.* Fig. 171). There are also low fin folds projecting from the sides of the atrial cavity and constituting the lateral or metapleural fins (Fig. 170), and a median ventral fold between the atrial pore and anus, called the ventral fin (Fig. 166). The dorsal and ventral fins are stiffened by a number of gelatinous rods more numerous than the myotomes of the corresponding regions of the body.

The alimentary canal of *Amphioxus* is a perfectly straight tube consisting of stomodaeum or mouth gut, pharynx or bran-

chial gut, and intestine or digestive gut. The pharynx has along both dorsal and ventral middle lines grooves lined with cilia connected with each other by a circular groove just inside the velum or true mouth. The ventral groove is called the Endostyle or Hypopharyngeal groove, the upper groove is termed the Hyperpharyngeal, and the connecting groove the Peripharyngeal band (Figs. 169, 170, 172). The function of these grooves is curious.

The endostyle produces a cord of mucus which is worked forwards by its cilia and pressed up the sides of the peripharyngeal bands. Here it is caught by the intruding current of water produced by the cilia of the oral cirri and swept back along the hyperpharyngeal groove to the opening of the intestine, entangling in its passage the small plants and animals carried by the water; the latter of course escapes into the atrial cavity through the hundred or so long narrow gill-slits. The intestine is prolonged forward on the right side of the pharynx into a blind pouch, the so-called liver (*l*, Fig. 178), which probably secretes a digestive juice.




FIG. 177. Portion of transverse section through the pharynx of *Amphioxus*, to show position of excretory tubule. After Weiss.

ao. Left aorta. *at.* Atrial cavity. *at.e.* Atrial epithelium. *c.* Coelom.
ch. Notochord. *i.m.* Intercoelic membrane. *l.d.* Dorsal wall of atrial
 cavity. *nph.* Nephridium. *p.b.* Gill-bar. *ph.e.* Epithelium
 of hyperpharyngeal groove. *ph.f.* Fold attached to gill-bar containing
 branchial coelomic canal. *s.ch.* Sheath of notochord. *t.b.* Tongue-bar.

The excretory organs of *Amphioxus* are small and have only recently been discovered. We have seen that in the region of the pharynx the coelom has become reduced to a narrow canal, beneath the pharynx, and to two dorsal canals at the sides of the notochord (Figs. 170, 177). These latter canals have at the level of each tongue-bar a wide funnel leading into a short tube connecting them with the atrial cavity. The edges of the funnel are supported by strings crossing the coelomic canal and inserted in its wall. These tubes are the nephridia and taken collectively constitute

the kidney. It has been proved that carmine injected into the animal is excreted by them. Besides these a number of thickened patches of the atrial epithelium, discovered by Johannes Müller and called by him renal papillae, are thought to assist in excretion (Figs. 169 and 171).




FIG. 178. *Amphioxus* dissected from the ventral side $\times 2$. After Rathke, slightly altered.

an. Anus. at. Position of atrial pore; the extension of the atrium behind this point is indicated by the dotted line passing over to the right side of *i*, the intestine. e. Endostyle. g. Gonadic pouches. l. Liver. m. Entrance to mouth with the oral cirri lying over it. p. Pharynx.

The blood system is exceedingly simple. The blood from the alimentary canal is brought back by a sub-intestinal vein which like a broad river is often subdivided into two or three parallel channels which then reunite with one another; in a word it is more a plexus than a tube. It runs to the tip of the liver on its outer side, returns on its inner side, and pursues its course then as a single channel under the pharynx, where it is called the ventral aorta. In this region it is contractile, deriving its muscles from the walls of the ventral coelomic tube. Vertical branchial vessels called arterial arches are given off; these ascend in the gill septa, that is, the portions of the wall of the pharynx intervening between the gill-slits. Arriving at the dorsal line of the pharynx these vessels empty into two longitudinal vessels, the dorsal aortae, which further back unite into one (Figs. 170 and 171). The tongue-bars also contain vessels emptying into the dorsal aortae; these communicate with the branchial vessels through what are called synapticulae, that is, cross pieces tying the tongue-bar to both sides of the gill-slit which it divides (Fig. 172).

Both gill-bar and tongue-bar are strengthened with rods of gelatinous tissue. These are the precursors of the visceral arches, which form such an important part of the skeleton in the

higher Vertebrata. Similar gelatinous tissue forms the rays of

the dorsal and ventral fins, the sheaths of the notochord and nerve-chord, and the dermis. It differs from ordinary connective-tissue in that although it consists of a ground substance with a deposit of fibres in it, it contains no amoebocytes or "connective-tissue corpuscles." The fibres in ordinary connective-tissue are largely if not entirely produced by the metabolic activity of the amoebocytes ; but in *Amphioxus* it appears that they are produced




FIG. 179. Diagrammatic transverse section of *Amphioxus* to show the relation of the excretory and genital organs.

- | | | | |
|--|-----------------------------|----------------|-----------------------|
| 1. Nerve-cord. | 2. Notochord. | 3. Myotome. | 4. Hollow sclerotome. |
| 5. Gonadic pouch. | 6. Dorsal coelomic canal. | 7. Nephridium. | |
| 8. Branchial coelomic canal in gill-bar. | 9. Endostylar coelom. | | |
| 10. Pharynx. | 11. Hyperpharyngeal groove. | 12. Endostyle. | |
| 13. Dorsal aorta. | 14. Atrial cavity. | 15. Myocoel. | |

by the cells of the coelom, ectoderm, and endoderm, which adjoin the connective-tissue. Thus the sheath of the notochord is deposited partly by the cells of the notochord, but chiefly by a hollow outgrowth from the myotome called the sclerotome (4, Fig. 179), the fin-ray by a coelomic sac (*d.f.c.* Fig. 171) which disappears in the

adult, the rods of the gill- and tongue-bars largely by the epithelium of the pharynx. The connective-tissue of the Cephalochordata is therefore in a peculiarly interesting primitive condition; and that of the Hemichordata has the same structure.

The reproductive organs are very simple in construction. The sexes are separate, and ovaries and testes closely resemble each other in external appearance (Fig. 178). They take the form of squarish masses, called gonadic pouches, embedded in the outer walls of the atrial cavity. When ripe they burst into the atrial cavity, the eggs escape through the mouth or atrial pore, the spermatozoa through the atrial pore. The fertilized egg develops into a free-swimming larva of a remarkable form. There are no atrial folds covering the gills, but one set of slits is developed long before the other, and the mouth appears on the right side. It has been proved that the sexual organs are outgrowths from the lower ends of the myotomes, and remain throughout life connected with these by strings of cells (Fig. 179).


The Hemichordata and Cephalochordata are found all over the tropical and temperate regions of the world wherever a suitable substratum is found. The Hemichordata burrow in mud rich in decaying matter, but the Cephalochordata prefer clean sand, their food as we have seen consisting of swimming organisms.

Sub-Phylum III. TUNICATA OR UROCHORDATA.

By many the group of Tunicata or Urochordata would be considered the lowest portion of the phylum Vertebrata, and if we had regard only to the adult structure this could not well be denied, for in the adult hardly a trace of the Vertebrate relationship is discernible. But the Tunicate commences life as a larva showing a more developed structure in several important points than *Amphioxus* possesses at any period of its life-history, and hence we must regard the simple organization of the adult as a degraded rather than a primitive condition of affairs.

The typical Tunicate larva is often called the Ascidian tadpole

Larva. because its form recalls that of the well-known larva of the frog. It attains a length of about a quarter of an inch, and consists of a small round trunk, and a thin vertical tail four or five times as long as the trunk. The tail is the organ of locomotion, and is provided with a sheet of muscles on either side



180

181

FIG. 180. Side view of the anterior end of a larva of *Ascidia*, which has been free-swimming for two days $\times 375$. FIG. 181. Dorsal view of the same. After Kowalewsky.

- | | |
|------------------------|---|
| 1. Mouth. | 2. The connection of the brain with the stomodaeum. |
| 3. Endostyle. | 4. Intestine. |
| 5. Branchial cavity. | 6. 1st gill-slit. |
| 7. 2nd gill-slit. | 8. Atrial opening. |
| 9. Blood corpuscles. | 10. Cavity of brain. |
| 11. Dorsal nerve-tube. | 12. Notochord. |
| 13. Muscles. | 14. Fixing organs. |
| 15. Otocyst. | 16. Eye. |

by the alternate contraction of which powerful side-strokes are executed and the animal is propelled forward (13. Fig. 181). The tail is stiffened by a well-developed notochord—which does not extend into the trunk, hence the name “Urochordata” (Gr. οὐρά, tail; χορδή, a string). A uniform flap of skin, a continuous fin, forms a border to the tail. The trunk contains the enlarged pharynx which opens by a narrow mouth in front: and laterally communicates with the exterior by two ciliated openings—the gill-slits. Its ventral wall is swollen out into a pocket which causes the under lip to protrude as a bulky chin. In this pocket we find developed a ciliated groove, the endostyle, having the same position to the organ similarly named in *Amphioxus*. On the chin outside are three peculiar warts which secrete a sticky slime, and which are used by the larva to fix itself to surrounding objects. The pharynx leads behind into a short intestine which is attached to the ectoderm high up on the side far in advance of the root of the tail. Hence the process of shifting forward the anus, and the corresponding development of a purely muscular tail, has been carried much further in the Ascidian tadpole than in *Amphioxus*.

The nervous system in the tail is a simple neural tube; but in the trunk it expands into a thin walled vesicle, the so-called sense-vesicle, which is the representative of the cerebral vesicle of *Amphioxus* and the forerunner of the brain of the higher Vertebrata. As in the larva of *Amphioxus*, the sense-vesicle opens to the exterior, but the spot where this occurs is involved in the invagination which forms the stomodaeum. The tube connecting the sense-vesicle and the stomodaeum is called the neuropore (2. Figs. 180 and 181). Part of the side-wall of this vesicle is modified so as to form a cup-shaped eye with a simple cuticular lens directed inwards. From the roof hangs a ball of lime suspended by a pillar of cells; this acts as an otolith, and the whole forms a rudimentary ear.

Thus both in the structure of the nervous system and the position of the anus, the Ascidian tadpole is more advanced than the *Amphioxus*.

Although, as we have seen, both mouth and anus are present, yet they cannot be used, for they are closed by a sheet of gelatinous matter. This is the test which is secreted by the ectoderm cells and envelopes the whole body, so that during its brief free-swimming life the Ascidian takes no food.

After swimming for a short time the larva fixes itself by its chin-warts to a suitable substratum and undergoes a very rapid

metamorphosis. The tail shrinks and is absorbed, notochord and nerve-tube disappear: the sense-vesicle also disappears, only its hinder thickened wall persisting as the adult ganglion (6. Fig. 182). The neuropore however

Metamor-
phosis.

persists and develops into a mass of tubes underlying the ganglion, which is called the sub-neural gland. Its opening acquires a crescent form with thickened lips, and is called the dorsal tubercle. Meanwhile the chin grows enormously, so as to rotate the mouth up and away from the substratum, and thus the long axis of the pharynx becomes vertical instead of horizontal. The skin of the region where the anus becomes situated is depressed so as to form a groove. This becomes confluent with the outer parts of the two gill-slits, so as to form a single dorsal cavity termed the atrial-cavity, the opening of which is not far from the mouth. It must be noticed that this cavity does not correspond to the similarly named cavity in *Amphioxus*: in the case of the last-named animal the atrial walls originate from the dorsal edges of the gill-slits and meet one another beneath the animal; whereas in the




FIG. 182. Diagram of the fixing and changes undergone by a larval *Ascidian*. From Lankester.

1. Mouth. 2. Anus. 3. Gill-slits.
4. In A, notochord; in B and C, vanishing tail. 5. In A, tail. 6. Brain.

Urochordata they arise from the ventral edges of the slits, and are united with one another on the dorsal edge. The gill-slits them-




FIG. 183. *Ciona intestinalis* $\times 1$. The live animal seen in its test; some of the organs can be seen, as the test is semi-transparent.

1. Mouth. 2. Atrial orifice. 3. Anus.
4. Genital pore. 5. Muscles. 6. Stomach.
7. Intestine. 8. Reproductive organs.
9. Stalk attached to a rock. 10. Tentacular ring. 11. Peripharyngeal ring. 12. Brain.

selves become changed by the growth of numerous partitions, transverse to the axis of the pharynx, into a series of narrow slits: and then by the formation of another series of stronger bars parallel to the long axis, into a veritable ciliated trellis-work. All this trellis-work is supported by horny rods like the gill-bars of *Amphioxus*. The test thickens enormously and becomes invaded by a finger-like outgrowth from the hinder part of the body, which carries blood-vessels to it and buds off cells into it which nourish it and change its character. With these changes the adult form is attained. Few would see any resemblance to a Vertebrate in the motionless sac-like body fixed to a stone or rock and looking more like a plant than an animal (Fig. 183).

Nevertheless, the Tunicate in some points, even when adult, recalls the structure of *Amphioxus*. Thus we encounter a ring of delicate tentacles a short distance inside the mouth strikingly recalling the velar tentacles of *Amphioxus*. As in that animal also there is a long hypo-pharyngeal groove or endostyle passing in front into a peripharyngeal band, and secreting a cord of mucus which is worked forward. This mucus is torn into strings by the intruding current

of water, and swept backwards to the opening of the oesophagus, entangling in it food particles just as in *Amphioxus*. Instead of a hyperpharyngeal




FIG. 184. View of *Ciona intestinalis* lying on its right side. Both the branchial and the atrial cavities have been opened by longitudinal incisions.

1. Mouth. 2. Tentacles. 3. Peripharyngeal groove. 4. Perforated walls of branchial sac. 5. Endostyle. 6. Oesophageal opening leading from the branchial sac to the stomach, rather diagrammatic. 7. Stomach. 8. Intestine showing typhlosome; part of it removed to show subjacent structures. 9. Rectum. 10. Anus. 11. Atrial aperture. 12. Inner surface of mantle showing longitudinal and transverse muscle fibres. 13. Dorsal tubercle. 14. Subneural gland and brain. 15. Cut edge of branchial sac. 16. Heart. 17. Ovary. 18. Pore of vas deferens. The openings of the oviduct and the vas deferens are shown enlarged to the right. 19. Testicular tubes on intestine. 20. Oviduct. 21. Septum shutting off that part of the body-cavity which contains the heart, stomach, and generative organs.

groove, there is a series of tags hanging down from the dorsal wall of the pharynx, called languets. These in life curve round so as to form a row of hooks supporting and directing the mucous strings.

The oesophagus leads into a dilated stomach which bends on itself and leads into an intestine which after one or two coils runs forward and opens into the atrial cavity. Its ventral wall is folded inwards, forming a typhlosole similar to that of an Earthworm. As usual the straight terminal portion of the intestine is called the rectum. Near the anus open the ducts of the ovary and testes, for the animals are hermaphrodite. These organs are branched clumps of tubes, the testis being spread over the surface of the stomach, the ovary forming a mass between the stomach and intestine. Oviduct and vas-deferens are closely applied to one another, the vas-deferens being the more superficial. The latter opens by a rosette of small pores, the ovary by a broad opening, and so the water from the gill-slits, as it passes out of the atrial cavity, sweeps away the sexual cells.

On the ventral side of the pharynx is a V-shaped heart, which is enclosed in a space called the pericardium. The heart is only a specially thickened part of a ventral blood-vessel, which lies immediately under the endostyle and communicates through a network of vessels in the gill trellis-work with the dorsal blood-vessel. Waves of contraction pass over the heart so as to drive the blood forward. After a certain interval the direction of these waves is reversed, so that the blood alternately goes to the dorsal vessel from the heart and *vice versâ*. With the exception of the heart, however, the blood-vessels do not seem to have definite walls, and are really, as in the Enteropneusta, chinks left between various organs.

The sluggish life of the Ascidian has as its only external manifestation the sudden closing of the mouth and atrial cavity by sphincters, and the consequent ejection of water—whence the popular name Sea Squirt. In consequence metabolism is at a low intensity and not much waste is produced. A good deal of this waste is probably got rid of by the throwing off of the mantle from time to time, but for the rest no definite excretory organ is required. The nitrogenous excretion is stored up as crystals of insoluble uric acid in little vesicles attached to the hinder part of the intestine. These vesicles, together with the cavities of the genital organs and the pericardium, may be looked on as the remnants of the coelom, so that here a similar phenomenon has taken place to what was met

with in the case of Arthropods, namely an obliteration of the coelom through the expansion of blood-vessels.

The Tunicata or Urochordata abound on every rocky shore and exhibit a surprising diversity of form. Their principal divisions are as follows.

Class I. COPELATA or LARVACEA.

Small forms which retain the larval condition throughout life. The gill-slits are undivided and the anus ventral. There is no atrial cavity: each of the two gill-slits opens directly to the exterior. The tail is usually carried bent forward at a sharp angle with the body. A temporary test devoid of blood-vessels is found: the animal when disturbed wriggles out of it and forms another.

Class II. The ACOPA.

Forms which have lost the tail with its nerves and muscles. These are divided into

Order I. The **Ascidiceae**, fixed forms.

Order II. The **Thaliaceae**, which have secondarily acquired the power of swimming by contractions of the whole body carried out by transverse bands of muscle.

The Ascidiceae constitute the great bulk of the Urochordata. Some of them, such as the form taken as a type in the general description given above, remain solitary throughout life, but others bud and form colonies embedded in a common test; these are called Compound Ascidi-ans, but the group is not a natural one, since budding is




FIG. 185. Two groups of individuals of *Botryllus violaceus*, after Milne Edwards.

1. Mouth opening. 2. Common cloaca of the group.

carried out in different ways in different families, and has therefore probably originated several times. The commonest method is by the outgrowth of a hollow finger-shaped process of the pharynx,




FIG. 186. Dorsal view of a fully-grown specimen of the solitary form of *Salpa democratica* \times about 10. From Brooks.

1. Muscle bands.
2. Narrow band representing the dorsal wall of the pharynx, the so-called "gill."
3. Endostyle.
- 4.Peripharyngeal band.
5. Brain.
6. Ciliated pit.
8. "Nucleus" consisting of stomach, liver, intestine.
9. Stolon, row of young.
10. Processes of mantle.
11. Mouth.

called a stolon, arising at the hinder end of the endostyle, which becomes divided into pieces, each forming a bud. On the other hand in *Botryllus* a different method is followed, since in this case the buds originate simply as little pockets of the atrial-wall of the parent. *Botryllus* is one of the most beautiful colonial forms; in it the buds are arranged in circles; the atrial openings of the members of a circle open into a common pit in the centre called the cloaca. *Pyrosoma* is a free floating colonial form, with the shape of a cylinder open at both ends, the atrial cavities of the constituent persons opening on the inner surface, the mouth on the outer.

The Thaliaceae are extraordinary forms. They have the shape of cylinders with the mouth at one end and the atrial opening at the other, and their body is surrounded wholly or partly with muscular hoops like the hoops encasing a barrel. The commonest form is *Salpa*, which at intervals may be seen in countless numbers swimming at the surface of the sea. In this

animal the test is of a glassy transparency. The two original atrial openings or gill-slits of the larva do not become divided by

partitions, but develop into two huge vacuities in the side walls of the pharynx, reducing its dorsal wall to a mere band, the so-called "gill." There are two distinct forms of this animal, a sexual and an asexual, one giving rise to the other, so that here we have a case of "the alternation of generation." In the asexual form we find an endostyle-process or stolon which gives rise to a chain of small sexual forms which one by one drop off. Each sexual form




FIG. 187. Semi-diagrammatic view of left side of *Salpa*. From Herdman.

- | | | | |
|--------------------------|-----------------------|---------------------------|---------------------|
| 1. Branchial aperture. | 2. Atrial aperture. | 3. Anus. | 4. Branchial sac. |
| 5. "Gill." | 6. Sub-neural gland. | 7. Endostyle. | 8. Heart. |
| 9. Oesophagus. | 11. Languet. | 12. Muscle bands. | 13. Nerve ganglion. |
| | 14. Embryo in ovisac. | 15. Peribranchial cavity. | |
| 16. Peripharyngeal band. | 17. Stomach. | 18. Testes. | 19. Test. |
| 20. Sub-neural gland. | | | |

produces only one egg. This when fertilised does not give rise to a tailed larva, but becomes attached to the atrial wall of the mother by a knob of maternal tissue containing blood-vessels, called the placenta, which is embedded in a disk of embryonic tissue, through which nourishment diffuses from mother to embryo. In this position it grows up into an asexual form and eventually breaks loose and swims away.

CHAPTER XIV.

INTRODUCTION TO SUB-PHYLUM IV CRANIATA.

THE CYCLOSTOMATA.

ALL the remaining Vertebrata are distinguished by possessing a skull and brain, and are grouped together as Craniata. The Craniata are separated by a deep gap from all the lower forms : they themselves present a fairly continuous and graded series from the lowest to the highest forms, and their comparative anatomy, especially when we take into account the fossil representatives of the sub-phylum, gives us a fairly good idea of the course which the evolution of Vertebrata has pursued ; so much so indeed, that the group might be compared to the fairly reliable and complete records of a country during the historical period, whilst the Hemichordata, Cephalochordata and Urochordata represent the few scattered and scarcely decipherable documents of prehistoric epochs.

The Craniata are defined, as we have seen, by the possession of a skull and a brain, though these are only two of the
Characters. many characters which distinguish them from the other Vertebrata. The skull is composed of either cartilage or bone ; and even in cases where the adult skull is completely bony, in the embryo the bone is partly, at any rate, represented by cartilage. Cartilage and bone are really only two peculiar modifications of connective tissue whose fundamental characters it may be useful to recall. There is in every case a gelatinous ground substance traversed by fibres, and applied to these fibres are cells, which are connected with one another by delicate threads of protoplasm and which secrete the greater part of the ground substance and fibres contained therein. In cartilage, the ground substance becomes cheesy in consistence, the fibres being masked, and the cells are arranged by twos and threes in little pockets. In bone, on the other hand, the cells remain single whilst the

ground substance becomes hardened by depositions of carbonate and phosphate of lime. The spaces occupied by the cells are known as lacunae, and the delicate processes which connect the cells give rise to the capillary canals known as canaliculi in the dried bone, whilst the spaces occupied by blood-vessels traversing the bone are known as Haversian canals.

In the simplest form the skull consists of two pairs of pieces of cartilage, one pair embracing the front end of the notochord and termed the parachordals. In front of these is the second pair, the trabeculae, united behind and before with each other but diverging in the middle so as to embrace between them the pituitary body, which morphologically represents the sub-neural gland of the Urochordata, but the function of which is unknown. The parachordals develop ridges which wall in the sides of the brain and may form a roof over its hinder portion.

Primitive
skull.

The brain is only the enlarged and modified anterior end of the neural tube, and the existence of a skull is correlated with the presence of neural arches protecting the hinder part of the nervous system. These arches consist of paired pieces of cartilage meeting above the neural tube. They have been shown to be formed as solid outgrowths of the myotomes representing the hollow sclerotomes of *Amphioxus*, and hence it may be that the cranium itself is derived from the walls of the most anterior myotomes which early become fused with one another and otherwise modified.

Haemal arches, paired pieces of cartilages with their upper ends implanted in the sheath of the notochord and their outer ends directed downwards, are also always present, and like the neural arches are derivatives of the myotomes. In the region of the tail the haemal arches meet each other so as to form a V beneath the notochord, but in the trunk they simply project out between adjacent myotomes as transverse processes¹, the ends of which may become moveable on the basal parts and are then known as ribs.

The brain of all Craniata is sharply divisible into three primary regions called fore-brain, mid-brain and hind-brain (Fig. 188). Of these the first is certainly the enlarged and highly developed representative of the sense vesicle of the Urochordata and of the cerebral vesicle of *Amphioxus*.

Brain.

¹ This statement applies to the transverse processes of the lower Craniata: those of the higher Craniata are secondary outgrowths from the neural arches.




FIG. 188. *Seyllium catulus*. Dissection of the brain and of some of the cranial nerves. A. Ventral view. B. Dorsal view. C. Longitudinal median section. D. Diagram of embryonic brain showing the three primary vesicles.

1. Cerebrum. 2. Pincal stalk. 3. Olfactory lobe. 4. Cerebral hemisphere. 5. Thalamencephalon. 6. Pituitary body. 7. Optic lobes. 8. Optic lobes. 9. Cerebellum. 10. The roof of hind-brain. 11. Superior oblique muscle. 12. Internal rectus muscle. 13. Superior rectus muscle. 14. External rectus muscle. 15. Ninth or glossopharyngeal nerve. 16. Branch of vagus nerve to second branchial cleft. 16a. Branch of vagus nerve to third branchial cleft. 17. Main trunk of vagus to fourth and fifth gill-slits, to lateral line and to viscera. 11a. In A, optic chiasma. iv, v, vi, vii, viii, ix, and x. Roots of fourth to tenth cranial nerves. In D, i, ii, iii represent the first, second, and third primary vesicles of the embryonic brain.

In the embryo it is a simple thin-walled vesicle, the lateral walls of which become changed into the retina or the essential sensory portion of the eyes. This, as is the case in the Ascidian tadpole, has its perceptive surface turned inwards towards the brain cavity. The nerves by which the eyes are connected with the brain are really the narrowed connections of the lateral portions of the fore-brain with the central portion. The roof of the fore-brain remains thin throughout life and from it a stalk arises leading to a third median eye, the so-called pineal-gland, vestigial in all living forms. From the front wall of the fore-brain an outgrowth takes place, giving rise to a bilobed vesicle termed the cerebrum, each of the two lobes of which it is composed being termed a cerebral hemisphere. This in the higher Craniata is the seat of the more complex mental processes, but in the lower appears to be intimately connected with the organ of smell. The cerebrum in these cases remains thin-roofed, but its base thickens owing to a great development of nervous matter. In order to distinguish it from the cerebrum the original fore-brain is denoted by the name *thalamencephalon*.

The mid-brain acquires thick lateral pouches, the so-called optic lobes: the hind-brain remains thin-roofed, except in front where a transverse nervous band, the cerebellum, is formed. The cerebellum is believed to be the portion of the brain intimately connected with the semicircular canals of the ear and to have for its function the control of the muscles so as to maintain the equilibrium of the body. The rest of the hind-brain is termed the medulla oblongata or spinal bulb; it controls the beating of the heart and the respiratory movements. The hinder part of the neural tube is known as the spinal cord, and it develops thick walls, so that its cavity is exceedingly small.

The essential element in the nervous system of Vertebrata, as in all other nervous systems, is a kind of cell which has been variously styled nerve-cell, ganglion-cell and neuron. This last name is undoubtedly the best, as it avoids the old misapprehension that regarded the nerve-cell and nerve-fibre as two independent structures.

The minute structure of the nervous system.

On page 52 it was pointed out that the nerve-fibre is a very fine basal outgrowth of a modified ectoderm cell which is the nerve-cell. The cell, including its outgrowth, is termed the neuron. Important discoveries have recently been made on the minute structure of the nervous system of Vertebrata, and we are now able to form a

simple and connected idea of the principles on which it is built up. Originating as a simple strip of ectoderm which becomes rolled up so as to form a tube, it is at first composed of cells which extend through its entire thickness, and which all abut on the cavity of the tube. Some retain this position but develop branches and deposit a large amount of cuticular substance in their protoplasm: these, constituting the supporting elements of the system, are termed collectively neuroglia. Other cells retire from the cavity of the tube, becoming more or less rounded in form, but developing a number of outgrowths: these cells are the neurons. Each neuron is provided with a number of branching processes, sometimes arising from a single thick stem; these are called receptive dendrites (Gr. δένδρον, a tree), and they receive stimuli. Stimuli are transmitted through one long basal process, called the axis-cylinder process or nerve-tail, which ends in a tuft of processes often thickened at the tips, which are called terminal dendrites. The name axis-cylinder is suggested by the circumstance that amongst Vertebrata this process is in nearly every case surrounded by a fatty sheath of a conspicuous white colour, called the medullary sheath: the process together with its sheath making up what is ordinarily known as a nerve-fibre. The tuft of dendrites in which the axis-cylinder ends is found to be in close contiguity either with the receptive dendrites of another neuron, by which means the stimulus is transmitted from one neuron to another, or else with the muscle-plate of a muscle-fibre, by which means the fibre is stimulated. The muscle-plate is a disc of protoplasm with several nuclei situated at the side of the muscle-fibre. The axis-cylinder process may give off several branches termed collaterals. These like the main stem end in tufts of dendrites; in this way a stimulus may spread over several paths. The receptive dendrites of a neuron may also receive stimuli from the terminal tufts of several axis-cylinder processes, and in this way stimuli are co-ordinated and combined.

As mentioned above, the skull and brain are by no means the only characters which distinguish the Craniata from other Chordata. Perhaps the next in importance is the possession of three well-developed pairs of sense-organs, nose, eyes and ears. Of these the nose is the most simply constructed. It consists merely of a pair of pits in the skin at the most anterior portion of the body, the lining of which develops ridges covered with sensory cells, having an olfactory function

(Fig. 189). The essential element in all sense-organs is the sense-cell, which resembles the neuron in possessing a basal process terminating in a tuft of dendrites by which the stimulus is transmitted to a neuron, for in Craniata a sense-cell is never in direct communication with a muscle-fibre. It differs from the neuron in possessing one or more stiff peripheral processes projecting from the surface of the body, by which stimuli are received from the external world. These are termed sense-hairs, and in the olfactory cells they are excessively delicate in structure. Sense-cells are never combined by themselves into an epithelium: they are always intermixed with stiff supporting cells which usually have at the base several root-like branches. The front end of the brain comes in direct contact with the wall of the nasal sac and the tails of the sensory cells stretch into the brain constituting the olfactory nerve (Fig. 188).




FIG. 189. Transverse section through the snout of a Dogfish, *Scyllium canicula*, to show the structure of the nose $\times 2$.

1. Anterior naris, or external opening of olfactory sac.
2. Olfactory epithelium.
3. Ethmoidal region of the cartilaginous skull.

The ears are also at first pits of the skin placed further back at the sides of the hind-brain. In the lower forms these pits retain a narrow connection with the exterior throughout life through a long tube called the ductus endolymphaticus (2, Fig. 190). In the higher forms this tube is still recognizable but no longer opens to the exterior. In almost every case the pit gives rise to three flat outgrowths placed in planes at right angles to one another (Fig. 190).

These outgrowths become converted into half-rings by the meeting of their walls in the middle of each, and in this way three semicircular canals are formed, called respectively anterior, posterior,




FIG. 190. Ear of *Chimaera monstrosa* L. From Retzius. \times about 4. Seen from the inner side.

1. External aperture on roof of skull. The wall of 2, the "ductus endolymphaticus," is partly removed to show that it is a tube.
3. Anterior, 4, posterior, and 5, horizontal semicircular canals.
6. Anterior, 7, external, and 8, posterior ampullae.
9. Sacculus.
10. Auditory or 8th nerve.

and horizontal. The primary function of the whole organ, like that of the otocysts of Medusae, Crustacea and Molluscs, is to

enable the animal to perceive its position. As at the commencement of each semicircular canal there is a gelatinous cup closely resting on certain sense-cells with very long sense-hairs (Fig. 191), we see how admirably adapted the whole organ is to record change of position in any direction, since any change of position can be completely analysed into movements in three planes. The part of the canal containing the cup is somewhat enlarged and is called the ampulla. The central part of the organ is called the sacculus; it has cells adapted to perceive vibrations or to hear. It grows out into a pouch called the cochlea in higher forms. The sense-cells of both the ampullae and the sacculus are remarkable for possessing excessively short basal processes: the




FIG. 191. Section of an ampulla of the internal Ear.

1. Sense-cell bearing a long hair.
2. Sense-hair.
3. Nerve termination branching round base of sense-cell (dendrites of a deeply placed neuron).
4. Interstitial cell.
5. Gelatinous cup in which the sense-hairs are embedded.

auditory cells have each several short, stout sense-hairs. Both nose and ear have cartilaginous or bony coats which become firmly connected with the skull; these are known as the sense-capsules.

The eye is the most complicated, and in the higher Craniata by far the most important, of the sense-organs. In its origin, as we have seen, it is the lateral portion of the fore-brain which when constricted off is known as the primary optic vesicle (Fig. 192). The outer wall of this becomes modified into a sensory epithelium called the retina. This consists of a row of visual cells, their free ends directed inward towards the brain and produced into the characteristic striated rods. Beneath these sense-cells lie a

number of ganglion-cells, the dendrites of which, mingling with the dendrites of the sensory cells, give rise to a comparatively thick bed of nervous tissue. Long, however, before the sense-cells are developed, the primary vesicle of the eye has completely altered its shape. The outer wall has become pushed in on the inner so as to completely reverse the shape of the sac (Fig. 192). Its cavity is reduced to a mere slit, and it takes on the form of a very deep




FIG. 192. Transverse section through a third day Chick to show origin of Retina from the brain and of the lens from the ectoderm. Highly magnified.

1. Cavity of brain.
2. Outer layer of retina surrounding the black, thicker layer which will form the rods and cones.
3. Lens arising as a hollow invagination.
4. Pineal gland originating.
5. Embryonic connective tissue.

double cup with its concavity directed outwards. This is the cavity of the eyeball, or so-called secondary optic vesicle, the clear gelatinous connective tissue inside which is known as the vitreous humour. The connective tissue surrounding the vesicle peripherally forms a tough fibrous or even cartilaginous capsule called the sclerotic, which, however, unlike those of the ear and nose, remains quite free from the skull. The sensitive and nervous outer layer of the primary vesicle is known as the retina, the other layer (which becomes loaded with pigment) as the choroid epithelium. If we analyse the structure of the retina, we find that it has fundamentally the same structure as the central

nervous system of which, as its origin shows, it is really a part. Thus there are a number of branched and cuticularized supporting cells called fibres of Müller, extending throughout the whole thickness of the retina, and the main mass of the retina is made up of neurons. There is, however, in addition a layer of characteristic visual cells: that is to say, of sense-cells, with a comparatively thick striated rod in place of the ordinary sense-hair. Visual rods have already been described in the eyes of Anthomedusae (p. 53) and of Arthropoda (p. 122); they occur wherever the capacity for vision

is developed. In the retina of Craniata there are two varieties of visual cell, called respectively rod-cells and cone-cells. In the first, the visual rod is narrow and cylindrical, and the body of the cell beneath is filamentous with a rounded swelling for the nucleus; the basal process ends in an unbranched knob, that is to say, in a single dendrite. In the cone-cell the rod is conical with a broad base, to which the body of the cell containing the nucleus is immediately applied; the basal process ends in the normal manner in a tuft of




FIG. 193. Diagram to illustrate structure of a Retina. The several "layers" are indicated by the numerals III, &c. in order from within (vitreous humour) outwards.

1. Cone. 2. Rod. 3. Nucleus of rod-cell. 4. Small neuron.
5. Large neuron. 6. Choroid epithelium. 7. Fibre of Müller, a supporting cell.

dendrites. The basal processes of both kinds of sense-cell are in close relation to the receptive dendrites of a layer of small neurons; the axis-cylinder processes of these in turn end close to the receptive dendrites of a layer of large neurons situated close to the outer basal surface of the retina, which give rise to the fibres constituting the optic nerve. Taking a general view therefore we may say that the retina is a sensory nervous epithelium consisting of a layer of sense-cells underlaid by two layers of neurons. Before its structure was thoroughly understood, however, the appearance of the retina in

transverse section was a bewildering mass of fibres and nuclei, in which for descriptive purposes different layers were distinguished. These, reckoning them in the order proceeding from the inner side of the eyeball towards the lens, were as follows:—(a) the layer of rods and cones; (b) the outer nuclear layer (vi. Fig. 193) consisting of the bodies of the visual cells containing their nuclei; (c) the outer molecular layer (v. Fig. 193) consisting of sections of the basal processes of the visual cells and of the receptive dendrites of the small neurons; (d) the inner nuclear layer (iv. Fig. 193) consisting of the bodies of the small neurons; (e) the inner molecular layer (iii. Fig. 193) consisting of sections of the basal process of the smaller, and of the receptive dendrites of the larger neurons; (f) the layer of nerve-cells consisting of the bodies of the larger neurons; and finally (g) the layer of nerve-fibres consisting of the basal processes of the larger neurons which constitute the optic nerve.

The remainder of the eye is to be looked on as a part of the skin of the side of the head which has been rendered transparent in order to allow light to reach the retina. It consists of a lens and cornea, separated by a chamber containing the aqueous humour. The lens is an originally hollow plug of ectoderm cells, which breaks loose from the skin and lies in the mouth of the secondary optic vesicle (Fig. 192). The skin outside the lens forms the cornea, which is transparent. Between the cornea and the lens is watery connective tissue, called the aqueous humour. The cornea being joined to the edges of the sclerotic completes the boundary of the eyeball, as the fully elaborated sense-organ may be termed. If the above description has been followed it will be seen that in a Craniate light must reach the visual cells through their basal and not through their visual ends. As this is contrary to the almost universal rule obtaining throughout the animal kingdom, we cannot believe it to be a primitive arrangement. Rather we must believe that when the eye was developing the rods of the visual cells were directed towards the light, and that the epithelium of which they form a part was exposed, and not rolled up into a neural tube; in a word, that the front portion of the nervous system of Vertebrata at any rate was once a plate of sensitive skin. It is most instructive to note that in the larva of the Hemichordata we find such a plate with two eye-spots at the apex of the prae-oral lobe.

The external layer of the skin or ectoderm of Craniata is quite peculiar in the animal kingdom in that it consists not of one, but of many layers of cells. On closer inspection, however, it is seen that

the deepest layer, consisting of columnar cells alone, really represents the ectoderm of the other phyla. This layer
Skin. instead of becoming directly converted into cuticular substance, as, for example, in the Arthropoda, buds off flattened cells from its outer surface which become bodily converted into horny matter and scale off. The ectoderm rests on a specially firm bed of connective tissue called the dermis.

A very peculiar feature in the Craniata is the character of the scattered sense-cells of the skin. These end in
Nerves. sense filaments embedded in the ectoderm, not projecting beyond it. These filaments have however grown enormously, and with their growth the bodies of the cells with the nuclei have come to lie deep down in the body. Here they form segmentally arranged packets of cells lying at the side of the nerve-cord and known as the spinal ganglia. They are connected with the nerve-cord by their basal outgrowths or nerve-tails, which constitute the dorsal roots of the spinal nerves corresponding to the dorsal sensory nerves of *Amphioxus*. To each myotome a motor nerve is given off, as in *Amphioxus*, but in the Craniates the fibres of this nerve are bound up for a certain distance with the long peripheral hairs of the sense-cells constituting the spinal ganglia, so as to form a compound sensory-motor nerve, which is then said to have a dorsal sensory and a ventral motor root.

The power of transmitting and modifying stimuli, characteristic of the nerve-cell, is merely one of the fundamental properties of all protoplasm, specially developed. It therefore probably resides to a small extent in all cells. In the ectoderm from its exposed condition this function has been largely exercised, and hence the nervous system of most animals consists of modified ectoderm cells. But the endodermic tube is likewise stimulated by the passage of food through it and it is therefore not surprising to learn that some of its cells develop nerve-tails and are even converted into small neurons. In this way a tangle or plexus of fibres with intermixed cells is formed, which is the basis of the nervous system of the gut, or 'sympathetic' system. In most groups of animals the endodermic nervous system is never developed beyond this point; but in Craniata the tails of the endodermic cells extend out at regular intervals and come in contact with portions of the spinal ganglia which early separate from the rest and are called the sympathetic ganglia. These ganglia retain their connection with the spinal ganglia by nerves called the rami communicantes, in

which motor fibres going to the gut are included. Successive sympathetic ganglia are connected by a longitudinal commissure, and so there is a sympathetic chain of ganglia on each side of the spinal cord.

It is usual to reckon ten pairs of nerves as appertaining to the brain, but these are of very unequal value. The first or olfactory pair are really drawn-out portions of the cerebrum. In the lower Craniata these parts have the shape of swellings connected by narrow stalks with the brain and these stalks were confused with nerves (Fig. 188). The terminal swelling comes into close contact with the epithelium of the nasal sac, and a large number of small nerves—the true olfactory nerves—connect the two. The second or optic nerve is, as we have seen, really the stalk uniting the primary optic vesicle with the brain (Figs. 188 and 192). The nerve fibrils which run in this stalk go mainly but not entirely to the opposite side of the brain. Thus in the floor of the thalamencephalon, or primitive fore-brain, there is a crossing of fibres proceeding from the two eyes. This part of the floor becomes nipped off as a groove from the rest—and is known as the optic chiasma. The chiasma is connected with the combination of the sensations received by the two eyes so as to produce a single image, each side of the brain receiving sensations from both eyes. The third, fourth and sixth nerves are motor nerves, supplying the eye muscles derived from the head cavity, the first myotome and the second myotome respectively. The fifth and seventh are most interesting nerves, being sensory as well as motor, and the sense-organs they supply in the lower Craniata are peculiar. These organs are scattered over the prae-oral part of the body or snout and the sides of the head, and are known as the mucous canals. On the snout they have the shape of deep tubes swelling out at the bottom into sacs or ampullae; and on the head, of canals communicating at intervals with the exterior by vertical tubes. Certain of the cells lining these tubes develop blunt, freely projecting sense-hairs, recalling the character of the auditory cells, whilst others secrete the mucus with which the tubes are filled and whence they derive their name. It is probable that the function of these organs is somewhat allied to that of the ear, balancing combined with hearing (or at any rate, perception of vibrations), for it has been proved that a fish deprived of its eyes is still able to guide itself along tortuous passages, so long as this organ remains intact, and this is only explicable on the assumption that the reflected pulses of the water are felt by these organs. The

branches of the fifth and seventh nerves which supply them are usually for some distance in close juxtaposition and are known as the ophthalmic nerves. The eighth or auditory cranial nerve goes to the ear, and arises in such close proximity to the seventh that it may be regarded as a specialized branch of it, the ear itself being very possibly a highly specialized mucous canal. The motor divisions of the fifth and seventh are distributed to the region of the mouth and to that of the first gill-slit respectively. They both fork; the upper branch of the fifth goes to the upper jaw, and the lower to the lower jaw, whilst one branch of the seventh passes in front and the other behind the first gill-slit or spiracle. The ninth nerve is similarly forked round the second slit (Fig. 188). The tenth nerve, which is certainly a compound one, gives off a branch to each of the remaining slits, to which it bears a relation similar to that borne by the ninth nerve to the second slit. The main stem of the nerve passes along the alimentary canal and sends nerves to its muscles and to those of the heart, all these muscles being developments of the inner or splanchnic wall of the unsegmented coelom. The tenth nerve has also in the lower Craniata a sensory division. This separates from it soon after it leaves the brain and passes backward, supplying an immensely long mucous canal, called the lateral line, which extends from head to tail along the mid-lateral portion of the body, and is provided with a series of openings to the exterior. On account of its extensive area of distribution the tenth nerve has received the name of *vagus* (wandering).

The alimentary canal exhibits a marked difference from the condition found in the Lower Chordata. The gill-slits are reduced in number, there being as a rule not more than eight: it would indeed be more correct to speak of them as gill-pouches. In this respect Craniata agree with the Hemichordata in contrast to the Cephalochordata and Urochordata. No trace of a tongue-bar has however been found in any Craniate.

The endostyle becomes shut off from the pharynx and thus loses entirely its original function; it branches and forms a mass called the thyroid gland. The evil results following on its removal show that some substance, absolutely essential to the proper metabolism of the body, is manufactured by this gland and poured into the blood.

The sub-neural gland of the Urochordata, on the other hand, seems to be represented by a structure called the pituitary body.

This like the sub-neural gland is a dorsal pocket of the stomodaeum, but it becomes cut off from all connection with the mouth and intimately associated with a downgrowth of the brain, called the infundibulum, to form a compound organ which has some obscure influence on the well-being of the animal. Since in the case of the Urochordata the sub-neural gland is fashioned out of the persistent communication of the sense vesicle with the exterior, one is tempted to regard the close connection of the infundibulum and the pituitary body as remnants of the former connection of the brain and stomodaeum in the ancestors of the Craniata. Some authors maintain that a rudiment of the infundibulum is to be seen even in the cerebral vesicle of *Amphioxus* (see Fig. 174).

Except in the lowest forms the alimentary canal is differentiated into several well-marked divisions. The pharynx, as the first of these is called, is a composite structure consisting not only of the stomodaeum but also of that part of the endodermic tube into which the gill-slits open. The line of demarcation between ectoderm and endoderm is entirely obliterated in the adult. Following on the pharynx is a tube of narrow diameter, termed the oesophagus or gullet, which leads into the stomach. The stomach, which consists of the first of the loops into which the alimentary canal is bent in consequence of being longer than the body, is a greatly dilated portion of the canal and in it the food is stored until a large amount of digestion is accomplished. As in other animals, the food is moved from place to place by peristaltic contractions of the visceral muscles derived from the inner wall of the coelom. There is a particularly powerful girdle of these called the pyloric sphincter, which by remaining contracted keep the distal end of the stomach, the so-called pylorus, closed until the work of digestion is accomplished, when they relax and allow the food to pass on into the next division of the canal, the intestine. The walls of the proximal part of the stomach are produced into small pouches, the lining cells of which secrete a substance called pepsin, which has the power of turning the proteid of the food into soluble peptone.

Pepsin is an example of a class of substances called ferments (nitrogenous compounds of unknown constitution): they have the power, as yet unexplained, of effecting a large amount of chemical change without themselves undergoing perceptible alteration. Pepsin is only active in an acid medium, and free hydrochloric acid is found in the contents of the stomach in small quantities, produced by special cells in the walls of the pouches just mentioned.

An organ called the liver is very conspicuous (Fig. 206). It consists of a ventral outgrowth of the gut, arising just behind the stomach, which extends forwards and branches into an immense tree-like mass of tubes welded together by connective tissue into a solid mass extending forwards and nearly obliterating the front part of the body cavity. Whether this organ really performs the same function as the so-called liver in *Amphioxus* is doubtful. It has been proved that the function of the Craniate liver is largely the elaboration of an alkaline fluid called the bile. This is partly excretory in nature, but has an important influence upon the processes of digestion and absorption in the intestine. The main stem of the liver tubes is called the bile-duct; there is often a lateral outgrowth from this which acts as a reservoir for the bile, called the gall-bladder. Besides this, the liver cells can form from the sugar brought to it from the intestine a substance called glycogen, allied to starch in composition. This acts as a reserve of carbohydrate material available for the varying needs of the times. The liver exercises other important influences upon the chemical processes of the body.

Another outgrowth from the intestine arises sometimes just behind the opening of the bile-duct, sometimes from the duct itself. This outgrowth, like the liver, branches into a tree of tubes which are bound together by connective tissue to form a solid mass, though one of much smaller size than the liver. This organ is called the pancreas and it produces a secretion called pancreatic juice, by which the process of digestion is completed. This juice contains three ferments which are only active in an alkaline medium. These are amylopsin, which turns starch and allied substances into soluble sugar; trypsin, which turns proteid into even simpler and more soluble substances than peptone; and steapsin, which splits up fat into fatty acid and soluble glycerine. The fatty acid is partly made soluble by uniting with the alkali present in juice, but is largely dissolved in the bile without undergoing this change.

The intestine is always somewhat longer than the body. Hence it must be to some extent looped or twisted (Fig. 207), though this may express itself only in a slight curvature. A fold projecting into it in some forms represents the typhlosole of the Urochordata and is known as the spiral valve, since it shares in the twisting. In the intestine the digested food is absorbed and transferred to the blood-vessels and lymph-canals. The last portion of the intestine

is usually of larger diameter than the rest and is called, when thus distinguishable, the large intestine. In it the indigestible material or faeces accumulate before being expelled from the anus.

The blood system of the Craniate is distinguished by the possession of a large and well-developed heart, which, like the heart of the Urochordata, is an enlargement and specialization of part of the ventral vessel. The space in which it apparently lies—really, into which it protrudes,—is called the pericardium, and is only an anterior part of the coelom shut off from the rest by the development of a transverse septum. The heart is constricted into four chambers, becoming successively more thick-walled as we proceed forwards, and named, beginning from behind, the sinus venosus, the atrium, the ventricle, and the conus arteriosus (Fig. 195). It is bent into an S-shape, so that the sinus venosus is dorsal and posterior, the atrium dorsal and anterior, the ventricle ventral and posterior, and the conus arteriosus ventral and anterior. The conus arteriosus leads into the ventral aorta, which gives off the arterial arches; these are branches which ascend between the gill-sacs and ramify on their walls. From the gills the blood collects into epibranchial vessels which join to form two vessels on the dorsal wall of the pharynx, the roots of the dorsal aorta. These unite behind the pharynx into a single dorsal aorta, giving blood to all the hinder part of the body. The forward extensions of the two epibranchial vessels carry blood to the head and are known as the carotid arteries. There can be little doubt that the impulse leading to the evolution of the heart came from the necessity of having a strong force to drive the blood through the capillary channels on the walls of the gill-sacs.

Each chamber of the heart is separated from the one behind by valves, which are flaps of membrane free to move in one direction so as to open and admit blood from behind, but restrained by tendinous cords from being driven further back than so as just to meet when the chamber contracts, and thus prevent the backward movement of the blood. In the conus there may be several transverse rows of pocket valves. These valves as their name implies are loose pockets of membrane which are pressed flat against the wall of the conus during the forward movement of the blood, but which when the conus contracts become filled with blood and swollen out so as to meet one another and prevent the reflux of blood into the ventricle.

The development of the liver has exercised a profound influence on the afferent part of the blood system corresponding to the

hinder part of the sub-intestinal vein of *Amphioxus*. The vast mass of tubes projecting into it has broken it up into a network of capillary channels called the hepatic portal system. In front of




FIG. 194. Diagram of the ventral and dorsal aortas and their branches in *Scyllium* \times about 1.

this, where it enters the sinus venosus, it is known as the hepatic vein; behind, branches from the walls of the intestine so overshadow the original ventral trunk that this, embedded between the limbs of the spiral valve, appears as merely a small branch of the composite trunk, the portal vein.

The blood from the muscles and kidneys, in a word, from the dorsal and outer parts of the coelom, collects into two longitudinal channels called the cardinal veins. These empty into the sinus venosus by transverse trunks called Ductus Cuvieri. These transverse trunks divide the veins into anterior cardinals returning blood from the head, and posterior cardinals returning it from the rest of the body. In the tail the two posterior cardinals are represented by the median caudal vein, which further forward splits into two. Just as the course of the original sub-intestinal vein has been obstructed by the growth of the liver, so that of the posterior cardinal has been choked by the growth of the kidney tubes. The blood from the tail and hind limbs is forced to filter amongst these in a series of narrow channels called the renal-portal system. The front part of the vein retains the name posterior cardinal: the hinder part is called the renal-portal vein. Since the kidney tubes also receive blood from the dorsal aorta they, like the liver, have a double supply.

The blood of Craniata has in addition to the ordinary amoebocytes a much larger number of oval or round cells impregnated with haemoglobin, called red blood-corpuscles. Haemoglobin has been mentioned when describing *Lumbricus*, in which worm it is found diffused in the blood fluid. The great characteristic of haemoglobin is its power of forming a bright red, unstable compound with oxygen. This compound is formed in the respiratory organ and carried by the circulation to all parts of the body. In the capillaries it is broken up and the oxygen absorbed by the tissues. The haemoglobin having lost its oxygen changes in colour, and the impure blood which leaves the tissues is in consequence bluish. From the tissues the blood also takes up carbon dioxide; this is given off again in the respiratory organs.

On page 119 it was pointed out that both blood and connective tissue have been derived from a jelly-like secretion such as is found in Coelenterata. This in the embryo coelomate animal fills up the interstices between ectoderm, endoderm and coelomic sacs, these interstices being collectively termed the primary body-cavity or haemocoel. It was also pointed out there, that whereas in the

part of the jelly which was converted into connective tissue a large number of fibres were developed, in the portion destined to form blood, on the contrary, no fibres appeared and the jelly remained fluid, and in consequence the amoebocytes which had wandered into it from the neighbouring epithelia were able freely to move about. In Annelida, Arthropoda and Mollusca certain of the blood-spaces acquire muscular walls derived from the adjacent coelomic sacs, and thereby attain contractility which may be specially localized in a dilatation called the heart. The spaces with muscular walls are the arteries. In Craniata a further differentiation has taken place: we find not only a definite heart and arteries leading away from it, but also equally definite veins leading into it as described above, and arteries and veins are connected with one another by narrow channels called capillaries with well-marked walls. Heart, arteries, veins and capillaries are all lined by a single layer of flattened cells called an endothelium, which has been developed from the flattening out and union of a certain number of amoebocytes. The capillaries possess no other wall, but arteries and veins have both a layer of circular muscles outside this developed from the adjacent coelomic sacs. These muscles do not contract regularly like those of the heart, but maintain a condition of continued contraction called tone, which renders the blood-flow caused by the beats of the heart steady and even. This tone can be varied locally by various stimuli and so the amount of blood entering an organ is regulated.

In Craniata however, outside the definite arteries, veins and capillaries, there exists a large portion of the haemocoel in the form of irregular channels and interstices, in many cases without definite walls, an endothelium being found only in the larger trunks. This system of spaces is known as the lymphatic system. It contains a clear fluid in which amoebocytes float, but no haemoglobin-containing cells, and at one or several points the main trunks of the system open into the large veins. The finer branches of the system ramify amongst all the organs of the body. There is no circulatory current in the lymph canals except in those belonging to the viscera, but there are valves arranged so that with every contraction of neighbouring muscles some fluid can pass forwards in one direction but not backwards.

It will be seen that in Craniata, unlike Arthropoda and Mollusca, the blood, being everywhere confined to vessels with definite walls, does not directly bathe the tissues of any organ; but that materials

must first diffuse through the walls of the blood-vessels into the lymph-spaces before they can reach the tissue.

The supply of amoebocytes to both blood and lymph is provided for by the presence of several actively growing nodules of cells which bud off amoebocytes into the adjacent lymph-channels. These packets of cells are called lymphatic glands: the largest is a mass, usually of a reddish colour, called the spleen, which is attached to the mesentery just dorsal to the posterior end of the stomach.

The muscles of the Craniata like those of the Cephalocordata are developed from the inner walls of a series of dorsal coelomic pockets, in a word, from myotomes. Unlike that of the Cephalochor-

Cœlom.




FIG. 195. Diagram of the venous system of *Mustelus antarcticus*. From T. J. Parker.

1. Orbital sinus. 2. Hyoidean vein. 3. Ductus Cuvieri. 4. Anterior cardinal vein. 5. Jugular vein. 6. Conus arteriosus. 7. Ventricle. 8. Atrium. 9. Sinus venosus. 10. Hepatic vein. 11. Liver. 12. Hepatic vein. 13. Hepatic portal vein. 14. Left cardinal vein. 15. Brachial vein. 16. Sub-clavian vein. 17. Gonad. 18. Posterior cardinal vein. 19. Spermatoc vein. 20. Lateral vein. 21. Renal-portal veins from caudal vein to kidney. 22. Right posterior cardinal vein. 23. Alimentary canal. 24. Vein connecting orbital sinuses. 25. Sub-intestinal vein. 26. Kidney. 27. Pelvic vein. 28. Cloacal vein. 29. Femoral vein. 30. Caudal vein.

data the trunk coelom does not become at first completely divided into separate sacs, the ventral portions of which fuse later. In the Craniata this stage is skipped in development, and the coelom appears from the first as a pair of elongated sacs undivided below, but segmented above. After the complete separation of the dorsal portions as myotomes the ventral parts of the two sacs unite beneath the intestine, whilst above it their walls become apposed, forming the vertical sheet of tissue known as the mesentery, in which the intestine is slung.




FIG. 196. Dorsal view of head of *Scyllium canicula* $\times 1$. The right orbit has been exposed so as to show the muscles that move the eye and the second and fourth nerves.

1. Lens of the eye.
2. Superior rectus muscle of the eyeball.
3. External (or posterior) rectus muscle.
4. Inferior rectus muscle.
5. Internal (or anterior) rectus muscle.
6. Inferior oblique muscle.
7. Superior oblique muscle; the slender nerve entering this muscle is the fourth cranial.
8. Second cranial or optic nerve, the nerve of sight.

No representative of the collar coelom of the Hemichordata and Cephalochordata has yet been with certainty detected, but there exists in the embryo of the lower Craniates a well-defined representative of the anterior coelom or proboscis cavity of the Hemichordata. This is termed the anterior head-cavity and is a bilobed sac lying beneath the eyes. Sometimes the two halves are

completely separated. Its walls give rise to the majority of the muscles which move the eyeballs. It is necessary of course for the efficient action of the eyes that they should be moveable, and this is brought about by the space around the eyeball becoming converted into a cavity called the orbit, which in the lower Craniata is continuous with the anterior cardinal vein, and thus contains blood (Figs. 195 and 196). To each eyeball six muscles are attached, two arising from the anterior part of the orbit and inserted one above and one below the eyeball, and named respectively the superior and inferior oblique; and four arising close together from the posterior corner of the orbit and inserted on the eyeball one above and one below, the superior and inferior recti, and one antero-laterally, the internal or anterior rectus, and one postero-laterally, the external or posterior rectus.

The inferior oblique, the internal, superior and inferior recti are developed from the walls of the anterior head-cavity. The superior oblique is developed from the first myotome lying on the edge of the mouth. This possibly corresponds to the collar cavity, since in the embryo it has a downward extension. The external rectus is formed by the second myotome. The muscles derived from the anterior head-cavity are supplied by a common nerve, the third cranial; the superior oblique is supplied by the fourth, and the external rectus by the sixth cranial.

Most of the muscles which compress or expand the gill-sacs are derivatives of the wall of the unsegmented, ventral portion of the coelom. From the inner wall of this part of the coelom all the muscles of the alimentary canal, which in Craniata are longitudinal as well as circular, arise, as do the muscles in the walls of the blood-vessels. From the myotomes are derived the muscles by which the locomotion of the animal as a whole is carried out. In the lower Craniata these have the same simple arrangement as was found in the case of *Amphioxus*, but in the higher forms where the movements are complicated by the development of limbs, these muscles are divided into numerous bundles, with a very complex arrangement. All the muscles derived from the myotomes are composed of striated fibres. Most of those governing the movements of the alimentary canal and blood-vessels are composed of smooth fibres, but to this statement the muscles of the heart form an exception.

The excretory and reproductive organs are closely related in development, and by recent research their relation to those of

the Cephalochordata has been made tolerably plain. The unit in the excretory system is a tube opening into the body-cavity at one end and at the other into a longitudinal duct which opens into the proctodaeum behind. If it opened to the exterior directly it would be essentially identical with the nephridium which constitutes the excretory organ of Annelida and Mollusca. Of these tubes in the Craniata there are two kinds: the first or pronephric tubules, called collectively the pronephros, develop in continuity with the duct into which they open. This is called the archinephric duct, or sometimes the

Urino-genital
Organs.




FIG. 197. Diagrams illustrating the development of the urino-genital organs of Craniata. [For full explanation see sections on Elasmobranchii and Amphibia.]

- A. Development of pronephros and segmental duct. B. Atrophy of pronephros, development of mesonephros. C. Differentiation of pro- and mesonephric ducts. D. Development of metanephros, male type. E. Female type. 1. Allantoic bladder. 4. Gonad. 5. Intestine. 7. Mesonephric duct. 8. Nephrostome. 9. Metanephric duct. 10. Metanephros. 12. Ovary. 13. Oviduct. 14. Pronephros. 15. Archinephric duct. 16. Testis.

Wolffian duct, after Caspar Wolff, who first saw it develop in the embryo. The pronephric tubules are situated at the upper and outer angle of the unsegmented coelom, a position exactly corresponding to that of the nephridia of *Amphioxus*, except that in the

The pronephric tubules are only developed in the larval form and so far as is known they persist in no adult Craniate. They become replaced by the second kind of tubules, termed the mesonephric tubules, which, like the pronephric, open into the coelom, but unlike these swell out immediately beyond this, forming thin-walled capsules, termed the Malpighian capsules, into which a thin-walled plug containing a plexus of blood-vessels, the glomerulus, projects. A similar structure, it is true, projects from the root of the mesentery into the general coelom opposite the openings of the pronephric tubules. The cells covering this plug in both cases extract water and excreta from the blood and discharge them in the one case into the Malpighian capsule, in the other case into the coelom, whence they are swept into the open pronephric funnel.

The mesonephric tubules are developed from the necks connecting the myotome with the general coelom, that is, from the lower end of the myotome, a position corresponding to the point of origin of the genital organs in *Amphioxus*. These necks, which may be termed nephrotomes, break loose from the myotomes, curve round and acquire openings into the archinephric duct. It is the central part of the tubule which swells out to form the Malpighian capsule.

It has been suggested that the mesonephric tubules are the homologues of the genital sacs of *Amphioxus*, and this suggestion receives support from the fact that the genital organs in the lower Craniata originate from the lower ends of the nephrotomes, just where these enter the general coelom, and consequently the genital organs are at first segmented. The change of function suggested above seems at first sight a little forced, but we must remember




FIG. 198. Diagrammatic transverse section of a hypothetical ancestral Elasmobranch to show origin of renal and genital organs. On left side a later condition is shown than in the right.

- | | | | |
|---|-------------------------------|------------------------|-----------------------|
| 1. Nerve-cord. | 2. Notochord. | 3. Myotome. | 4. Dorsal sclerotome. |
| 5. Ventral sclerotome. | 6. Nephrotome. | 7. Pronephric tubule. | |
| 8. Archinephric duct as an open groove. | 9. Rudiment of genital gland. | 10. Aorta. | 11. Alimentary canal. |
| 12. Unsegmented coelom. | 13. Mesonephric tubule. | 14. Archinephric duct. | |
| 15. Seminal tubule. | | | |

that in primitive Vertebrata, as in Annelida, the whole coelomic wall had probably an excretory function, and hence if permanent instead of temporary pores for the discharge of genital products were formed, these pores would allow the escape of excreta thrown out by the neighbouring portions of the coelom, the excretory function of which would therefore be stimulated.

The genital rudiments soon coalesce to form continuous ridges projecting into the general coelom on either side of the root of the

mesentery. In the female the sexual cells or ova, when ripe, drop into the coelom and are conveyed to the exterior by an oviduct opening into the body-cavity with a wide funnel. The oviduct arises from a groove in the dorsal coelomic wall, the edges of which meet. Posteriorly it opens into the proctodaeum. In the male, on the other hand, the sexual cells arrange themselves in tubes, the seminiferous tubules, which retain in most Craniata a permanent connection with certain of the mesonephric tubules through a set of tubes called the testicular network which like the organs they connect are derived from the nephrotomes. The archinephric duct therefore acts as vas deferens or male duct. Since through the opening of the proctodaeum not only the faeces are expelled but also the excretory products and spermatozoa from the archinephric duct, and ova from the oviduct, this aperture has received the name of cloaca, the Roman name for 'sewer.'

Division I. CYCLOSTOMATA.

The Craniata are divided into two main groups, namely, the Cyclostomata and the Gnathostomata. The former division, distinguished by the absence of true visceral arches and of jaws, includes at the present day only a few, probably degenerate, worm-like animals, with like *Amphioxus* short tails, and with naked skins. The name Cyclostomata means Round-mouthed (Gr. κύκλος, a circle; στόμα, mouth), and alludes to the circumstance that the

edges of the mouth are stiffened by a ring-shaped cartilage, the annular cartilage, so that the mouth cannot be closed (2, Fig. 201). There is a piston-shaped tongue supported by a lingual cartilage, and the whole is protruded by a muscle attached to the annular cartilage in the lips (Fig. 200). Both the tip of the tongue and the walls of the stomodaeum are beset with horny teeth, developed from the agglutinated cells of the skin. The expansion of the stomodaeum causes the mouth to act like a sucker, and the whole animal is thus enabled to adhere to some foreign body, such as a stone, or to some victim, usually a fish, in which case the rasp-like tongue works a hole in the flesh of the prey. The stomodaeum is greatly elongated and is supported in its roof by several broad cartilages, the so-called labial cartilages; in consequence the eyes and gill-slits appear to be pushed very far back.

The condition of the sense-organs is one of the most marked characteristics of the Cyclostomata. The nose is represented by a single sac placed far back in consequence of the elongation of the stomodaeum, as above explained. This single sac is drawn out into a long tube passing beneath the brain, and in one order, the Myxinidae, or the Hag-fishes, this opens into the roof of the stomodaeum. The tube-like prolongation is really the pituitary




FIG. 199. The Musk Lamprey, *Petromyzon wilderi*, in the act of spawning.
From Bashford Dean and Sumner.

body, which in the embryo develops close to the nasal sac. The groove connecting the two organs becomes closed so as to form a canal, and then by the great development of the suctorial mouth the external openings of the two organs widely removed from one another.

The eye develops no proper cornea or aqueous humour, the lens remaining in connection with the skin. The ear is represented either by two semicircular canals and a vestibule (or sacculus) in the Lamprey, or by a single membranous tube in the Hag-fish.




FIG. 200. The Lamprey, *Petromyzon marinus*; right half seen from the inside of a female specimen, the various structures being, for the most part, in longitudinal section (nat. size).

1. Horny teeth on inside of stomodaeum. 2. Mouth. 3. Dorsal half of annular cartilage in section. 4. Mouth cavity. 5. Nasal aperture. 6. Nasal capsule lying over nasal sac. 7. Brain. 8. Notochord.
9. Oesophagus. 10. Respiratory tube. 11. Ventral aorta. 12. Retractor of tongue. 13. Velum.
14. Inferior jugular vein. 15. Ventricle. 16. Auricle. 17. Hepatic vein. 18. Posterior cardinal vein.
19. Anterior cardinal vein. 20. Intestine. 21. Ovary.

tongue-bars. The external opening is very small; the connection with the gullet, on the other hand, is a vertical slit (Fig. 200).

The whole set of sacs is supported on a framework of cartilage consisting of longitudinal dorsal and ventral bars, connecting cross-pieces pass between the sacs and give off branches encircling their outer openings (Fig. 201). The whole of the branchial basket, as it is called, is a development of the dermis and has nothing to do with the visceral arches of the Craniata, as will be shown later.

The commencement of the true alimentary canal is marked, as in *Amphioxus*, by a velum. What corresponds to the hyperpharyngeal groove in that animal is in many species of Cyclostomata completely constricted off from the remainder of the gullet, but opens into the alimentary canal, and is known as the oesophagus, though this word is used in a different sense from that in




FIG. 201. A, dorsal; B, lateral, and C, ventral view of the skull of *Petromyzon marinus* $\times 1$ (after Parker).

1. Horny teeth. 2. Annular cartilage. 3. Anterior labial cartilage.
4. Posterior labial cartilage. 5. Nasal capsule. 6. Auditory capsule.
7. Dorsal portion of trabeculae. 8. Lateral distal labial cartilage.
9. Lingual cartilage. 10. Branchial basket. 11. Cartilaginous cup supporting pericardium.
12. Sheath of notochord. 13. Anterior neural arches fused together.

which it is used in the case of the Gnathostomata. The lower part of the gullet which communicates with the gill-slits ends blindly behind and is called the respiratory tube.

The hinder part of the alimentary canal is a nearly straight tube, the spiral valve having a very slight deviation from a straight course. There is no dilatation of any kind in its course. The large liver empties its secretion by the bile-duct, which opens into the intestine a short distance behind the branchial region.

The only fins present consist of a fringe of skin similar to that found in *Amphioxus* surrounding the hinder end of the body in the vertical plane. This fringe is divided by a notch into an anterior (or dorsal) and a caudal fin. The dorsal fin is supported by cartilaginous rays situated above the neural arches which protect the spinal cord; the caudal fin has in addition to these, rays situated below the haemal arches. A caudal fin of this description, which the notochord divides into two equal lobes, is called diphycercal.

Besides the neural arches (13, Fig. 201) and small haemal arches in the tail no other cartilage is developed in connection with the axial skeleton, the notochord with its thick fibrous sheath persisting unchanged throughout life.

The pericardium is not completely separated from the remainder of the body-cavity, and the genital organs take the form in both sexes of a single median ridge projecting into the body-cavity (Fig. 200). No connection of the testis tubules with the kidney tubules exists, nor is there any trace of an oviduct, both ova and spermatozoa being freely shed into the body-cavity and escaping by two abdominal pores or simple openings in the body-wall placed ventrally to the openings of the kidneys. Inasmuch as these latter open directly to the exterior, and are quite independent of the opening of the intestine which is placed more ventrally, we may state that no cloaca has yet been developed.

Living Cyclostomata, represented by a single class which may be called Marsipobranchii (Gr. *μάστιπος*, a pouch),
 Classification. are divided into two families: (i) PETROMYZONTIDAE,
 (ii) MYXINIDAE.

(i) In the first family, familiarly known as the Lampreys, the pituitary body appears as a blind process from the nasal sac: each gill-sac opens directly to the exterior, and the hyperpharyngeal groove is separated from the rest of the alimentary canal as a distinct tube, the so-called oesophagus.

The Lampreys (*Petromyzon*) are conspicuous in the early spring, when they ascend small brooks to spawn. Several species inhabit the rivers of Great Britain, Canada, and the United States, but the differences between them are trifling, depending mainly on the development of the horny teeth covering the tongue. One species, *Petromyzon marinus*, attaining a much larger size than the others, inhabits the sea. It may reach a length of three feet, whereas the other forms do not grow longer than from ten to twelve inches. The eggs of Lampreys develop into a most interesting larval form which stands in many respects nearer to the other Craniates than does the adult, and supplies an intermediate stage between *Amphioxus* and an ordinary Craniate. This larva is called the Ammocoetes, and its mode of life resembles on the whole that of *Amphioxus*. Like that animal the Ammocoetes lives on what the currents of water, produced by the cilia inside the velum, bring. The thyroid gland, which, as we have seen, represents the endostyle, remains open, and still performs its primitive function of secreting a cord of mucus, which is carried up dorsally by a ciliated groove, the peripharyngeal band, situated just behind the velum. The hyperpharyngeal groove is represented by a dorsal strip of ciliated cells, the current produced by which sweeps the mucus backward into the alimentary canal just as it does in *Amphioxus*.

The tubular suctorial stomodaeum is represented by a hood-like upper lip, and a distinct short under lip, and when the mouth is contracted the velum is produced into tentacles just as in the Urochordata and in *Amphioxus*. The lateral eyes are exceedingly rudimentary, but there is a large pineal eye, and the nasal sac has a median septum.

(ii) The MYXINIDAE are characterised by the persistent connection of the pituitary body with the stomodaeum, so that there is a tube leading from the nasal sac to the mouth. There are eight tentacles called barbels at the sides of the mouth, and there is no special oesophagus distinct from the rest of the gullet. The skin has a double series of mucous glands placed at the sides of the body, and so much mucus can be thrown out that a large amount of water can be rendered semi-solid. The intestine has no spiral valve. The Myxinidae are the animals known as Hag-fish. They adhere to fish on whose flesh they feed, but unlike the Lampreys, they can actually burrow into their victims so that the stomodaeal region is completely buried. In connection with these habits the stomodaeal region is enormously elongated, and the eyes remain in a

rudimentary condition, whilst the gill openings are pushed very far back.

The Myxinidae include two genera, *Bdellostoma* and *Myxine*. In the former, which is a genus inhabiting the southern Atlantic and Indian Oceans, the gill-sacs are seven in number on each side and open separately; in *Myxine*, on the other hand, each external opening of the six gill-sacs is drawn out into a long tube, and the tubes of each side curve back and unite, to open by a common atrial pore placed so far back that this animal can insert almost half its length into the body of its victim without interfering with its breathing. The portal vein is rhythmically contractile. *Myxine* is common on both the Atlantic and Pacific coasts of North America and on the European coast.

Division II. GNATHOSTOMATA.

The great division of the Gnathostomata includes all the remaining Craniata, and is characterised by the development of definite visceral arches, jaws and paired limbs. The visceral arches are jointed rods developed from the inner or splanchnic wall of the coelom; they cannot therefore be considered as corresponding to the branchial basket of Cyclostomata. They are placed in the forms which retain gill-slits between these openings, and hence are often called gill-bars. The first pair of visceral arches lie in the sides of the mouth, and consist on each side of two pieces, hinged on one another and called the upper and under jaws respectively. By the motion of these on one another the mouth can be opened and closed. The nose is always represented by two sacs and the ear has three semicircular canals.

The Gnathostomata are divided into five classes. In the first three of these the temperature of the blood varies with that of the surrounding medium.

Class I. PISCES.

Gnathostomata with fins supported by fin rays, and breathing chiefly by gills.

Class II. AMPHIBIA.

Gnathostomata with pentadactyle or five fingered limbs and without fin rays. Gills and gill-slits functional in the young but

generally entirely lost in the adult. An amnion is not formed in the embryo. The skin is soft and moist.

Class III. REPTILIA.

Gnathostomata with pentadactyle limbs. The young are born similar to the adult and in embryonic life develop an amnion. Skin with horny scales.

Class IV. AVES.

Gnathostomata agreeing with Reptilia in most points, but with hot blood which retains a constant temperature independent of the temperature of the surrounding medium : the skin is provided with feathers instead of scales and the fore limb is used as a wing.

Class V. MAMMALIA.

Gnathostomata agreeing in many points with Reptilia, but clothed with hair instead of scales. The blood, like that of Aves, retains a constant temperature independent of that of the surrounding medium. The young are nourished after birth by the secretion of certain glands of the mother termed milk glands or mammary glands.

CHAPTER XV.

SUB-PHYLUM IV. CRANIATA.

Class I. PISCES.

THE class Pisces, or true Fish, are not, as many would imagine, characterized by their gills (since some Amphibia retain these throughout life), but by their fins. In addition to the vertical flap of skin with which we have become acquainted in the case of the Cephalochordata and the Cyclostomata, we have typically two pairs of lateral flaps, an anterior pair called the pectoral fins, and a posterior pair known as the pelvic fins (Figs. 205 and 206). Both from a study of their development and their condition in the oldest fishes, it is believed that the paired fins are derived from the division of two originally continuous lateral flaps, of which the intermediate portions have disappeared. In the embryo the remains of these ridges are known as the Wolffian ridges, which, as we have seen, can be with some probability identified with the flaps overhanging the groove that became converted into the primitive kidney duct. If this be so, we have representatives of the lateral fins in the walls of the atrial cavity of *Amphioxus*, of which the rudimentary folds known as the meta-pleural folds form part. If we accept this view it follows, since Cyclostomata possess a kidney duct, that they once possessed either a continuous lateral fin or the two pairs possessed by modern fish.

Whilst the possession of paired fins discriminates the Pisces from the lower Vertebrata, the forms of these members equally sharply mark the Pisces off from the class with which they are most nearly allied, namely, the Amphibia. In all the Pisces the limb or fin is a blade-like organ which never exhibits the slightest resemblance to the typical form familiar to all in the human limb, but the Amphibia have as the representative of the paired fins limbs in which the

plan of the human arm and leg can be at once recognised. The blade-like type of fin is known as the ichthyopterygium (ἰχθύς, a fish; πτερύγιον, a little wing), the other type of limb as the cheiropterygium (χείρ, the hand). Pisces therefore are defined by the possession of ichthyopterygia.

The median or vertical fin is almost always divided, by the dying away of intermediate portions, into one or more dorsal fins, a caudal or tail fin and a ventral fin (Fig. 208). Both the median and the paired fins are supported by dermal fin-rays which are characteristic of Pisces and distinctive of them. These rays are not to be confounded with the gelatinous fin-rays of *Amphioxus*, or their representatives, the cartilaginous rays of the Cyclostomes. Such rays are present in the lower Fish, but the dermal fin-rays are far more superficial. They consist of parallel bundles of fibres belonging to the connective tissue forming the dermis. These bundles are firmly glued together and converted into horny matter. Since in a flap there are two sheets of dermis, each underlying the ectoderm of one side, we find the ray made up of two longitudinal pieces loosely connected together.

It will be seen that since the equivalent of lateral fins is found in *Amphioxus*, but not in Cyclostomes, we must conclude that the latter are in some points degenerate. For this degeneration of the paired fins we are able with some plausibility to suggest a reason. The function of these organs is a balancing one, the maintenance of the upright position in an animal which is flattened laterally, so that if left to itself it would fall on one side. Now the Cyclostomata are almost cylindrical and hence the need for balancers has disappeared.

The class Pisces is divisible into four orders, namely, the Elasmobranchii, the Holocephali, the Dipnoi, and the Teleostomi. These orders can also be distinguished in the case of fossil fish, though the differences become less marked as we recede backward in time, and many indications point to the conclusion that the common ancestors of the four orders would, if we could examine them, be classed as Elasmobranchii. Hence the Elasmobranchii may be termed the basal group of the Pisces, although modern Elasmobranchii, like all modern animals, are specialized in many respects.

Order I. **Elasmobranchii.**

The Elasmobranchii are distinguished (i) by not possessing any gill-cover or operculum, as it is called, each gill-sac opening separately to the surface; (ii) by the absence of an air-bladder opening into the alimentary canal; and (iii) by the absence of large bones in the skeleton. In addition to these negative characters, they are distinguished (iv) by the possession of a peculiar scale quite characteristic of the order.

This scale, the so-called placoid scale, consists of a little spike attached to a small plate at its inner end. The plate consists of true bone: the spike of a modification of true bone called dentine. Dentine is distinguished from bone by possessing no Haversian canals or spaces occupied

Placoid
scales.




FIG. 202. Section through the skin of an Elasmobranch showing formation of a dermal spine. Highly magnified.

- | | | |
|-----------------------------|-----------------------|---|
| 1. Horny layer of ectoderm. | 2. Malpighian layer. | 3. Columnar cells of ectoderm secreting |
| 4. Enamel. | 5. Dentine (black). | 6. Dental pulp. |
| 7. Bony basal plate. | 8. Connective tissue. | |

by blood-vessels, nor even lacunae, since the cells of the connective tissue, out of which it is formed, remain external to the dentine. Their protoplasmic processes known as dentine fibres do however penetrate it and give rise to canals called dentinal canals. The core of soft connective tissue is called the dentinal pulp.

The spike therefore may be described as a little wart of dermis calcified on the outside. It pushes the ectoderm before it, and it becomes encrusted with crystals of carbonate of lime forming the

enamel layer (Fig. 202). These closely set crystals are secreted by the inner or basal ends of the ectoderm cells. One would naturally expect that structures like scales, which are closely arranged all over the body, would also invade the stomodaeum, which is merely a part of the skin. This we find to be the case, but here the scales are very greatly enlarged in size and changed in function; they are the well-known teeth which are used for the purpose of retaining and lacerating prey which has been seized. The spike of the tooth is usually flattened and blade-like, and provided with strongly serrated edges. Fusions of several teeth can occur. The teeth are developed in a deep fold of skin, part of the stomodaeum, situated just inside the lower jaw, and usually speaking only the outermost row are in use at one time, the skin working forward the next set as each row wears out.

The skull is much better developed than is the case in the

Skull.

Cyclostomes. In the cranium the parachordals and trabeculae give rise to a firm continuous plate, in which the pituitary fossa is reduced to a minute hole; there is a high and well-developed side wall and the roof extends a long distance forward. The sense-capsules, nasal and auditory, are well developed and firmly united with the cranium. The eyes are large and highly-developed, and the side wall of the cranium is indented to make room for the spacious orbits in which the eyes move. There is a considerable part of the head in front of the brain, which usually also projects in front of the mouth. This is the rostrum or snout, and it is supported by three cartilaginous rods, one ventral and two dorsal, projecting from the front end of the cranium. These rods are the forerunners of the ethmoidal region in other forms. In most species the opening of the nasal sac is connected with the mouth by a groove called the oro-nasal groove (Fig. 207). There are usually six gill-clefts and seven visceral arches in Elasmobranchs. The first cleft,




FIG. 203. Diagram of a section through the jaw of a Shark, *Odontaspis americanus*, showing the succession of teeth. From Reynolds.

1. Teeth in use. 2. Teeth in reserve. 3. Skin. 4. Cartilage of the jaw. 5. Encrusting calcification of cartilage. 6. Connective tissue. 7. Ectoderm lining the mouth.

sometimes called the spiracle, is rudimentary and in some cases entirely absent. On the other hand there is one family, the Notidanidae, with two extra clefts behind, so that there are in all eight clefts and nine visceral arches in this family.

The first pair of visceral arches form as we have seen the jaws. The upper jaw is known as the palato-ptyerygo-quadrata bar, a compound appellation derived from the names of the bones by which it is represented in the higher forms: the term is sometimes shortened to pterygo-quadrata. The lower jaw is called Meckel's




FIG. 204. Lateral view of the skull of a Dogfish (*Scyllium canicula*) $\times \frac{2}{3}$. From Reynolds.

1. Nasal capsule. 2. Rostrum. 3. Interorbital canal for the passage of a blood-vessel. 4. Foramen for hyoidean artery. 5. Foramen for the exit of the ophthalmic branches of Vth and VIth nerves. 6. Foramen through which the external carotid leaves the orbit. 7. Orbitonasal foramen which allows a blood-vessel to reach the nose. 8. Auditory capsule. 9. Foramen through which the external carotid enters the orbit. 10. Ethmo-palatine ligament. 11. Palato-ptyerygo-quadrata bar. 12. Meckel's cartilage. 13. Hyomandibular. 14. Cerato-hyal. 15. Pharyngo-branchial. 16. Epi-branchial. 17. Cerato-branchial. 18. Gill rays; nearly all have been cut off short for the sake of clearness. 19. Extra-branchial. 20. Pre-spiracular ligament. II. III. IV. V. Va. VIIa. IX. X. foramina for passage of cranial nerves.

cartilage: in front a strong ligament, the so-called ethmo-palatine ligament, attaches the upper jaw to the skull, whilst behind it is supported by another ligament, called the pre-spiracular ligament, running in the front wall of the spiracle. The second pair of arches is spoken of as the hyoid, and this too is divided into two portions, an upper, the hyomandibular, which is firmly connected to the skull just below the auditory capsule, and a lower, the ceratohyal (Fig. 204). The upper jaw is firmly connected by ligament to the hyomandibular, which thus helps to suspend the jaws from the skull. In the vast majority of the Elasmobranchs

this is the principal skeletal support for the jaws, and such an arrangement is spoken of as hyostylic; in the *Notidanidae* and *Cestracion* on the other hand the upper jaw is partly slung by the hyomandibular but also directly articulates with the skull, in the first case behind the orbit, in the second in front of it, the arrangement then being spoken of as amphistylic. The remaining visceral arches have only a muscular connection with the skull, and are termed the branchial arches, since to their sides are attached the gills. The branchial arches are jointed into several pieces, which are placed in an oblique position and so arranged that when they are raised by the levator arcuum—muscles attaching them to the skull—they diverge and expand the gill-sacs lying between them. The segments of each branchial arch are typically four in number, named respectively pharyngo-branchial, epi-branchial, cerato-branchial, and hypo-branchial. The first-named are situated in the dorsal wall of the pharynx and are horizontal in direction; the epi- and cerato-branchial stiffen the sides of the pharynx—the cerato-branchial being the main portion of the arch, whilst the hypo-branchial pieces are found in the ventral wall of the pharynx and converge to unite in a median plate, the basi-branchial. Lying outside the visceral arches are a varying number of cartilaginous rods developed from the dermis and possibly representing the branchial basket of the *Cyclostomata*. Those situated at the sides of the gape are called labial cartilages, those external to the hinder visceral arches extra-branchials (19, Fig. 204).

The first gill-slit, called the spiracle, is situated between the jaw and the hyoid just outside the internal ear (Fig. 208). It is a narrow tube and its use in the more typical forms appears to be to allow vibrations to come more closely in contact with the ear, and in some cases to admit the water for breathing. The other slits are really flattened sacs, the walls of which are raised up into thin folds richly supplied with blood-vessels, which are the true gills. The folds are supported by thin rods, called gill-rays, branching from the visceral arches. A rudimentary gill, the pseudobranch, is sometimes developed on the front wall of the spiracle. No gill is developed on the posterior wall of the last gill-sac.

In *Elasmobranchs* we find, as in *Cyclostomata*, well-developed dorsal (or neural) and ventral (or haemal) arches, with their ends deeply embedded in the thick sheath of the notochord. This sheath has been converted

Vertebral
column.

into cartilage by amoebocytes wandering into the gelatinous layer secreted by the cells of the notochord, and it is divided into separate pieces called centra. Between the centra the sheath remains membranous, and in the middle of each centrum the notochord becomes very much narrowed, so that instead of being a uniform rod it is like a row of beads. The haemal arches meet beneath in the tail, but further forward they stretch out horizontally and become jointed; their outer segments are the ribs, this is the first appearance of these organs. There are usually twice as




FIG. 205. Dorso-lateral view of the pectoral girdle and fins of a Dogfish, *Scyllium canicula*, $\times \frac{2}{3}$. From Reynolds. The gaps between the radialia are blackened.

1. Hollow in the midventral part of the pectoral girdle which supports the pericardium. 2. Dorsal (scapular portion) of pectoral girdle. 3. Meta-ptyrgium. 4. Meso-ptyrgium. 5. Pro-ptyrgium. 6. Pro-ptyrgial radial. 7. Meso-ptyrgial radial. 8. Meta-ptyrgial radial. 9. Outline of the distal part of the fin which is supported by horny fin-rays.

many neural arches as there are centra, and every alternate one is small and does not meet its fellow, and hence is called an intercalary piece: the haemal arches are as numerous as the centra. The cranium, visceral arches and centra are all strengthened by a calcareous deposit in the ground substance of the cartilage. This calcified cartilage is to be carefully distinguished from true bone, represented in Elasmobranchs by the bases of the scales and teeth.

The primitive tail-fin of Vertebrata, as we have seen, is a fringe surrounding the end of the tail. Only a small and narrow remnant of this persists in Elasmobranchs, the whip-like end of the tail being bent up; beneath it there is a well-marked fin, and this together with the remains of the primitive fin constitute the new tail-fin, which is now denominated heterocercal, since the axial skeleton does not divide it into two equal parts (Fig. 208).

The paired fins are attached to hoops of cartilage (the limb arches), called respectively the pectoral and pelvic girdles, the pectoral being situated just behind the last gill-cleft, the pelvic just in front of the anus. The pectoral girdle extends a considerable distance up the side of the animal: the pelvic is little more than a transverse bar. The fins in modern Elasmobranchs are of what is called the uniseriate type, that is to say, there is a thick jointed main axis with cartilaginous rays attached only to its anterior border. Fossil Elasmobranchs show in some cases a biseriate fin with rays attached to both borders; and one, *Cladose-lache*, shows a still more primitive condition, where the fin is merely a lateral flap supported by parallel bars of cartilage. By the coalescence of these at the base the axis was formed, and later by the disappearance of the rays on one side, the uniseriate fin.

In the pectoral fin the basal portions of some of the rays coalesce to form two large cartilages called propterygium and mesopterygium, whilst the axis itself is called the metapterygium. In the pelvic fin of the male the axis bears distally a grooved rod which is termed the clasper, and is used in transferring spermatozoa to the female. The axis is called the basipterygium. The distal joints of the rays in both pectoral and pelvic fins are made up of numerous small cartilages called radialia.

The brain of Elasmobranchs is remarkable for the great development of the olfactory lobes, which are in close contact with




FIG. 206. Dorsal view of the pelvic girdle and fins of a male Dogfish, *Scyllium canicula*. From Reynolds.

1. Pelvic girdle.
2. Basipterygium.
3. Clasper.
4. Radialia.

the nasal sac, and are attached by a narrow stalk to the cerebrum.

Brain. This is only imperfectly divided into two hemispheres, and has nervous tissue on its roof, as well as its floor.

The cerebellum is developed into a great flap which projects back and covers the thin roof of the medulla oblongata (Fig. 188). It has also lateral outgrowths called cerebellar lobes.

Alimentary Canal. The alimentary canal is considerably longer than the body and is consequently folded. It has, as a matter of fact, an U shape: the first limb and a part of the next constitute the stomach, which is marked off from the intestine by a constriction and a powerful development of the circular muscles forming a sphincter or circular muscle. To the posterior aspect of the loop is attached the prominent spleen. The intestine, although outwardly straight, is probably derived from a corkscrew coil by the adhesion of successive turns: for the "spiral valve" which, as we said, is merely a ventral infolding, has a very strongly marked spiral course. The liver opens by the bile-duct into the beginning of the intestine, and close to its opening is situated that of the duct of the pancreas. A small gland of unknown function, the rectal gland, opens into the hinder end of the intestine.

The pericardium is almost completely separated from the rest of the coelom, communicating only by two narrow holes with it. The heart has the typical structure described in the last chapter (see p. 334). In the conus there are at least two transverse rows of pocket-valves, occasionally more. The arterial arches arising from the ventral aorta run up between successive gill-sacs and break up into capillaries on the surface of the gills: from these the blood is collected by vessels in the form of loops completely surrounding the gill-sacs. From these loops four pairs of epibranchial vessels arise and run backwards in the dorsal wall of the pharynx converging to form the single dorsal aorta, which supplies blood to all the hinder part of the body. The last gill-sac has a gill only on its anterior border; the blood from this does not reach the dorsal aorta directly but is connected by a transverse vessel with the loop surrounding the preceding gill-sac. The dorsal aorta gives off on each side a sub-clavian artery to the pectoral fin and then three median arteries which run down through the mesentery* and supply the alimentary canal. These are named the coeliac, anterior mesenteric, and posterior mesenteric arteries respectively (Fig. 194). The most anterior, the coeliac, has two important branches

(1) the hepatic, running backwards and supplying the liver with arterial blood, and (2) the anterior gastric, supplying the anterior part of the stomach. The anterior mesenteric artery supplies the greater part of the intestine and sends a branch, called the lienogastric (sometimes arising as an independent trunk from the aorta), to supply the posterior part of the stomach and the spleen. The posterior mesenteric supplies the concluding portion of the intestine or rectum and the rectal gland. After giving branches to the genital organs, kidneys and pelvic fins, the aorta continues its course into the tail as the caudal artery. From the two most anterior branchial loops two vessels arise running forward in the dorsal wall of the pharynx and at the same time converging. These are the common carotid arteries, which supply blood to the head. Each divides into two main branches, an external carotid, which pierces the floor of the orbit and supplies the eye and the jaws, and an internal carotid, which pierces the floor of the skull near the middle line and supplies the brain. The pseudo-branch on the front wall of the spiracle receives its blood from the hyoidean artery which, branching from the loop surrounding the first gill-sac, runs forward in the roof of the mouth parallel with the common carotid artery and eventually joins the internal carotid. In the venous system the anterior portion of the sub-intestinal vein is represented by a pair of hepatic veins returning the blood from the liver, opening into the sinus venosus close to the middle line, whilst the posterior portion has dwindled to a small vein embedded between the folds of the spiral valve; this however is joined by branches from the sides of the intestinal wall to form the main trunk of the portal vein. Both anterior and posterior cardinal veins are represented by wide, somewhat irregular spaces. Each anterior cardinal has an expansion called the orbital sinus which surrounds the eye. The two orbital sinuses communicate by an interorbital canal tunnelled in the base of the skull. The blood from the ventral sides of the gill-sacs and pharynx is returned to the Ductus Cuvieri by a pair of independent trunks called the jugular veins. These are each connected with the anterior cardinal vein of its side by the hyoidean vein lying in a groove on the hyomandibular cartilage (Fig. 195). The blood from the tail is returned by a median caudal vein lying beneath the caudal artery and like it enclosed between the centra and the united ventral ends of the haemal arches. At the level of the posterior end of the kidneys the caudal vein divides into the two renal portal veins




FIG. 207.

FIG. 207. *Scyllium canicula*. ♀. Ventral view of viscera.

1. Left naris. 2. Mouth. 3. Pectoral fin. 4. Pelvic fin.
5. Aperture of cloaca. 6. Pericardial cavity. 7. Ventricle. 7'. Conus arteriosus.
8. Auricle. 9. Sinus venosus. 10. Coelomic opening of oviducts.
- 10'. Falciiform ligament. 11. Shell-gland. 12. Oviduct.
13. Ovary. 14. Liver. 15. Proximal limb of stomach.
16. Distal limb of stomach. 17. Intestine. 18. Rectum. 19. Spleen.
20. Pancreas. 21. Pancreatic duct. 22. Bile-duct. 23. Dorsal fin.
24. Spinal cord. 25. Notochord in centrum of vertebra.
26. Caudal artery. 27. Caudal vein. 28. Lateral line. 29. Myotomes.
30. Abdominal pores. a. Hepatic artery. b. Intestinal branch of anterior mesenteric artery.
- c. Lieno-gastric artery. d. Gastric branch of lieno-gastric artery (posterior gastric artery).
- e. Splenic branch of lieno-gastric artery. f. Portal vein. g. Intestinal vein.
- h. Splenic vein.

lying on the outer edges of the kidneys. These veins, as has been already explained (see p. 336), are the hinder portions of the posterior cardinal veins which break up into the renal portal system of capillaries. These filter amongst the kidney tubules and reunite on the inner side of the kidney to form the spacious posterior cardinal sinuses, as the front portions of the posterior cardinals are named. These two sinuses lying ventrally to the kidneys partly coalesce. Each sinus curves forwards and outwards to join the Ductus Cuvieri and at this point it is met by the large subclavian vein returning blood from the pectoral fin. The pelvic vein receives the blood from the side of the cloaca by the cloacal vein and the blood from the pelvic fin by the femoral vein. It then opens into a longitudinal trunk, called the lateral vein, which runs along the side of the body beneath but parallel to the posterior cardinal vein. The lateral vein in front receives the brachial vein from the ventral side of the pectoral fin (not to be confounded with the subclavian from the dorsal side of the same organ) and then opens into the Ductus Cuvieri. The cloacal veins further give off median branches which unite and then distribute blood to the viscera, so that some blood from the pelvic fin may also return to the heart through a portal system.

The ovary is a single ridge of the dorsal coelomic wall; the oviducts are long and united far in front so as to open by a common internal opening, situated ventral to the liver (Fig. 207). In the middle of its length each oviduct has an enlargement caused by a thickening of its walls due to the development of gland cells. This is called the oviducal gland, and its function is to secrete the pillow-shaped, elastic egg-shell. In all cases a considerable amount of development takes place before the egg is laid: in many cases development goes so far that the egg-shell is absorbed,




FIG. 208.

FIG. 208. *Scyllium canicula*. ♂. View of viscera from right side.

1. Mouth. 2. Spiracle. 3. Gill-slits. 4. Gall-bladder. 5. Oesophagus.
6. Pectoral fin cut off. 7. Vesicula seminalis lying on metanephros.
8. Testis. 9. Anterior dorsal fin. 10. Posterior dorsal fin.
11. Median ventral fin. 12. Dorsal lobe of caudal fin. 13. Ventral lobe of caudal fin. 14. Right lobe of liver. 15. Proximal limb of stomach. 16. Distal limb of stomach. 17. Intestine. 18. Rectum.
19. Spleen. 20. Pancreas. 21. Rectal gland. 22. Bile-duct.
23. Claspers. 24. Ligament carrying the vasa efferentia. 25. Vas deferens.
- a. Coeliac artery. b. Hepatic artery. c. Anterior gastric artery. d. Pancreatic branch of the coeliac artery. e. Anterior mesenteric artery. f. Lienogastric artery. g. Posterior mesenteric artery. h. Splenic artery and vein. j. Posterior mesenteric artery.
- k. Portal vein. l. Intestinal vein.

and the embryo takes in nutriment from the wall of the oviduct, and may reach a very large size before birth. The egg is large and well charged with yolk. The oviducts open behind along with the archinephric duct and intestine into the proctodaeum, or cloaca. There are two testes, and these are connected by a testicular network with the anterior part of the mesonephros. The tubules constituting the hinder portion of the kidney are called the metanephros. They unite to form about six trunks, which in turn join one another so as to form a true ureter or metanephric duct, which has an opening into the cloaca separate from that of the archinephric duct; by this arrangement the secretion of these tubes is prevented from mingling with the spermatozoa.

The front sexual portion of the kidney retains the name mesonephros, and is rudimentary in the female; from this circumstance we may conclude that the tubules of the mesonephros (in the narrower sense) have largely lost their excretory function and serve merely as ducts to convey the spermatozoa into the archinephric duct.

Actual sexual congress or copulation takes place in the Elasmobranchs; the most posterior rays of the pelvic fins called the claspers are enlarged, and used to distend the cloaca of the female to allow of the entrance of spermatozoa (Fig. 208). This is correlated with the large size and small number of the eggs, and their long retention in the oviduct. In the male the spermatozoa are stored in a special pouch of the cloaca lying on the ventral side of the kidney, termed the vesicula seminalis. It is probable that the claspers, the large eggs and the division of the kidney into two parts are specializations peculiar to modern Elasmobranchs.

The Elasmobranchs are the Sharks, Dog-fish, Skates and Rays of our seas. They are almost exclusively marine and are a group

much detested by fishermen, since they are excessively voracious and their flesh is of little value.




FIG. 209. A. *Scyllium canicula*. From Day. Reduced.
B. Egg-case opened to show young embryo with yolk sac.

They are divided into two great divisions, the Selachii and the Batoidei. The first consists of powerful swimmers with cylindrical bodies, well-developed tail-fins and moderate pectoral fins; the latter are ground fish with broad backs and bellies and narrow sides, whip-like tails with rudimentary tail-fin and enormous pectoral fins extending forward to the extreme end of the snout.

The SELACHII are known as dog-fishes or sharks, according to their size. The common English dog-fish, *Scyllium canicula*, is about two feet long (Figs. 207, 208, and 209); another kind, the Spiny dog-fish, *Squalus acanthias*, is distinguished by having a spine, a greatly enlarged scale, in front of each of the two dorsal fins. This latter genus is very common on the Atlantic coast of North America, where it is known as the Spiny-dog. The American smooth dog-fish, *Galeus canis*, is distinguished from *Scyllium* by being viviparous. Amongst the sharks the most remarkable are *Zygaena*, the Hammerhead, in which the roofs and floors of the orbits are produced outwards, so that the eyes are set as it were on peduncles; and *Carcharodon*, the great white shark, which has lost its spiracles and possesses a tail-fin with crescentic under lobe. Owing to their powerful swimming capacities, sharks are, as a rule, not limited in distribution. *Carcharodon* is the dreaded man-eater of the Adriatic and the warmer seas everywhere. *Zygaena* occasionally carries terror into the bay of Naples, and species of both genera are found off the American coast.

The BATOIDEI, or Rays are, as we have seen, ground feeders. All have the true gill openings on the underside of the body: the spiracle alone opens on the dorsal side and is enlarged. It has, in fact in this group, taken on the function of pumping in water into the pharynx, a duty which cannot be conveniently undertaken by the mouth when this is burrowing in the mud at the bottom. *Raia* is the common skate on both sides of the Atlantic, it has no caudal fin but two dorsals. *Torpedo* is distinguished by a more elongated body. The muscles on either side of the head are converted into electric organs, consisting of batteries of vertical hexagonal tubes filled with a clear gelatinous fluid, each tube representing a metamorphosed muscle-fibre. By means of these organs it can inflict a severe shock on its enemies. *Trygon* is the sting-ray. In it the tail is long and thin and the dorsal fin-rays are practically absent, but at the spot where the tail merges into the body there is a large recurved spine, at the base of which is a poison gland, so

that by a blow of the whip-like tail it can inflict a severe wound. The pectoral fins are joined in front of the snout. *Pristis* is the saw-fish. It has an immensely elongated rostrum, at the sides of which large pointed teeth are set; the body is elongated, but it




FIG. 210. *Raia maculata*. From Day.

- A. Dorsal surface, showing the spiracles just behind the eyes. Reduced.
B. View of mouth and olfactory pits of *Raia maculata*.

shows all the essential features of the Batoidea. The teeth in the mouth, like those of other Batoidei, are flattened. *Pristis* is found both in the Mediterranean and Caribbean Seas and elsewhere.

Order II. Holocephali.

The second order of Pisces, the Holocephali, differ from Elasmobranchs chiefly in the skeleton; in the viscera they resemble them very closely. The Holocephali are distinguished by having the upper jaw completely confluent with the cranium, a condition called autostylic (Fig. 211): the orbits are so deeply indented that the brain is pressed back from between them, and their two cavities are only separated by a vertical plate of cartilage, called the inter-orbital septum. There is no spiracle and the last gill-cleft is also




FIG. 211. Skull of a male *Chimæra monstrosa*. After Hubrecht.

1. Nasal capsule. 2. Cartilaginous appendage to the ethmoid region representing the rostrum of Elasmobranchii. 3. Erectile appendage
4. Foramen by which the ophthalmic nerves leave the orbit. 5. Foramen by which the ophthalmic branch of the Vth nerve enters the orbit.
6. Auditory capsule. 7. Interorbital septum. 8. Meckel's cartilage articulating with an outgrowth from the posterior part of the palato-ptyergo-quadrato cartilage. 9. Teeth. 10. Labial cartilage. II III. V. VII. IX. X. foramina for the passage of cranial nerves.

closed. A fold of skin, called the operculum, extends back over the gill-slits, which are, however, still in the form of sacs. The snout or praeoral part of the body is much reduced in size and supported only by a single rod of cartilage.

The scales have almost entirely disappeared and are represented only by the great spine, the so-called ichthyodorulite which stiffens the front edge of the dorsal fin, by the teeth and by the prickles on a peculiar tentacle situated on the snout of the male. The teeth are confluent, forming ridges of dentine covered with

enamel. Of these there are a pair in the lower jaw, called dentary plates, and two pairs in the upper, termed vomerine and palatine plates respectively, placed one behind the other. The peculiar tentacle on the head of the male arises from a pit situated in the middle line of the snout, and bearing sharp tooth-like scales at its tip. Its use is unknown.




FIG. 212. *Chimaera monstrosa*, Lin.
Male with process on snout. Reduced.

The notochordal sheath is not broken up into centra, but in *Chimaera* it has developed within it a large number of calcified rings, three to five times as numerous as the neural arches.

The Holocephali were once a numerous group, now they are represented by three closely allied genera, of which the best known is *Chimaera*, sometimes called the Rabbit-fish, common to the Mediterranean and to the Atlantic coast of Europe and Africa. *C. monstrosa* is found on the East coast of N. America. On the Pacific coast *C. collei* occurs in such numbers as to be a serious nuisance to fishermen. It eats the baits off their lines. It is known as the Rat-fish, in allusion to the shape of the tail. *Callorhynchus* occurs in the temperate waters of the Southern Hemispheres. The third genus, *Harriotta*, is a deep-sea form.

Order III. Dipnoi.

The third order of Fishes, the Dipnoi, are very interesting animals, inasmuch as they afford indications as to how land animals were evolved from fishes. They are distinguished by the possession of true lungs, represented by two sacs opening by a common tube into the ventral side of the oesophagus. The blood is supplied to the lungs by vessels given off from the last two pairs of afferent gill-arteries (Fig. 216), and it is returned not into the general circulation, but direct to the heart, where it opens into a special section of the atrium, the left auricle, cut off from the rest by a septum. As in the Holocephali the upper jaw is fused with the cranium. There are four or five gill-clefts and no spiracle. There is a large gill-cover which completely covers the clefts; it is strengthened in *Ceratodus* by two strong membrane-bones, the so-called squamosal or pre-operculum, and the operculum; there is also a third smaller bone called the inter-operculum. The oro-nasal groove has become closed so as to form a canal, the end of which opens within the stomodaeum as the posterior naris or choana. Owing to the forward growth of the jaws the mouth has become terminal.



FIG. 213. *Lepidosiren paradoxa*. Male, showing the feathered pelvic fins of the breeding season. From Graham Kerr. Much reduced.

The cranium is not narrowed between the orbits, and the cartilage behind is replaced by true bone, there being two exoccipital bones at each side of the hole called the foramen magnum from which the spinal cord issues. Above the foramen magnum the cranium is quite obviously composed of fused neural and ventral arches; the spines of the former and ribs of the latter are quite distinct. As in *Chimaera* the teeth have coalesced to form great dentary ridges in the lower jaw and in the roof of the mouth, the so-called vomerine and palatine plates, the first named being anterior (Fig. 214).

It will be observed that in the Dipnoi we for the first time meet with large bones, and it is instructive to notice under what circumstances they appear. The exoccipital bones are quite distinct from

the calcifications of the cranium met with in the Elasmobranchii.

In the latter case there was hardening of the ground substance of the cartilage; here the bone is formed in the membrane surrounding the cartilage and eats into and destroys the cartilage. This sort of bone is true cartilage-bone. Besides such bones, however, we have many which are traceable to the fusion of the small bony bases of the typical scales which we found in Elasmobranchs. These little bony plates fuse together to form large structures which are then termed membrane-bones. A first trace of this process is seen in the fusion of the teeth to form compound plates, as in the Holocephali.




FIG. 211. Dorsal (to the left) and ventral (to the right) views of the cranium of *Ceratodus miolepis*, after Günther.

- 1 Cartilaginous part of the quadrate with which the mandible articulates. 2, 3, 4. Roofing membrane bones. 5. Nares. 6. Orbit. 7. Preopercular (squamosal). 8. Second rib. 9. First rib. 10. Vomerine dental plate. 11. Palatine dental plate. 12. Palato-pterygoid. 13. Parasphenoid. 14. Interopercular.

The Dipnoi are eel-like fish with elongated whip-like paired fins, and they are covered all over with thin rounded cycloid scales. These scales represent the enlarged bases of the scales of Elasmobranchs, of which the spikes have been lost. On the upper side of the head these scales have joined to form median and lateral bones; in front near the nasal sacs there are two smaller bones. The Dipnoi are quite peculiar among Craniata in having an unpaired series of large roofing bones on the top of the head. The palatine dental plates are supported by a bone which surrounds and

replaces the cartilaginous upper jaw, and is called the palato-ptyergoid. The roof of the mouth is sheathed by a great plate of bone called the parasphenoid, derived from the bases of vanished teeth (Fig. 214). Besides these there is a large membrane-bone outside the pectoral girdle, which is the first trace of a collar bone or clavicle, and the two bones already mentioned in the opercular flap. The sheath of the notochord is converted into cartilage, but is not divided into centra.

The paired fins are remarkable for having a long jointed axis and two rows of rays; they are in a word biserial (Fig. 215). The tail-fin is of the primitive type found in *Amphioxus* and *Cyclostomata*, in which the fringe of skin supported by the fin-ray is equally developed above and below the notochord. It is in fact a diphycercal tail.

As was to be expected, the blood system has undergone interesting modifications. The conus arteriosus is long, and as in *Elasmobranchs* and *Holocephali* has several transverse rows of pocket valves. From its anterior end four arteries are given off in a bunch on each side to the gill arches to supply the gills: there is no ventral aorta. From the last on each side branches arise, which form the artery going to the lungs. An oblique septum divides the cavity of the conus into two, in such a way as to cut




FIG. 215. Lateral view of the skeleton of *Ceratodus macleayi* (after Günther).

- 1, 2, 3. Roofing membrane-bones. 4. Cartilaginous posterior part of cranium.
 5. Pre-opercular (squamosal). 6. Opercular. 7. Suborbital.
 8. Orbit. 9. Pectoral girdle. 10. Proximal cartilage of pectoral fin.
 11. Pectoral fin. 12. Pelvic girdle. 13. Pelvic fin. 14. Spinal column.
 15. Caudal fin (diphycercal).

off the openings of the last gill arteries from the front ones, so that the blood passing to the lungs does not mingle with that going on to the head. This is very like the arrangement found in Amphibia. The likeness to the Amphibian blood-system is heightened by the presence of a median "vena cava" which returns the blood from one kidney directly to the heart. One posterior cardinal vein persists, the other has atrophied (Fig. 217).




FIG. 216. Diagram of arterial arch of *Ceratodus* viewed from the ventral aspect.

- I. II. III. IV. First, second, third, and fourth arterial arches. 5. 6. 7. 8. First, second, third, and fourth gill. 9. 10. 11. 12. First, second, third, and fourth efferent branchial vessel. 13. External carotid. 14. Internal carotid. 15. Pulmonary artery. 16. Dorsal aorta.

The lungs are long, wide sacs, extending between the intestine and notochord, although their opening into the gullet is ventral. The gill-arches and gills are on the other hand very small, and the opening between the gill-cover and the body is narrow.

Only three species of

Classification. Lung-fish are still living,

but the group has very many fossil representatives. The Australian lung-fish, *Ceratodus forsteri*, has well developed paired fins (Fig. 215). It inhabits rivers which at certain seasons become foetid with decaying vegetation, and during this time it breathes air. The African and South American lung-fishes (*Protopterus* and *Lepidosiren*) have whip-like paired

fins consisting of little more than the axis of the limb skeleton (Fig. 213). They bury themselves in mud during the dry season, a necessary precaution, since they inhabit swamps which dry up. *Lepidosiren*, the South American form, has been shown to have larvae with long feathery external gills, strikingly recalling the larvae of Amphibians. The young *Protopterus* has similar structures and retains traces of its external gills throughout life.

Ceratodus, on the other hand, has a development practically completed within the egg-shell.

Order IV. Teleostomi.

The fourth order of Fish, the Teleostomi, is by far the largest and contains the overwhelming majority of living fishes. They differ from the Dipnoi, in that the lung or air-bladder, as it is called, receives its blood from the dorsal aorta and returns it to the general circulation, so that the organ is as a rule not so much respiratory as hydrostatic. The lung is undivided and its opening has in most cases apparently become shifted up the side of the throat to the mid-dorsal line. Since the opening of the air-bladder is dorsal some authorities have held that it is quite a different organ from the lung, the opening of which is ventral. But it is very difficult to believe that we have to deal with two totally distinct organs in *Polypterus* and *Lepidosteus*, more especially as in the latter fish it seems possible that the air-bladder subserves respiration. The air-bladder is never paired: if we suppose it to represent one lung we can imagine how the opening could be gradually shifted dorsally. The anus of Urochordata has undergone a similar shifting.

Another point of difference, distinguishing Teleostomi from the Dipnoi, is that there are no median membrane-bones on the head, all the bones being originally paired. Further, a set of membrane-bones bearing teeth appear in the sides of the mouth outside the primitive jaws, or, as we may express it, in the lips. These lip-bones functionally replace the true jaws, and as the mouth has now




FIG. 217. Diagram to show arrangement of the principal veins in a Dipnoan.

1. Sinus venosus—gradually disappearing in the higher forms.
2. Ductus Cuvieri = superior vena cava. 3. Internal jugular = anterior cardinal sinus. 4. External jugular = sub-branchial.
5. Subclavian. 6. Posterior cardinal, front part = venae azygos and hemiazygos. 7. Inferior vena cava. 8. Renal portal = hinder part of posterior cardinal.
9. Caudal.

received its full armature, the name Teleostomi, or Perfect-mouthed Fish (τέλειος, perfect; στόμα, mouth) has been given to the Order. As in Elasmobranchs the upper jaw is joined to the skull only by the upper half of the hyoid arch, which is ossified as the hyo-mandibular. There is a strongly developed gill-cover, armed with several bones, called the operculum. The septa between the gill-sacs are reduced to narrow bars, so that we have gill-clefts, not gill-pouches. The gills themselves develop into long triangular processes freely projecting, attached only at the base. Often there is a rudimentary gill attached to the posterior aspect of the hyoid arch. This is called the pseudobranch or sometimes the opercular gill. This is not to be confounded with the pseudobranch of Elasmobranchii, which is attached to the first visceral arch. The opening of each nasal sac is divided into two by a bridge and there is no oro-nasal groove. The cloaca is divided into two openings; an anterior, the anus, communicating with the intestine, and a posterior, serving for the discharge of the genital products and excreta of the kidneys.

It was formerly customary to divide the fish here grouped as Teleostomi into two orders, the Teleostei, or completely bony fish (ὀστέον, a bone), and the Ganoids, or fish with shining scales (γάμος, glitter, brightness). As, however, there is far more difference between different families included in the Ganoids than there is between some Ganoids and some Teleostei, this arrangement is regarded as unnatural. The Ganoids are in fact composed of widely different families, retaining certain primitive characteristics once shared by all Teleostomi. A far more rational division of the Teleostomi is that now usually adopted into Crossopterygii and Actinopterygii.

Sub-Order A. Crossopterygii.

The Crossopterygii include only two living genera, *Polypterus* and *Calamoichthys*, which inhabit the rivers of Africa. In former geological periods, however, the Crossopterygii constituted an immense group. They are distinguished by retaining the biseriata paired fin with a shortened and broadened axis, covered by scales. This scaly lobe is consequently fringed by the rays, whence the name (κρόσσοι, a fringe; πτέρυξ, wing or fin). The so-called air-bladder is paired and the two halves open on the under side of the pharynx. The spiracle still persists, having a special little gill-cover strengthened by several small bones. It has recently been

proved that the air-bladder is a respiratory organ, and that the expired air escapes by the spiracle.

The whole body is covered with lozenge-shaped scales covered by a thick layer of shining enamel, and the dorsal fin is subdivided into a large number of finlets, each supported by a large stiff ossified fin-ray (Fig. 218). The head is covered with numerous membrane-bones arranged in pairs, replacing the cartilage of the cranium. There are not only exoccipital bones, but also a basi-occipital situated beneath the foramen magnum, and the front wall of the auditory capsule is ossified by a pro-otic bone. The notochord is narrowed in parts by the formation of bony centra; these however are not, as in the Elasmobranchs, mere rings in the notochordal sheath, but are formed of the coalesced expanded bases of the bony neural and haemal arches. The term chorda-centra has been proposed for centra such as those of Elasmiobranchii, formed by the segmentation of the sheath of the notochord; whilst centra such as those of the Crossopterygii are called arco-centra. The centra have concavities before and behind and the space between two vertebrae is filled with an expanded section of the notochord, which in the middle of the vertebrae is reduced to a mere thread if not obliterated altogether. Vertebrae, hollowed on each side, are said to be amphicoelous (Gr. ἀμφί, both; κοίλος, hollow).

It is obvious that an axis composed of vertebrae is a much more efficient organ of support than the flexible notochord with its loosely adherent neural and haemal arches. Hence it is not surprising to find that vertebrae have been independently developed in Fishes, Amphibia, and Reptiles, and have




FIG. 218. *Polypterus*.

had an independent origin even in different families of the same order—the Halecomorphi and Lepidosteidae, for example. Different investigators therefore in their endeavours to find exactly corresponding parts in the vertebral columns of various animals have arrived at discrepant results. After years of research however Dr Gadow has been enabled to give a consistent account of the evolution of the column in all the Craniata, and to his account we shall adhere.

Vertebral
column.

According to Dr Gadow, all arco-centra originate from four pairs of cartilaginous pieces; some of which may be entirely suppressed in some vertebrae, but all of which are represented in some part or other of the column. These are (1) basi-dorsals, the expanded bases of the neural arches; (2) basi-ventrals, the expanded bases of the haemal arches (to these when present the rib is always attached); (3) inter-dorsals—cartilaginous pieces situated between successive basi-dorsals, and derived from the segmentation of the apical ends of the haemal arches which have extended upwards round the notochord; (4) inter-ventrals—cartilaginous pieces placed beneath the notochord alternating with the basi-ventrals, and derived from the segmentation of the apical ends of the neural arches which have extended downwards round the sheath of the notochord.

In an ancestral Craniate therefore corresponding to each myotome there were on each side of the notochord four cartilaginous pieces. These pieces in different groups of animals have been variously combined with their successors and predecessors, the joint between two successive vertebrae being formed not between two pieces but by the absorption of cartilage in the middle of a piece at the place where the maximum bending occurs.

The Crossopterygii are probably in some respects more nearly related to the ancestors of Amphibia than are modern Dipnoi. This view is strengthened by the fact that the air-bladder is occasionally used as a lung. The young have one large external gill attached to the operculum. As in the Dipnoi the mouth is terminal.

Sub-Order B. Actinopterygii.

The Actinopterygii are distinguished by having a uniseriate fin, the base of which is not covered by scales, and by having the opening of the air-bladder dorsal. Among the most primitive

subdivision is that of the CHONDROSTEI, or Sturgeons. In these fish there is a long shovel-shaped snout or prae-oral part of the head, which is used for shovelling up the mud at the bottom of rivers in search of prey. This old-fashioned feature is not found in any other family of the Actinopterygii, all of which have terminal mouths. The notochord of the Sturgeons has a thick sheath without any trace of centra, and the only cartilage bones in the cranium are small ossifications on its side walls, called the orbitosphenoid and the alisphenoid bones, and a pro-otic in the front wall of the auditory capsule. The hyomandibular segment of the hyoid arch is ossified by two bones—a hyomandibular where it articulates with the skull, and a symplectic below where it joins the first visceral arch. A large part of the cranium is covered with a number of membrane-bones which pass insensibly into the great scutes or bony plates which cover the body. These latter, like the bones of the head, are derived from the fusion of scales. Though the mouth is often toothless, there is a distinct maxillary bone in the upper lip outside the pterygoid bone which supports the pterygoquadrate cartilage. A great parasphenoid supports the base of the skull.

The common sturgeon *Acipenser* is found in the Pacific and North Atlantic, and enters the rivers of Europe and America. The ovary forms the Russian delicacy known as caviare. The spoon-bill *Polyodon*, found in the Mississippi, has a very broad snout, and has lost nearly all its scutes, but it retains some at the sides of the tail, and a series forming a comb-like fringe along the dorsal edge of the upper lobe of the tail, called fulcra.

The subdivision of the HALECOMORPHI is represented at the present day by only one species, *Amia calva*, the Bow-fin of the St Lawrence, and other American rivers. Like *Polypterus* this species has complete amphicoelous centra formed by the fusion of the expanded bases of the neural and haemal arches: the cranium is also largely replaced by bone, not only behind where the foramen magnum is encircled by four bones, the supra-occipital, two ex-occipitals, and a basi-occipital, but at the sides and in the snout where a mesethmoid is formed. In addition there is a complete helmet of membrane-bones surrounding the cranium above and at the sides, and the lips have above a pre-maxilla and a maxilla, and below a dentary, all well provided with teeth. The whole body is covered with thin rounded scales. *Amia* is a voracious fish about two feet long.




FIG. 219. *Acipenser sturio*, the Sturgeon. From Day.

The next family, that of the LEPIDOSTEIDAE, are the most bony of all fish. They are the Bill-fish or Gar-pikes of the Northern and Central American and Cuban lakes and rivers. The whole body is covered with scales, like those of *Polypterus*, coated with a thick layer of enamel. The jaws are long, and in both the upper and under lips there is a series of three or four bones bearing teeth, a rare condition. The skull is as bony as that of *Amia*. The vertebral centra have become opisthocoelous, that is to say, each centrum is convex in front, fitting into a concavity of the hinder surface of the one in front of it, so that the notochord has almost disappeared. The ovary, by the fusion of its free edge with the coelomic wall, has become converted into a sac, to which the funnel of the oviduct has become adherent, so that ovary and oviduct are continuous. The spiral valve on the intestine is rudimentary.

The Gar-pike are said to lie in wait among the reeds on the banks of the lakes, and to seize small animals visiting the swamp in their long pincer-like jaws./

The remaining families of the Actinopterygii are grouped together as TELEOSTEI and have certain well-marked characters in common which distinguish them from the preceding families grouped together as the GANOIDEI. The first of these characters is the structure of the tail. In all the Actinopterygii so far mentioned the tail is heterocercal, though in some, such as *Amia*, the ventral lobe is very predominant. In the Teleostean families the ventral lobe forms the whole of the tail and is placed in a straight line with

the rest of the body, the end of the notochord being sharply bent up almost at a right angle with the remainder and surrounded by a bony sheath. Such an apparently symmetrical tail-fin is called homocercal, and it is to be sharply distinguished from the really symmetrical diphyccercal tail of the Dipnoi.

Another important point in the anatomy of Teleostei is the structure of the heart. The conus arteriosus with its several rows of valves has become completely absorbed into the ventricle. Only the anterior row of valves remains, separating the enlarged ventricle from the ventral aorta, at the origin of which there is a non-contractile swelling, the bulbus arteriosus.

The stomach is distinctly sac-like, the two limbs of the loop of the alimentary canal of which it is constituted showing a tendency to coalesce.

The intestine has become longer and more coiled and has completely lost its spiral valve. Close to the entrance of the bile-duct there is a series of short, blunt diverticula of the intestine, called pyloric caeca. These were supposed to be a modified true pancreas, but the true pancreas has recently been discovered in the form of a number of very delicate tubes intermixed with the pyloric caeca. In no Teleostean, so far as is known, does the pancreas form a compact gland. The ovary is a hollow organ continuous with its duct; in this point, it is true, *Lepidosteus* has Teleostean characters, but in Teleostei the testis is also continuous with its duct, which shows no relation to the kidney; so that in the male there is a complete departure from the normal Craniate arrangement. The cloaca has undergone more division than even in the primitive Actinopterygii, for the conjoined kidney ducts have an opening behind and distinct from that of the united genital ducts.

In the brain the roof of the cerebrum is a thin non-nervous membrane, but the optic lobes and cerebellum are greatly developed. The interlacing of the fibres of the two optic nerves, which was alluded to above as the optic chiasma, has entirely disappeared, so that the optic nerve from the left side proceeds straight to the right eye, crossing but not interlocking with those from the right side to the left eye. The eyes are exceedingly large, so that in nearly all Teleostei, as in the Holocephali, an inter-orbital septum is formed, along the upper edge of which the olfactory stalks run.

In the skeleton there is hardly a feature which is not shared by some or other of the members of the more primitive families of the Actinopterygii, but in the combination of features it is

characteristic, and it is of such an uniform type throughout a large number of families that it merits a special description.

The notochord is constricted by the formation of amphicoelous centra, which have developed four ridges projecting outwards in two planes at right angles to one another. In the intervals between these ridges the ends of the neural and haemal arches are inserted, all being converted into bone. The pectoral arch is represented by a small plate of cartilage on each side, in which are two bony centres, an upper scapula and a lower coracoid (Fig. 220). Outside this there is a strong curved membrane-bone, strengthening the hinder border of the opercular slit,




FIG. 220. The right half of the pectoral girdle and right pectoral fin of a Cod, *Gadus morrhua*, $\times \frac{1}{2}$.

- | | | | |
|---------------------|--------------------|---------------------------------|--------------|
| 1. Post-temporal. | 2. Supra-clavicle. | 3. Clavicle. | 4. Coracoid. |
| 5. Scapula. | 6. Post-clavicle. | 7. Ossified radials of the fin. | |
| 8. Dermal fin-rays. | | | |

the clavicle. This is connected with the skull by a supra-clavicle and post-temporal bar, whilst from its lower end a pre-clavicle runs forward beneath the gills. From its hinder edge a post-clavicle often projects back into the muscles. The anterior paired fins are attached to the girdle where the scapula and coracoid join. In them the cartilaginous skeleton is almost

all absorbed, the basal portions of the fin rays becoming changed into true membrane-bone and articulating direct with the pectoral girdle. The pelvic fin has a similar structure, and the pelvic girdle has quite disappeared.

The cranium is completely covered with bones. Even where cartilage persists it is covered with the bones which
 The skull. in other allied forms have displaced and absorbed the underlying cartilage. The cranium, as already mentioned, is so strongly compressed between the orbits that it is divided into two portions, an ethmoid region in front of the eyes and an occipital region behind them, connected by a narrow sphenoid isthmus running between them. In the cartilaginous roof there are several membranous windows or "fontanelles." The anterior fontanelle lies between the nasal sacs; the posterior fontanelles are a pair of windows situated one at each side of the supra-occipital bone. The supra-occipital, two exoccipitals and a basi-occipital form the hindermost portion of the brain-case surrounding the foramen magnum (Fig. 221). The supra-occipital, which is situated in the mid-dorsal line, has a great vertical ridge to which the powerful longitudinal muscles of the body are attached. The auditory capsule is completely replaced by bone; above it is covered by a pointed epiotic, in front and below by the pro-otic, behind by the opiotic, and on the outer side by the pterotic with which it articulates. On its inner side the capsule covers the brain by membrane. In the inter-orbital region the sphenoid articulates with the supra-sphenoid in front, an alisphenoid behind and the pterotic above partly extending into the auditory capsule, whilst below and behind in the base of the skull there is a Y-shaped bone, the basi-sphenoid, just in front of the basi-occipital (Fig. 222). The ethmoid region in front of the eyes is the part in which most cartilage persists; it is ossified above by the median ethmoid and on the sides by the lateral ethmoids. Connected with the cartilaginous upper jaw there is a large quadrate bone developed where it articulates with the lower jaw; a pterygoid bone replacing the cartilage on the outer and an entopterygoid on the inner side; lastly a metapterygoid above and in front of the quadrate. The palatine bone is situated in front of the pterygoid and articulates with the lateral ethmoid. This bone covers a bar of cartilage of uncertain significance. By some it is regarded as an anterior portion of the pterygoid bar separated from the rest and corresponding to part of the upper jaw

of Elasmobranchs; by others it is regarded as having an independent origin from this. In the lower jaw we have a bone, the articular, which moves on the quadrate. In the second or "hyoid" visceral arch, we find, as in all hyostylic fish, an upper segment, the hyomandibular, articulating with the skull, and a lower segment, the ceratohyal, which supports the




FIG. 221. A. dorsal and B. ventral view of the cranium of a Salmon, *Salmo salar*, from which most of the membrane bones have been removed. After Parker. Cartilage is dotted.

1. Supra-occipital. 2. Epiotic. 3. Pterotic. 4. Sphenotic. 5. Frontal.
6. Median ethmoid. 7. Parietal. 8. Lateral ethmoid. 9. Parasphenoid.
10. Vomer. 11. Exoccipital. 12. Opisthotic.
13. Alisphenoid. 14. Orbitosphenoid. 16. Foramen for passage of an artery.
17. Prootic. 18. Articular surface for hyomandibular.
- II. VII. IX. X. foramina for the passage of cranial nerves.

opercular flap and from which in Teleostei bony rays, called branchiostegal rays, extend, on which the membranous part of the membrane is stretched, as an umbrella on its ribs. The hyomandibular segment is formed here, as in all Actinopterygii, of two bones, an upper hyomandibular, *sensu stricto*, uniting with the skull, and a lower symplectic joined to the quadrate. The ceratohyal segment likewise is represented by three bones, a main

ceratohyal, a small interhyal uniting the latter to the symplectic, and a hypohyal extending inwards from its lower end. The two hypohyals are joined by a median bone, the glossohyal. This supports a projection of the floor of the pharynx which is the rudiment of the tongue. The other visceral arches are composed each of four bones, except the last which is rudimentary. The uppermost segments extend inwards on the roof of the pharynx and bear teeth; they are called the superior pharyngeal bones. Owing to the forward slope of the visceral arches these bones are




FIG. 222. Lateral view of the cartilaginous cranium of a Salmon, *Salmo salar*. After Parker. A few membrane bones are also shown. Cartilage is dotted.

- | | | | |
|---|---|-----------------------------|---------------------------|
| 1. Supra-occipital. | 2. Epiotic. | 3. Pterotic. | 4. Opisthotic. |
| 5. Exoccipital. | 6. Basisphenoid. | 7. Parasphenoid. | 8. Sphenotic. |
| 9. Alisphenoid. | 10. Orbitosphenoid. | 11. Lateral- or ectethmoid. | |
| 12. Olfactory pit; the vomerine teeth are seen just below. | 14. Prootic. | | |
| 15. Basisphenoid. | 16. Foramen for the passage of an artery. | 17. Anterior fontanelle. | 18. Posterior fontanelle. |
| I. II. V. VII. IX. X. foramina for the passage of cranial nerves. | | | |

directly above the seventh or last pair of arches, which consist on each side of a small bone bearing teeth, the inferior pharyngeal bone. Whatever chewing is done by fish is effected by these bones, the teeth in the front part of the mouth are chiefly used for retaining prey. The presence of teeth on the gill-arches is not easy to explain. Teeth, as we have seen, are structures developed from the dermis and ectoderm, whilst the gill-arches support the walls of the pharynx which are certainly endodermal. We must either suppose that some portion of the ectoderm has migrated inwards through the gill-slits or that the endoderm has acquired the power of producing teeth: on the whole the first supposition seems the more probable.

The membrane-bones in the Teleostean skull are numerous and are traceable to two sources, namely, the scales of the skin and the bases of the teeth. To the former category belong the roofing bones of the skull, the parietals at each side of the supra-occipital, and the great frontals which cover the anterior fontanelle, but which also extend outwards and roof in the orbits. A pair of delicate nasal bones lie on the nasal sacs. On the side of the head there is a chain of bones surrounding the eye, called the orbital ring, and four bones stiffening the upper part of the opercular




FIG. 223. Mandibular and hyoid arches of a Cod, *Gadus morrhua* $\times \frac{1}{2}$.

- | | | | |
|-----------------|--------------------|-------------------|--------------------------|
| 1. Palatine. | 2. Ento-ptyergoid. | 3. Pterygoid. | 4. Quadrate. |
| 5. Symplectic. | 6. Meta-ptyergoid. | 7. Hyomandibular. | 8. Angular. |
| 9. Articular. | 10. Dentary. | 11. Interhyal. | 12. Epihyal |
| 13. Ceratohyal. | 14. Hypohyal. | 15. Glossohyal. | 16. Branchiostegal rays. |

flap, a pre-operculum in front, an operculum above and behind, a sub-operculum below it, and an inter-operculum between the pre-operculum and the sub-operculum.

To the fusion of the bases of teeth we must ascribe the origin of the great parasphenoid bone, which stiffens the roof of the mouth and extends back under the basi-occipital, although in no Teleostean does it bear teeth. Similarly, in front of it we have the vomer made of two bones joined in the middle line, which still bear teeth in their anterior portions. It is possible that the palatine

and pterygoid may also be traceable to the fusion of groups of teeth placed more laterally, but in this case the membrane-bone has become a cartilage bone by extending into and replacing the cartilaginous bar beneath it.

The membrane-bones in the lips, which are essentially characteristic of the Teleostomi, have probably had a double origin—scales of the outer skin united with teeth developed just inside the mouth.




FIG. 224. Lateral view of the Skull of a Salmon, *Salmo salar*. After Parker. Cartilage is dotted.

1. Supra-occipital. 2. Epiotic. 3. Pterotic. 4. Sphenotic. 5. Frontal.
6. Median ethmoid. 7. Parietal. 8. Nasal. 9. Lachrymal.
10. Sub-orbital. 11. Supra-orbital. 12. Cartilaginous sclerotic.
13. Ossification in sclerotic. 14. Ento-ptyergoid. 15. Meta-ptyergoid.
16. Palatine. 17. Jugal. 18. Quadrate. 19. Maxilla. 20. Pre-maxilla.
21. Articular. 22. Angular. 23. Dentary. 24. Hyoman-dibular.
25. Symplectic. 26. Epihyal. 27. Ceratohyal.
28. Hypohyal. 29. Glossohyal. 30. Opercular. 31. Sub-opercular.
32. Infra-opercular. 33. Pre-opercular. 34. Supratemporal.
35. Branchiostegal rays. 36. Basi-branchiostegal.

There are, in the upper lip, the pre-maxilla in front, the maxilla behind, and occasionally behind these a third bone, the jugal. As we have already seen, the number of these upper lip bones is greater in the Lepidosteidae. In the lower lip there are in front the dentary, behind and on the inner side the splenial, and behind and below, the angular. The branchiostegal rays mentioned

above are membrane-bones, and between those of opposite sides there is a median bone called the basi-branchiostegal.

Taking a general view of the skeletons thus far studied, we see that the replacement of cartilage by cartilage bone tends to take place first wherever there is a joint. Thus in Dipnoi we find the hinder part of the cranium replaced by exoccipitals, whereas in the Chondrostei, where all the skull and front part of the notochordal sheath form one solid mass, no such bones are developed. Again, in Teleostei, the only replacement of the lower jaw by cartilage bone takes place at its proximal end, where it joins the upper jaw. Then again we find the lateral ethmoid developed where the front part of the palatine articulates with the skull, and the articulation of the hyomandibular has probably had something to do with bringing about the ossification of the auditory capsule.

With the exception of the Ganoidei all the Teleostomi differ fundamentally from the Elasmobranchs and Holocephali, in having small eggs. These rapidly develop into larvae with primitive tails and other primitive features which ally modern fish with the old-fashioned fossil forms. The development into the adult is very slow and dangerous, and during this period an enormous number of the young perish. The habits, distribution and food of these young form one of the most important economical problems that zoologists of the present day are seeking to solve.

Since in the animal kingdom small eggs and a prolonged larval life constitute the more primitive arrangement, and eggs charged with yolk and cared for by the parent a secondary modification, we conclude that in this matter the Teleostei have retained primitive habits. This throws some light on a question which must often arise in the minds of all students of zoology, namely, how it is that comparatively primitive forms, like the Elasmobranchs, and highly modified forms, like the Teleostei, exist side by side? We can see that in each case there has been some great modification of the primitive arrangement, in Elasmobranchs in the egg and young, in Teleostei in the skeleton and scales. It is improbable that any living animal preserves all the characters of the common ancestor of the group to which it belongs; some traits are preserved in one case, others in another.

There are some 10,000 species of fish included amongst the Teleostei. The limits of this work forbid us to mention more than a very few, and these will be

Systematic.




FIG. 225. A Roach, *Leuciscus rutilus*, dissected to show its brain, gills, and viscera. Slightly diminished in size.

1. Olfactory lobe.
2. Right optic lobe.
3. Cerebellum.
4. Heart, auricle.
5. Lymphatic gland, the so-called head-kidney.
6. Kidney.
7. Liver.
8. Intestine.
9. Genital gland.
10. Air-bladder.
11. Anus.
12. Genital opening.
13. Opening of ureter.
14. Dorsal fin.
15. Pectoral fin.
16. Pelvic fin.
17. Caudal fin.

chiefly the commoner food-fish. It is possible to separate a number of families, as **PHYSOSTOMI**, distinguished by the two ancient characters of having the air-bladder opening into the oesophagus and having the pelvic fins abdominal in position, that is to say, placed far back near the vent. All the rest are termed **PHYSOCLISTI**; in them the air-bladder is a closed sac having lost its connection with the oesophagus, and the pelvic fins have been in nearly every case shifted forwards and are either thoracic, that is, placed just behind the pectoral fins, or jugular, that is, placed in front of them.

The families of the **Physostomi** which we shall mention are the Cat-fish (**SILURIDAE**), the Eels (**ANGUILLIDAE**), the Herrings (**CLUPEIDAE**), the Salmon and Trout family (**SALMONIDAE**), and the Carp family (**CYPRINIDAE**).

The Cat-fish receive their name from the peculiar appendages called barbels which hang down from their upper and under lips.




FIG. 226. A Cat-fish, *Amiurus catus*. From Cuvier and Valenciennes.
Diminished.

Other fish may have them on the under lip, but in the **SILURIDAE** the maxilla bears no teeth and forms only a support for the great barbels. The **Siluridae** are very different from the other **Teleostean** families, and it appears possible that they are more nearly related to the ancient **Chondrostei** than to other **Teleostei**. Thus the Cat-fish never have scales, they either have large glistening bony scutes or are naked. The teeth are feeble. The skull is not narrowed between the orbits; the anterior vertebrae are fused together and the sub-opercular bone is wanting. The first ray in the dorsal and in the pectoral fin is replaced by a strong spine. The Cat-fish are mainly a tropical group abounding in South America and Africa, and nearly all are fresh-water. The forms with bony scutes are confined to South America. Several, however, of the naked species

are found in North America, two being marine Sea-Cats. *Ictalurus* is the White Cat, an excellent food-fish ranging north to New England. *Amiurus* is common in the Eastern States, and one species, the Bull-head, *A. nebulosus*, is found in the St Lawrence.

The ANGUILLIDÆ or Eels are long, cylindrical creatures with either small deeply imbedded scales or none. The dorsal, ventral and caudal fins are contiguous, the pelvic fins being absent. The skull resembles that of the Cat-fish in not being narrowed between the orbits, and in having only one or two bones in the gill-cover. Eels spawn in the sea. *Anguilla*, the common eel, ascends streams and even crosses wet grass to get to isolated ponds; it has small scales. *Echelus* (*Conger*), the conger eel, is entirely marine, and devoid of scales; it attains a length of six feet. The eggs of both species develop into a peculiar ribbon-shaped larva with colourless blood and slightly developed tail called *Leptocephalus*.

The CLUPEIDÆ or Herrings are distinguished by the fact that their maxillae bear teeth and form part of the edge of the jaw, and further that the maxilla is really composed of two or three pieces placed end to end, recalling the condition in the Lepidosteidae. The tail-fin is forked. The genus *Clupea*, with compressed belly, edged by projecting scales, includes not only the Herrings, which come in shoals to the English and Scotch and American coasts to spawn, but also the Shad, a high-backed herring, which frequents the coasts of Canada and New England, and which spawns in the rivers. The eggs of Clupeidae, as a rule, are large and heavy and sink to the bottom, unlike those of most Teleostei, which float at the surface of the sea. The Anchovy, with a projecting snout, and a rounded belly, the Pilchard and the Sprat also belong to this family.

The SALMONIDÆ have a toothed maxilla and a jugal bone in the upper lip and a small soft fin devoid of rays behind the dorsal, called the adipose fin. In the female the oviduct has disappeared, the eggs escaping by two pores. The genus *Salmo* includes the well-known Salmon, which ascends rivers to deposit its spawn, and also the Brown River Trout of Europe, which is permanently confined to fresh water. The brook-trout of North America belongs to a different genus, *Salvelinus*, and the great King-Salmon of British Columbia, canned in such enormous quantities, is *Oncorhynchus tshawytscha*. From a sportsman's point of view it is distinguished from the true Salmon by the circumstance that it

does not take the fly. *Coregonus*, the white fish of the great American lakes, much esteemed for its delicate flavour, also belongs to this group. The habit of ascending the rivers to spawn probably points to the conclusion that the whole group was originally fresh-water, and that the Salmon is a river fish which has taken to the sea, whereas the Eel is a salt-water fish which has taken to fresh-water. Whether all the Herring family were ever fresh-water or not is doubtful, but it is interesting to note that the Pilchard has a small floating egg.

The CYPRINIDÆ include the Carp and American Minnows. The maxilla does not form part of the edge of the mouth, but merely serves to stiffen the membranous cheek. Teeth are absent from the lips although well-developed on the gill arches, there is no adipose fin, and the stomach is not well marked. The Gold-fish is a Japanese species.

The great division of the Physoclisti includes five main subdivisions, the *ANACANTHINI*, the *ACANTHOPTERI*, the *PHARYNGOGNATHI*, the *LOPHOBRANCHII*, and the *PLECTOGNATHI*. The last two groups are in some respects aberrant.

I. The *ANACANTHINI* have all the fin-rays soft and flexible and the pelvic fins are shifted forward in front of the pectorals. The GADIDÆ are the Cod family and includes the Cod, Haddock,




FIG. 227. *Pleuronectes platessa*, the Plaice, found from the coast of France to Iceland.

Whiting and Pollack. The fish spawn out at sea, one female cod producing as many as 9,000,000 eggs. The PLEURONECTIDAE, or flat fish, also belong here. They are fish with compressed backs and bellies, and broad sides; they habitually swim on one side, and the eye belonging to the side kept downwards is twisted on to the upper side deforming the bones of the skull. The anus is very far forward, the dorsal and ventral fins both being about equally long; the air-bladder is absent. The most valued member of this family in British water is the Sole, *Solea*, distinguished by its elongated shape. Other food-fish belonging to this family are the Flounder, the Plaice, the Turbot, the Brill, and the Dab. On the coasts of Europe and of North America is found the immense Halibut, *Hippoglossus*, which may attain a length of 6 feet and a weight of 400 pounds.

II. The *ACANTHOPTERI* are the spiny-rayed fish in which the first rays of the dorsal and ventral fins are converted into bony dermal spines. Many families of most varied structure are included in this subdivision: the two best known are the SCOMBRIDAE, including the Mackerel and the PERCIDAE or Perches. The first are distinguished by the small dorsal fin supported by spines only, followed by a long dorsal fin, the end of which is broken into finlets. In the Percidae the scales have a toothed posterior border, that is, they are ctenoid and the first spinous dorsal fin is long. The American fish called Bass belong to two families, the river-bass being one of the CENTRARCHIDAE, distinguished by high compressed body and undivided dorsal, whilst the sea-bass belongs to the SERRANIDAE, a family closely allied to the Perches.

III. The *PHARYNGOGNATHI* have the lower pharyngeal bones firmly united with one another. This division includes the LABRIDAE or Wrasses, distinguished by their thick lips and protrusible pre-maxillae, the TRIGLIDAE or Gurnards, which walk on the spines of the pelvic fin, the GOBIIDAE and many other small fish.

IV. The *LOPHOBRANCHII* are peculiar fish covered with rings of large plates; their gill processes are club-shaped instead of triangular, and are attached in tufts to the side of the clefts; there are no pelvic fins and the tail-fin is rudimentary. The jaw-bones, the pterygoid and maxilla, are elongated so as to form a long muzzle at the end of which is the tiny mouth. *Siphonostoma* is the Pipe-fish which moves slowly amongst the long green fronds of the green sea-weed *Zostera*, which it resembles, picking off minute Crustacea and Molluscs. It is common both

on the British and American coasts. *Hippocampus*, the Sea-horse, has the muzzle bent down at an angle with the rest of the body so as to present a whimsical resemblance to a horse's head. It




FIG. 228. A. The Sea-horse, *Hippocampus* sp. B. Head of the same, the operculum has been turned back to show the gills.

1. Branchial aperture. 2. Pectoral fin. 3. Dorsal fin.
4. Brood pouch. 5. Gills.

anchors itself by curving its tail round weeds, and swims slowly but with dignity by means of the dorsal fin. This genus is found in the Mediterranean and also on the more southern parts of the American coast. The Lophobranchii show a peculiar mode of caring for the young; the male has a brood pouch enclosed by two folds of skin on the under side of his body in which he carries the eggs until they are hatched.

V. The *PLECTOGNATHI* resemble the Lophobranchii in being covered with plates instead of scales and in having lost the pelvic fins. The pelvic fins are represented by spines or are entirely absent. The pre-maxilla and hyomandibular are immoveably fused to the skull, whilst the inferior pharyngeal bones remain distinct. In *Ostracion*, the trunk-fish, the plates form as compact a cuirass as the shell of an Echinus: the only flexible spots being around the articulations of the fins and the lower jaw. In *Diodon* and *Tetodon* the teeth have coalesced to form great transverse ridges of enamel, and the dermal plates bear spines which are usually directed backwards, but which are erected when

the body is rendered tense by swallowing air into the gullet and stomach. These extraordinary fish are confined to tropical waters; they haunt small crevices of the rocks, in which, when the tide retires, very small quantities of water are left, and it appears that the gills absorb oxygen from the air they swallow.

The Pisces are classified as follows :

Order 1. **Elasmobranchii.**

Pisces devoid of air-bladder or lung ; with placoid scales ; no bones developed except at the bases of these scales. Cartilaginous centra formed by the division of the notochordal sheath and not corresponding to the neural arches. The jaws slung to the skull by the second arch. No operculum : well-developed gill-sacs present.

Sub-order (1). **Selachoidei.**

Elasmobranchii of cylindrical form with well-developed tail-fin, and pectoral fins of moderate size. Spiracle small or absent.

Ex. *Carcharodon*, *Scyllium*, *Acanthias*.

Sub-order (2). **Batoidei.**

Elasmobranchii of flattened form, the tail whip-like and the tail-fin rudimentary, the pectoral fin very large and joined to the skull. Spiracle very large and opening on the dorsal surface, openings of the other gill-slits ventral.

Ex. *Raja*, *Trygon*.

Order 2. **Holocephali.**

Pisces devoid of air-bladder or lung : the skin naked, a series of slender bony rings in the unsegmented notochordal sheath, besides this no other bones. Upper jaw completely confluent with the skull. An operculum present, well-developed gill-sacs.

Ex. *Chimaera*.

Order 3. **Dipnoi.**

Pisces with a large lung, sometimes divided into two, opening by a ventrally situated glottis into the oesophagus : the atrium of the heart divided into two, the left division receiving blood from the lung only. The body is covered with thin flat scales. Membrane-bones covering the skull and roof of the mouth. Cartilage bones in the upper jaw and in the hinder region of the skull, but the notochordal sheath is undivided. The upper jaw completely fused with the skull. An operculum present, the septa between the gill-sacs reduced so that they become gill-slits.

Ex. *Ceratodus*, *Lepidosiren*, *Protopterus*.

Sub-order 1. **Crossopterygii.**

Teleostomi in which the pectoral and pelvic fins have the form of a lobe covered with scales fringed anteriorly and posteriorly with fin-rays. The air-bladder is bilobed and its opening is ventral. The scales are rhomboidal and covered with enamel.

Ex. *Polypterus*.

Sub-order 2. **Actinopterygii.**

Teleostomi in which the paired fins bear rays only on their posterior borders and in which the base of the fin is never covered with scales. The opening of the air-bladder is dorsal.

Division A. **GANOIDEI.**

Actinopterygii which retain the optic chiasma, several rows of valves in the conus arteriosus and a spiral valve in the intestine. A heterocercal tail.

Subdivision (1) *Chondrostei.*

Actinopterygii clothed with large bony plates which pass uninterruptedly into the membrane-bones of the head, the notochordal sheath undivided! very few cartilage bones. A long snout projecting in front of the mouth. Teeth rudimentary.

Ex. *Acipenser*.

Subdivision (2) *Halecomorphi*.

Actinopterygii with thin scales: many cartilage bones and the notochordal sheath surrounded by well-formed amphicoelous vertebrae. Mouth terminal.

Ex. *Ania*.

Family (3) *Lepidosteidae*.

Actinopterygii with rhomboidal scales covered with enamel: the skull completely ossified and the vertebrae opisthocelous. Jaws very much elongated, each carrying a row of long teeth.

Ex. *Lepidosteus*.

Division B. TELEOSTEI.

Actinopterygii in which the optic nerves cross without intermingling, the conus is absorbed into the ventricle, leaving one row of valves. No spiral valve in the intestine. A homocercal tail.

Section 1. *Physostomi*.

Teleostei which retain the opening of the air-bladder into the alimentary canal: the pelvic fins are abdominal in position.

Family (1) *Siluridae*.

Physostomi with a skin naked or covered with bony plates: the skull unconstricted between the orbits, maxilla without teeth, bearing a long barbel.

Ex. *Amiurus*, *Ictalurus*.

Family (2) *Anguillidae*.

Physostomi devoid of scales, skull not constricted between orbits. No reproductive ducts. A continuous dorsal-caudal-anal fin.

Ex. *Echelus*, *Anguilla*.

Family (3) *Salmonidae*.

Physostomi with thin scales, the skull constricted between the orbits, the maxilla forming part of the edge of the jaw and bearing teeth. A small soft dorsal fin behind the main dorsal.

Ex. *Salmo*, *Salvelinus*, *Oncorhynchus*.

Family (4) *Clupeidae*.

Physostomi in most points resembling the last family; the maxilla consists of several pieces, and there is no soft dorsal fin.

Ex. *Clupea*.

Family (5) *Cyprinidae*.

Physostomi in which the maxilla is toothless and buried in the cheek membrane.

Ex. *Cyprinus*.

Section 2. **Physoclisti.**

The remaining sections of the Teleostei have lost the opening of the air-bladder into the alimentary canal. This organ becomes a closed vesicle.

Sub-section 1. **Anacanthini.**

Teleostei in which the fin-rays are all soft and flexible, and the pelvic fins are shifted forward anterior to the pectorals.

Family (1) *Gadidae*.

Anacanthini of symmetrical shape not especially compressed.

Ex. *Gadus*.

Family (2) *Pleuronectidae*.

Anacanthini very much compressed laterally, which swim always on one side: the eye belonging to the lower side being rotated on to the upper side.

Ex. *Solea*, *Platessa*, *Hippoglossus*.

Sub-section 2. **Acanthopteri.**

Teleostei in which some at least of the fin-rays of the median fins are hard and unjointed.

Family (1) *Scombridae*.

Elongated Acanthopteri in which there is short spinous dorsal fin followed by a long softer one, the hinder portion of which is broken up into finlets.

Ex. *Scomber*.

Family (2) *Percidae*.

Short stout Acanthopteri with one long dorsal fin followed by a short one and having a toothed posterior border to the scales.

Ex. *Perca*.

Family (3) *Serranidae* (Sea Bass).

Closely allied to the *Percidae*, but distinguished by having the dorsal fin undivided. Teeth large and numerous, a large pseudobranch.

Family (3) *Centrarchidae* (River Bass).

Acanthopteri which have a laterally compressed body and undivided dorsal fin. Teeth small, a small pseudobranch.

Sub-section 3. *Pharyngognathi*.

Teleostei in which the bones (rudimentary fifth gill-arches) bearing the pharyngeal teeth are firmly united together.

Ex. *Labrus*.

Sub-section 4. *Lophobranchii*.

Teleostei covered with bony plates, the facial bones elongated so that the jaws are at the end of a tube-like proboscis. The branchial processes are arranged in tufts and thickened at their free ends. The pelvic fins absent.

Ex. *Syngnathus*, *Hippocampus*.

Sub-section 5. *Plectognathi*.

Teleostei covered with bony plates, the pre-maxilla and hyomandibular immoveably joined to the skull. The gills normal. Pelvic fins absent or represented by spines.

Ex. *Ostracion*, *Diodon*, *Tetrodon*.

CHAPTER XVI.

SUB-PHYLUM IV. CRANIATA.

Class II. AMPHIBIA.

THE class Amphibia includes the familiar frogs and toads, the less-known newts and salamanders, and some very curious worm-like tropical forms which burrow in the earth. The name means double life (Gr. ἀμφί, double; βίος, manner of living), and refers to the fact that all the typical members of the class commence their lives as fish-like larvae, breathing by gills, and afterwards become converted into land animals, breathing by lungs. This strongly marked larval type of development is one of the great distinctions between the Amphibia and the only other class of Vertebrata with which they could be confounded, viz., the Reptiles. In the Reptiles, as in the Birds, a large egg abundantly provided with nutritive material is produced, and the young animal practically completes its development within the egg-shell and is born in a condition differing from the adult chiefly in size.

It might at first sight be thought that the fact that Amphibia breathe air in their later life and live on land would be sufficient to mark them off from the fish. But we have already seen that one order of fish—the Dipnoi—possess lungs and breathe air, and on the other hand some Amphibia retain gills throughout life and rarely if ever leave the water.

The unbridged gap between true fish and Amphibia is to be found, not in the breathing organ but in the structure of the limb. Fish possess fins—median and paired—which are in both cases supported by horny rays, as well as an internal skeleton; and the paired fins have an internal skeleton which has the form of a jointed axis bearing similar rays on one or both sides (Figs. 205 and 215).

The Amphibian limb, on the other hand, is what is known as a pentadactyle limb; that is to say, it is constructed on the familiar type of the human limb, and the median fin when present has no fin rays (Figs. 229 and 231).

The pentadactyle or five-fingered limb (Gr. *πέντε*, five; *δάκτυλος*, a finger), also called the cheiropterygium (Gr. *χείρ*, a hand; *πτερύγιον*, little wing, hence, an appendage), consists of three segments, a proximal, containing one long bone; a middle, containing two bones placed side by side and occasionally fused into one; and a distal, containing a series of small squarish bones arranged in lines so as to give rise to a series of diverging rays; the last-mentioned constitute the skeleton of the fingers and toes. In the proximal part of this lowest segment the bones are much crowded together and the rays tend to coalesce: this part has received a special name, as has also the portion where the rays although separate are embedded in the same muscular mass.

The fore-limb is called the arm, and its divisions the brachium or upper arm, the ante-brachium or fore-arm, and the manus or hand (B, Fig. 229). The hind limb is the leg, and its divisions are the femur or thigh, the crus or shank, and the pes or foot (A, Fig. 229).

The manus is divided into three regions, viz.: (a) the carpus or wrist where the rays tend to coalesce; (b) the metacarpus or palm where the rays although separate are bound together by flesh and skin; (c) the digits or free ends of the rays. The pes is similarly divided into tarsus or ankle, metatarsus or sole, and digits or toes.

The bone of the brachium is called the humerus, that of the femur bears the same name as the segment to which it belongs;




FIG. 229. A. A skeleton of a right posterior, and B of a right anterior limb of a Newt, *Molge cristata* $\times 1\frac{1}{2}$.

1. Femur. 2. Tibia. 3. Fibula.
4. Tibiale. 5. Intermedium. 6. Fibulare.
7. Centrale of tarsus. 8. Tarsale 1.
9. Tarsalia 4 and 5 fused. I. II. III. IV. V. Digits.
10. Humerus. 11. Radius.
12. Ulna. 13. Radiale. 14. Intermedium and ulnare fused.
15. Centrale of carpus, the pointing line passes across carpal 2.
16. Carpal 3. 17. Carpal 5.

those of the ante-brachium are called radius and ulna, those of the crus tibia and fibula (Fig. 229).

The skeletons of the pes and manus are typically exactly the same. Situated proximally close to the middle segment of the limb is a transverse row of three small bones, the central one being called the intermedium in both limbs, whilst the outer and inner are named after the bones of the middle segment of the limb adjacent to them. Thus we find in the wrist a radiale and ulnare and in the ankle a tibiale and fibiale. Beyond this row of bones there is a single central bone which probably belongs to the middle ray, and beyond it a row of five small bones corresponding to the digits. This last row are denominated carpalia in the wrist and tarsalia in the ankle. The individual bones are called carpale (or tarsale) 1—5 in accordance with the digits opposite which they are situated.

In almost every case this typical skeleton of nine bones has undergone some modification, owing either to the absence of some bones or the fusion of others, but in the hind-limb of the lower Amphibia it is exactly typical. In the higher Amphibia not only has great reduction of the elements taken place but the radius and ulna in the fore-limb and the tibia and fibula in the hind-limb have coalesced, a groove only being left to show their primitive distinct-

The primitive position of the limbs with reference to the trunk is, from the study of development, assumed to be one in which they are stretched out at right angles to it, with the inner surface of the hand and the sole of the foot directed ventrally and in such a position that a line joining the tips of the fingers is parallel to the long axis of the body. If we suppose an imaginary line or axis to run down the centre of each limb, we shall be able to distinguish a pre-axial from a post-axial side. In the lower Amphibia the only change from this position that has taken place in the hind-limb is that each segment of the limb is bent at right angles on the one which follows it. The fore-limb is bent similarly, but it is also rotated backwards so that its upper segment is almost parallel to the axis of the body, and the elbow points backwards. If this position were maintained the first digit would become external; but the manus in most cases is at the same time twisted forwards so that the lower end of the radius lies internal to that of the ulna, and the radius thus crosses the ulna in its course. In the higher Vertebrata this twisting can be undone and the hand reverts to

an untwisted position. This movement is known as supination, the reverse movement being known as pronation.

The hind-limb in the higher Amphibia and other Vertebrata is likewise rotated forward so that the knee points forward and the first digit is internal, but this does not occur in the lower Amphibia, such as *Molge*.

The pectoral girdle is not essentially different in the lower Amphibia and the more primitive Teleostomi, but the pelvic girdle is firmly joined to the transverse process of one of the vertebrae, which is called the sacral. This is one of the most distinctive features of all pentadactyle animals; it is a consequence of the adaptation of the pentadactyle limb to raise the body from the ground (Fig. 230). It is necessary for this purpose that the limb should have a firm purchase on the axial skeleton. Consequently when we find some Amphibia which never use their limbs for crawling but only for swimming, we may be assured that this is a secondary degenerate condition.

Next to the character of the limb one of the most distinctive features of Amphibia is the nature of the skin. Indeed the five great classes of Gnathostomata—Fish, Amphibia, Reptiles, Birds, and Mammals—are each perfectly characterised by the nature of their skin. In a typical Amphibian the skin is soft and moist and devoid altogether of any ossifications like the scales of fish. The skin is a most important breathing organ, since the lung alone cannot meet the demand for oxygen, and if the skin becomes dry and consequently incapable of absorbing oxygen the animal dies. The necessary moisture is supplied from a series of pockets, to form which the ectoderm is pouched inwards—or to use a more convenient term ‘invaginated’—at various points, and the cells lining these pouches have the power of secreting great quantities of mucus. As the cells become




FIG. 230. Skeleton of Triton, *Molge cristata* $\times 1$.

The skull always articulates by two pegs—the exoccipital condyles—with the first vertebra (Fig. 232). It is remarkable for its extremely flattened shape; the jaws are widely bent outwards so that the large eyes in no way compress the cranium, which is thus evenly cylindrical. Both membrane- and cartilage-bones are present, but the ossification is by no means complete. The exact arrangement of the bones will be given when the type is studied.

The vertebrae are either procoelous (Gr. *πρό*, in front; *κοῖλος*, hollow), or opisthocelous (Gr. *ὀπισθο-*, behind), that is to say either concave in front and convex behind, or *vice versá*, and the arrangement may differ in allied genera.

The vertebrae articulate with one another, not only by the centra but also by facets called zygapophyses (Gr. *ζυγόν*, a yoke), on the sides of the neural arches. The anterior facets, pre-zygapophyses, look upwards and are covered by the posterior facets or post-zygapophyses of the vertebra in front which look downwards.

The circulatory system closely resembles that of the Dipnoi. The atrium is divided into two auricles and the blood from the lungs returns direct to the left auricle by the pulmonary veins. A median vein, the inferior cava, returns the blood from the kidneys directly into the sinus venosus, receiving in its course the hepatic vein. The anterior portions of the posterior cardinals are much reduced in size and may be altogether absent.

The lungs open by a common stem, the laryngeal chamber, into the throat. The opening is called the glottis, and its sides are stiffened with cartilage.

The kidneys and reproductive organs show essentially the same arrangement as in the Elasmobranchs, the kidney being divided into a sexual part connected with the testis and a posterior non-sexual part. There is one opening for all discharges, the cloaca.

The ventral wall of the cloaca, however, is produced outwards

into a great thin-walled sac, the allantoic bladder, in which when the cloaca is closed the urine accumulates. This organ acquires immense importance in the development of the higher animals and is found in no fish.

In the larva, which is to all intents and purposes a fish, there are present those peculiar sense organs called mucous canals, supplied by the 5th and 10th nerves, but these are usually lost in the adult.

Living Amphibia are divided into three well-marked orders, viz.

the URODELA, the ANURA, and the GYMNOPTERON.
 Classification. The URODELA (Gr. οὐρά, tail; δῆλος, conspicuous) have long cylindrical bodies and long, flattened tails. The limbs are short and comparatively feeble, barely strong enough to lift the belly from the ground. Both pairs of limbs are about equal in size. The ANURA (Gr. ἀν-, no; οὐρά, tail) have much broader and shorter bodies; the tail is totally lost and the hind limbs are powerfully developed and adapted for jumping. The GYMNOPTERON (Gr. γυμνός, naked; ὄφις, snake) have lost both pairs of limbs and their cylindrical bodies give them a worm-like appearance; their habits heighten the resemblance since they burrow in moist earth. They have embedded in the skin small bony plates, relics of the scales which their fish-like ancestors once possessed. The tail has in these animals almost disappeared.

In the Carboniferous rocks the remains of a large number of Amphibia have been found which have been called STEGOCEPHALA (Gr. στέγω, to cover; κεφαλή, the head) from the circumstance that the head is covered with a compact mosaic of membrane-bones extending from the mid-dorsal line of the cranium outwards to the lips. Similar small bones or scales are found on the ventral surface. These features were no doubt inherited from the ancestral Dipnoan or Crossopterygian fish, from which Amphibia are probably descended, and the small scales of the Gymnopteron are the last remnants of this armature. Stegocephala include both long and short-tailed forms, and whilst some of their descendants—the Labyrinthodonta—became highly specialized in the structure of their teeth and died out in the next geological period, others, in all probability, gave rise to modern Amphibia.

URODELA.

Returning to the Urodela, which are the most primitive of modern Amphibia, we find that in Great Britain they are represented

by three species, all belonging to the genus *Molge* (*Triton*) and popularly known as eft or newts. *Molge cristata*, the warty eft, and *Molge vulgaris*, the common eft, are found in ponds and ditches all over the country, but *Molge palmata* is much more local. We may select *Molge cristata*, the greater or warty eft, or crested newt, as a type of the anatomy of Urodela (Fig. 231).




FIG. 231. *Molge cristata*, the Warty Eft. From Gadow.

1. Female. 2. Male at the breeding season with the frills well developed.

The animal is about five or six inches long, half the length being made up of the tail, which has a continuous fringe of skin, the median fin. This fin in the male extends forwards to the head dorsally and is greatly enlarged in the breeding season, but it is at all times devoid of fin rays.

The skin is clammy, owing to the secretion of the dermal glands: it is dark coloured above and yellow spotted with black below. The opening of the cloaca is placed behind the hind legs: it is a longitudinally placed oval slit which in the male has thickened lips.

The fore-limbs have only four fingers, the outermost corresponding to the human little finger being wanting, but there are five toes in the hind-limb. The animal when out of water crawls feebly along, but it swims actively in the water by means of its vertically flattened tail. The head is flattened dorso-ventrally and of somewhat oval outline, and the gape is of moderate extent. The eyes are of a fair size and project a little. The nostrils are very small and situated at the extreme front end of the snout.

If the newt be carefully watched when out of the water the skin of the under side of the head between the two sides of the lower jaw will be seen to throb at regular intervals, being alternately puffed out and drawn in. It can be further seen that the nostrils are closed when the skin is drawn in and opened when it is puffed out. These movements constitute the mechanism of breathing in the newt. As in the case of the Dipnoi, each nasal sac communicates with the interior of the mouth by an opening called the choana or internal naris, and the air passes through this from the nostril when the cavity of the mouth is enlarged. When the cavity of the mouth is compressed the nostril is closed by a flap of skin constituting a valve, and the air is forced through the open glottis into the lung, whence it is forced out again by the elastic recoil when the pressure is removed.

If the animal be laid on a board with the ventral side uppermost and skinned, a thin sheet of muscles, the mylo-hyoid will be seen stretching between the two halves of the lower jaw. When this muscle is relaxed the floor of the mouth is arched upwards and the under side of the head consequently becomes concave. When the muscle contracts and straightens the cavity of the mouth enlarges and air is drawn in. Above the mylo-hyoid (underneath from the point of view of the dissection) are two longitudinal muscular bands, and in these are embedded the reduced remains of the visceral arches to which the gills of the larva were attached (Fig. 233). These muscles are called genio-hyoid in front of the arches, sterno-hyoid between them and the pectoral girdle, and they are continued backwards along the belly as the straight muscles of the abdomen, the recti abdominis.

These sterno-hyoid muscles can draw the visceral arches downwards and backwards and probably assist the mylo-hyoid in depressing the floor of the mouth. The genio-hyoid muscle on the contrary pulls the arches forwards and helps to restore them and the floor of the mouth with them to their old position. In this action muscles called petro-hyoid, which run from the arches to the middle line of the back, also take part. These muscles are representatives of the levatores arcuum of fish, and they raise the arches and consequently the floor of the mouth.

The glottis or opening into the lungs is stiffened at the sides by a pair of cartilages, which it seems probable are the remains of a hinder pair of visceral arches: and these cartilages have similar raising muscles to those of the arches. Hence the same muscular

action which lifts the floor of the mouth opens the glottis and admits air into the lungs.

The remaining muscles of the body are not much altered from those of the fish. In the tail and the ventral part of the trunk there are V-shaped myotomes, but this arrangement is disturbed in the neighbourhood of the limbs.

Turning now to the skeleton we find that the vertebrae are procoelous, and bear stout transverse processes to which are articulated short ribs (Fig. 230). The ribs borne by the sacral vertebra are expanded in accordance with the strain put on them by the attachment of the ilium. In the tail the centra are composed of all four pieces, basi-dorsal, basi-ventral, inter-dorsal, and inter-ventral (see p. 378); the joint between two vertebrae passing through the middle of the inter-dorsal and inter-ventral pieces. In the trunk the only difference is that the basi-ventral is almost suppressed, and the rib which is the distal portion of the haemal arch is thus deprived of most of its original support. To compensate for this it acquires a new attachment to the side of the neural arch, which is drawn out into a transverse process to meet it. This transverse process is to be distinguished from the similarly named outgrowth in fish, which is part of the haemal arch. The proximal end of the rib is called the capitulum, and its original attachment to the basi-ventral, which is only the proximal part of the haemal arch, is called the capitular attachment. The facet with which it joins the transverse process is called the tuberculum, and this attachment the tubercular attachment. If the skeleton of one of the larger Urodela be examined the ribs can be seen to be borne by broad outgrowths from the centra. In these outgrowths the tubercular and capitular parts can be distinguished as bars of bone which are united by a thin web of bone. Owing to the weakness of the basi-ventral and its outgrowths, the capitulum or head of the rib appears to extend further inwards towards the centrum than the tuberculum. The haemal arches of the tail are, like the ribs, outgrowths of the basi-ventral, but they do not exactly correspond to the ribs, for they are placed nearer the middle line.

In the skull the cranium is cylindrical, being quite uncompresssed between the eyes. The bones of the jaws and face are widely arched outwards, so that the whole skull has a flattened shape. The nasal and auditory capsules form easily recognizable buttresses projecting from the cranium.

In both the floor and roof of the cartilaginous cranium the

proper wall is largely deficient. The deficiency of the roof is the anterior fontanelle, in the floor the greatly enlarged pituitary fossa. But these deficiencies are not seen in the uninjured skull; because the hole in the roof is closed in by two pairs of membrane-bones, the frontals and the parietals, and that in the floor is underlain by a broad parasphenoid membrane-bone (Fig. 232).




FIG. 232. A dorsal, B ventral, and C lateral views of the skull of a Newt, *Molge cristata* $\times 2\frac{1}{2}$. After Parker.

The cartilage is dotted, the cartilage bones are marked with dots and dashes, the membrane bones are left white.

- | | | | |
|------------------------------|---|--|---|
| 1. Premaxilla. | 2. Anterior nares. | 3. Posterior nares. | 4. Nasal. |
| 5. Frontal. | 6. Parietal. | 7. Prefrontal. | 8. Maxilla. |
| 9. Fused vomer and palatine. | 10. Parasphenoid. | 11. Orbitosphenoid. | |
| 12. Pterygoid. | 13. Squamosal. | 14. Pro-otic region of fused exoccipital and pro-otic. | 15. Quadrate. |
| 16. Quadrate cartilage. | 17. Exoccipital region of fused exoccipital and pro-otic. | 18. Articular. | |
| 19. Articular cartilage. | 20. Dentary. | 21. Splenial. | 22. Middle narial passage, a cleft in the cartilage of the snout filled with connective tissue. |
- II. V. VII. IX. X. Foramina for the exit of cranial nerves.

Only at its extreme front and hind ends is the wall of the cranium converted into cartilage-bone. In front there is on each side an orbito-sphenoid bone, in the side wall, extending into the roof and floor and ossifying also the hind wall of the nasal sac; behind, two exoccipital bones are placed at the sides of the foramen magnum,

which they nearly encircle (Fig. 232). These bones bear the two condyles, so characteristic of Amphibia, for articulation with the vertebral column.

The first visceral arch, which constitutes the cartilaginous jaws, remains entirely cartilaginous. It consists of an upper part immovably attached to the skull, corresponding to the pterygo-quadrato bar or upper jaw of Fish, and a lower part, Meckel's cartilage, forming the basis of the lower jaw. It will thus be seen that Amphibia, like Holocephali and Dipnoi, are autostylic. The same is true of all the higher groups of the Craniata. The upper jaw consists of two regions, the suspensorium which is fused with the skull and to which the lower jaw is attached, and the pterygoid




FIG. 233. Visceral arches of *Molge cristata*. The ossified parts are slightly shaded, the cartilage is white. From Parker.

2. Hyoid arch. 3. First branchial arch. 4. Second branchial arch. 8. Copula, i.e. the median piece connecting successive arches.

process, a spur of cartilage which runs forward towards the nasal capsule. Both suspensorium and the articular end of Meckel's cartilage are slightly calcified. They are denominated quadrate and articular in Fig. 232, but there is no true bone present in either case. The front of the auditory capsule is ossified by a large bone, the pro-otic, which in fully adult specimens becomes confluent with the exoccipital. The hinder visceral arches in the adult are present in a very degenerate condition. Traces of three remain (Fig. 233).

It is usual to speak of the hinder visceral arches of Amphibia and higher Vertebrata as the hyoid apparatus,

or simply as the hyoid. The name suggests a misleading comparison with the second visceral arch of Fish; it is distinctly to be remembered that the hyoid bone of even Man contains more than this second arch; a good definition of the hyoid of Amphibia and higher animals would be "the degenerate remains of the hinder visceral arches."

Turning now to the membrane-bones of the skull, we find that it is roofed by three pairs, viz., the nasals, frontals, and parietals. The nasals of course roof in the nasal sacs. In the palâte there is one median bone, the parasphenoid, and three pairs of lateral bones, viz. the vomers in front of the posterior nares, the palatines fused with them and running along the edges of the

parasphenoid, and lastly the pterygoids underlying the pterygoid process. Some of these bones are actually built up by the fusion of the bases of minute conical teeth in the larva. The vomers and palatines retain their teeth in the adult, whilst the parasphenoid loses them.

The upper lip has tooth-bearing pre-maxillary and maxillary bones developed, the lower has a dentary on the outside of Meckel's cartilage and a splenial on the inner. Above the maxilla there is a small pre-frontal bone.

If we examine the skeleton of the limbs we find that the pectoral girdle consists of two plates of cartilage which slightly overlap in the mid-ventral line. The lower half of each is forked, the forks being called precoracoid and coracoid respectively. The centre of each half of the girdle has a hollow termed the glenoid cavity for the articulation of the arm. All around the glenoid cavity the girdle is converted into bone; there is a bone termed the scapula above, and a coracoid bone below. The unossified part of the coracoid is simply termed the coracoid cartilage. The upper part of the girdle dorsal to the scapular bone is called the supra-scapula. It remains cartilaginous, but is often calcified. The two coracoids are fastened behind to a small median cartilage called the sternum. The meaning of this is discussed later.

The manus has only four fingers, the little finger and the corresponding small bone in the wrist or carpus having disappeared




FIG. 234. A, ventral, and B, lateral view of the shoulder girdle and sternum of an old male Crested Newt, *Molge cristata* $\times 3$. After Parker.

1. Scapula. 2. Supra-scapula. 3. Coracoid. 4. Glenoid cavity. 5. Precoracoid. 6. Sternum.




FIG. 235. A, Right antebra-chium and Manus of a larval Salamander, *Salamandra maculosa*. After Gegenbaur.

B, Right Tarsus and adjoining Bones of *Molge sp.* After Gegenbaur.

1. Radius. 2. Ulna. 3. Radiale. 4. Intermedium. 5. Ulnare. 6. Centrale. 7. Carpale 2. 8. Carpale 3. 9. Carpale 4. 10. Carpale 5. 11. Tibia. 12. Fibula. 13. Tibiale. 14. Intermedium. 15. Fibulare. 16. Centrale. 17. Tarsale 1. 18. Tarsalia 4 and 5 fused. I. II. III. IV. V. Digits.

The pelvic girdle on each side is firmly joined to the rib of the sacral vertebra, and the two halves meet in the mid-ventral line. The upper part of the girdle above the cavity for articulation of the thigh is a bone, the ilium; below this cavity, which is termed the acetabulum, there is a so-called "ischiopubic" cartilage, in the hinder part of which a small bone, the ischium, is developed. In the mid-ventral line, in front of the union of the two halves of the pelvic girdle, there is a forked piece of cartilage, the epipubis (Fig. 236). In the pes the only departure from the typical arrangement is the fusion of the tarsalia 4 and 5.

If the muscles be carefully cut through in the middle line and reflected, the body

Viscera.

cavity and the organs contained therein will be exposed. In general the difference from the arrangement of the organs in a dog-fish is only in the relative size of the organs, in a word, in details.




FIG. 236. Pelvic girdle of *Molge cristata* from below $\times 4$.

1. Pre-pubic process. 2. Ischiopubic cartilage. 3. Ilium. 4. Ischium.

The alimentary canal is thrown into a number of loops. The oesophagus is not in any way sharply marked off from the stomach, and the latter is nearly straight, extending only a short way round the bend of the first loop. There is a well-marked large intestine or rectum, ventral to which lies the bladder. The spleen is an oval red body lying at the side of the stomach attached to the mesentery. The ducts of the

pancreas and liver coalesce into the intestine.

The newt feeds on small worms and aquatic insects, which it




FIG. 237. A male *Molge cristata* cut open so as to expose the internal organs, about natural size.

- | | |
|---|--------------------------------|
| 1. Mylo-hyoid muscle with genio-hyoid underneath. | 2. Conus arteriosus. |
| 3. Ventricle. | 4. Auricle. |
| 5. Sinus venosus. | 6. Carotid arch. |
| 7. Systemic arch. | 8. Pulmonary artery. |
| 9. Anterior vena cava of left side. | 10. Coracoids pulled outwards. |
| 11. Liver. | 12. Gall-bladder. |
| 13. Lung. | 14. Spleen. |
| 15. Stomach. | 16. Intestine. |
| 17. Rectum. | 18. Allantoic bladder. |
| 19. Fat-body. | 20. Testes. |
| 21. Anterior abdominal vein, displaced. | 22. Kidney with duct. |
| 23. Pancreas. | |

seizes with its jaws. Both upper and lower jaws are armed with minute teeth, and there are in addition two longitudinal rows of teeth on the roof of the mouth borne by the conjoined vomer and palatine on each side. The function of these teeth is not so much to crush as to retain a hold of the prey, which is swallowed whole. The tongue is a circular cushion on the floor of the mouth, supported by the second visceral arch. Its hinder edge is partially free. The lungs are long, narrow, smooth-walled, tube-like sacs, attached to the liver and other organs at their base, but their tips float freely in the body-cavity.

The heart lies far forward, between the roots of the lungs, enclosed in the pericardium. Externally all the four divisions of the piscine heart are visible, viz., sinus venosus, atrium, ventricle, conus. The venous system is essentially that of the dog-fish, only the veins are indicated by names borrowed from human anatomy. Thus the blood from the head is returned by two internal jugular veins, representing the anterior cardinals of the fish. These are joined by external jugulars from the superficial part of the throat and face, corresponding to the sub-branchial veins and by a sub-clavian vein from each arm. The common trunk formed by the union of all three is, of course, the Ductus Cuvieri, but it is called the superior vena cava, and it receives on each side close to the middle line a posterior cardinal vein. As in fish, this vein in its course filters through the kidney, and along the outer edge of the kidney, its posterior portion, the renal portal, may be made out. The two renal portals when followed further back are found to coalesce in the caudal vein which returns the blood from the tail: each receives a sciatic vein from the dorsal side of the leg joined by a femoral from the ventral surface of the limb.

The increased importance of the hind limb has brought with it this increase in the vessels draining it, which is represented only by the small pelvic vein in fish.

There are certain vessels, however, unrepresented in any fish except the Dipnoi. These are: first, the pulmonary veins, which receive the blood from the lungs and open directly into the left side of the atrium, which is separated from the rest by a septum and constitutes the left auricle; secondly, the inferior vena cava, a large trunk situated in the median dorsal line just beneath the aorta, which receives most of the blood that has traversed the kidneys and conveys it into the sinus venosus just between the

openings of the two superior venae cavae. The inferior cava coalesces with the hepatic veins returning blood from the liver: these thus lose their independent openings into the sinus venosus which they had in the Dog-fish. In its hindermost portion between the kidneys the vena cava joins the posterior cardinal.

So far the peculiarities of the Newt are shared by the Dipnoi: but there remain two veins highly characteristic of Amphibia. The musculo-cutaneous vein receives blood from the skin and pours it into the subclavian; we have already seen that the skin is a very important breathing organ, and this vein returns the blood, which has been oxygenated in the skin, to the heart. The anterior abdominal vein arises on the ventral side of the body near the cloaca from the union of two forks given off by the femoral veins; it runs forward in the mid-ventral line, eventually joining branches of the portal vein and entering the liver. This vein is found also in the lower Reptiles, and in the embryos of Mammalia, where it is of the utmost importance in both nutrition and respiration.

When the veins are cut away it is possible to follow out the arteries. There is no ventral aorta, since on each side three arterial arches arise in a bunch from the front end of the tubular conus. The first of these arches is called the carotid arch, and (as in Dipnoi) it no longer opens into the dorsal aorta, but after giving off a lingual artery which supplies the ventral side of the throat, it passes up round the gullet, to which it gives some twigs, and continuing as the common carotid supplies the upper part of the head and the




FIG. 238. Diagram to show arrangement of the principal Veins of an Urodele.

1. Sinus venosus, gradually disappearing in the higher forms.
2. Ductus Cuvieri = superior vena cava.
3. Internal jugular = anterior cardinal sinus.
4. External jugular = sub-brachial.
5. Subclavian.
6. Posterior cardinal, front part.
7. Inferior vena cava.
8. Renal portal = hinder part of posterior cardinal.
9. Caudal.
10. Sciatic.
11. Femoral.
12. Anterior abdominal.

brain. Just after giving off the lingual artery, the arch swells up into a little knot, called the carotid gland. In this structure the channel of the artery is broken up into a network of fine passages and its function is believed to be that of holding back the blood from entering the head until, at the close of the contraction of the ventricle, the blood has returned from the lungs. The second arch supplies most of the blood to the root of the dorsal aorta, and on this account is called the systemic arch. The hinder-




FIG. 239. Diagram of Arterial Arch of *Molge* viewed from the ventral aspect.

- I. First arterial arch. II. Second arterial arch. III. Third arterial arch. IV. Fourth arterial arch. 15. Pulmonary artery. 16. Dorsal aorta.

most two pairs of arches unite on each side into one trunk, which passing round the gullet joins the root of the dorsal aorta. From the hindermost arch is given off the pulmonary artery which supplies the lung. On this account it is termed the pulmonary arch. Where the two roots of the aorta join a large branch is given off on either side to the other breathing organ, the skin, which is known as the cutaneous artery. In the larva of *Molge* there are on each side four arterial arches, of which the third disappears whilst the fourth persists as the apparent third in the adult. In the allied genus *Salumandra* all four arches persist.

It is comparatively easy to uncover the brain and spinal cord of the newt owing to the thinness of the bones which cover them. The cerebral hemispheres are long and cylindrical, and devoid of any other connection with one another than that by way of the thalamencephalon; through the thin roof of the latter two thickenings in its floor, the optic thalami, can be clearly seen. The mid-brain is a simple smooth vesicle, and the cerebellum is a slight inconspicuous transverse band (Fig. 241).

The word olfactory lobe is in Amphibia and higher animals

Nervous
system.

generally used in a different sense from that in which it is used in the case of Fish. In the latter case a stalk arises from the extreme anterior end of the hemisphere, which swells out into a rounded mass, the olfactory lobe, which is in immediate contact with the nasal sac. In Amphibia a similar stalk is given off from the fore-brain but it does not swell into a bulb; on the contrary, it gives off a brush of nerves to the nasal sac. The term olfactory lobe is applied in the Amphibia to denote the extreme anterior end of the cerebral hemisphere, which is marked off by a slight groove from the rest.

The course of the cranial nerves is substantially the same as in the Dogfish; owing, however, to the loss of the gills and the mucous canals in the adult, the branches are simplified. The 9th or glossopharyngeal, as its name implies, is distributed to the pharynx and tongue. The vagus supplies the larynx and glottis, but its main stem runs on to the heart and stomach.

The first spinal nerve comes out from behind the first vertebra and is called the hypoglossal; it runs directly to the respiratory muscle, the mylo-hyoid, crossing the vagus and glossopharyngeal in its course. At the sides of the dorsal aorta the two chains of sympathetic ganglia can be made out, connected by cross branches with the spinal nerves.

To turn now to the excretory system, the kidney can be seen when the alimentary canal is removed. It is a long narrow strip on each side adjacent to the aorta. In front it tapers to the merest thread, but behind, close to the cloaca,

Urino-genital organs.




FIG. 240. Brain of Triton, *Molge cristata* \times about 8.

1. Olfactory nerves, representing the olfactory lobes of the Dogfish.
2. Olfactory lobes.
3. Cerebral hemisphere.
4. Thin roof of thalamencephalon.
5. Optic thalami.
6. Pineal body.
7. Mid-brain.
8. Cerebellum.
9. Medulla oblongata. From Burekhardt.

it thickens somewhat. Along its outer edge runs the archinephric duct, and external to the archinephric duct is situated the long oviduct.

The tubules which compose the kidney retain throughout life the ciliated openings into the body-cavity, and if the narrow part of the kidney be cut off and mounted in a little salt solution it is possible, at least in small specimens, under a low power of the microscope, to see the funnels and to observe the whirlpools due to the currents produced by their cilia.

The genital gland in both sexes is represented by a pair of ridges suspended to the inner edges of the front parts of the kidney by slings of peritoneum similar to the mesentery suspending the gut, and on this account called mesenteries. In the female the oviduct opens by a ciliated funnel adjoining the root of the lung. The funnel leads into a long convoluted tube running back to open into the cloaca. The testis, which takes the form of two conical bodies with their broad ends apposed, or sometimes a row of three rounded lobes, communicates by a number of vasa efferentia with the anterior part of the kidney, which is on this account termed the sexual portion or mesonephros. In the male the kidney tubules belonging to the hinder larger non-sexual portion, or metanephros, are split off from the archinephric duct and unite into an exceedingly short common




FIG. 241. Urino-genital organs of a Female *Molge cristata* \times about 5.

1. Ovary. 2. Remnant of vasa efferentia. 3. Remnant of longitudinal canal connecting the vasa efferentia. 4. Sexual portion of kidney. 5. Archinephric duct. 6. Oviduct. 7. Posterior non-sexual portion of kidney. 8. Opening of archinephric duct. 11. Internal opening of oviduct. 12. Suspensory ligament. 13. External opening of oviduct.

trunk, the ureter, which has an independent opening into the cloaca.

It has been stated above that the genital glands are a pair of ridges. In the larva the inner portions of the ridges degenerate, the cells becoming largely converted into fat-bodies. In the adult these fat-bodies appear running parallel to the genital organs on the inner side. They serve as a store of nourishment for the eggs which develop during the winter-sleep. The Newt, like other Amphibia, passes the winter buried in the mud at the bottom of ponds and takes no food. The conversion of some of the possible eggs into fat to feed the rest is simply an example of the same principle as the sacrifice of some of the dogs in an Arctic expedition to feed the rest.

The development of *Molge*

Larva.

is interesting. The male emits the spermatozoa in a bundle which the female then introduces into her cloaca, and the eggs commence their development in the body of the mother. Soon afterwards they are laid and attached to water plants. After some time larvae are

hatched out which in many respects resemble fish. They are provided with three long feathery appendages on each side of the neck, in which there is an active circulation, and rich blood supply.




FIG. 242. Urino-genital organs of a Male *Molge cristata* \times about 5.

1. Testes. 2. Vasa efferentia. 3. Longitudinal canal connecting the vasa efferentia. 4. Sexual portion of kidney showing nephrostomes. 5. Wolffian duct. 6. Rudimentary oviduct. 7. Non-sexual portion of kidney. 8. External opening of the archinephric duct which has received the ureter 9 made up of a number of ducts from the posterior part of the kidney. 10. Fat-body.

These are the external gills found only in Amphibia, Dipnoi, and in *Polypterus*. There is also a pair of curious rod-like organs in front of the gills attached to the sides of the head. These "balancers," as they are termed, are possibly a first pair of external gills peculiarly modified. They have mucous cells at the tip, and by means of them the young larva suspends itself for hours at a time to plants. There is a long fish-like tail, the organ of locomotion, with a fringed fin. The fore-limbs are tiny buds. No trace of hind-limbs is apparent and the gill-slits are not open.

As development proceeds the fore-limbs make their appearance provided with only two toes. The gill-clefts, three in number, appear on each side. After a considerable time the third finger appears and the hind legs sprout out as buds; still later the fore-limbs get all four fingers and the hind-limbs five. The animal has now attained the appearance of the adult except in so far as the gills are concerned. These are retained for a long time, and exceptionally, in Switzerland in high Alpine localities, the larva may




FIG. 243. Larva of Triton, *Molge cristata* $\times 5$. After Rusconi. Showing external gills.

become sexually ripe and never leave the water. More usually with the closing of the gill-slits and the shrivelling of the external gills the adult state is attained.

The Urodela have been variously divided, but on the whole the best classification is that of Huxley, who divided them into the ICHTHYOIDEA and the SALAMANDROIDEA. The ICHTHYOIDEA are animals which retain throughout life gill-slits or external gills or both. Invariably the limbs are reduced in size, the animals rarely if ever leaving the water. In one case the hind-limbs have totally disappeared.

North America is the great head-quarters of the Ichthyoida. *Menopoma* (*Cryptobranchus*) retains one gill-slit throughout life. This animal attains a length of 18 inches. It is fairly common on

the Mississippi and its tributaries. An allied species found in Japan, and attaining a length of two feet, is the largest living Amphibian.

Amphiuma is a snake-like animal about 18 inches long, with one gill-slit. It is found in the same region as *Menopoma*. The limbs are exceedingly rudimentary, each having only two toes.

Necturus, the Mud-puppy, has small but well-developed limbs. It retains throughout life two gill-slits and three external gills on each side. *Necturus* is abundant in the shallows of the St Lawrence, wriggling in and out around the roots of aquatic plants. A somewhat similar animal, *Proteus*, with more rudimentary limbs, is found inhabiting the limestone caverns of Carniola in Austria. Lastly, there is the aberrant *Siren*, which has a horny beak ensheathing the premaxilla and dentary; it has no hind-limbs, but is similar to *Necturus* in its gills; it is found inhabiting the swamps of the Southern United States.

Since the Ichthyoidea possess both gills and lungs it is tempting at first sight to regard them as the little modified descendants of an animal just making the transition from water-breathing to air-breathing life. There are however insuperable difficulties in the way of such an explanation. If we turn to other groups of the animal kingdom we find that the first step in fitting an animal for a land life is the covering up of the respiratory organ so as to protect it against drying up. But in hardly any fish are the respiratory organs so exposed as in *Necturus*, *Proteus*, and *Siren*.

Further, it was pointed out that the great gap between fish and Amphibia is to be found in the structure of the limb. But the Ichthyoidea do not in any way assist in bridging the gap. On the contrary their limbs are obviously degenerating, a fact which seems to show that the aquatic life has been re-acquired. Now when the similarity between say *Necturus* and the late larva of *Molge* is borne in mind, and the further fact that these larvae may abnormally become sexually ripe, the conclusion is irresistibly suggested that the Ichthyoidea are larvae in which the adult stage has been suppressed. In the case of one large American newt, *Amblystoma mexicanum*, the larvae regularly breed under certain circumstances and were at one time supposed to be a distinct genus, called *Siredon*.

The second division of Urodela, the SALAMANDROIDEA, are in general very similar to *Molge*, both in appearance and anatomy and size.

As in Ichthyoidea, so likewise North America is very rich in

PLETHODONTIDAE includes the American Cave- and Land-Newts which rarely enter water but wriggle about actively on land. These Newts resemble the Desmognathidae in their teeth, but differ in possessing amphicoelous vertebrae. Although the most terrestrial in their habits of the New-world Urodela, these animals have undergone an extraordinary modification in their respiratory system. The lungs have totally disappeared, and the septum between the auricles has become absorbed: and the animals depend for their oxygen entirely on their skin and the lining of the pharynx, the walls of which still execute active respiratory movements. This curious association of terrestrial habits with the absence of lungs suggests the idea that the lung in such Urodela as retain it may be chiefly used as a hydrostatic organ like the air-bladder of fish, for were it of prime importance as a respiratory organ it would be difficult to explain its disappearance in terrestrial forms. *Spelerpes* includes the Cave-Newts, of which there are twenty species in America and one isolated species in Italy. In these animals the tongue is long and not adherent to the floor of the mouth. It can be suddenly protruded, and is used to catch insects in the same

way as the tongue of the Anura. This is an exceptional occurrence amongst Urodela, most of which seize their prey with the jaws. *Plethodon erythronotus* has a normal tongue. This is the common Land-Newt in the neighbourhood of Montreal, being found under old logs and in other damp situations.

II. ANURA.

The Anura or Batrachia are at once recognized by their broad, flattened, tailless bodies and their powerful hind-limbs.
 Structure. These limbs are not only efficient in jumping but also in swimming, and the toes are connected with one another by a thin web of skin in order to aid them in performing this function. The toes are stretched apart in the back stroke to present a large surface to the water, in the forward stroke they are folded together and offer little resistance.

Anura are much more abundant than Urodela and are found all over the world, whereas the Urodela are restricted to the Northern hemisphere. They are in fact the dominant Amphibia of the present day, but they are highly specialized, and the Urodela give a much better idea of the relation of the Amphibia to the Fish on one hand and the Reptiles on the other, for which reason *Molge* was selected as the type.

Besides the absence of a tail, the powerful character of the hind-limbs and the differences in the skeleton connected therewith, Anura differ from Urodela in the skull and jaws, in the pectoral girdle, in the heart and lungs, and in the kidneys, genital organs and development.

Two genera and four species of Anura occur in the British Isles. *Rana temporaria*, the common frog, and *R. esculenta*, the edible frog (the last named is thought by some not to be indigenous but to have been introduced), represent the family RANIDAE, whilst the BUFONIDAE or toads are represented by *Bufo vulgaris*, the common toad, and by *B. calamita*, the Natterjack, which occurs in numbers in certain restricted localities, as a rule with a sandy soil.

As the Common Frog, *Rana temporaria*, is easily attainable, the principal points in which it differs from *Molge*
 The Frog. will be briefly described.

The animal when at rest normally squats on its haunches,

supporting itself slightly on its palms. Under these circumstances, the pelvic girdle makes a considerable angle with the vertebral column and the powerful iliac bones raise the skin of the back into a well-marked hump, the so-called sacral hump.

The gape is enormous, and is caused by the lower end of the suspensorium, or part of the skull to which the lower jaw is hinged, slanting backwards instead of projecting directly downwards as in Urodela. The tongue is fixed to the floor of the mouth in front, but is free behind; it can be rapidly thrust out of the mouth by bending the posterior end forwards and as rapidly retracted. It is used to whisk the insects on which the animal feeds into the mouth.

Behind the eye is a circular patch of thin, tightly stretched skin. This is the ear-drum or tympanum, which closes externally the Eustachian pouch of the gullet. It is believed that this pouch is the remains of the first gill-cleft, the spiracle of Elasmobranch fish. Sound impinging on the ear-drum is conveyed to the wall of the ear capsule by a rod of cartilage called the columella auris. In the Urodela sound has to find its way as best it can through the skin and muscle of the head to its auditory organ. All Anura possess Eustachian pouches and a columella auris, but all do not have a well-developed ear-drum.

The skin is most loosely attached to the muscles underneath. Large spaces containing lymph are interposed between them. These lymph spaces form a protection against the danger of drying up. There are two pairs of sacs placed, one pair just between the upper ends of the pectoral girdle, and another pair just at the sides of the rudimentary stump of a tail, which have the power of contraction and pump the surplus lymph into the veins of the neighbourhood. These are called the anterior and posterior pairs of lymph-hearts.

Little trace is left in the muscles of the Frog of the myotomes. The muscle however which forms the ventral line of the belly, the rectus abdominis, is divided by bands of connective tissue into five pieces corresponding to the vertebrae.

Turning now to the skeleton; we observe many points of difference between the Frog and the Newt. The ribs in the Frog are indistinguishably fused with the transverse processes; in very few Anura are they distinct, and they are always rudimentary. The vertebrae differ from those of the Urodela in the entire suppression of the inter-ventral element so that the centrum is constructed out

of basi-dorsal, inter-dorsal, and basi-ventral elements, the last named being very rudimentary. In some Anura the basi-ventral piece is entirely absent, and in this case, since the centrum is constructed entirely of dorsal elements, the notochord is found for a considerable period of development lying in a groove on its under surface. This is the so-called epichordal type of development. The stump of the tail is ossified as a bony style, called the urostyle. Besides it there are only nine vertebrae.




FIG. 244. A, Dorsal, and B, Ventral view of the Cranium of a Common Frog, *Rana temporaria*, from which the membrane bones have mostly been removed $\times 2$. After Parker.

- | | | | |
|--|---------------------------------|---|--------------------|
| 1. Sphenethmoid. | 2. Palatine. | 3. Pterygoid. | 4. Suspensorium. |
| 5. Columella. | 6. Exoccipital. | 7. Ventral cartilaginous wall of cranium. | 8. Pro-otic. |
| 9. Anterior fontanelle. | 10. Right posterior fontanelle. | 11. Quadratojugal. | 12. Nasal capsule. |
| II. V. VI. IX. X. foramina for exit of cranial nerves. | | | |

The skull is constructed on the same plan as that of *Molge*, but it is broader and flatter; this is due to the wide arching out of the upper jaws, leaving a very large opening between them and the cranium. The cause of this again is to be sought in the large protruding prominent eyes, so marked a feature of all Anura. The floor of the cartilaginous cranium is complete in the Frog, the pituitary fossa having shrunk to insignificant dimensions. The orbitosphenoids have coalesced to form a box-like bone which ossifies not only in the front part of the cranium but also in the hinder parts of the nasal sac, and is called the sphenethmoid. The parietal is fused with the frontal.

The suspensorium sends forward a pterygoid process which

becomes attached to the skull in the nasal region. Underneath the posterior part of the pterygoid process there is a pterygoid bone which surrounds it and partly replaces it, so that whereas the pterygoid in *Urodela* is a true membrane bone, here it has become a cartilage bone, eating into and largely replacing the cartilage.




FIG. 245. A, Dorsal, and B Ventral views of the Cranium of a Common Frog, *Rana temporaria* $\times 2$. After Parker.

In this and the next two figures the cartilage is dotted, cartilage bones are marked with dashes, membrane bones are left white.

- | | | | |
|---|------------------------|--------------------|---|
| 1. Sphenethmoid. | 2. Fronto-parietal. | 3. Pterygoid. | 4. Squamosal. |
| 6. Exoccipital. | 7. Parasphenoid. | 8. Pro-otic. | 9. Quadratojugal. |
| 10. Maxilla. | 11. Nasal. | 12. Premaxilla. | 13. Anterior nares. |
| 14. Vomer. | 15. Posterior nares. | 16. Palatine. | 18. Columella. |
| 19. Quadrate. | 20. Occipital condyle. | II. Optic foramen. | V. VII. Foramen for exit of trigeminal and facial nerves. |
| IX. X. Foramen for exit of glossopharyngeal and pneumogastric nerves. | | | |

The pterygoid sends out a fork which underlies that part of the suspensorium which forms an articulation for the lower jaw. The front part of the pterygoid process where it bends in to rejoin the skull is ossified by the palatine, which like the pterygoid has become a cartilage bone. The palatine is transverse to the axis of the skull, as in *Amblystoma*. Neither palatine nor pterygoid bears teeth, but the vomers bear a little group of teeth towards their hinder edge. These vomerine teeth are used for crushing the food.

The upper lip has a series of three bones on each side, reaching completely to the suspensorium, an additional quadrato-jugal being added to the two present in the Newt. There is a large

membrane bone of a characteristic T-shape, known as the squamosal, lying outside the suspensorium. In the lower lip there is a splenial and a dentary, whilst in front the cartilaginous lower jaw is replaced by a pre-dentary bone. Only the premaxilla and maxilla and vomer bear teeth. Most Anura agree with the Frogs in this, but the Toad, *Bufo*, and its allies are entirely toothless.

The hinder visceral arches are reduced to a still more rudimentary condition than those of *Molge*. They are represented by a thin plate of cartilage called the basilingual with short blunt processes, of which only the last pair, which embrace the glottis, are ossified (Fig. 247). This pair are termed the thyrohyals. The whole "hyoid" apparatus is the remains of the second visceral arch and of the median piece (copula) which unites this to the third, with perhaps a trace of the third arch.

The pectoral girdle is much more strongly developed than in the Urodela. The coracoid and pre-coracoid processes are joined at their inner ends by a longitudinal bar, the epicoracoid, so as to enclose a space called the coracoid foramen. The two epicoracoids are in the frog firmly united in the middle line. In many Anura however they merely overlap.

The upper portion of the pectoral girdle is ossified by a bone called the scapula. As in Urodela, however, the cartilage projects a long way beyond it, and this portion is called the supra-scapula and may become partially ossified. There is a distinct coracoid bone ossifying the coracoid process, and the pre-coracoid is under-




FIG. 246. A, Lateral view of the Skull, B, Posterior view of the Cranium, of a Common Frog, *Rana temporaria* $\times 2$. After Parker.

1. Sphenethmoid. 2. Fronto-parietal.
3. Pterygoid. 4. Squamosal. 5. Tympanic membrane. 6. E.
7. Parasphenoid. 8. Pro-otic.
9. Quadratojugal. 10. Maxilla.
11. Nasal. 12. Premaxilla. 13. Anterior nares.
14. Pre-dentary.
15. Dentary. 16. Splenial. 17. Basilingual plate.
19. Quadrate.
20. Columella. 21. Occipital condyle.
22. Anterior cornu of the hyoid (ceratohyal).
23. Foramen magnum.
- IX. X. Foramina for the exit of cranial nerves.




FIG. 247. Visceral arches of Amphibia. A. *Rana temporaria* adult. After Parker. B. Tadpole of *Rana*. After Martin St Ange.

In A the ossified portions are slightly shaded, while the cartilaginous portions are left white.

1. Basilingual plate. 2. Hyoid arch. 3. First branchial arch. 4. Second branchial arch. 5. Third branchial arch. 6. Fourth branchial arch. 7. Thyrohyal.

meet one another in the mid-ventral bone, this must be considered doubtful.

In the arm the two points to be noticed are the complete fusion of the radius and ulna into one bone, and the reduction of the carpus, in which there are only six bones, three of the distal small bones having coalesced. The first digit or thumb is rudimentary.

In the pelvic girdle there is no epipubis: the ilium is a very long cylindrical bone: the ischium ossifies most of the ischio-pubic cartilage and is closely applied to its fellow. In the leg the tibia and fibula are fused into one bone, which is about the same length as the femur. The ankle is remarkably elongated, the tibiale and the fibiale being long cylindrical bones, easily mistaken for the middle segment of the limb. The distal bones of the tarsus have nearly disappeared, only two or three small nodules being

present on the axial side. The longest toe is the fourth, that corresponding to the human big toe is the shortest. It is a matter of great interest to see that there is a rudiment of a sixth digit on the inner side of the great toe. It is a common occurrence for the number five to be diminished, but very rare for it to be increased. It is believed that the pentadactyle limb is derived from a fin like that of the Dipnoi by a shortening of the main axis and a reduction in the number of rays. It is interesting to find in the lowest land animals traces of extra rays.




FIG. 248. Shoulder-girdle and Sternum of

A. An old male Common Frog, *Rana temporaria*.

B. An adult female, *Doedicophryne gigantea*. After Parker, to illustrate the structure in Arcifera.

In both A and B the left suprascapula is removed. The parts unshaded are ossified; those marked with small dots consist of hyaline cartilage, those marked with large dots of calcified cartilage.

- | | |
|---|--------------------------------------|
| 1. Calcified cartilage of suprascapula. | 2. Ossified portion of suprascapula. |
| 3. Scapula. | 4. Coracoid. |
| 5. Epicoracoid. | 6. Precoracoid. |
| 7. Clavicle. | 8. Glenoid cavity. |
| 9. Coracoid foramen. | 10. Episternum. |
| 11. Omosternum. | 12. Sternum. |
| | 13. Xiphisternum. |

The main differences between the circulatory system of the Frog and that of the Newt are to be found in the arterial system. The last arterial arch has become entirely cut off from the aorta and in addition to supplying the lung it sends a large branch to the skin, for which reason it is called the pulmo-cutaneous arch. The conus arteriosus, as in *Molge*, has two transverse rows of pocket valves, one near the heart and one near the outer end, but in the Frog there is in addition a longitudinal valve with a free ventral edge running somewhat obliquely from the one row of

valves to the other. When the ventricle contracts it is, at first, full of impure blood from the right auricle. This blood passes almost exclusively into the short and wide pulmonary passages, as they offer least resistance. As however these become filled it passes over the ventral edge of the longitudinal valve and into the systemic arches. By this time some of the blood has returned from the lung to the left auricle, and so mixed blood passes to the hinder portion of the body. The longitudinal valve, as more and more blood passes on the systemic side, is made to lie against the




FIG. 249. Diagram of Arterial Arch of Frog viewed from the Ventral Aspect.

- I. First arterial arch. II. Second arterial arch. IV. Fourth arterial arch (the third has disappeared). 15. Pulmonary artery. 16. Aortic arches uniting to form the dorsal aorta which gives off immediately the coeliaco-mesenteric artery. 23. Lingual artery. 24. Carotid arch with carotid gland.

openings to the pulmonary arches and so prevent any more blood entering them. When the pressure in the ventricle rises to its highest point, the last blood, which is entirely pure,—all from the right auricle having been driven out,—is able to overcome the resistance in the carotid gland and go to the head.

The posterior cardinal veins are only represented by their hinder

portions, the renal portals, all the blood from the kidneys being carried by the inferior vena cava.

The brain of the Frog and of *Anura* in general is more highly developed than that of the *Urodela*. Thus (Fig. 251) the olfactory lobes of the cerebral hemispheres are connected together, and the optic lobes of the mid-brain are well developed.




FIG. 250.

- A. The heart, after removal from the body, seen from the front, the aortic arches of the left side having been removed. From *Huxley*.
 - B. The same from behind, the sinus venosus having been opened up, to show the sinu-auricular valves.
 - C. The same, dissected from the front, the ventral wall together with one of the auriculo-ventricular valves having been removed.
1. Ventricle. 2. Right auricle. 3. Left auricle. 4. Truncus arteriosus. 5. Carotid arch. 6. Lingual artery. 7. Carotid gland. 8. Carotid artery. 9. Arch of aorta. 10. Pulmocutaneous trunk. 11. Innominate vein. 12. Subclavian vein. 13. Vena cava inferior. 14. Vena cava superior. 15. Opening of sinus venosus into right auricle. 16. Pulmonary vein. 17. Aperture of entry of pulmonary vein. 18. Semi-lunar valves. 19. Longitudinal valve. 20. Point of origin of pulmocutaneous trunk. 21. Rod passed from ventricle into the truncus arteriosus, indicating the course taken by blood which flows into the carotid and aortic trunks.

It was pointed out (p. 352) that the limbs of Vertebrates are in all probability derived from two lateral flaps of skin—two longitudinal fins. The muscles in these fins were originally prolongations of the myotomes and the nerves were of course branches of the motor nerves going to the myotomes. Now as these longitudinal flaps were converted into paired fins and these by a continual




FIG. 251. Brain and Spinal Cord of Frog
x about 2.

- a. Cerebral hemisphere. b. Olfactory lobe. c. Eye. d. Thalamencephalon. e. Optic lobes. f. Cerebellum. g. Medulla oblongata. h. Fourth ventricle. i. Spinal cord. I. Olfactory nerves. II. Optic nerve. III. Oculomotor nerve. IV. Trigeminal. V. Fifth nerve. VII. Facial nerve. VIII. Auditory nerve. IX. Glossopharyngeal nerve. X. Vagus nerve. 1—10. First to tenth spinal nerves. 2 and 3 unite to form the brachial, and 7, 8, and 9, to form the sciatic plexus.

narrowing of their bases acquired greater distinctness from the body, the portions of the myotomes supplying the musculature, and the nerves in connection therewith became so to speak bunched together at the base of the limb. In adult Craniata all trace of the original metameric arrangement of the limb muscles is lost; but the metamerism of the nerves can still be seen, and the bundles of these supplying the pectoral and the pelvic limbs are known as the brachial and the sciatic plexus respectively. In the Frog, where the limbs are of far greater importance to the life of the animal than are the fins to fish, the nerves forming the brachial and the sciatic plexus are powerful trunks (Fig. 251, 2, 3, and 7—10).

The lungs are shorter than in the Newt but much wider, and their inner surface is covered with a network of low ridges which much increases their area. The kidney is a comparatively short and broad organ, very different from the long tapering organ of the Newt. The testis is connected by vasa efferentia with certain special tubules of the kidney. These tubules do not open into the archinephric duct, but into a special duct which runs along the surface of the kidney and opens into the archinephric duct

behind. Thus in a somewhat different way the separation of urine and spermatozoa is carried out quite as efficiently as in the *Newt*. The archinephric duct has a number of pouches developed on its walls which collectively form the vesicula seminalis in which




FIG. 252.

- A. The urino-genital organs of the male, dissected from the front, after removal from the body. From Howes.
- B. The urino-genital organs of the female, dealt with in the same manner as the above, except that, in order to show the natural relations of the mouth of the oviduct, the left lung and a portion of the oesophagus were also removed from the body.
- A. 1. Fat-body. 2. Fold of peritoneum supporting the testis. 3. Efferent ducts of testis. 4. Ducts of vesicula seminalis. 5. Vesicula seminalis. 6. Archinephric duct. 7. Cloaca. 8. Orifice of ureter. 9. Proctodaeum. 10. Allantoic bladder. 11. Rectum. 12. Kidney. 13. Testis. 14. Adrenal body.
- B. 1. Oesophagus. 2. Mouth of oviduct. 3. Left lung. 4. Corpus adiposum. 5. Left ovary. 6. Archinephric duct. 7. Oviduct. 8. Allantoic bladder. 9. Cloaca. 10. Aperture of oviduct. 11. Orifice of archinephric. 12. Proctodaeum. 13. Fold of peritoneum supporting the ovary. 14. Kidney.

the spermatozoa are stored up. In *Bombinator* the vasa efferentia apparently open directly into the archinephric duct in front of the kidney. The oviduct often appears as a rudiment in the male, and in *Alytes* the vasa efferentia open into it. This last is a very abnormal arrangement.

The eggs develop entirely outside the body, and there is a large thin-walled swelling of the oviduct in which the ripe eggs accumulate just before being discharged. The male clasps the female round the waist and remains in this position sometimes for weeks, uttering loud croaks at intervals until the eggs are discharged. When the eggs are discharged he emits the spermatozoa on to them. The croaks are made by pumping the air from the lungs through the glottis into the pharynx, and *vice versâ*. The pharynx has usually two side pouches, the vocal sacs, which become inflated with air. It is thus possible for the frog to croak when under water.




FIG. 253. Tadpole of *Rana esculenta*, Lin. taken near St Malo $\times 1$. From Boulenger.

1. Dorsal fin. 2. Tail showing myotomes. 3. Hind-limb.

The development is in many respects different from that of Urodela. Soon after the young are hatched they acquire, it is true, three external gills on each side, but there is no trace of limbs, and the gill-slits are closed, and as the mouth does not open into the alimentary canal no food is taken. Later the gill-slits appear; but a flap of skin, the gill-cover, grows back from the second visceral arch, the hyoid, and covers up the gill-slits and the external gills. The external gills when covered soon disappear. The two gill-covers unite with one another beneath the animal, so only one little

opening to the gill-chamber remains, usually on the left side. The mouth has by this time opened into the alimentary canal, and it is provided with two horny ridges, one above and one below, besides rows of little horny prickles. The horny jaws crop the water-weeds upon which the tadpole lives.

The larva is now the well-known tadpole, with a rounded body and a long flat tail with which it swims. The limbs gradually grow, but for a long time the front limbs are hidden beneath the gill-cover. When they finally burst through the animal sheds its horny jaws and comes on land. For a short time the tail is retained, but absorption soon removes all trace of it and the development is complete.

The Anura are divided into two main groups according to the development of the tongue. In the **Aglossa** it is entirely absent and the two Eustachian tubes have a common opening into the pharynx. This curious group only includes two genera. In one species, *Pipa americana*, the Surinam toad, the eggs are emitted from the protruded oviduct on to the back of the female, and here the young pass through the tadpole stage enclosed in deep pockets of the moist skin. This species as its familiar name implies is an inhabitant of S. America. In the **Phaneroglossa**, on the other hand, the tongue is well-developed, usually being free behind, and in this case used to flick the prey, which consists of insects, into the capacious mouth. The Eustachian tubes are separate. The **Phaneroglossa** are divided into the **Arcifera** and the **Firmisternia**. In the first division the two epicoracoids of each side overlap (Fig. 248, B); in the second they are firmly united in the middle line (Fig. 248, A). The first division includes several families, but the two largest and most important are those of the toads **BUFONIDÆ** and the tree frogs or **HYLIDÆ**.

The toads have no teeth whatever and their dermal glands secrete a poisonous juice; the skin is warty, owing to great thickenings of the horny layer of the epidermis. They only enter the water at the breeding season and toads are in many respects more adapted to a land life than are frogs. Two species live in Great Britain; *Bufo vulgaris*, found everywhere, and *Bufo calamita*, the natter-jack, a species with comparatively feeble hind-limbs, which crawls and does not jump. The natter-jack frequents sandy places and is thus local in its distribution.

One species of *Bufo* (*B. americana*) is found in the north of North

America. But besides the Bufonidae another family of the Arcifera, the PELODYTIDAE, which have teeth, is represented by *Scaphiopus*, a burrowing species, provided with a sharp spur on the inner side of each foot, whence the name spade-foot frog.

The HYLIDAE have teeth on the vomers and on the upper jaw, but their most remarkable peculiarity consists in the possession of fleshy cushions underneath the terminal joints of the digits, the bones of which are bent up and claw-like. By means of these cushions the Hylidae are able to adhere to smooth vertical surfaces, and so climb trees, in which they mostly live, only approaching the water for the purpose of laying their eggs. There is no species of this family in Great Britain and only one in Europe. In North America there are several species belonging to three genera: *Hyla*, *Chorophilus*, and *Acris*.

The FIRMISTERNIA have the two epicoracoids fused in the middle line and include the Frogs or RANIDAE. There is only one species, *Rana temporaria*, which was taken as the type of the Anura, really native to Great Britain, but there exist a few colonies of the common European species, *Rana esculenta*, mostly in the Eastern Counties. The frogs of this species are most powerful croakers, and as their name implies they are used as food. It is believed that they were introduced by the monks from Europe who before the Reformation used to pay periodical visits to England to supervise their property.

In Canada and the Northern United States there are eight species of frogs. A species believed to be identical with *Rana temporaria* is found, but the two commonest are *Rana virescens*, of a green ground colour with lines of velvety black patches, and the great Bull-frog, *Rana catesbiana*, which attains three or four times the size of *Rana temporaria*, and is of brownish yellow colour, peppered over with minute black dots.

III. GYMNOPHIONA.

The order Gymnophiona is, as has already been mentioned, distinguished by the entire absence of limbs and the worm-like appearance and habits of its members. In the skeleton the retention of a complete roof of bones over the space between cranium and upper lip, known as the temporal fossa, and the existence of minute bony scales embedded in the dermis, are features retained

from the Stegocephala. In accordance with their retiring habits the members of this order have very small and nearly, if not quite, functionless eyes. The internal anatomy is in many respects like that of the Urodela, but the pulmonary arterial arch does not join the aorta. These animals often live at some distance from water and the larval development is passed through inside the egg-shell, but even there the embryo develops large external gills.

The species of this family are restricted to the tropics; *Epicrion* is found in Ceylon, *Coecilia* in South America, and *Hypogeophis* in Africa.

The class Amphibia is divided as follows:

Order 1. URODELA.

Amphibia retaining throughout life a long tail: the fore-limbs and hind-limbs are approximately equal in length.

Sub-order 1. Ichthyoidea.

Urodela retaining throughout life one or more open gill-slits on each side of the neck and frequently external gills in addition. Limbs more or less degenerate.

Ex. *Necturus*, *Proteus*, *Siren*, *Amphiuma*, *Menopoma*.

Sub-order 2. Salamandroidea.

Urodela which lose all trace of gills and gill-slits when adult. Limbs well developed.

Family (1) SALAMANDRIDÆ.

Salamandroidea in which the vomero-palatine teeth are arranged in two longitudinal series and in which the vertebrae are opisthocoelous.

Ex. *Molge*, *Salamandra*.

Family (2) AMBLYSTOMATIDÆ.

Salamandroidea in which the vomero-palatine teeth are arranged in a transverse row and in which the vertebrae are amphicoelous.

Ex. *Amblystoma*.

Family (3) DESMOGNATHIDÆ.

Salamandroidea in which the vomero-palatine teeth are

arranged in a transverse row, and in which there is a tuft of teeth on the parasphenoid ; vertebrae opisthocoelous.

Ex. *Desmognathus*.

Family (4) PLETHODONTIDAE.

Salamandroidea with teeth arranged as in preceding family, but in which the vertebrae are amphicoelous. In most (if not all ?) cases lungs absent and the atrium of the heart undivided.

Ex. *Spelerpes*, *Plethodon*.

Order 2. ANURA.

Amphibia which lose when adult all trace of tail, hind-limb much more powerful than the fore-limb and used for leaping.

Sub-order 1. Aglossa.

Anura devoid of a tongue ; both Eustachian tubes have a common opening.

Ex. *Pipa*.

Sub-order 2. Phaneroglossa.

Anura with well-developed tongue. Eustachian tubes with separate openings.

Group I. Arcifera.

Phaneroglossa in which the epicoracoids of opposite sides overlap.

Family (1) BUFONIDAE.

Arcifera with very warty skin and without teeth in the upper jaw. Pupil a horizontal slit.

Ex. *Bufo*.

Family (2) PELODYTIDAE.

Arcifera with teeth in the upper jaw. Pupil a vertical slit.

Ex. *Scaphiopus*.

Family (3) HYLIDAE.

Arcifera with teeth in the upper jaw, and expanded discs on the toes enabling them to climb.

Ex. *Hyla*.

Group II. Firmisterna.

Phaneroglossa in which the epicoracoids are firmly united in the middle line.

Family (1) RANIDAE.

Firmisternia with cylindrical sacral transverse processes.

Ex. *Rana*.

Order 3. GYMNOPTIONA.

Amphibia without limbs or tail, of worm-like appearance with rudimentary eyes.

Ex. *Coecilia*, *Hypogeophis*, *Epicrion*.

CHAPTER XVII.

SUB-PHYLUM IV. CRANIATA.

Class III. REPTILES.

THE name Reptile denotes literally anything that creeps (Lat. *repo* or *repto*, to crawl), and in this sense it is indeed often used; a newt, a centipede, or a spider, would each doubtless be called a reptile by many people.

General Characteristics.

Zoologically, however, the term denotes cold-blooded quadrupeds which are covered with horny scales and which lay large eggs, inside the shells of which the whole development is completed.

But it is not merely the size of the egg nor even the character of the embryonic development which distinguishes Reptiles from Amphibia. There are isolated cases of species of Amphibia in which the development is practically completed within the egg-shell, but in all Amphibia the whole egg becomes converted into the body of the larva. In Reptiles on the other hand part of the egg is made into a hood termed the amnion, which is wrapped around the body of the embryo. This structure is cast off entirely at birth, and the wound caused by its tearing is healed. With it is also cast off a portion of the urinary bladder—the allantois in the stricter and original sense—which extends into the amnion and appears to subserve respiration during embryonic life. In strictness, therefore, only a part of the egg is converted into the body of the embryo.

This peculiar mode of development is shared by Birds and Mammals, for which reason these two classes are often included with the Reptiles in the term Amniota.

Next to the development perhaps one of the most characteristic features of Reptiles is the nature of their skin. They are typically covered with scales which are widely different from the scales of fish. The latter are essentially areas of the dermis hardened by the

deposition of lime with sometimes the addition of a layer of crystals from the basal ends of the ectoderm cells (enamel)

The scale of the Reptile on the contrary is nothing but an area of the horny layer of the skin where the cells are converted into horn or ceratin, and adherent to one another. In the mass of the scale the horn is rendered brown by the presence of pigment but the outermost layer is composed of clear cells and is known as the epitrichial layer. Such a structure is found in one or two Mammals, but otherwise nowhere else than in Reptiles. A sloughing or ecdysis of the scaly epidermis is a constant feature of the Reptilia. It may take place bit by bit, or as is the case with many Sauria the whole 'skin' is cast in one piece.




FIG. 254. Section through the Scale of a Lizard.

- | | | |
|-----------------------------------|---|------------------|
| 1. Epitrichial layer. | 2. Heavily cornified cells forming the scale. | 3. Pigment cell. |
| 4. Ordinary cells of horny layer. | 5. Malpighian layer. | 6. Dermis. |

The dermal glands so characteristic of the Amphibia have almost totally disappeared, being restricted to a small area as, for instance, the front of the thigh in a lizard. It follows that a reptile is essentially a dry-skinned animal and by no means a "slimy beast."

Besides the structure of the skin Reptiles are distinguished from Amphibia by many other points in the anatomy. Thus the skull has a larger number of cartilage bones, and includes also a longer region of the vertebrae within itself, for the hypoglossal nerve (see p. 417) is now a cranial nerve. The skull articulates with the vertebral column by one condyle. In the heart the conus arteriosus has disappeared and the ventricle is partly divided. The sexual part of the kidney is entirely disjoined from the asexual.

The lungs have to some extent acquired a spongy texture, and the mechanism for inhaling and exhaling air is usually to be found in the ribs, not in the hyoid or remains of the hinder visceral arches, as in the Amphibia.

Living Reptiles are divided into five orders, of which one consists only of one species, *Sphenodon punctatus*, found in New Zealand. This animal is the type of the order (i) **Rhyncocephala**, and is especially interesting as not only being to some extent intermediate in structure between other orders of living Reptiles, but as recalling very closely the structure of some of the oldest fossil Reptiles known to us; indeed it retains in many respects a structure which we believe was possessed by the common ancestors of the remaining four groups.

These orders are the (ii) **Lacertilia** (Lizards), the (iii) **Ophidia** (Snakes), the (iv) **Chelonia** (Turtles and Tortoises), and lastly the (v) **Crocodylia** (Alligators and Crocodiles). Of these four orders only the second and third are represented in Great Britain, and these by very few species; in North America the last four are well represented. Of the five orders, the Lacertilia and the Ophidia are the most closely related and they are often grouped together under the same term **SAURIA**.

As type we may select the common lizard, *Lacerta vivipara*, which may be seen on very warm days disporting itself in sandy and stony places in the South of England. On the Continent it and allied species are far more abundant: in the South of Europe in summer the whole country is alive with lizards. Almost every step in the country causes two or three specimens to rush rapidly away into some retreat, either a hole under a stone or a cleft in the bark of a tree.

Structure of
Lacerta.

The English Lizard has roughly the shape of a Newt, but there is a distinct neck region in front of the fore-limb, and the limbs are sufficiently powerful to completely raise the belly well above the ground, and also to run at a comparatively rapid rate. Both manus and pes have five digits, which end in sharp claws. The body is covered all over with minute scales (Fig. 254), of which the prevailing colour is reddish brown above, and orange passing into yellow beneath. On the ventral surface and the top of the head the scales are larger and arranged in pairs. The ear-drum is situated at the bottom of a slight pit, this is the first appearance of the outer ear. It is not developed in all Reptiles.

The cloaca is a transverse slit at the root of the tail behind the hind pair of legs. In front of the thigh the scales are perforated by a row of pores, the openings of the only dermal glands which the lizard possesses.

Turning at once to the skeleton, we find that the vertebral column consists of procoelous vertebrae. All the vertebrae articulate with one another by overlapping facets called pre- and post-zygapophyses as in Amphibia. Although externally similar to the vertebrae of Amphibia, the vertebrae of the Lizard, and of Reptiles generally, are formed of different elements. Thus the basi-dorsal and inter-dorsal have been suppressed, whilst the basi-ventral forms an intervertebral disc of cartilage which in the tail bears a pair of processes united with one another to form a Y shaped chevron bone, recalling in its shape the haemal arches of fish. In the neck region the basi-ventrals bear each a bony wedge which is called the sub-vertebral wedge bone. The centrum is formed by the inter-ventral, the very element which is suppressed in the trunk-vertebrae of Amphibia. The rib has shifted its position so that the capitulum is attached to the front end of the centrum (inter-ventral) behind the basi-ventral to which it belongs. The tubercular attachment is represented by ligament. There are two sacral vertebrae which have expanded transverse processes with which the ribs are fused. Behind these come the vertebrae of the tail—the caudal vertebrae. Each of these bones is made up of two halves, an anterior and a posterior, which are but loosely connected with one another. The consequence is that when a Lizard is seized by the tail this organ snaps in two, one of the vertebrae breaking into an anterior and a posterior half.

All vertebrae in front of the sacrum, except the first two, have distinct ribs attached to their transverse processes. The first two are called respectively the atlas and axis vertebra. The first is as in the case of Amphibia a mere ring. It is composed of the first pair of neural arches united with the first pair of basi-ventrals, and is therefore to a certain extent homologous with one of the intervertebral discs. The second has a well-marked centrum, to the front of which is attached a peg-like process—the so-called odontoid process which projects through the ring of the atlas. This odontoid process is quite unrepresented in the Amphibia, but it is characteristic of all Reptiles and Birds and Mammals. It is formed by the first pair of inter-ventrals, and is therefore the first centrum. In young specimens it can be seen to be separated from the centrum

1. Interclavicle.
2. Clavicle.
3. Scapula.
4. Coracoid.
5. Precoracoidal process.
6. Glenoid cavity.
7. Sternum.
8. Sternal bands not united.
9. Sternal rib.

separate behind. The hole in the middle also is a place where they do not unite.

The skull is distinguished from the Amphibian skull by many features. The jaws do not arch outwards at the sides of the cranium, as in the frog, but are bent inwards underneath it. Behind, the cartilage of the cranium is completely replaced by four bones—by the supra-occipital above the foramen magnum, the ex-occipitals at the sides of this opening, and the basi-occipital beneath. This last bone bears a single knob or condyle which articulates with the atlas vertebra. To the formation of this condyle the ex-occipitals in some degree contribute. The basi-occipital and the single condyle and the supra-occipital are highly characteristic of all Reptilia—as is also the basisphenoid bone. This is a bone replacing the cartilaginous floor of the cranium just in front of the basi-occipital. The parasphenoid so characteristic

of Amphibia is reduced to a mere splint attached to the front of the basisphenoid.

The anterior part of the cranium is so compressed between the large eyes that its cavity completely disappears and it becomes re-




FIG. 256. A, Lateral view, and B, Longitudinal section of the Skull of a Lizard, *Varanus varius* $\times \frac{2}{3}$.

- | | | | | |
|----------------------|-------------------|-----------------|--------------------------------------|---------------------|
| 1. Premaxilla. | 2. Maxilla. | 3. Nasal. | 4. Lateralethmoid. | 5. Supra-orbital. |
| 6. Lachrymal. | 7. Frontal. | 8. Postfrontal. | 9. Prefrontal. | 10. Basisphenoid. |
| 11. Pro-otic. | 12. Epi-otic. | 13. Pterygoid. | 14. Epipterygoid (columella cranii). | 15. Jugal. |
| 16. Transverse bone. | 17. Parasphenoid. | 18. Quadrate. | 19. Parietal. | 20. Squamosal. |
| 21. Supratemporal. | 22. Exoccipital. | 23. Dentary. | 24. Splenial. | 25. Supra-angular. |
| 26. Angular. | 27. Coronoid. | 28. Articular. | 29. Vomer. | 30. Basisoccipital. |
| 31. Orbitosphenoid. | | | | |

placed by a vertical sheet of membrane, the inter-orbital septum. It follows that in the dried skull the two orbits apparently open widely into one another. Almost the entire brain is pushed back behind the

eyes into the hinder part of the cranium. Only the olfactory stalks run through holes in the upper part of the septum. The orbitosphenoid of Urodela and the sphenethmoid of the frog are quite unrepresented, though in some of the larger lizards allied to *Lacerta* there is a minute orbitosphenoid bone in the upper part of the inter-orbital septum (31, Fig. 256). The inter-orbital septum is certainly a characteristic of the primitive Reptilia. It has however been lost in some of the most recent and highly modified forms.

The auditory capsule as in Teleostei is completely converted into bone, but it is ossified by three bones only, an epi-otic above, which fuses with the supraoccipital, an opisthotic, behind which joins the exoccipital, and a pro-otic which remains distinct. There is no trace of the pterotic bone so characteristic of Teleostei.

As in Amphibia the first visceral arch is represented by an upper half consisting of a suspensorium with a pterygoid process, and a lower half—Meckel's cartilage. In the upper half, however, the cartilage is completely replaced by bone. The suspensorial portion forms the quadrate bone which is attached to the side of the auditory capsule. The pterygoid process is completely ossified by the pterygoid bone behind and the palatine in front.

A curious bone characteristic of the Lacertilia excluding the *AMPHISBAENIDAE*, and called the epipterygoid or columella bone, runs from the pterygoid vertically up to the parietal. This bone is however only found in some Lacertilia, not in Reptiles generally.

The two pterygoid bones, however, instead of arching outwards converge under the base of the cranium, and they articulate with outgrowths from the basisphenoid, called basipterygoid processes. The palatines are united in front with the floor of the nasal capsule: they bear on their inner sides slight ridges which project somewhat into the cavity of the mouth. These ridges support a flap of the lining of the mouth, the palatal flap, which is most characteristic of all Reptilia but is not found in any Amphibian (Fig. 259). It is a first trace of the process which ends in the higher animals and even in some Reptiles in the division of the mouth-cavity into an upper air-passage and a lower food-passage.

The end of Meckel's cartilage which articulates with the quadrate is converted into a bone, the articulare. Three pairs of the hinder visceral arches are preserved. These retain their rod-like form as in Urodela, the median connecting pieces (copulae) remaining small.

The membrane bones of the skull are one of its most characteristic features. The roofing bones are the same as in the Urodela—paired nasals, frontals and parietals. On the roof of the mouth there are two vomers and a parasphenoid. The vomers, however,




FIG. 257. Diagram of the Cranial Roof in a Stegocephalian, various Types of Reptiles, and a Bird, showing Modifications in the Postero-lateral Region. From Smith Woodward.

- A. Stegocephalian (*Mastodonsaurus giganteus*, about one-fifteenth nat. size, after E. Fraas). B. Generalized Rhynchocephalian and Crocodilian. C. Generalized Lacertilian, often losing even the arcade here indicated. D. Generalized Bird. fr. Frontal. j. Jugal. l. Lateral temporal fossa. la. Lachrymal. mx. Maxilla. n. Narial opening. na. Nasal. o. Orbit. pa. Parietal. pmx. Premaxilla. prf. Prefrontal. ptf. Postfrontal. pto. Postorbital. qj. Quadrato-jugal. qu. Quadrate. s. Supratemporal fossa. s.t. Supratemporals. sq. Squamosal. Vacuities shaded with vertical lines, cartilage bones dotted.

are rod-like, toothless and placed close together, and the parasphenoid is a small rudiment.

The bones of the side of the head and the upper lip form a most peculiar scaffolding which is widely separated from the cranium.

The Lizard is in an intermediate condition between the Stegocephala, where a continuous sheet of bones extends from the cranium to the upper lip, and modern Amphibia, where all those bones have disappeared, leaving a large vacuity between the cranium and upper lip.

In front in the upper lip there is a premaxilla bearing teeth followed by a maxilla in which there are also teeth. The maxilla is joined to the pterygoid by an ectopterygoid or transverse bone. Between the maxilla and frontal on the side of the face are two bones known as prefrontal and lachrymal. The line of bones in the upper lip is continued by the jugal. This unites with a bone placed behind the eye termed the postfrontal, which joins both the frontal and parietal. Thus the eye is surrounded by a ring of bone.

The squamosal is a characteristic V-shaped bone. The apex of the V articulates with the upper side of the quadrate: of the two arms one is directed forwards and meets the postfrontal, thus forming a bony bar parallel to the cranium which is called the upper temporal arcade. The other limb is directed backwards and inwards and meets a crest on the parietal so that a bridge is formed extending over the hinder part of the cranium. The space in the dried skull existing between this bridge and the cranium is called the post-temporal fossa. In many reptiles, including most Lacertilia, there is a similar space between the cranium and the lateral bridge formed by the junction of the squamosal and postfrontal. This space is roofed over in *Lacerta* by two membrane bones called supratemporals, but when uncovered it is known as the supratemporal fossa.

Finally, the space intervening between the quadrate and jugal on the side of the face is known as the latero-temporal fossa. In *Sphenodon*, *Crocodylia* and a very large number of extinct Reptiles it is bounded below by a quadrato-jugal bone which joins the jugal to the quadrate. When the quadrato-jugal is present the series of bones consisting of maxilla, jugal and quadrato-jugal is known as the lower temporal arcade. The upper temporal arcade is formed as we have seen by the postfrontal and the squamosal. The loss of the quadrato-jugal in Lacertilia is doubtless connected with the greater mobility of the jaws. In some lizards, notably in Geckos, the quadrate can move slightly on its articulation with the skull, as can also the pterygoid on the basipterygoid process. When the lower jaw is pulled downwards and backwards by its depressor

muscle it tends to throw the lower end of the quadrate slightly forwards: the pterygoid slides on the basisphenoid, and pushing the ectopterygoid tilts the maxilla slightly upwards. With the maxilla all the other bones of the face move, and the membranous inter-orbital septum permits the ethmoidal region of the cranium to be slightly bent on the hinder one.

The cartilaginous lower jaw is ensheathed by five distinct membrane bones. The dentary and splenial occupy the same positions as in Teleostomi and Urodela. The angular clamps the under side of the articulare, the cartilage bone replacing the upper end of the cartilage. The supra-angular lies above the angular on the outer side of the articular. The coronoid is a small projection on the upper edge.

The pectoral girdle is at first sight exceedingly complicated, but in reality it consists of the same parts as in the Anura. Above the cavity for articulation of the arm—the glenoid cavity—there is the cartilaginous scapula; below the girdle forks into a coracoid and procoracoid united by an epicoracoid. The cartilage bones present are the scapula, precoracoid and coracoid. The cartilage above the scapular bone is slightly hardened by lime but is not converted into bone; this region as in Amphibia is called the supra-scapula. Along the inner edge of the supra-scapula, scapula and precoracoid runs a strong membrane bone, the clavicle which reaches a median bone, the T-shaped interclavicle. This bone underlies the sternum. The two epicoracoid cartilages join the anterior edges of the sternum (Figs. 255 and 258).

The space between the coracoid and precoracoid is called the coracoid fontanelle. Since in the Urodela it is not closed by an epicoracoid it may be regarded as a bay or indentation in the lower half of the originally simple pectoral girdle. The condition of affairs in Urodela throws considerable light on what occurs in certain other Lacertilia, such as the American Iguana. There we find that a similar deep indentation has become developed on the inner side of both scapula and coracoid, so that




FIG. 258. Lateral view of the Shoulder-Girdle of *Varanus* $\times \frac{3}{8}$.

1. Suprascapula. 2. Scapula.
3. Glenoid cavity. 4. Coracoid.
5. Clavicle. 6. Interclavicle.
7. Precoracoid process.

projections are formed to which the names mesoscapula and mesocoracoid have been given. These are not ossified by separate bones but are regions of the scapula and coracoid bones.

The fore-limb of the lizard might be taken as the type of the pentadactyle limb, since there are five fingers and the carpus has all the nine bones developed.

The pelvic girdle differs markedly from that of any Amphibian, in that in its lower portion there is a hole called the obturator foramen, corresponding to the coracoid foramen in the pectoral girdle. The girdle is ossified by three bones, viz. a vertical ilium articulating with the ribs of the sacral vertebrae, a pubis ossifying the anterior limb of the lower half of the girdle and an ischium ossifying the posterior limb. Both pubis and ischium meet their fellows in the middle line; such a union is termed a symphysis. The two obturator foramina are closed below and at the same time separated from one another by a longitudinal ligament which may have a certain amount of ossification in it. All three bones contribute to the formation of the acetabulum, the cavity for the articulation of the femur.

The presence of the obturator foramen and a distinct pubis is characteristic of all Reptiles, Birds, and Mammals, and at once discriminates them from Amphibia.

On the hinder edge of the pubis there is a projection which is called the lateral process. In some extinct reptiles this process was extraordinarily long and ossified by a distinct bone, which has been called the post-pubis. It is the post-pubis which forms the so-called pubis of Birds and Mammals.

The most marked feature of the hind limb is the formation of a sharply-marked "ankle" joint. There is one place and one only where the foot bends on the shank; whereas in Urodela bending can take place at any place in the mosaic of small bones which forms the tarsus.

In the lizard all the three upper bones of the tarsus are joined to form a horizontal bar. The lower bones have almost entirely coalesced with the corresponding metatarsals, only the third and fourth of the series being distinguishable. Thus the lizard has what has been called a inter-tarsal joint—an arrangement which is highly characteristic of many Reptiles and of all Birds.

All trace of the division of the muscles into myotomes has disappeared, but the innermost layer of the muscles of the flanks has become divided secondarily into a series of bands connecting each rib with its successor. These

Viscera.

bands are termed the intercostal muscles and each consists of an external and an internal layer of fibres. The fibres of the external layer slope upwards and forwards and, in contracting, cause the ribs to rotate forwards; the fibres of the inner layer slope upwards and backwards and have the reverse effect. Respiration is effected by the pulling forwards and backwards of the ribs by these intercostal muscles. In their relaxed condition the ribs slant strongly backwards. When they are pulled forward by muscles attaching them to the anterior vertebrae and by the external intercostals, they rotate forwards so as to stand out at right angles to the vertebral column and thus enlarge the cavity of the chest, that is of the coelom. The lungs which project into the coelom tend to expand also—the air they contain is under diminished pressure and hence air rushes in through the glottis to equalize the pressure inside with the atmospheric pressure. The lungs, which are comparatively short sac-like organs, are thus filled. The network of low ridges which is found already on the inner side of the Frog's lung has here greatly increased in complexity. The primary ridges are much higher, and between them are lower secondary and even tertiary ridges: the cavity of the lung is as it were partly filled up by a spongy mass. In all Saurians however the central cavity is easily recognized

as a wide space: whilst in Crocodiles and Tortoises, still more so in Birds and Mammals, it is represented only by the bronchial tubes.




FIG. 259. Open mouth of *indicus* $\times 1$.

1. Posterior or internal nares.
2. Palatal folds. 3. Internal opening of Eustachian tubes.
4. Opening of oesophagus. 5. Glottis. 6. Tongue half protruded
7. Teeth of lower jaw.

origin, that which passes to the right of the oesophagus arising from the left of the ventricle and *vice versâ*. The first pair of arterial arches, corresponding to the carotid arches of Amphibia, are well developed in the Lizard. They have a common stem which arises from the right aortic trunk. After passing to the sides of the oesophagus they give off the carotid arteries; they then join the roots of the aorta, so that in this respect the Lizard is more primitive even than the Newt. This feature is however found in no other order of reptiles, and is even wanting in some genera of the Lacertilia.

The ventricle has projecting into its cavity two imperfect partitions, or septa. One is the continuation of the division between the two auricles, the other is a ridge which arises from the ventral side and tends to separate the opening of the pulmonary arteries from that of the right and left aortic arches. When the ventricle at first begins to contract it is full of impure blood from the right auricle: by the time purified blood has commenced to enter it from the left auricle, the ventral septum mentioned above has been driven against the opposite wall, so as to shut off the pulmonary trunk from the rest of the ventricle and prevent its receiving any more blood. The left aortic arch, which arises on the right, receives mostly impure blood from the right auricle, the right aortic arch pure blood from the left auricle, and it is from this arch, as mentioned above, that the carotid arteries arise. Hence the head receives comparatively pure blood, and all the rest of the body mixed blood.




FIG. 261. Diagram to show arrangement of the principal veins in the *Anura* and *Reptilia*.

1. Sinus venosus, gradually disappearing in the higher forms. 2. Ductus Cuvieri = superior vena cava.
3. Internal jugular = anterior cardinal sinus. 4. External jugular = sub-branchial. 5. Subclavian.
6. Posterior cardinal, front part = vena azygos. 7. Inferior vena cava. 8. Renal portal = hinder part of posterior cardinal.
9. Caudal. 10. Sciatic = internal iliac. 11. Pelvic. 12. Anterior abdominal. 13. Femoral = external iliac.

The veins, on the whole, closely resemble those of *Molge*. There is no large cutaneous vein however, and the anterior part of the posterior cardinal, now called the vena azygos, is only found on the right side, where it receives the numerous intercostal veins, returning the blood from the muscles connecting the ribs. The renal-portal, sciatic, femoral and anterior abdominal veins have the same arrangement as in the Urodela.




FIG. 262. Urinogenital organs of Male Lizard.

1. Testis. 2. Vas deferens = archinephric duct. 3. Epididymis = (mesonephros). 4. Kidney = metanephros. 5. Ureter. 6. Bladder. 7. Rectum cut and turned back. 8. Cloaca laid open. 9. Opening of Vas deferens. 10. Groove leading to opening of penis. 11. Penis. 12. Dorsal aorta.

The brain is distinguished by the comparatively large size of the cerebral hemispheres, which overlap the thalamencephalon above and at the sides. They end in front in large pear-shaped olfactory lobes. The cerebellum is a high vertical ridge, very much better developed than in any Amphibian. The remainder of the hind brain, the medulla oblongata, includes a longer portion of the spinal cord than it does in Amphibia, for the hypoglossal nerve arises from its side and escapes through an aperture in the exoccipital bone. This nerve is reckoned the twelfth cranial, not the eleventh, for there is a trunk called the spinal accessory or eleventh cranial. This arises by several roots from the side of the medulla oblongata, joins the

vagus in a ganglion, and then leaving the skull supplies some of the neck muscles. In the *Chelonia* this nerve is not distinguishable from the vagus.

In the genital organs, the Lizard and Reptiles generally are

distinguished from Amphibia by the complete separation of the mesonephros from the metanephros or functional part of the kidney. The mesonephros, now known as the epididymis, is only developed in the male, where it is closely connected with the testis. As in the Newt it receives the vasa efferentia. In the female the oviduct is shorter and has a wider internal funnel than in the Amphibia, and it is also placed further back, so as to be rather nearer to the ovary. This is an arrangement suited to the large size of the eggs, which are too heavy to be drawn any distance by the current produced by the cilia of the oviduct.

The egg is fertilized whilst still in the oviduct. The male lizard has two organs called copulatory sacs or penes, situated, one on each side, on the hinder wall of the cloaca. These, when not in use, are hollow pouches opening into the cloaca. When in use they are turned inside out, and are then seen to have grooves leading to the openings of the vasa deferentia or archinephric ducts.

Most lizards lay their eggs in crevices amongst stones, and allow them to be hatched by the heat of the sun. In all cases a considerable amount of development goes on before they are laid. In the English species *Lacerta vivipara* the young burst through the egg-shell and use up all the yolk whilst they are still in the oviduct, so that in common parlance they are born alive, that is, as little lizards, and not as eggs.

Order I. Rhynchocephala.

As mentioned above, the order Rhynchocephala is represented by the single species, *Sphenodon punctatus*, found only in New Zealand. This is a very Lizard-like animal. The back is covered with small scales which in the middle line form a comb-like crest: the belly is covered with large square scales. In the skeleton and male genital organs, however, *Sphenodon* is widely different from the Lizard. The quadrate in the skull is quite immovable, being firmly clamped by the squamosal and quadratojugal. The latero-temporal fossa is thus completely bounded below and the supra-temporal fossa is uncovered. Between the parietals is a gap called the interparietal foramen: in this is situated the tip of the pineal body which has here all the characters of a simple eye (see p. 321).

The animal has teeth when young, but they become worn away,

and the edges of the maxilla and premaxilla become converted into cutting edges.

The vertebrae are amphicoelous, and the basi-ventrals, represented by the sub-vertebral wedge bones and chevrons, are placed beneath the interspaces between the vertebrae throughout neck, trunk and tail, and not as Lizards in the neck and tail regions only.




FIG. 263. Skull of *Sphenodon punctatus* x 1.

A. Lateral. B. Dorsal. C. Ventral. D. Posterior. After von Zittel.

1. Premaxilla. 2. Nasal. 3. Prefrontal. 4. Frontal. 5. Post-frontal. 6. Parietal. 7. Squamosal. 8. Quadratojugal. 9. Quadrate. 10. Postorbital. 11. Jugal. 12. Maxilla. 13. Vomer. 14. Palatine. 15. Pterygoid. 16. Ectopterygoid or transverse bone. 17. Exoccipital. 18. Epipterygoid. 19. Basisphenoid. 20. Supratemporal fossa. 21. Lateral temporal fossa. 22. Orbit. 23. Post-temporal fossa. 24. Foramen magnum. 25. Anterior nares. 26. Interparietal foramen. 27. Dentary. 28. Supra-angular. 29. Articular.

The ribs have three divisions, there being a small intermediate piece intercalated between the dorsal and sternal rib. From the dorsal rib a hook-like outgrowth, the uncinat process, projects backwards, which overlaps the next rib as in Crocodiles and Birds.

Behind the sternum there is a long series of rod-like bones, the so-called abdominal ribs, embedded in the muscles of the belly.

They are placed parallel to the direction of the sternal ribs, that is they slope obliquely forwards and inwards. They are regarded as membrane bones and supposed to correspond to the ventral fish-like scales of the Stegocephala.

All these peculiarities of the skeleton are found in many of the oldest fossil reptiles.

There is no proper copulatory organ: the cloaca is used for this purpose just as in the Urodela.

From a condition in many respects represented at the present day by *Sphenodon*, the ancestors of living reptiles appear to have diverged in two directions.

On the one hand, the original stock gave rise to descendants with long flexible bodies and extensible jaws—this latter feature involving of course a moveable quadrate. The cloaca became converted into a transverse slit and copulatory organs became developed behind it. This stock includes the Snakes and Lizards which are often included in the one comprehensive order the Sauria.

On the other hand, the descendants of the common ancestral form diverged in the direction of heavily armoured forms, in which membrane bones underlying the scales were developed and in which the jaws are very powerful, the quadrate remaining immoveably clamped by the quadratojugal. The cloaca became a longitudinal slit and developed the single median copulatory organ on its front wall. This stock includes the Turtles and Crocodiles.

SAURIA.

We now turn to the SAURIA. Most people would imagine that the task of distinguishing a lizard from a snake was an easy one. But if we were to collect together all the limbless species of Reptiles we should find, not only that they differed very much from one another in the structure of the skull, and in other points, but that they were more nearly related to different families of lizards than to one another. There is no doubt that the snake-like forms have been derived from four-limbed reptiles like lizards, for some of them have rudimentary vestiges of limbs. It is evident then that there must be an advantage in certain situations in getting rid of limbs, and it is further evident that the effect of this advantage has been that not only in one but in many families of lizards

some species have lost their limbs. The kind of life to which a snake-like form is suited is a lurking one amongst crevices in stones, or thick vegetation, or in the soil, where movement is best effected by wriggling, and limbs would be in the way.

Under these circumstances, we must either class together all limbless Sauria as snakes, and thus give up the idea that the members of an order must necessarily be descended from the same ancestral species, or else we must select one group as the true Snakes (Ophidia), the members of which have many other characters in common besides the negative one of having no limbs. This latter course is that which has been adopted by Huxley, who defines true snakes somewhat arbitrarily as those forms which have lost all




FIG. 264. A Lizard, *Anguis fragilis*, the blind-worm, slightly reduced.

trace of the pectoral girdle and of the urinary bladder, although they may retain traces of hind-limbs.

This course will be followed here, though it is doubtful whether the advantage gained is more than a putting off of the evil day; for the more closely the animal world is examined, the more frequently does evidence appear of the composite origin of the groups which zoologists make. The real connection between the members of these groups seems to be that their ancestors have undergone a set of similar changes, occurring in the same order: it stands to reason, that if the world in geological times at all resembled what it does now, similar species would undergo similar modifications, under the stress of natural selection, and hence similarity of structure must be regarded as the result primarily of

similarity of experience, not from blood relationship in the strict sense of the term.

Order II. Lacertilia.

The Lacertilia, then, include all species of Sauria which have the right and left halves of their mandibles connected by a sutural symphysis. They also have a pectoral arch and a bladder, and are a very diversified group. Some, e.g. *Draco volans*, have the hinder ribs expanded so as to press out two expansions of skin and form a parachute-like expansion on each side, by means of which they are supported as they flit from tree to tree in great leaps. Most feed on insects, worms, &c. like the English lizards; some are large enough to seize mice and birds and frogs. The limbless forms are represented in England by the Blind- or Slow-worm, *Anguis fragilis*, and in North America by the allied glass-snake, *Ophisaurus ventralis*. These animals have skulls like that of *Lacerta* and rudiments of pectoral girdles. Besides the Blind-worm, the Common Lizard, *Lacerta vivipara*, and the Sand-Lizard, *Lacerta agilis*, are British.

In North America four families of Lizards are represented, one being that of the limbless ANGUIDAE, and the most remarkable of the others is that of the IGUANIDAE. These animals have short, thick tongues, and overlapping scales which form a crest of spines on the head and back and round the throat. *Phrynosoma douglasi*, the horned "toad," is found all through the Central States and even penetrates into Ontario; it is the sole lizard found in Eastern Canada.

Order III. Ophidia.

The Ophidia, or true snakes according to definition, have the right and left halves of the mandible connected by an elastic band; they are also devoid of a urinary bladder and of any trace of a pectoral girdle. Besides this however they have a large number of other characters which severally are shared by some families of Lizards but which collectively are found only in the Ophidia.

The vertebrae in addition to the zygapophyses on the sides of the neural arch have median bosses and pits by which they fit into one another, called respectively zygantra and zygosphenes (Gr. *ἄντρον*, a cave or hollow; *σφήν*, a wedge). There are no sternal ribs or sternum, but the dorsal ribs are elongated and curved ventrally,

and a snake literally walks on the ends of them; it is in a sense a vertebrate centipede.

In the skull the chief point to be noticed is the extreme mobility of the jaws. The jugal as well as the quadratojugal has disappeared, the pterygoids no longer articulate with the base of the skull, and the quadrate itself is pushed away from the cranium by the squamosal, which is a rod-like bone (Fig. 265). The result of




FIG. 265. Dorsal (to the left) and ventral (to the right) views of the skull of the Common Snake, *Tropidonotus natrix*. After Parker.

1. Premaxillae (fused). 2. Anterior nares. 3. Nasal. 4. Prefrontal.
 5. Frontal. 6. Parietal. 7. Maxilla. 8. Transverse bone.
 9. Palatine. 10. Pterygoid. 11. Pro-otic. 12. Exoccipital.
 13. Supra-occipital. 14. Opisthotic. 15. Epi-otic. 16. Quadrate.
 17. Parasphenoid. 18. Basisphenoid. 19. Basisphenoid. 20. Occipital condyle.
 21. Splenial. 22. Dentary. 23. Angular. 24. Articular.
 25. Supra-angular. 26. Coronoid. 27. Vomer. 28. Squamosal.
- IX, X. Foramina for the ninth and tenth cranial nerves.

this arrangement is that when the lower jaw is pulled down, the quadrate is quite free to thrust the pterygoid forward and push up the maxilla by means of the transverse bone; that is to say there is the same mechanism as was described in the lizard, only more easily set in motion and capable of much more movement. The halves of the mandible, or lower jaw, are connected by elastic fibres, and thus they can be widely separated. The result of this is, that a snake has an enormous gape and can swallow prey almost as large as itself. Snakes of quite moderate size dispose of frogs, birds, &c. The large Pythons of India can crush an animal larger than a half-

grown sheep into a shapeless mass by coiling themselves around it, and they then swallow it whole.

The hyoid, including under that name the remains of all the hinder visceral arches, is rudimentary, consisting of a single bone on each side. This permits of the pulling of the glottis far forward between the halves of the mandible when the animal is engaged in swallowing its prey, otherwise choking would result.

In the skull the brain extends forwards between the eyes and there is consequently no interorbital septum. That this is a secondary and not a primary state of affairs is shown by the fact that the front part of the brain is protected at the sides by downward extensions of the frontal and parietal bones, whereas in animals, such as the Urodela and Mammalia, where an interorbital septum has never been formed, the side-walls of the cranium are constituted by the orbitosphenoid and alisphenoid bones. It is curious to find this absence of an interorbital septum in a family of limbless lizards, the AMPHISBAENIDAE. What relation, if any, it has to the snake-like habits it is hard to guess.

One lung is small, and the other (the right) greatly elongated, the hinder part being quite smooth. One pulmonary artery supplies both lungs, the other has disappeared.

The two eyelids have coalesced to form an extra guard in front of the eye, but there is a transparent portion in the lower one through which the animal can see. The outer covering of scales is shed periodically, half-a-dozen times every year or oftener and replaced by a new set formed by the activity of the ectoderm, and during this process, since the covering of the eye is affected, the snake is blind.

Snakes are divided into many families, of which two are represented in Great Britain and three in the temperate parts of North America. A rough classification would divide them according to their habits into: (a) those which poison their prey, (b) those which crush their prey, and (c) those which swallow their prey directly.




FIG. 266. Diagram of Arterial Arch of Snake viewed from the ventral aspect.

- I. First arterial arch. II. Second arterial arch.
- IV. Fourth arterial arch.
- 15. Pulmonary artery.
- 16. Dorsal aorta. 17. Right auricle. 18. Left auricle. 19. Ventricle.

Those which crush their prey are confined to the tropics; those which swallow their prey directly are the non-venomous snakes, and are represented in both England and North America by the family COLUBRIDAE. In this family the maxilla is long and bears numerous teeth, as does also the pterygoid and the lower jaw. The head is much broader behind than at the muzzle. There are about thirty species belonging to eighteen genera in North America,




FIG. 267. The Texas Rattlesnake, *Crotalus atrox*, from Stejneger after Baird and Girard. Reduced.

of which *Tropidonotus sirtalis*, the garter-snake frequently met with in Canada, is one of the commonest; and in England the family is represented by two species, the smooth-snake, *Urodonella laevis*, and the grass- or ring-snake, *Tropidonotus natrix*.

The venomous snakes in America belong to two families. In the first, the ELAPIDAE, the maxilla is a long bone and bears in

front two large teeth which are grooved, to allow the secretion of glands in the lip to trickle down into the wound which they make. The teeth behind are not grooved. The American Harlequin Snake, *Elaps fulvius*, belongs to this family. This snake receives its name from its brilliant colours; it has seventeen crimson rings bordered with yellow. Another family is that of the VIPERIDAE. The maxilla is much shortened and bears one enormous fang, which when the mouth is closed lies against the roof of the mouth: when the mouth is opened the maxilla is rotated by means of the ecto-pterygoid, so as to erect the tooth. The typical Rattlesnake—*Crotalus horridus* or *C. atrox*—derives its name from an appendage of about 8 to 9 loosely connected horny rings which it bears at the end of its tail, the shaking of which makes a noise like a rattle. This is one of the most deadly snakes known: it is found all over the United States in mountainous places and enters Canada. Like all CROTALINAE or Pit-vipers it has a sensory pit between eye and nose. The English Adder, *Vipera berus*, is like all the Old-World Viperinae devoid of such pits.

Order IV. Chelonia.

The Chelonia or Turtles are the most peculiar order of the Reptilia. In some respects they are nearest to the Amphibia, but they are highly specialized. Their leading peculiarity is the possession of two great shields, a dorsal the carapace and a ventral the plastron, composed of bones firmly connected together, so that most of the organs of the body are enclosed in a box. The horny scales which cover in this box are very large and form what is known as tortoise-shell. The carapace is formed of a central row of neural plates which are expansions of the spines of the dorsal vertebrae with a nuchal plate in front of these and a pygal behind, the two last-named being of dermal origin.

On each side there are costal plates; this name is given to broad expansions of the outer surfaces of the ribs (Fig. 268). The ribs curve inwards to join the centrum, and since this, as in all Reptiles, is formed by the interventral, each rib is nearly opposite the interspace between two centra and sometimes unites with them both. The transverse process is represented by the expansion of the neural plate which meets the costal plate. The almost horizontally directed outer ends of the ribs are received into a series of dermal bones called marginals, which form the edge of the carapace.




FIG. 268. A, Dorsal and B, ventral view of the carapace of a Loggerhead Turtle, *Thalassochelys caretta*. After Owen. In A the outlines of the superficial horny scales constituting the tortoise-shell are indicated by heavy lines, whilst the outlines of the bones of which the carapace is composed are represented by lighter lines.

1. Nuchal plate. 2. First neural plate. 3. Second costal plate.
4. Marginal plate. 5. Pygal plate. 6. Rib. 7. Thoracic vertebra.
8. First vertebral shield. 9. Costal shield.

In front and behind the plastron and carapace are separated by soft flexible skin; their edges project so as to form roof and floor to cavities into which the head and neck and arms in front and the legs and tail behind can be withdrawn. A study of the development of modern *Chelonia* and of the anatomy of fossil species makes it plain that the ancestors of the present forms were provided with a carapace composed entirely of dermal bones underlying the horny scales, just as is the case with *Crocodylia*. This dermal carapace however was gradually replaced by the development of bony expansions of the ribs and neural arches; though remnants of it persist in the nuchal, pygal, and marginal plates.

There is no trace of sternal ribs or sternum: but the pectoral

and pelvic girdles occupy the peculiar position of being within instead of outside the ribs, a consequence of the almost horizontal direction of these. The girdles are in fact converted into pillars or struts which keep the plastron and carapace apart. In front the scapula forms a vertical pillar and is completely fused with the precoracoid; the two are separated by a suture from the coracoid, which slopes backwards and inwards. The ilium and pubis serve to support the carapace posteriorly. The pelvic girdle is similar to




FIG. 269. The Plastron of a Green Turtle, *Chelone midas* $\times \frac{1}{4}$. (Camb. Mus.)

1. Epiplastron (clavicle). 2. Entoplastron (interclavicle). 3. Hyoplastron.
4. Hypoplastron. 5. Xiphiplastron.

that of a Lizard but the pectoral girdle has no epicoracoid. The limbs are essentially similar to those of the Lizard but the toes are shorter and blunter. The neck is extraordinarily flexible; the vertebrae composing it fit one another by cup and ball joints, one is amphicoelous, another is biconvex. The dorsal vertebrae have flat faces.'

'The skull is utterly devoid of teeth and the premaxilla and maxilla are short. Both they and the dentary have sharp cutting edges ensheathed in horn so as to form a kind of beak. In all

species the orbit is encircled with a bony ring and the ectopterygoid is wanting. The palatal crest on the palatine is hardly perceptible. The squamosal does not usually join either the postfrontal or parietal: hence the upper temporal arcade is absent and there is




FIG. 270. Ventral view of the Skeleton of *Chelone midas*, the Green Turtle
 × about $\frac{1}{2}$. The plastron has been removed.

- | | | | |
|---------------------------|--------------------------|-----------------|-------------|
| 1. Lower jaw or mandible. | 2. Nuchal plate. | 3. Precoracoid. | 4. Scapula. |
| 5. Marginal bone. | 6. Coracoid. | 7. Ilium. | 8. Pubis. |
| 9. Ischium. | 10. Centrum of vertebra. | 11. Humerus. | 12. Radius. |
| 13. Ulna. | 14. Carpus. | 15. Femur. | 16. Tibia. |
| | | 17. Fibula. | |

no distinction between the supra-temporal and latero-temporal fossae. In the marine *Chelone* and its allies however the post-frontal, squamosal, parietal and quadratojugal coalesce to form a sheet of bone from the crest of the skull to the lip, roofing over a cavity lying at the side of the cranium and containing muscles.

Breathing is performed, as in *Amphibia*, by a mylohyoid muscle and other muscles causing movements of the hinder visceral arches, of which there are three pairs.

The copulatory organ is a grooved rod attached to the front




FIG. 271. Longitudinal vertical section through the Cranium of a Green Turtle, *Chelone mydas* $\times \frac{3}{4}$.

1. Parietal. 2. Squamosal. 3. Quadrate. 4. Basisphenoid. 5. Basis-occipital. 6. Quadratojugal. 7. Pro-otic. 8. Opisthotic. 9. Pterygoid. 10. Palatine. 11. Rod passed into narial passage. 12. Exoccipital. 13. Epi-otic fused to supra-occipital. 14. Supra-occipital. 15. Pre-maxilla. 16. Maxilla. 17. Jugal. 18. Postfrontal. 19. Vomer. 20. Prefrontal. 21. Frontal. V 1 & 2, VII, VIII, IX, X, XI, XII, foramina for the exit of cranial nerves.

wall of the cloaca. The groove leads to the openings of the male ducts, the vasa deferentia.

The members of the order Chelonia have very various habits and modes of life. Some are vegetable feeders, others purely animal. None are found in Great Britain, but the representatives of six groups are found in temperate North America. These are

- (1) The TESTUDINIDAE or Land Tortoises.
- (2) The EMYDIDAE or Pond Turtles.

- (3) The CINOSTERNIDAE or Box Turtles.
- (4) The CHELYDRIDAE or Snapping Turtles.
- (5) The TRIONYCHIDAE or Mud Turtles.
- (6) The CHELONIDAE or Marine Turtles.

The TESTUDINIDAE have a very arched carapace and short club-like limbs in which the toes are tightly bound together by skin. Only a few species, the burrowing gopher, *Testudo polyphemus*, the Gopher, and *Cistudo carolina*, the Box Tortoise, are known in temperate North America.

The EMYDIDAE are represented by many species. In this family the carapace has a wide horizontal margin and the toes are connected by a web. Most of the species are aquatic, a few however are almost as terrestrial as the TESTUDINIDAE. *Chrysemys picta*, the painted Pond Turtle, ranges north into the St Lawrence.

The CINOSTERNIDAE have a long and narrow carapace with the margins produced downwards: it is highest behind. The front part, and sometimes the hind part, of the plastron moves like a hinge on the rest and close in the head and tail, whence the name Box Turtle. Sole genus *Cinosternum*, e.g. *pennsylvanicum*.

The CHELYDRIDAE are the so-called Alligator- or Snapping-Turtles. The head, neck and tail are all large and cannot be completely protected between the carapace and plastron. The carapace is highest in front. The jaws are hooked and powerful, and the animals are very vicious. *Chelydra serpentina*, the "Snapper," is one of the commonest of American turtles. It is found everywhere from Canada to the tropics.

The TRIONYCHIDAE or Mud Turtles have no horny scales; both carapace and plastron are covered with leathery skin. There is a soft pig-like snout; only the three centre toes have claws. They seek their food by burrowing in the bottom of ponds.

The CHELONIDAE are distinguished by their peculiar skull and the absence of many or all of the nails. Their extremities have become flattened and form very efficient paddles.

Order V. Crocodilia.

The last and highest order of the Reptilia is the Crocodilia. These animals agree with the Chelonia in having a series of bony plates underlying the horny scales of the skin, also in having an immoveable quadrate and a single median copulatory organ.

The Crocodiles are of large size and are decidedly Lizard-like in

their general appearance, the chief observable external difference between them and the *Lacertilia* being in the jaws, which are exceedingly long in comparison with the rest of the skull, so that the gape is very wide.




FIG. 272. Palatal aspect, A, of the Cranium, B, of the Mandible of an Alligator, *Caiman latirostris* $\times \frac{1}{3}$.

1. Premaxilla. 2. Maxilla. 3. Palatine. 4. Pterygoid. 5. Posterior nares. 6. Transverse bone. 7. Posterior palatine vacuity. 8. Anterior palatine vacuity. 9. Basi-occipital. 10. Opening of median Eustachian canal. 11. Jugal. 12. Quadratojugal. 13. Quadrate. 14. Dentary. 15. Splenial. 16. Coronoid. 17. Supra-angular. 18. Angular. 19. Articular. 20. Lateral temporal fossa. 21. Openings for the passage of blood-vessels supplying the alveoli of the teeth.

The dermal plates form rings on the tail, but on the body, as in *Chelonia*, they form a dorsal and a ventral shield separated by intervening softer skin. In many Crocodiles the ventral shield is very rudimentary.

In the general arrangement of the bones and the temporal fossae the skull resembles that of *Sphenodon*: but there are great differences in the jaws and palate. The maxilla is very long and is

armed with conical teeth which are implanted in distinct sockets or alveoli, the bone having grown up round their bases.

The two palatal folds have met so as to completely divide the upper air passage from the lower food passage: both the palatines and the pterygoids being completely united in the middle line (Fig. 272). The choanae or posterior nares are therefore situated very far back directly over the glottis, whilst the external nostril is at the tip of the snout.

In consequence of this position of the external nostril the crocodile can lie for hours hidden under the water with only the tip of the snout exposed, and so surprise any unwary animal coming to the water to drink.




FIG. 273. First four Cervical Vertebrae of a Crocodile, *C. vulgaris*. Partly after von Zittel.

1. Neural spine of atlas. 2. Lateral portion of atlas. 3. Odontoid process. 4. Ventral portion of atlas. 5. Neural spine of axis.
6. Postzygapophysis of fourth vertebra. 7. Tubercular portion of fourth cervical rib.
8. First cervical rib. 9. Second cervical rib. 10. Convex posterior surface of centrum of fourth vertebra.

All the cervical and trunk vertebrae and some even of the caudal vertebrae bear ribs. The manner in which these ribs are articulated to the atlas and axis vertebrae throws much light on the relation of these peculiar vertebrae to the rest. Thus we observe that the first pair of ribs are articulated with their heads to the lower part of the atlas, showing that this represents a basi-ventral homologous with the intervertebral cartilaginous pads of the rest of the column. The heads of

the second pair of ribs are united to an intervertebral cartilage separating the odontoid process from the centrum of the second vertebra. This cartilage is therefore the second basiventral, and the odontoid process is the first interventral, homologous with the centra of all succeeding vertebrae. The tubercle of each of the second pair of ribs has also an attachment to the odontoid process lying obliquely above and behind the capitular attachment and hence the centrum of the axis vertebra has no rib attached to it. The third pair of ribs has shifted its capitular attachment back on the centrum of the third vertebra. This backward shifting of the

capitular attachment has taken place in all succeeding vertebrae, and the head of the rib is attached directly under its tubercle. In the trunk, as we proceed backwards, the capitular attachment to the centrum is gradually raised till it reaches the transverse process and is confounded with the tubercular attachment, and the hindmost vertebrae are single headed.

There are abdominal ribs, as in *Sphenodon*; they are arranged in transverse rows, each row on each side consisting of three or four bones (Fig. 274).

The pectoral girdle consists of simply a scapula and coracoid, the latter reaching the sternum, which is cartilaginous but protected ventrally by an interclavicle (Fig. 275). In the fore-limb the carpus has retained three bones in the proximal row, but the distal row consists of a block of cartilage representing the first and second carpalia and a bone representing the remaining three. There is consequently an intercarpal wrist-joint corresponding to the intertarsal joint common to Reptiles.

The pelvic girdle is very peculiar. The ilium is broad and rounded above and joins the two sacral vertebrae. The true pubis




FIG. 274. Sternum and Associated Membrane-bones of a Crocodile, *C. palustris* $\times \frac{1}{2}$.

The last pair of abdominal ribs which are united with the epipubes by a plate of cartilage have been omitted.

- | | | |
|--------------------------|------------------|-----------------|
| 1. Interclavicle. | 2. Sternum. | 3. Sternal rib. |
| 4. Abdominal splint rib. | 5. Sternal band. | |




FIG. 275. Left half of the Pectoral Girdle of an Alligator, *Caiman latirostris* $\times 2$.

1. Scapula. 2. Coracoid. 3. Interclavicle.
4. Glenoid cavity.

modified. It consists of a proximal row of two bones, one of which, the fibulare or calcaneum, forms a distinct heel. The distal row consists of two bones, one representing the first, second, and third tarsalia, the other the fourth and fifth.




FIG. 276. Pelvis and Sacrum of an Alligator, *Caiman latirostris* $\times 3$.

1. Ilium. 2. Ischium. 3. True pubis.
4. Epipubis (so-called pubis). 5. Acetabular foramen. 6. Neural spines of sacral vertebrae. 7. Union of the two ischial bones. 8. Process bearing prezygapophysis.

is a small round bone inserted and fused with the anterior edge of the ischium and ilium, but what is ordinarily called the pubis, or better the epipubis, is a bone directed forwards which does not meet its fellow, nor does it form any part of the socket for the femur or acetabulum (Fig. 276). This so-called pubis or epipubis can only be compared to that of Urodela and Marsupials. The tarsus, like the carpus, is much reduced and

The heart of the Crocodile is remarkable for the fact that the septum in the ventricle has grown forwards so as to completely divide it into two halves, the right and left ventricles. The left root of the aorta arises from the right ventricle and crosses the right root, which arises from the left ventricle and gives off the two carotids. The left root

wall of the cloaca: with a moveable quadrate, with a pectoral girdle, and with the rami of the mandibles united by a zymophysis.

Ex. *Lacerta*, *Anguis*.

Order 3. Ophidia.

Reptilia with two copulatory sacs on the posterior wall of the cloaca: with a moveable quadrate but with no trace of a pectoral girdle; with the rami of the under-jaw united by ligament.

Ex. *Crotalus*, *Vipera*, *Tropidonotus*.

Order 4. Chelonia.

Reptilia with one median copulatory organ on the anterior wall of the cloaca, an immoveable quadrate. No sternum, the ribs expanded horizontally to form a dorsal shield: a ventral shield of dermal bone is present.

Ex. *Testudo*, *Chelone*.

Order 5. Crocodilia.

Reptilia with one median copulatory organ on the anterior wall of the cloaca, an immoveable quadrate. A well-developed sternum, joined by the ribs.

Ex. *Crocodylus*, *Alligator*, *Gavialis*.

CHAPTER XVIII.

SUB-PHYLUM IV. CRANIATA.

Class IV. AVES.

It is probable that if the first child one met were asked to describe a bird, he would say that birds were animals which were covered with feathers and had wings to fly with. Though it often happens that the marks by which the ordinary person distinguishes one animal from another are not those which seem most important to a Zoologist, yet in this case the Zoologist could not find more important features to serve as the basis of a definition of the class Aves or Birds.

Birds then are vertebrate animals in which the fore-limb is modified into a wing or flying organ and in which the body is covered with feathers. Bats likewise have the fore-limb converted into a wing, but they are covered with hair, not feathers, and their wing is not constructed on the same plan as that of the bird.

Birds are sometimes classed along with the Reptiles as Sauropsida, since they have a good many features in common with them, and are contrasted with the Mammalia, or ordinary quadrupeds. This, however, gives a wrong view of the relationships of the three groups. Both Birds and Mammals are believed to be descended from Reptilian-like ancestors, and it is an open question, whether the changes which Birds have undergone are not at least as important as those which have taken place in Mammals in the process of their evolution from ancestors which, had they lived now, would have been termed Reptiles.

Birds agree with Reptiles in that they lay large eggs, from which the young are hatched in a form closely resembling the

parent; they are like Reptiles also in the structure of their jaws—the lower jaw consisting of five bones and articulating with a quadrate bone—and in the structure of the hinder part of their skulls, of their breast-bones, and of their ankle-joints. The vertebrae very rarely have epiphyses like those of Mammals; though they are found in Parrots. As in Reptiles, the number of neck vertebrae is variable. Like Reptiles, Birds have nuclei in the red corpuscles of the blood, and the sole remaining complete arterial arch goes to the right (Fig. 285), like the principal arch in Reptiles. On the other hand, they are warm-blooded, that is to say, the temperature of the blood remains practically the same and does not alter as the surrounding air gets hot or cold; it is in fact higher than that of the blood of any mammal; the ventricle of the heart is completely divided into two, and in addition to the wings and feathers, the structure of the leg and hip-bones and of the brain, distinguishes them from any living Reptile.

Strange as the statement may appear, it is true, nevertheless,

Feathers.

that the feathers are really scales like those found in lizards, immensely developed and with the edges frayed out. Like scales, they are epidermal, that is, developments of the outer or horny layer of skin. The area which is about to form the feather becomes raised into a little finger-shaped knob by the growth of the deep sensitive layer of the skin or dermis which carries the blood-vessels. The little knob thus formed is in turn sunk in a pit called the follicle, the skin immediately surrounding it being depressed. Thus the lowest part of the feather is a little hollow tube of horny cells formed round the knob of dermis, but the upper part, like the scale of a lizard, is only formed on one side of the knob, and this part as it is pushed away by the growth of the deeper parts becomes frayed out so as to form the vane of the feather. In the latter we can distinguish a central stem or rachis, and two rows of branches or barbs, which are kept in position by a number of secondary processes or barbules. The barbules bear little hooks which interlock with one another. Down consists of small feathers growing between the bases of the larger ones. In these the barbules are absent, so that the barbs are not held together but float freely about, forming a kind of fluff. When a bird is plucked it is seen that the feathers are confined to certain tracts separated by others called apteria devoid of feathers. Thus in most birds the mid-ventral and mid-dorsal lines are apteria. The colour of the feathers is partly due to coloured

substances or pigments in the epidermal cells and partly to minute ridges which cause interference of the light reflected from them.

That the wing is really only the fore-leg or arm is clear at once to anyone who has ever seen a plucked bird. One can recognise the parts corresponding to upper arm, fore-arm and hand, and it is easy to perceive by gently squeezing the wing that the first bone mentioned consists as usual of a single bone, the humerus, and the second of two bones placed side by side, the radius and the ulna.




FIG. 277. Section through the Skin of a Bird showing a developing Feather. Highly magnified.

1. Epidermis. 2. Malpighian layer. 3. Dermis. 4. Young feather.
5. Follicle round base of feather. 6. Pulp which develops blood vessel and is the organ of nutrition of the feather.

When the wing is at rest the upper arm extends backwards, the fore-arm is sharply bent up on this, the wrist again is sharply bent down. When the wing is expanded these are partially, but never entirely, straightened out, so that a bird begins the downstroke of the wing with the arm bent in a very similar way to that in which a swimmer's arm is bent when he strikes back with it. In the hand we find as a rule three digits, the first, second and third.

These have their first joints, the metacarpal bones, closely united together. In Man the metacarpals of the various fingers are united by a web of skin and flesh which constitutes the palm, but they are moveable on one another, whereas in the bird the metacarpals of the second and third digits are firmly joined at both ends. The index has in addition to the metacarpal, in most birds, three other small bones called phalanges, of which the end one sometimes carries a claw, thus emphasising the fact that the wing is an arm; the third digit has only one bone or phalanx besides the metacarpal. The metacarpal of the first digit or thumb is very small, but is likewise completely soldered to the other metacarpals. Besides this the thumb has two joints and often a claw.

Compared with the arm or fore-leg of other animals the arm of a bird strikes one as being very skinny. This is because the muscles which make up the bulk of ordinary arms are very poorly developed; thus the fingers, whose muscles usually constitute the bulk of the flesh of the fore-arm, cannot be moved on one another, and so we need not wonder that the fore-arm is poorly developed. Further, the movement of the arm on the fore-arm is simple in character, namely, a movement of bending and unbending, and this only when the wing is being expanded, hence a few muscles suffice for its needs and the upper-arm is consequently as thin as the fore-arm.

The movements which constitute flying, namely, the powerful down-stroke of the whole arm and the slower up-stroke, are carried out by the immensely developed breast muscles, great fleshy masses which cover the breast-bone or sternum. This bone has a more or less pear-shaped outline, rounded in front and pointed behind, the ribs ending in its sides (Fig. 279). In accordance with the tendency in all birds to develop the body into a long neck and a rounded trunk, we find evidence that the number of ribs encircling the body and joining the sternum has been reduced. Not only do we find




FIG. 278. Bones of the right Wing of a Gannet, *Sula alba* $\times \frac{1}{3}$

- | | |
|----------------------|-----------------------|
| 1. Humerus. | 2. Radius. |
| 3. Ulna. | 4. Second metacarpal. |
| 5. Third metacarpal. | 6. Thumb or pollex. |
| 7. Second digit. | |
- The distal phalanges of the thumb and second digit were wanting in the specimen from which this figure was drawn.

small free ribs connected with the hinder cervical vertebrae, but attached to the sternum are outgrowths called costal and xiphoid processes (Fig. 279) which are regarded as the remains of sternal ribs the dorsal halves of which are rudimentary or lost. If we picture to ourselves the pectoral girdle being thrust backwards and the pelvic girdle forwards so as to crowd the viscera into a small space we shall realize the meaning of the differences between the skeleton of the trunk of a Reptile and that of a Bird. From the middle line of the sternum projects a great vertical crest stretching outwards, called the carina or keel, and it is from the sides of this mainly that the breast muscles take their origin. There are two main muscles on each side. First the pectoralis major on the surface, which passes into a tendon attached to the upper end of the humerus. The contraction of this muscle brings about the down-stroke of the wing, the effective stroke in flying. Underneath the pectoralis major is situated the pectoralis minor, a much smaller muscle. Its tendon passes underneath the arch formed by the clavicle and the coracoid bone, the latter of which, as in Reptiles, connects the shoulder-blade firmly with the sternum. Having passed through this arch the tendon is attached to the back of the humerus, so that the contraction of the muscle pulls the humerus and thus the wing upwards and backwards and not downwards, the upper end of the coracoid acting as a pulley round which it passes.




FIG. 279. Shoulder-girdle and Sternum of Peacock, *Pavo cristatus* $\times \frac{2}{3}$.

1. Carina of the sternum. 2. Coracoid. 3. Scapula. 4. Clavicle. 5. Costal process. 6. Surfaces for articulation with the sternal ribs. 7. Posterior (xiphoid) and oblique processes.

Returning to the wing, we must now notice how the feathers are arranged. The great quill feathers are attached chiefly to the upper and posterior edge of the hand, but there are also a large number which are implanted in the posterior surface of the ulna. These two groups of feathers are pushed one over the other when the wing is folded, just like the silk of a closed umbrella, but when the wing is stretched out they only overlap very slightly, and thus a coherent




FIG. 280.

FIG. 280. Wing of a Wild Duck, *Anas boschas* $\times \frac{1}{3}$.

- A. Right wing seen from the dorsal side, with the coverts removed. B. Left wing disarticulated and seen from the ventral side, with the coverts removed. C. The dorsal side of a right wing. D. The ventral side of a left wing. From Wray, *P. Z. S.*

- In A and B. 1. Humerus. 2. Radius. 3. Ulna. 4. Radial carpal. 5. Ulna carpal. 6. First phalanx of first digit. 7. Second metacarpal. 8. Third metacarpal. 9. First phalanx of second digit. 10. Second phalanx of second digit. 11. Vestigial quill. 12. Tertiaries. 13. Secondaries. 14--17. Primaries.

- In C and D. 1, 2, 3, 5, and 7. Coverts. 4. Bastard wing. 6. Primaries. 8. Secondaries. 9, 10. Tertiaries.

and practically air-tight surface is formed. Those feathers which are attached to the hand are called primaries (6, Fig. 280, C), those arising from the ulna, secondaries (8, Fig. 280, C); a few arising from the upper arm are called tertiaries; any air which might escape between the bases of the long feathers is stopped by an upper layer of shorter feathers, called coverts (2, 3, 5 and 7, Fig. 280, C and D). Air is prevented from escaping in front by the hand, which is stretched out in a vertical plane, and by two folds of skin, one in the angle between fore-arm and upper arm, the other between the upper arm and the body. The name bastard-wing is given to a tuft of feathers borne by the thumb (4 Fig. 280, C and D).

The full mechanical explanation how the down-stroke of the wing not only prevents a bird from falling but urges
Flight. it onwards is not completely understood, and much

of what is generally accepted is too complicated for an elementary text-book, but the broad principles involved may be simply set forth. A bird when it is in the air, like any other heavy body, is continually falling: the blow of the wing has therefore not only to effect a forward impulse, but also an upward one sufficient to compensate for the distance the bird has fallen between two strokes. These impulses are of course derived from the elastic reaction of the air compressed by the down-stroke of the wing. When the wing is expanded, it is slightly convex above and concave beneath. This arises from the fact that the quill feathers are attached to the upper edge of the webbed limb and project gently downwards and backwards, so that there is a space left which is bounded behind by the quills, and in front by the bones and web of the limb. Now if this space had a symmetrical shape the air would be compressed in such a way that the resultant impulse would be directly upwards; but it is not symmetrical, for its roof has a very

steep slope in front and a very gentle one behind, and the air is compressed in such a way that an oblique reaction results, a reaction which we can resolve by the parallelogram of forces into an upward and an onward one. So much for the flight of a bird in still air. The air is, however, very rarely still, and the currents which exist are never quite horizontal, but generally inclined slightly upwards, since the lowest layer of air is checked by friction against the ground, and birds which are good flyers can, by inclining their wings at the proper angle, obtain quite sufficient support from the play of the current against the wing without exerting themselves to any great extent. This is called soaring, and can be beautifully seen in the flight of the Sea-gull. In




FIG. 281. Lateral view of the Pelvis and Sacrum of a Duck, *Anas boschas*. $\times \frac{3}{4}$.

1. Ilium. 2. Ischium. 3. Pubis. 4. Pectineal process, the rudiment of the prepubis corresponding to the pubis of the Lizard. 5. Acetabulum. 6. Ilio-ischiatic foramen. 7. Fused vertebrae. 8. Facet on which the projection on the femur, the trochanter, plays.

this manœuvre birds are assisted by the tail, which is really a fan-shaped tuft of strong feathers, attached to the coccyx, that very small vestige of a true tail, or portion of the vertebral column extending behind the anus, which modern birds possess (Fig. 282). In this region the vertebrae are thin disks, several of which may be soldered together so as to form a bone called the pygostyle.

The legs of birds can be shown to be constructed on essentially the same type as those of Reptiles, but modified so as to enable them to support the body in an upright position.

The arrangements to effect this are very interesting, as they differ markedly from those found in the human skeleton.

In the pelvic girdle the ilia are lengthened so as to be attached to a considerable number of vertebrae, six or more, and




FIG. 282. Skeleton of the Common Fowl, ♂, *Gallus bankiva*. $\times \frac{1}{2}$.

Premaxilla. 2. Nasal. 3. Lachrymal. 4. Frontal. 5. Mandible.
 6. Lower temporal arcade in region of quadratojugal. 7. Tympanic
 cavity. 8. Cervical vertebrae. 9. Ulna. 10. Humerus.
 11. Radius. 12. Carpo-metacarpus. 13. First phalanx of second
 digit. 14. Third digit. 15. Second digit. 16. Ilium.
 17. Ilio-ischiatic foramen. 18. Pygostyle. 19. Femur.
 20. Tibio-tarsus. 21. Fibula. 22. Patella. 23. Tarso-
 metatarsus. 24. First toe. 25. Second toe. 26. Third toe.
 27. Fourth toe. 28. Spur. 29. Pubis. 30. Ischium.
 31. Clavicle. 32. Coracoid. 33. Keel of sternum. 34. Xiphoid
 process. The forked bone just in front of 7, is the Quadrate.

so a firm attachment of the limb to the main skeleton is effected. In Reptiles only two vertebrae are joined to the ilium, but in their case the weight of the body is supported on all four limbs, whereas in a Bird the whole vertebral column has to be balanced about two points of support, and hence the ilium must be quite immovably strapped to the vertebral column. The result of this has been to cause some of the hinder ribs to atrophy: and the ventral halves of some of these form the xiphoid processes of the sternum. The ischium is directed backwards parallel to the hinder part of the ilium, and often fused with it so as to surround a space called the ilio-ischiatic foramen. The pubis is a very slender bone which is also directed backwards. It is in fact a postpubis corresponding to the lateral process on the pubis of the lizard (see p. 450). The two pubes never, as in Reptiles and Mammalia, unite with one another ventral to the cloaca, the absence of a pubic symphysis (except in the Ostrich) facilitating the laying of the egg, which is very large relatively to the size of the animal. The thigh is bent sharply forwards and the shank backwards, and the ankle is raised to a considerable height above the ground by the great length and upward direction of the bones of the sole or metatarsals (Fig. 282). Thus a Bird walks on its toes and like Reptiles possesses an intertarsal ankle-joint. In Birds however, in order to give firmness to the leg, the metatarsals are closely united together and the small bones of the tarsus have entirely disappeared, the proximal row having been incorporated with the tibia, whilst the distal bones have fused with the metatarsals. Thus in an adult Bird the ankle-joint is a simple hinge between two compact bones, the upper being a tibia-tarsus, the lower a tarso-metatarsus. There are usually four toes, but the first, corresponding to the human great toe, is sometimes, like the fifth, absent, its metatarsal remains distinct from the other three. It is, except in *Steganopodes*, generally directed backwards. The raised sole of the foot really constitutes the visible "leg" of most birds, the thigh being altogether, and the shank mostly, buried in the feathers. In many birds the sole is plated by scales which are raised horny plates of skin, similar to the scales of Reptiles.

The most characteristic features about a bird, next to the limbs and feathers, are certainly the head and neck. The skull is high and arched behind in order to make room for the comparatively large brain; in front it slopes gradually downwards to the pointed beak, which is encased

Head and
Neck.

one another. The eyes are of great size: a bird has little or no sense of smell, and governs its life mainly by the sense of sight, and in correspondence the orbits or eye-sockets are so enlarged that the skull between them is reduced to a thin vertical plate, the inter-orbital septum, in which there is no brain cavity. This great development of the eye-sockets and the obliteration of the brain cavity between them is not, however, confined to birds: it is found as already mentioned in many reptiles also, and is indeed one of the several points in which a bird's skull may be said to be Reptilian. It is however characteristic of Birds, as opposed to Reptiles, that this interorbital septum is largely converted into bone. In its hinder and upper portions it is composed of orbito-sphenoid bones, like those found in Teleostean fish, which support the exit of the optic nerve, but in its lower part it is composed of a vertically compressed presphenoid bone corresponding to that which ossifies the front part of the floor of the cranium in Mammalia. In front the interorbital septum is continuous with the internasal or ethmoid septum: this latter is ossified by a mesethmoid bone, which unites, but not quite immoveably, with the presphenoid. The hinder part of the floor of the cranium is ossified by the basioccipital and basisphenoid bones, and the front of the latter is drawn out into a long spur called the basisphenoidal rostrum. Underlying the basisphenoid there is a membrane-bone called the basitemporal, a relic of the parasphenoid of Fishes and Amphibia. In some Reptiles traces of the front part of this bone remain, but never any of the hinder portion, an indication that Birds are descended from a type of Reptile more primitive in some respects than any now existing. Other points of resemblance to Reptiles are that the lower jaw is made up of no less than five distinct bones interlocking with each other; and that instead of there being a direct hinging or articulation of the lower jaw to the skull, a

bone called the quadrate is interposed, as in Reptiles, which articulates on the one hand with the lower jaw and on the other with the skull. This quadrate bone is moveable, and to it in front are jointed the bones of the palate, the pterygoids and palatines, which slide on, but are not fixed to the base of the skull. So that when the lower jaw is opened, i.e. pulled down, these bones are pushed forward, and the upper beak, to which they are fastened in front, is slightly tilted up, thus increasing the width of the gape. In parrots the front part of the skull, including the bones of the




FIG. 283. Brain of Pigeon, *Columba livia*. \times about 2.

- | | | | |
|-----------------------|--------------------------|--------------------------------|-------------------|
| 1. Optic lobes. | 2. Cerebral hemispheres. | 3. Pineal gland. | 4. Optic lobes. |
| 4a. Optic chiasma. | 5. Cerebellum. | 6. Lateral lobe of cerebellum. | II. Optic nerves. |
| III. Motor oculi. | IV. Patheticus. | V. Trigeminal. | VI. Abducens. |
| VII. Facial. | VIII. Auditory. | IX. Glossopharyngeal. | X. Vagus. |
| XI. Spinal accessory. | XII. Hypoglossul. | | |

face, has an actual joint with the hinder part of the skull. Thus it follows that in spite of the presence of a quadratojugal the quadrate is moveable. It is to be remembered however that the quadratojugal is here a small flexible bone, very unlike the great bony bar of *Chelonia* and *Crocodylia*. The hyoid apparatus consists of the second and third pairs of visceral arches. The second pair, which correspond to the hyoid of Fish, are very short and mainly consist of the median piece or glosso-hyal which is closely connected to the median piece of the third pair. The latter are elongated rods to which are attached the muscles which protrude the tongue. As

in the Reptilia, the skull has one central knob or condyle for articulation with the backbone, not two, as is the case with the Amphibia and Mammalia.

The features peculiar to the Bird are, firstly, the great elongation of the premaxilla carrying the beak—this causes the nostrils to be placed at the base of the snout instead of at the tip, as is the case with Reptiles; secondly, the enormous size of the orbit and the absence of any bony bar to separate it from the temporal fossa, or hollow on the side of the skull, in which the muscles that close the jaws lie; and, thirdly, the height and arched character of the hinder part of the skull, which lodges the brain.

The bones of the skull are usually indistinguishably united in the adult and are hollow and contain air, and are in consequence very light, as befits an animal which flies. Similar air spaces also exist in the larger bones of the trunk and limbs. The insects, which also have taken to the air, have somewhat analogous air reservoirs. Like the birds, insects also show a large number of species which all exhibit great uniformity of structure.




FIG. 284. Third Cervical Vertebra of an Ostrich, *Struthio camelus*. $\times 1$. A, anterior, B, posterior, C, dorsal view. A and B after Mivart.

1. Neural spine. 2. Neural canal. 3. Prezygapophysis. 4. Postzygapophysis. 5. Posterior articular surface of centrum. 6. Anterior articular surface of centrum. 7. Vertebral arterial canal. 8. Hypapophysis, a median ventral outgrowth of centrum.

When the brain itself is examined, the meaning of many of the peculiarities of the skull are seen. What we might perhaps, with a little exaggeration, call the organs of

The Brain.

thought, the hemispheres of the fore-brain, are greatly enlarged, being high and rounded. The parts of the brain supplying the nose, the olfactory lobes, are, on the other hand, very small and poorly developed, in accordance with the feebly-developed nasal sacs, the sense of smell being rudimentary, as mentioned above (Fig. 283). The brain is sharply bent on itself, so that the optic lobes of the

mid-brain—the portions connected with vision—are pressed downwards and the hemispheres are brought close to the cerebellum, which, in contradistinction to what is the case in most reptiles, is large and transversely wrinkled. Evidence is accumulating that the main function of the cerebellum is to stimulate the muscles so as to bring about the balancing of the body. Hence we can see why in both Fish and Birds it should be so large, for in their case this function is of great importance; but it is of much less importance in the comparatively broad-bellied Amphibia and Reptilia, where, as a consequence, the cerebellum remains smaller.

All birds have comparatively long necks (Fig. 282), and the vertebrae which form the support of this part of the body have the surfaces with which they articulate with one another shaped like saddles, being concave from side to side and convex from above downwards in front and exactly the opposite curvatures behind (Fig. 284). This arrangement allows great freedom of movement, and, as all know, a bird is able to twist the head completely round and look straight backwards.

Vascular System.

In doing so of course it squeezes the skin of one side of the neck and stretches that of the other, and so the great jugular vein, which carries blood from the head, is liable to be blocked on one side (Fig. 286). To obviate this difficulty, the two jugulars are connected by a cross piece just under the chin, so that the blood from both sides can always have a free passage. The carotid arteries, which take blood to the head, come close together at the base of the neck and run up just under the vertebrae. As they are placed close to the axis of rotation and are further protected by curved rods growing out from the vertebrae and forming arches over them, they are never compressed, however much the bird twists its neck.




FIG. 285. Diagram of Arterial Arch of a Bird viewed from the ventral aspect.

II. Second arterial arch. IV. Fourth arterial arch. 15. Pulmonary artery. 16. Dorsal aorta. 17. Right auricle. 18. Left auricle. 21. Right ventricle. 22. Left ventricle.

Turning now to the consideration of the internal organs, we have first to notice the structure of the heart. In Birds the ventricle is completely divided into two, a condition only found in the Crocodiles among reptiles, and even there the great trunks leaving the two parts of the ventricle communicate. In Birds only one arterial arch remains complete; this passes round to the right, coming off from the left half of the ventricle; in the reptiles, it will be recollected, the left fellow of this one was still present. From the arch of the aorta on each side a brachio-cephalic artery arises, which splits up into a carotid supplying the head and a subclavian for the breast and wing. Embryological research shows that the left brachio-cephalic artery is a remnant of the left arterial arch, present in Reptiles but lost in the Bird. The subclavian artery divides into a brachial artery of moderate size for the wing, and a very much larger pectoral artery which supplies the pectoral muscles. These, as we have seen, are the real seat of the activities of the wing. The arteries supplying the lungs, the pulmonaries, which, as in the Reptiles, have no longer any connection with the aorta, come off from the right side of the heart; one passes to each side to reach the lungs. The fact that the blood of a bird is hot—hotter even than ours—is testimony to the activity of its life and vital processes. The arteries of the hinder part of the trunk agree in their general arrangement with those of Reptilia and Amphibia. In the venous system the connection of the two jugulars has been already referred to. The jugular joins a large subclavian vein to form the superior vena cava. The largest part of the subclavian vein, like that of the corresponding




FIG. 286. Diagram to show arrangement of the principal Veins of a Bird.

1. Sinus venosus—gradually disappearing in the higher forms. 2. Ductus Cuvieri = superior vena cava. 3. Internal jugular = anterior cardinal vein. 5. Subclavian. 6. Posterior cardinal front part. 7. Inferior vena cava. 8. Renal portal=hinder part of posterior cardinal. 9. Caudal. 10. Sciatic. 12. Coccygeo-mesenteric. 13. Femoral. 14. Anastomosis of jugulars.




FIG. 287. The chief Viscera of the Pigeon, *Columba livia*. $\times \frac{2}{3}$.

1. Trachea. 2. Thymus gland. 3. Oesophagus. 4. Crop. 5. Syrinx.
 6. Heart. 7. Liver. 8. Gizzard. 9. Duodenum. 10. Pancreas.
 11. Small intestine. 12. Rectum. 13. Cloaca. 14. Air-sacs.
 15. Left carotid. 16. Left subclavian. 17. Right carotid. 18. Brachial
 artery. 19. Right subclavian. 20. Muscles of syrinx. 21. Pecto-
 ralis major muscle cut across.

artery, is made up of a pectoral vein returning blood from the pectoral muscles. The front parts of the posterior cardinal veins have disappeared: but their hinder parts remain as the renal-portal veins which as usual arise by the bifurcation of the caudal vein and receive on each side a femoral and a sciatic vein from the leg. The renal-portal pours its blood into the inferior vena cava, not as in Amphibia and Reptiles through a system of capillaries, but directly by a single vessel channelled through the substance of the kidney. Hence in Birds the kidney tubules receive blood only from the aorta and do not, as in the lower Craniata, receive a double supply. From the point where the caudal vein divides into the two renal-portals a vein is given off which descends into the mesentery and opens into the posterior mesenteric branch of the portal vein, thus establishing a connection between the portal and cardinal systems of veins. This vein is called the *coccygeo-mesenteric* (12, Fig. 286), and is quite peculiar to Birds.

The lungs are firmly fitted in against the ribs; they do not, as in most Reptiles or as in us, hang freely in a cavity; their most remarkable feature is the possession of great thin-walled bladder-shaped outgrowths, the air-sacs, of which the prolongations extend even into the bones.

Respiratory
System.

There are nine of these great air-sacs, one placed at the base of the neck, and the other eight situated in pairs at the sides of the body cavity under the ribs (Fig. 287). When the ribs are in their normal position, the air-sacs are expanded, but when the ribs are pulled backwards so as to compress the air-sacs, air is driven out; when the ribs and wall of the body behind come into their natural position again, the air-sacs are expanded and air rushes in, filling the lungs on its way. Breathing out or expiration is therefore the active function, drawing in air is an elastic reaction, the opposite to what is the case in man and other mammals. The windpipe or trachea is long, and the rings of cartilage which stiffen it are complete hoops, so that it is not easily compressed (Fig. 287). Like most other land vertebrates, birds have a larynx or organ of voice, at the top of the trachea formed in the usual manner by the enlargement of some of these rings of cartilage, and the stretching of a thin membrane between them and two special cartilages, the arytenoids, which lie at the opening of the windpipe into the gullet. But this organ of voice seems merely to be an inheritance from reptile ancestors, where they probably were of little use.

The effective organ of voice in Birds, the *syrix*, is found

much deeper down, at the spot, namely, where the windpipe splits into two tubes, the bronchi, which lead to the lungs. The inner walls of the bronchi, just where they join one another, are thin and membranous, and together constitute the *membrana tympaniformis interna*. From the fork a flexible valve, termed the *membrana semilunaris*, projects up into the windpipe, and as here the cartilage rings have the form of half-hoops, which are drawn together by special muscles, the width of the opening of the bronchus into the windpipe is small. When air is forcibly expelled the valve above mentioned is set vibrating like the reed in an organ-pipe, and by this mechanism the song is produced. The muscles which connect the half-rings together (intrinsic muscles) and two which connect the syrinx with the sternum (extrinsic muscles) by altering the tension of the sides of the trachea, and consequently the rate at which it vibrates, change the pitch of the note produced.

The alimentary canal commences with the buccal cavity or stomodaeum, partially divided by the palatal flaps into an upper air-passage, and a lower food-passage. The tongue, which is pointed and horny, ensheaths the glossohyal bone: it is protruded by the action of muscles which pull the enlarged third visceral arch forwards. Behind the tongue open the ducts of the sub-maxillary glands; at the corners of the gape the parotid glands pour their secretion into the mouth, whilst at the sides of the tongue the sub-lingual glands open. All these glands are pouch-like outgrowths of the ectoderm of the stomodaeum and secrete a mucus which assists in swallowing the food, and occasionally (as in Woodpeckers) in causing the prey to adhere to the tongue. The names indicate the position of the glands, as, for instance, parotid (Gr. *παρά*, beside, *οὖς*, *ὠτός*, the ear). Following on the buccal cavity and indistinguishably fused with it is the endodermal pharynx into which the glottis opens, and also the persistent remains of the first pair of gill-sacs, the Eustachian tubes. The pharynx leads into a long gullet lying dorsal to the trachea, which eventually passes into the stomach. The gullet in the Pigeon and many other birds develops a large thin-walled outgrowth on the ventral side called the crop. This is used as a storehouse for the food, and in the Pigeon may be found full of unaltered seeds. The stomach has a most characteristic form in Birds; it is sharply divided into two regions, an anterior egg-shaped one, called the proventriculus, and a large

Digestive
System.

posterior flattened one, called the gizzard. In the walls of the proventriculus are found the pepsin-forming glands, whilst on the other hand the endoderm of the gizzard develops a horny lining which is thin in Birds that live on an animal diet, but very thick in a grain-eating Bird like the Pigeon, where it forms upper and lower horny plates. When by the contraction of the greatly thickened visceral muscles of this part of the alimentary canal the upper and lower plates are brought together a crushing-mill is produced by which the food is broken up. The action of this mill is assisted by the habit which many Birds possess of swallowing fragments of stone. A collection of these, sometimes including fragments of glass, may be found on opening the gizzard of a Pigeon. It is a great development of this habit which has earned for the Ostrich its reputation of flourishing on a diet of nails, penknives, and match-boxes. The liver in Birds is remarkable for possessing two ducts, one opening as usual close to the pyloric end of the stomach and one into the distal end of the first loop of the intestine. The liver in Birds is therefore made up of a pair of outgrowths of the gut. The evidence gathered from the study of all other Craniata leads to the conclusion that the liver originated as a single ventral outgrowth from the intestine; and this duplication of such an old-established organ is very remarkable and on the whole rare, though not without parallel in other groups of the animal kingdom. The pancreas of Birds has three ducts and therefore consists of three separate diverticula instead of one; this is an instance of the same phenomenon as the duplication of the liver-duct. The intestine is folded into four or five loops, the arrangement of which has been made use of as a basis for classification. It ends by passing into a short rectum or large intestine. At the beginning of the rectum in many Birds two long outgrowths, the intestinal caeca, are given off. These are rudimentary in the Pigeon. The rectum ends in the proctodaeum or cloaca, the upper part of which receives the ducts of the kidneys and reproductive organs, whilst into the dorsal wall of the lower and outer part a glandular pouch of unknown function, called the Bursa Fabricii (12, Fig. 288), opens. This becomes smaller and sometimes entirely disappears in the adult Bird.

The structure of the kidneys and reproductive organs is essentially the same as in the Reptilia. The metanephros in both sexes is distinctly divided into lobes. The mesonephros is represented by a small lobed epididymis closely adherent to the testes. The supra-

Urogenital
Organs.

renal body (4, Fig. 288) is the same organ as the adrenal of Amphibia.

In most Birds there is no special copulatory organ, the whole end of the cloaca being turned inside out for this purpose, just as in Amphibia and Rhynchocephala. That this however is a secondary and not a primary state of affairs is shown by the existence in




FIG. 288. The Lungs, Kidneys and Gonads of a Pigeon, *Columba livia*. $\times \frac{2}{3}$.

1. Trachea. 2. Bronchus. 3. Lung. 4. Suprarenal body. 5. Ovary.
6. Oviduct. 7. Lobes of kidney. 8. Ureter. 9. Aorta. 10. Bursa Fabricii.
11. Rectum. 12. Opening of Bursa Fabricii. 13. Openings of ureters.
14. Opening of oviduct. 15. Cut pectoral muscle.

Ostriches and some other Birds of a long penis on the dorsal wall of the cloaca similar in structure to one of the penes or copulatory sacs of the Lizard.

There is only one ovary; an instance of the economy one observes throughout animated nature, for there is always a tendency,

when organs become expensive, that is so large as to be a serious tax on the system, to reduce their number, and the production of eggs of the size of a Bird's, is a great drain on the organism. There are two oviducts, but the right is small and useless. It must be remembered that the true egg formed by the ovary is the yolk; the white and the shell are additions derived from the oviduct.

The nests which Birds build and their care for the nestlings, whom they in some cases feed at short intervals for

Habits. about seventeen hours out of the twenty-four, are well-known to all. Most also are well aware that many birds migrate to other lands as winter sets in. It is less well known that quite as many migrate to lands further north on the approach of spring. Few imagine the enormous distances which are covered by birds on the wing. They constantly pass from the Bermuda Islands to the Bahamas, 600 miles, without a rest. Many species which have their home in North Africa go every spring to North Siberia to build their nests. They fly, when migrating, at such heights in the air as to be quite invisible and attain a pace which seems hardly credible.

The classification of Birds presents great difficulties. They used to be divided into six Orders, viz. *CURSORES*, or running birds; *NATATORES*, or swimming birds; *GRALLATORES*, or wading birds; *SCANSORES*, or climbing birds; *RAPTORES*, or birds of prey; and finally, the *INSESSORES*, or perching birds, a division which includes all our songsters, besides crows, rooks, magpies, sparrows, and many others. Such a classification is, however, no longer accepted, because it gives fundamentally wrong ideas about the true relationships of birds. The aquatic birds, for instance, include totally different types, such as the Gull and the Duck, which have been derived from quite distinct families of land birds. All are agreed, however, in separating the Ostriches and their allies from all the rest as a great main division, the *RATITAE* (Lat. *ratīs*, a raft): but it is doubtful if this is a 'natural' group. They are distinguished by possessing a dwindled wing, which is useless for flight. This leads to the dwindling of the great wing-muscles, the pectorals, and the consequent disappearance of the crest on the breastbone to which they are attached, and of the collarbone, or clavicle. The breastbone, having no longer a keel, has been compared to a raft, whence the name was suggested. The palate is also more like that of a

**Classi-
fication.**

These birds have enormously powerful legs and can run at a tremendous pace. The feathers are no longer required to form a compact surface, and hence the barbs have no barbules; this is the cause of the soft downy character which is so characteristic of them and makes them so prized for ornament. The true Ostrich, *Struthio*, is found in South Africa, *Rhea* in South America, the Cassowary, *Casuarius*, and Emeu, *Dromacus*, in Australia and New Guinea, and the smallest Ratite bird, the Kiwi, *Apteryx*, in New Zealand. In historical times, however, New Zealand had the largest of all Ratitae, the Moas, *Dinornis*, which had thigh bones larger and thicker than those of a horse.

All other birds are called *CARINATAE* (Lat. *carina*, a keel), and are distinguished by having a keel or crest on the sternum and well-developed flying muscles. It is impossible to define with any certainty any large main groups into which they can be divided, but the number of smaller natural groups is very large. Here we can only briefly allude to the main points in which birds differ from one another and which are relied on in classification.

These are :— (1) The form of the beak : this may be slender and pointed, as in the Robin; strongly curved, with sharp cutting edges, as in the Eagle; broad and lined internally with transverse ridges, as in the Duck. (2) The form of the palate : this resembles that of the Ostriches only in one family, the Tinamous. This type of palate is called dromaeognathous. In all other Carinatae the palatines slide on the base of the skull. The maxillae send plates inwards towards the middle line dorsal to the palatines, called the maxillo-palatines. When these are united and the vomers small or absent, or when they unite with the vomers, as in the Duck and Hawk, the bird is said to have a desmognathous palate; when the maxillo-palatines remain separate, as in the Fowl, and the vomers form a conspicuous rod pointed in front, the palate is schizognathous; finally when the maxillo-palatines remain separate and the vomers form a truncated wedge in front but diverge behind, aegithognathous is the term used. (3) The form of the

foot : there may be three or four toes, and these may be connected by a web throughout their whole length, or only at the base, or they may be quite free. The claws may be blunt, or they may be strong, grasping talons ; the raised sole, or tarsus, may be covered partly with feathers or partly or entirely with horny scales. (4) Lastly, the manner the young are cared for is a most important feature. Nearly all birds sit on or incubate their eggs. The Megapodes, or Mound-birds of Australia, however, merely collect a heap of grass and leaves, and leave the eggs to be hatched by the heat developed in fermentation. The just hatched young of the Pheasant and Game-birds are able to run about and look after themselves, whereas those of the Passeres or Songsters, require constant care and attention for a long time. These last are considered by leading ornithologists to be the most highly developed of all birds, both as to their intellects and their flying powers, so that it is hardly too much to say that the increasing sacrifice of the parents on behalf of the young has had its reward, in the improvement it has brought about in all the faculties of the race.

The Class Aves is classified as follows :

Sub-Order I. Ratitae.

Aves with rudimentary wings without clavicles or a keel (carina) on the sternum : the pterygoid bones united by basi-ptyergoid processes to the base of the skull.

Ex. *Struthio*, *Rhea*, *Casuaris*, *Apteryx*.

Sub-Order II. Carinatae.

Aves with typically well-developed wings, a large carina on the sternum and well-developed clavicles : the pterygoid bones moveable on the base of the skull.

Ex. *Columba*.

CHAPTER XIX.

SUB-PHYLUM IV. CRANIATA.

Class V. MAMMALIA.

THE class Mammalia (Lat. *mammae*, breasts), the last division of the phylum Vertebrata, includes those animals which suckle their young. Like the Birds, they are warm-blooded and have the ventricle of the heart completely divided into two halves. But they differ from Birds in never possessing feathers; only in one order is the fore-arm converted into a wing, and even in this case the arrangement of the parts is quite different from that in the Bird's wing.

General
Character-
istics.

Besides these characters however there are a large number of others in which, while Mammals differ from both Birds and Reptiles, the last-named two groups agree with one another. So that for a long time the opinion was held that Mammals were vastly further removed from Reptiles than were Birds; and indeed if only modern Reptiles were considered this could not well be denied. If however we examine the remains of the Reptiles which have existed on the earth in past time, we come to the conclusion that the better way to state the difference would be to say, that whereas Birds might be traced back to Reptiles not very unlike modern lizards, Mammals are derived from a type which has died out, leaving no modern representatives; and Mammals are in all probability an older group than Birds.

Just as feathers constitute an indubitable mark of a Bird, so true hairs are equally characteristic of Mammals. It is true that the word hair is loosely used, being often applied for instance to the delicate flexible spines of caterpillars, which are constructed on a totally different plan to the hairs of Mammals. A hair in the zoological sense is a rod composed of closely packed cells converted

into horn, and under a microscope the outline of these cells can be seen like a mosaic on the surface of the hair.

We saw that a feather originated as a little knob, the outside of which was composed of horny cells, whilst the interior consisted of soft living tissue supplied with blood-vessels; a hair on the other hand makes its appearance as a cylinder of horny cells growing down from the skin into the soft tissue underneath. This cylinder then becomes split into an outer sheath and an inner core, the latter of




FIG. 289. Section through the Skin of a Mammal. Highly magnified. Diagrammatic.

1. Outer layer of dead horny cells which are rubbed off from time to time, *Stratum corneum*.
2. Deeper layer of cells retaining their protoplasm, *Stratum Malpighii*.
3. Dermis or *Coreum*.
4. A hair.
5. Sweat-gland.
6. Opening of the duct of the sweat-gland.
7. Sebaceous or oil-gland.
8. Erector muscle of the hair.
9. Fibres of the connective tissue.
10. Blood-vessel.
11. Papilla conveying blood-vessels to the hair.

which elongates and forms the hair, whilst the former remains stationary and constitutes the follicle of the hair. The growth of the hair is rendered possible by a little plug of dermis carrying blood-vessels, which is pushed up into the lower end of the hair. In consequence of the rich supply of food brought by these vessels to the deep cells of the ectoderm lying above them, these cells bud off horny cells with great rapidity and persistence, and in this way a column of horny cells is formed which pushes out the older part of the hair and causes the whole structure to assume a great length, sometimes (as in women) equalling that of the body. The

plug of dermis is called the papilla of the hair, and when it dies from insufficient nourishment baldness ensues. In a few cases hairs may be aggregated so as to form overlapping scales, and practically all Mammals have nails or claws on the fingers and toes which are modifications of the reptilian scale.

Perspiration or sweat is also characteristic of Mammals. This consists of a fluid secreted by certain cells of the skin which remain soft and are not converted into horn like most of the outer cells. The cells which manufacture the perspiration are arranged to form long tubes called sweat-glands, which penetrate far below the ectoderm into the dermis underneath (Fig. 289). The production of perspiration is an arrangement by means of which the heat of the body is lowered, and by which certain excreta leave the body. The fluid poured out carries off a certain amount of heat and by its evaporation cools the skin. Besides the sweat-glands there are other tubes which are invaginations of the ectoderm, lined by a special kind of cell. These tubes, called fat or sebaceous glands, open into the hair follicles. They secrete the oil or fatty substance which gives the natural gloss to the fur (Fig. 289).

Mammals, as we have seen, feed their young after they are born by suckling them, that is providing them with milk. This milk is a peculiar fluid produced by the mammary glands, consisting of ectodermal tubes crowded together over certain areas of the ventral surface. They open at certain spots, raised above the general level, which constitute the nipple (or teat). Many zoologists believe that the mammary glands are really only modifications of the ordinary sweat-glands and sebaceous glands, for in the lowest Mammals there is no special raised skin area which can be called a teat.

As regards their internal structure the great differences between Mammals on the one hand, and Reptiles and Birds on the other, are to be found in the skull, the brain and the limbs and, to a lesser extent, in the heart and the arrangement of the great arteries and veins.

Turning first to the skull, we find that in a Mammal instead of having only one knob or condyle to fit into a cup on the first vertebra, as is the case with Birds and Reptiles, the skull has two, which are projections of the exoccipital bones that wall in the sides of the foramen magnum, whereas in Birds the single condyle is an outgrowth of the basi-occipital bone that forms the floor of the foramen magnum (Fig. 290). Then the brain instead

of lying behind the eyes extends forward between and above them; there is consequently no interorbital septum, and the side walls of the brain-case are thoroughly and firmly ossified, not merely represented by a vertical plate imperfectly ossified, as in a Bird, or nearly entirely membranous, as in some Reptiles. These walls are in fact constituted of alisphenoid bones behind and orbito-sphenoid bones in front, whilst a strong mesethmoid bone is developed in the internasal septum. This septum is prolonged beyond the bones of the face by a cartilaginous plate forming the support of a flexible nose or muzzle; this is a feature quite peculiar to Mammals. The base of the cranium is completely ossified, not only behind by the basi-occipital and basi-sphenoid bones but in front by the pre-sphenoid bones. To the last-named the conjoined vomers are attached, forming a wedge-shaped mass which projects down-




FIG. 290. Ventral view of the Cranium of a Dog, *Canis familiaris*. $\times \frac{2}{3}$.

1. Supra-occipital. 2. Foramen magnum.
3. Occipital condyle. 4. Tympanic bulla.
5. Basi-occipital. 6. Basi-sphenoid. 7. External auditory meatus. 8. Glenoid fossa.
9. Foramen lacerum medium, aperture through which the internal carotid passes to the brain.
10. Postglenoid foramen. 11. Alisphenoid.
12. Presphenoid. 13. Vomer. 14. Jugal.
15. Pterygoid. 16. Palatal process of palatine.
17. Palatal process of maxilla.
18. Posterior palatine foramen. 19. Anterior palatine foramen. 20. Palatal process of premaxilla.
21. Opening of tube in alisphenoid bone through which the carotid artery passes. 22. Hole for passage of Eustachian tube. 23. Process of squamosal to act as a stay for condyle of lower jaw.

II—XII. Exits of cranial nerves. i 2. Second incisors. C. Canine. pm 1, pm 4. First and fourth premolar. m 1. First molar.

wards and divides the air-space above the palatal folds into two. The name (Lat. *vomer*, ploughshare) is derived from the shape of the bone in Mammals; it is inappropriate as a description of its shape in other Craniata. The pterygoid bones take the form of thin




FIG. 291. Dorsal view of the Cranium of a Dog, *Canis familiaris*. $\times \frac{3}{8}$.

1. Supra-occipital. 2. Parietal. 3. Frontal.
4. Nasal. 5. Maxilla (facial portion).
6. Premaxilla. 7. Squamosal. 8. Jugal.
10. Postorbital process of frontal. 11. Infra-orbital foramen. 12. Anterior palatine foramen. 13. Lachrymal foramen. i 1. First incisor. c. Canine. pm 4. Fourth pre-molar.

vertical plates; they are attached throughout their whole length to the side wall of the cranium in the region of the alisphenoid. As in Crocodilia and desmognathous Birds the palatal folds are united in the middle line; the bones supporting them are processes of the premaxillary, maxillary, and palatine bones. Between the pterygoid bones however the palatal folds form a purely muscular bridge, called the soft palate, which ends posteriorly in a projecting lobe, called the uvula, lying close to the glottis. The processes of the palatine bones always meet so as to form a bony bridge, called the hard palate; those of the premaxilla and maxilla do so to a certain extent, leaving however vacuities known as the anterior palatine foramina (19,

Fig. 290). (The posterior palatine foramina are small holes in the palatine bones for the transmission of blood-vessels.) As in Chelonia, there is only a lower temporal arcade, which is formed mainly by the cheek-bone or jugal. There is however no quadrato-jugal, and the jugal joins a process of the squamosal, which is a

large bone covering the side of the skull and almost concealing the conjoined bones of the auditory capsule from view. It is characteristic of Mammalia that these bones, which in the embryo are distinct from one another, unite to form a single bone, called the periotic, which is fused to the squamosal. In Reptiles, on the other hand, the epiotic joins the supraoccipital and the opisthotic the exoccipital, whilst the prootic remains distinct. The outer ear, the funnel-shaped passage leading into the tympanum, which is termed the meatus auditorius externus, is surrounded by a bone called the tympanic, often swollen into a rounded form and then termed the tympanic bulla. There is often a tube-like prolongation of this bone into the base of the ear-flap or pinna.

There is no quadrate recognizable as such, the lower jaw consisting of a single dentary bone on each side, which articulates with a smooth cup-shaped facet on the squamosal, called the glenoid cavity. Occupying the position of the pre-frontal bone in Reptiles is a small bone called the lachrymal. This bone derives its name from the fact that it is pierced by a hole called the lachrymal foramen (13, Fig. 291) which permits of the passage of a duct leading from the orbit to the cavity of the nose. This duct carries off the excess of tears (Lat. *lacrima*, a tear), the secretion of the lachrymal gland, a development of the ectoderm between the eyelid and the eye. The lip-bones, the pre-maxilla and maxilla, are well developed and like the dentary normally bear teeth, all of which are implanted in distinct sockets formed by the upgrowth of the bone which bears them. Many of these teeth are rooted, that is to say, after a certain time the dermal papilla on which the tooth is moulded becomes constricted at the base, so as to be connected by only a narrow neck with the adjacent connective tissue, this appearing in the dried tooth as a small hole through which a blood-vessel passes. The term root is applied to the dentine surrounding the narrow neck. When it is formed, growth of the tooth ceases.

The teeth of Mammalia are amongst their most characteristic organs; they are more differentiated than those of other Craniata, and from the evidence they afford it is possible to identify many fossil remains as mammalian.

They are typically differentiated into four kinds, viz. incisors or cutting teeth, canines or stabbing teeth, premolars and molars, which taken together are termed cheek-teeth or back-teeth (Fig. 292). The incisors are borne by the premaxilla and have sharp,




FIG. 292. Dentition of a Dog, *Canis familiaris*. $\times \frac{1}{2}$.

i 2. Second incisor. c. Canine. pm 1, pm 4. First and fourth premolars.
m 1. First molar.

food is sufficiently broken up to permit of its being swallowed. The teeth of the lower jaw are of course all borne by the dentary and they are divided into the same varieties as those in the upper jaw. In Elasmobranchii, as we have seen (p. 355), the teeth are enlarged scales developed on a fold of skin which is invaginated within the lip, and as one row of teeth becomes worn out another takes its place, the skin bearing the old teeth slipping forward over the lip. In the higher Craniata this fold is represented by a solid

wedge of ectoderm, called the enamel germ, but in Amphibia and Reptilia it only bears one row of teeth. In Mammalia it normally produces two, the first of which lasts only for a short time during the youth of the animal, and is known as the milk dentition; the teeth belonging to this row are pushed out of the gum by those of the second row, or permanent dentition, which last throughout the life of the animal. In the milk dentition there are only incisors, canines, and molars; the milk molars are succeeded by the premolars of the permanent dentition, whilst the permanent molars have no predecessors and are regarded as belated members of the first dentition. The teeth of Mammalia have undergone profound modifications in accordance with the different habits assumed by different members of the class, and are one of the principal features on which the division of Mammalia into orders is based.

From a study of the dentition of living Mammalia the conclusion is arrived at that the typical number of teeth, that is to say, the number which the common ancestral form possessed, may be estimated at 44, i.e. 11 on each side of each jaw, made up of three incisors, one canine, four premolars, and three molars. This fact is expressed by the formula $\frac{3.1.4.3}{3.1.4.3}$, where the upper line denotes the teeth on each side of the upper jaw and the lower line those on each side of the lower jaw.

The complete absence of the quadrate bone in the upper, and of the articular in the lower jaw has given rise to much speculation as to what has become of these elements, which are so constantly present in Aves and Reptilia and are distinctly represented by cartilage even in Amphibia. For a long time the favourite theory was that they had been metamorphosed into the so-called ossicula auditûs or bones of hearing. In Anura, Reptilia, and Aves sound is conveyed from the ear-drum or tympanum to the wall of the auditory capsule by a single rod, called the columella auris. In Mammalia however the connection is effected by a chain of three small bones called the malleus (Lat. hammer), incus (Lat. anvil) and stapes (Lat. stirrup) respectively, the last named being apposed to a membranous spot in the auditory capsule, called the fenestra ovalis, whilst the malleus is in contact with the ear-drum. •

Now since in the embryo both malleus and incus are represented by blocks of cartilage which are for some time in continuity with Meckel's cartilage (v. p. 356), it was natural to suppose that they

The chief peculiarity of the brain as compared with Reptiles is the greater development of the cerebral hemispheres, in proportion to the hind brain or cerebellum. The former overlap completely and conceal the thalamencephalon and the mid-brain, and they are connected with one another by a great transverse band of nerve-fibres, called the corpus callosum. It is customary to map out the surface of the hemispheres into regions, in order to facilitate description in delimiting the areas which control the action of various parts of the body. These regions are called frontal, parietal, and temporal lobes. The temporal lobe is separated from the frontal by a deep groove, called the Sylvian fissure (11, Fig. 293, A). How well the increased size of the cerebrum is reflected in the shape of the cranium will be seen when it is recollected that the frontals and parietals, which represent merely the membrane covering the anterior fontanelle, not only form the

roof of the cranium but a large part of its domed side wall; and further that the orbitosphenoid and alisphenoid, which are portions of the cartilaginous brain-case, are restricted to the base of the




FIG. 293. Brain of Rabbit, *Lepus cuniculus*. $\times 2$.

A. Dorsal aspect. B. Ventral aspect.

1. Olfactory lobe. 2. Pituitary body. 3. Crura cerebri. 4. Pineal gland.
5. Anterior pair of corpora quadrigemina. 6. Pons Varolii.
7. Cerebellum. 8. Lateral lobe of cerebellum. 9. Floccular lobe of cerebellum.
10. Medulla oblongata. 11. Sylvian fissure separating the frontal lobe 12 from the temporal lobe behind.
- I. Origin of first or olfactory nerves. II. Optic or second nerves arising from the optic chiasma.
- III. Third or motor oculi nerve. IV. Fourth or patheticus nerve.
- V. Fifth or trigeminal nerve. VI. Sixth or abduccus nerve.
- VII. Seventh or facial nerve. VIII. Eighth or auditory nerve.
- IX. Ninth or glossopharyngeal nerve. X. Tenth or vagus nerve.
- XI. Eleventh or spinal accessory nerve. XII. Twelfth or hypoglossal nerve.

skull. The cerebrum has in fact protruded through the anterior fontanelle, pushing the membrane before it. The same phenomenon is observable in Birds, but not in Reptiles or Amphibia. The cerebellum however is also well developed, just as in Birds, having indeed in addition to the lateral lobes an outer pair of lateral projections, called flocculi, embedded in a hollow of the bone that covers the inner ear (Fig. 293). The two halves of the cerebellum are connected with one another by a powerful band of fibres in the floor of the brain, called the pons varolii. Speaking generally, the differences between the brains of Birds and Mammals are traceable to the great importance of the sense of sight in the first class, and of smell in the second. Hence in Mammals, the mid-brain, which receives the optic nerves, is comparatively feebly




FIG. 294. Sternum and sternal Ribs of a Dog, *Canis familiaris*. $\times \frac{1}{2}$.

1. Presternum. 2. First sternebra of mesosternum. 3. Last sternebra of mesosternum.
4. Xiphisternum. The flattened cartilaginous plate terminating the xiphisternum is not shown.
5. First sternal rib.

developed, and does not form, as in Birds, two large lateral lobes, although its roof is raised into two pairs of slight projections, called the corpora quadrigemina, whereas the part corresponding to the sense of smell, which is very feeble in a Bird, is well developed in a Mammal, being represented by the two pear-shaped olfactory lobes jutting out in the front of the fore-brain. The nose, except in aquatic Mammalia, is a highly developed sense-organ. The epithelium lining it is produced into scroll-like folds which are supported by thin plates of bone arising from the mesethmoid, and called ethmoturbinals. Above, where the mesethmoid joins the orbito-sphenoid, so numerous are the apertures in it to allow the bundles of nerve-fibres from the olfactory cells to pass to the brain, that this

part of the bone is reduced to a sieve, whence it has received the name of cribriform plate. From the maxilla, which forms the outer wall of the lower part of the nasal tube, a similar scroll-like bone, the maxillo-turbinal, arises which supports a corre-

sponding fold of epithelium. This fold however is supplied only by the second division of the fifth nerve, and is not believed to




FIG. 265. Skeleton of Rabbit, *Lepus cuniculus*. $\times \frac{2}{3}$. In sitting position.

have any olfactory function, but merely to act as a filter to free the inrushing air from grosser particles before it reaches the delicate olfactory epithelium.

The neck region of Mammals (with rare exceptions) always consists of seven vertebrae, and thus whereas a long-necked bird like the swan has numerous short vertebrae in this region, in a long-necked Mammal like the giraffe the same region consists of seven immensely long vertebrae. The sternum of Mammals also is peculiar, consisting of distinct pieces or sternebrae. The first of these is called the presternum, and bears a crest for the attachment of the pectoral muscles; the last ends in a spade-like xiphoid cartilage, and is called the xiphisternum. The intervening segments constitute the sternebrae of the mesosternum. The lower ends of a pair of ribs are attached opposite the junction of two sternebrae (Fig. 294).

In Mammalia as in other Amniota the centrum is formed from the intervertebral, and the head of the rib is articulated between two vertebrae; the articulation is not shifted on to the vertebra as in Crocodilia. The vertebrae have no cup and ball articulations with one another like those of Amphibia, Reptilia, and Aves, since the thick intervertebral cartilage allows of sufficient lateral bending, and the centra have flat ends which ossify late and for some time form separable disks of bone called epiphyses. These do not represent any new elements in the centrum, but only a method of ossification found only in the limb-bones in other Craniata, but in Mammalia extending to the vertebrae. This method consists in first forming a tube of bone round the centre of the cartilage, the ends of which remain soft and capable of further growth, being only replaced by bone when growth is diminishing, and united with the main ossification when growth has ceased.

In the fore-limbs of Mammals the chief point to be noticed is the reduction in size of the pectoral girdle to which the fore-limbs are attached. The lower part of this, the coracoid, which in Birds and Reptiles is a large, strong bone meeting the sternum, is here, with the exception of a few primitive forms, a small hook with no connection at all with the sternum. Hence the pectoral girdle is much more moveable than is elsewhere the case, and takes part in the movements of the limb. It is therefore not surprising to find that the upper portion of the girdle, the shoulder-blade or scapula, is broad, affording a large surface for the attachment of muscles; and that its surface is still further increased by the presence of a sharp vertical ridge rising up along its middle line (Fig. 295). To the end of this spine, as it is called, the collar-bone or clavicle is attached; this bone extends inwards to the

sternum and is loosely connected with it. In some Mammals the clavicle is absent.

The general form of the pelvic girdle to which the hinder limbs are attached is not very unlike that of birds; but there are two important differences. First, the ilia or hip-bones are only attached for a very short distance to the backbone; and secondly, the lower bones of the girdle, the pubis and ischium, meet their fellows of the opposite side in front of the belly beneath the anus, whereas in Birds they do not even approach each other in this place, though in *Rhea* the ischia do meet dorsal to the anus. It follows that this part of the body is extensible in birds and can be stretched as the large egg passes out through the oviduct.

The leg of Mammals differs from that of Birds and Reptiles in that the ankle-joint is situated between the bones of the shank (the tibia and the fibula) and the small bones of the ankle, instead of in the middle of these small bones (Fig. 295). The heel-bone or calcaneum is one of the uppermost tier of ankle-bones and corresponds to the bone called fibulare in the general scheme of the pentadactyle limb.

It is prolonged into the heel, to which the great gastrocnemial muscles which form the calf of the leg and which raise the heel are attached.

Turning now to the blood system of Mammals we find that the red blood corpuscles which give the colour to the blood are unlike those of other Vertebrates. They have no nuclei, are much smaller and (except in the Camel) are round, not oval, as in all lower Vertebrates. Like Birds, but unlike most Reptiles, the Mammals have a




FIG. 296. Diagram of Arterial Arch of a Mammal (Rabbit) viewed from the ventral aspect.

- II. Second arterial arch complete on the left where it joins the aorta, incomplete on the right where it merely forms the common stem (innominate artery) of the carotid and subclavian arteries. IV. Fourth arterial arch. 15. Pulmonary artery. 16. Dorsal aorta. 17. Right auricle. 18. Left auricle. 21. Right ventricle. 22. Left ventricle. 23. Right carotid artery. 24. Left carotid artery. 25. Right subclavian artery. 26. Left subclavian artery.

four-chambered heart; the main blood-vessel, the aorta, is supplied by the left systemic arch alone, the right one being cut off from connection with it and being represented by the common trunk of the right carotid and subclavian arteries, the so-called innominate artery (Fig. 296). This is exactly




FIG. 297. Diagram to show arrangement of the principal Veins in a Mammal.

1. Sinus venosus—gradually disappearing in the higher forms.
2. Ductus Cuvieri=superior vena cava.
3. Internal jugular=anterior cardinal sinus.
4. External jugular=sub-branchial.
5. Subclavian.
6. Posterior cardinal front part=venae azygos and hemiazygos.
7. Inferior vena cava.
9. Caudal.
10. Sciatic=internal iliac.
13. Femoral=external iliac.

the converse of the arrangement in Birds, and only one pulmonary arch remains from which both lungs are supplied, but this is the left one, not the right as in Snakes (compare Figs. 266 and 296).

In the venous system the blood from the head is returned by external and internal jugular veins, the former being much the larger. The hinder portions of the posterior cardinal veins have quite disappeared and the caudal vein is continued directly into the inferior vena cava, so that there is no longer even the outward appearance of a renal-portal system. The anterior portions of the posterior cardinals, however, persist as the venae azygos and hemiazygos, which on each side receive the veins from the spaces between the ribs—the intercostal veins. Only that on the right—the vena azygos—reaches the Ductus Cuvieri (superior vena cava); the left cardinal or vena hemiazygos develops a transverse branch through which its blood joins that of the right cardinal, and the veins from the legs, instead of traversing the kidneys, empty at

once into a great vena cava inferior situated in the middle line of the back, which is joined higher up by two short veins from the kidneys (Fig. 297).

One of the most interesting peculiarities of Mammals is their breathing mechanism. It will be remembered that whereas the

Amphibia simply swallow air, in the Reptiles the size of the chest cavity is enlarged by pulling the ribs forward and then separating them, and as the lungs are closely attached to the wall of the chest, they are likewise enlarged and air rushes into them. In Mammals this same mechanism exists, but in addition there is a totally independent means of pumping air into the lung. This is rendered possible by the existence of a diaphragm, a partition convex in front which separates the coelom of the chest from the rest of the body cavity. This partition is partly muscular, and when the muscle contracts the whole membrane is tightened and necessarily flattens, with the result that the chest cavity is enlarged and air enters the lungs. The action of the diaphragm in fact is precisely similar to that of the muscular floor of the mantle cavity of the snail. The diaphragm is attached ventrally to the xiphoid cartilage, dorsally to the vertebral column, and laterally to the ventral edges of the hinder ribs which do not reach the sternum. By it the coelom of the mammal is separated into a thoracic division in front and an abdominal one behind. Since therefore all the vertebrae which bear recognisable ribs which reach the sternum belong to the thoracic region, they are termed thoracic vertebrae, whilst the ribless vertebrae of the abdominal region are denominated lumbar.

In the digestive system the principal peculiarity of Mammals is the high state of development of the salivary glands. These glands are tubes, outgrowths of the ectoderm of the mouth-cavity or stomodaeum; they secrete a fluid which moistens the food and is swallowed with it, promoting digestion. They are foreshadowed by small glands in frogs and snakes, but in Mammals they form three large masses, viz. the sub-lingual, underneath the tongue, the sub-maxillary, under the angle of the jaw, and the parotid, just under the ear. Glands in similar positions are found in some Birds (see p. 491), but those of Mammalia secrete in addition to mucus a ferment, called ptyalin, which turns starch into sugar, so that the secretion which is called saliva when swallowed aids digestion. The development of the large intestine which acts as a reservoir for the faeces is also a characteristic of the Mammalian alimentary canal.

Mammals are divided into three great primary divisions or sub-classes according to the structure of the ovary and oviduct and to the stage of development attained by the young at birth. The lowest forms have large eggs

Classification.




FIG. 298. The Duckbill, *Ornithorhynchus anatinus*.

like those of birds: in the higher forms the egg is at first small but has the power of absorbing nourishment from the wall of the oviduct, which is here enlarged to form a womb or uterus. In the highest division a special organ of absorption, the placenta, is developed, as an enlargement of the embryonic bladder.




FIG. 299. Diagram to illustrate the arrangement of the female genital ducts in the Prototheria.

1. Ovary. 2. Oviducal funnel.
3. Oviduct.
4. Opening into cloaca.

The sub-classes are called:

- I. PROTOTHERIA, or primitive mammals.
- II. METATHERIA, or modified mammals.
- III. EUTHERIA, or perfect mammals.

Sub-class I. PROTOTHERIA.

The Prototheria include two extraordinary animals, the *Ornithorhynchus* (*Platypus*), or duck-billed mole, and the *Echidna*, or spiny ant-eater, which are found only in Australia, New Guinea,

and Tasmania. In these animals large eggs with a firm shell are laid in a nest and incubated by the mother, and in harmony with this arrangement the two oviducts are large throughout the whole of their length, and do not join each other at any point but open along with the intestine into a common vent or cloaca, as is the case with birds and reptiles. The ureters do not open into the bladder as they do in all other Mammalia, but they and the bladder open separately into the cloaca. In the male a copulatory organ or penis is present opening into the cloaca behind, and in front protruded from the cloaca. After they are hatched the young receive milk from the mother. There is no teat, but the fluid from the milk glands seems to soak into the hair and thence is sucked by the young. Before birth the young receive no nutrition at all from the mother.

The skeleton of the Prototheria presents many interesting features of agreement with the Reptiles; thus the vertebrae have no epiphyses, and there is not only a complete coracoid articulating with the sternum, but also two epicoracoids which overlap. Underneath these there are two clavicles and an interclavicle, so that the shoulder-girdle recalls the complicated one of the lizard.

Ornithorhynchus has webbed feet and lives in the water, feeding on worms and insects, which it digs out of the mud by its broad, shovel-like snout, whence the name Duck-bill (Fig. 298). It crushes its prey by means of horny plates, which are really patches of the hardened gum; when it is young, however, it has true calcareous teeth, two or three on each side of each jaw, but these it loses when it grows older. These teeth are covered by several rows of small points or tubercles.




FIG. 300. Ventral view of the Shoulder-girdle and Sternum of a Duckbill, *Ornithorhynchus paradoxus* $\times \frac{3}{4}$. After Parker.

- | | |
|-------------------|----------------------------------|
| 1 and 2. Scapula. | 3. Coracoid. |
| 4. Epicoracoid. | 5. Glenoid cavity. |
| 6. Interclavicle. | 7. Clavicle. |
| 8. Presternum. | 9. Third segment of mesosternum. |
| 10. Sternal rib. | 11. Intermediate rib. |
| | 12. Vertebral rib. |

Similar teeth are found amongst the oldest remains of Mammals which are known.

Echidna lives on ants and other insects, which it ensnares by putting out its tongue covered with sticky saliva. Like other ant-eaters it has a long snout and no teeth. It is covered with stiff spines like a porcupine.

Sub-class II. METATHERIA.

The division Metatheria includes the curious pouched Mammals of Australia and the neighbouring islands and the Opossums of America. In these animals the egg is exceedingly small, and the egg-tube is divided into an upper part of correspondingly narrow diameter, called the Fallopian tube, and a lower, wider




FIG. 301. Diagram to illustrate the arrangement in the female genital ducts of the Metatheria.

- | | |
|----------------|--------------|
| 1. Ovary. | 2. Oviducal |
| funnel. | 5. Fallopian |
| | tube. |
| 7. Vagina. | 6. Uterus. |
| 8. Median | |
| vaginal pouch. | |
| 9. Uri- | |
| nogenital | |
| vestibule. | |

part, called the uterus or womb. In this latter the small egg lies for a while and rapidly grows and develops, absorbing food from the womb through the thin egg-membrane, since there is never any egg-shell. Beneath the womb comes the lowest part of the egg-tube, the so-called vagina. The two vaginae come into close contact with each other above and then diverge, both opening below apparently into the lowest part of the bladder, as do the vasa deferentia in the male. What seems to be the lowest part of the bladder is really the front portion of the cloaca, which has become separated from the part behind that receives the opening of the intestine. This common vestibule for excretory and reproductive ducts is called the urinogenital sinus, and its opening is distinct from that of the intestine or anus, although the two openings are still surrounded by a common

muscle. From the spot where the vaginae meet above a pouch called the median vagina is often developed. This ends blindly in the young female, but in the mature female it acquires an opening into the urinogenital sinus and through this opening the

embryo is born, the lateral vaginae serving merely to admit the spermatozoa from the male.

When the young are born they appear not as eggs but as little mammals, which are however exceedingly small in size. They are



FIG. 302. *Petrogale xanthopus*. The Rock Wallaby with young in pouch.
After Vogt and Specht.

then placed by the mother, who is said to transfer them with her lips, in a pouch made by a fold of skin on the lower part of her body, whence the name Marsupials (Lat. *marsupium*, a pouch),

often given to these animals. This pouch is supported by two epipubic bones running forward from the pubes. Similar structures are found in Prototheria, in Crocodiles, and in Urodela, although of course these animals have no pouch. The young are quite incapable of feeding themselves, and therefore the mother by compressing the muscles of the belly squeezes the milk-gland and forces milk down their throats. In order to allow the young one to breathe at the same time, the back of the soft palate is wrapped round the upper end of the windpipe, which projects into the throat so that the air passes from the nose straight down the windpipe whilst milk flows down at the sides of the air-passage into the stomach.

In the mandible the angle, that is to say the lower and posterior end, is as a rule prolonged inwards as a horizontal shelf of bone. By this feature fossil skulls are recognized as belonging to the Metatheria.




FIG. 303. Skull of Lesueur's Kangaroo-rat, *Bettongia lesueuri*. To exhibit Diprotodont type of dentition.

The living Metatheria are divided into two great orders, of which the first is mainly carnivorous and the second herbivorous, though some members of both are insectivorous. The first order is termed *POLYPROTODONTIA*; the animals composing it have at least four incisors on each side of the upper jaw and three on each side of the lower, whence the name (Gr. πολὺ, many, πρῶτος, foremost, ὀδόντες, teeth). The *DIPROTODONTIA*, as the second order is called, derive their name from the circumstance that in the lower jaw there is one large pointed incisor on each side, the others being rudimentary or absent, so that only two prominent teeth are observable (Gr. δι-, two). The Polyprotodontia are represented in America by the family of the Opossums, *DIDELPHIDAE*, which is confined to that continent. It includes 24 species, most of which are found in

Mexico, Central America, and Brazil, but one, the Virginian opossum, *Didelphis marsupialis*, ranges north as far as the south bank of the Hudson river. In all the Didelphidae the great toe is large and can be separated from the other toes so as with them to grasp a support; it is said to be 'prehensile.' In Australia the Polyprotodontia are represented by three families, viz. the DASYURIDAE, the PERAMELIDAE, and the NOTORYCTIDAE. The first family includes the animals known as native cats, which resemble the American opossums, but are distinguished from them by the smaller number of incisor teeth and by having a rudimentary first digit in both fore- and hind-feet, whereas in the



FIG. 304. Banded Ant-eater, *Myrmecobius fasciatus* $\times \frac{1}{4}$.

opossum, as we have seen, this digit is long and prehensile. The largest member of the family is *Thylacinus cynocephalus*, the Tasmanian wolf, now confined to the wilder parts of Tasmania; it has a skull which strikingly resembles that of a dog; in its habits it resembles the wolf and is very destructive to sheep. The Banded Ant-eater, *Myrmecobius fasciatus*, is an aberrant member of the same family, which lives on insects, which it captures

with its long tongue. The insects are made to adhere to this organ by the viscid saliva. The teeth, though rudimentary, are distinct. There is no pouch: the young when first born cling to the teats and conceal themselves in the long hair of the mother's abdomen. The PERAMELIDÆ or Bandicoots are small animals somewhat resembling Rabbits and Hares in their appearance but with pointed muzzles; they are remarkable in possessing a type of foot characteristic of the Diprotodontia. The NOTORYCTIDÆ include the single genus *Notoryctes*, which in habits and appearance resembles the Mole, a similar mode of life having brought about similar modifications of structure.

The order Diprotodontia includes a number of species confined, with one exception, to Australia and the neighbouring islands. One species, the only living representative of the family EPANORTHIDÆ, has been recently found in South America. This animal, which has received the name *Cenolestes uliginosus*, has feet like the DIDELPHIDÆ, and this circumstance renders it possible that it has been independently evolved from the Didelphidae, whereas the other members of the order seem to have been derived from forms like the PERAMELIDÆ. The typical Diprotodontia have the second, third, fourth, and fifth toes of the hind-foot united by a web of skin. The fourth is the strongest toe, the fifth is a little shorter, but usually nearly as stout as the fourth; the second and third, though as long as the fourth, are much more slender, whilst the great toe is often rudimentary. Exclusive of the EPANORTHIDÆ there are three families in the sub-order. The first family, the PHASCOLOMYIDÆ, consists of one genus, *Phascolomys*, the Wombat, represented by three species. The PHASCOLOMYIDÆ are distinguished by possessing only one incisor on each side of the upper jaw, and as both upper and lower incisors are chisel-shaped the dentition resembles that of a Beaver or Rat. Wombats are heavy animals with a shuffling gait, about the size and appearance of a Badger.

The second family, the PHALANGERIDÆ, or Australian opossums, have normally three incisors on each side of the upper jaw; the fore- and hind-limbs are of about the same size, and the great toe is prehensile. These are small animals which like squirrels live in trees, and several species possess a parachute-like membrane extending from fore- to hind-limb, by the aid of which they sustain themselves in the air during their great leaps from tree to tree. *Phascolarctus*, the so-called native Bear, is a clumsy tailless Pha-

langer, in which the prehensile great toe is specially well developed. The MACROPODIDAE, or Kangaroos, are the most peculiar family of Diprotodontia, and indeed of the Metatheria. They resemble the Phalangeridae in having three upper incisors on each side, but differ totally in the structure of the limbs. The fore-limbs are so small as to be used only for grasping, and locomotion is effected by a series of leaps carried out by the hind-limbs aided by the powerful tail. The sole of the hind-foot is excessively narrow, the second and third digits being represented by bones so slender that they take no part in supporting the body. *Macropus giganteus*, the gray Kangaroo or "Old Man," may obtain a height of from 4 to 5 feet. The fourth toe of the hind-foot has a powerful claw with which when the animal is brought to bay it has been known to rip open a dog. The allied genus *Petrogale* includes smaller species, called Rock Wallabies, with only a short claw on the hind-foot. As their name implies they frequent rocky regions. The so-called Kangaroo-rats, *Bettongia* and others, are nocturnal animals of small size, which live on leaves, grass, and roots, the last of which they dig up with their fore-paws.

Sub-class III. EUTHERIA.

The highest division of the Mammalia, the Eutheria, includes all the most familiar animals, hedgehogs, rats, rabbits, cats, dogs, lions, tigers, horses, oxen, whales, elephants, monkeys, up to and including man himself. In them as in the Metatheria the egg is exceedingly small, in Man and the domestic animals for instance, it varies from $\frac{1}{120}$ to $\frac{1}{200}$ inch in diameter. The upper part of the oviduct, the Fallopian tube, is consequently narrow; the womb is however enlarged, for the egg not only lies there a long time—called the period of gestation or pregnancy—but as it is developing into the young mammal a special organ called the placenta is developed, which grows out and becomes interlocked with folds in the womb-wall. This organ is nothing but an enormous development of the bladder of the embryo, which is called the allantois, and which is also developed in the embryo of Birds and Reptiles, where it subserves respiration and lies above the embryo beneath the egg-shell. In Eutheria the surface of the allantois is covered with outgrowths called villi, which fit into pits on the wall of the womb. Both the membrane covering the allantois

and the lining of the womb degenerate, allowing the blood-vessels of mother and embryo to come into close contact. The placenta becomes gorged with blood driven into it by the heart of the developing embryo, and at the same time the womb becomes inflamed and loses its epithelium, so that the blood of the mother and that of the young approach very closely to each other. They are only separated by the thin outer wall of the placenta, and nourishment diffuses from the one to the other; so close is the connection that when the embryo is born and passes out of the womb carrying




FIG. 305. Diagrams to illustrate the arrangement of the female genital ducts in an Eutherian Mammal. A. Rabbit. B. Man.

1. Ovary. 2. Oviducal funnel. 5. Fallopian tube. 6. Uterus.
7. Vagina. 8. Urino-genital sinus.

with it the placenta, the latter in most cases tears open the vessels in the wall of the womb, and the mother loses a considerable quantity of blood. The lowest parts of the two oviducts are completely joined and pass into a single passage, the vagina, whilst the middle portions, or the wombs, are sometimes quite separate, as in the rabbit (A, Fig. 305), sometimes partly united as in the cat, rarely completely joined as in monkeys and man (B, Fig. 305).

Order I. **Edentata.**

When we take a general survey of the orders or main divisions into which the Eutheria are divided we find that we have three or

four strange groups, the relations of which to the others it is most difficult to decide. These include the curious Edentata of South America, comprising three families, the BRADYPODIDAE or Sloths, the MYRMECOPHAGIDAE or American Ant-eaters, and the DASYPODIDAE or Armadillos. With these the South African forms, included in the families MANIDAE or Scaly Ant-eaters and ORYCTEROPODIDAE or Cape Ant-eaters, are usually grouped, though their relationship is a matter of doubt. The name means "toothless," and was given to them by the early naturalists because they supposed them to be devoid of teeth. This is only the case with one small family, the Ant-eaters, or MYRMECOPHAGIDAE, which, like Echidna, have lost their teeth through disuse. In the rest there are teeth,



FIG. 306. Tamandua Ant-eater, *Tamandua tetradactyla*. From Proc. Zool. Soc. 1871.

but front teeth are always wanting. In the adult none of the teeth have enamel and all are similar to each other. The hands and feet are armed with great curved claws, adapted for holding on to supports, not for grasping or attacking, and incapable of being retracted or pulled back. Consequently the hands and feet are like hooks, on which the animals walk clumsily, bending the fingers under them. The apparent want of utility is however explained when the animals are looked at in their natural surroundings. It is then seen that one family, the Sloths (BRADYPODIDAE), spend all their time climbing about on trees, on the leaves of which they feed. In order to enable them to escape detection by their enemies there is a remarkable adaptation. The surface of the hairs is grooved and affords a resting-place for a

unicellular Alga which causes the animal to have a greenish appearance so as to be almost invisible amidst the foliage. The second




FIG. 307. The Six-banded Armadillo, *Dasypus sexinctus*. After Vogt and Specht.

family includes the true Ant-eaters or MYRMECOPHAGIDAE; in these the strong claws are used for pulling down and digging up ant-hills. The muzzle is long and toothless. There is a very long tongue,

and enormous salivary glands, the sticky secretion of which entraps the ants. The Tamandua Ant-eater, *Tamandua tetradactyla*, of Central and South America is arboreal in its habits and lives in the dense primeval forests of the New World; it uses its strong claws for climbing and has a prehensile tail. The third family, the Armadillos, DASYPODIDAE, can dig with such rapidity that a comparatively large animal will scoop out a burrow for itself in a few minutes. These Armadillos are also very remarkable as being the only Mammals in which the dermis or deeper skin develops into hard bony plates such as we find in Turtles and Crocodiles,




FIG. 308. White-bellied Pangolin, *Manis tricuspis*.

whilst the hair on the upper part of the body is replaced by horny scales like those of snakes and lizards, covering the bony plates.

It is thought that in comparatively recent times, geologically speaking, South America was an island, and just as Australia has preserved some curious animals which never could have held their ground against the powerful lions and tigers and wolves of the Old World, so in South America evolution seems to have run a course of its own.

In Africa there are found two other genera of Ant-eaters, *Manis*, the scaly Ant-eater, also found in Eastern Asia, and *Orycteropus*,

the Cape Ant-eater, both of which are usually classed under the Edentata. *Manis* has the hair agglutinated to form overlapping scales, but has no dermal plates, and no teeth. *M. tricuspis* is arboreal in its habits. *Orycteropus* has peculiar folded teeth and scanty hair. It is termed by the Boers the Aard-vark or Earth-pig, and is nocturnal in its habits, sleeping during the day in burrows which are usually found in the neighbourhood of the large ant-mounds so common on the veldt. Neither genus is believed now to have any close affinity with true Edentata, their reproductive organs being markedly different from those of the S. American forms, and they are provisionally grouped together in an order termed the *EFFODIENTIA*.

MARINE MAMMALS.

The second and third strange groups, the relations of which to the rest of the Mammals are unknown, are the two groups inhabiting the sea, viz. the Whales or Cetacea, and the Sea-cows or Sirenia. Both of these have some peculiarities in common, due to their having adapted themselves to peculiar and—for a Mammal—unnatural conditions. Thus both Whales and Sea-cows have lost all outward trace of hind-limbs, although a pair of small bones representing them are found embedded in the body. In both the tail has become flattened, developing flukes or fins at the sides, and, as in Fishes, it is by strokes of the tail that these Mammals principally move. But whereas in Fishes the tail moves from side to side, here, in accordance with its form, it moves up and down. Both Whales and Sea-cows have lost nearly all hair; Whales retain only one or two traces about the lips, whereas in Sea-cows there are scanty bristles all over the body, and the lips are thickly covered. The other Mammals which have taken to the sea, the Seals and their allies, are provided with a thick coating of hair (see p. 538).

We saw that the nose in Fishes was a sense-organ, adapted to perceive, by its chemical action, gases and other substances dissolved in the water. When land-animals were evolved, the air needed for breathing was drawn in past the nose; the oro-nasal groove leading from the nose to the mouth, which was at first an open gutter, became changed into a closed channel, the nasal passage, and the nose became modified in order to perceive vapours mixed

with air. In the marine Mammals air is still drawn in through the nasal passage, but they are concerned no longer with perceiving things which emit vapours into the air, but rather like fishes, with substances dissolved in the surrounding water. Since the true nose, the sense-organ, owing to its new connection with breathing, cannot be used for perceiving substances in the water, it ceases to be of use, and becomes vestigial; the nasal bones shrink away into small remnants and the nasal opening is placed far back on the snout near what appears to be the top of the animal's head.

Order II. Cetacea.

The order of Whales is distinguished by the great rounded cranium and by the elongation of the bones of the face and jaws. These support an immense prow-like snout formed chiefly of fat, which is an admirable buttress of defence for the animal's skull. The supra-occipital bone is of great size and forms the posterior surface of the cranial dome, interposing between the small parietals and meeting the frontal. The frontals develop great orbital plates flanking the face, beneath which is the small orbit, bounded below by the slender jugal. In Whales also the teats are situated far back, as they are in cows, and the mother forces the milk down the young one's throat; for in the Whale, as in the young marsupial, the windpipe and nose are directly connected; only here the connection lasts through life and allows a Whale to swim through the water with its mouth open whilst it breathes at the same time.

Whales are divided into two sub-orders, the whalebone Whales or *MYSTACOCETI* and the toothed Whales or *ODONTOCETI*. In the latter there are numerous teeth, but they are all alike and simple (Fig. 309), and the maxilla develops a great crest which conceals the orbital plate of the frontal. The great Sperm-whale, *Physeter macrocephalus*, of the Southern Seas, has teeth only in the lower jaw and feeds on cuttle-fish and fish, gripping the long flexible arms of the former by pressing them against the upper jaw. Spermaceti oil is the melted-down fat of this monster. The Ca'ing or Pilot Whale (*Globicephalus melas*), which also feeds chiefly on cuttle-fish, has teeth on both upper and lower jaws (Fig. 309). Pilot-whales are social in disposition, and the herds are occasionally driven into bays or fiords in the North Atlantic and captured. Smaller Toothed Whales are found round the coast of Britain, which have teeth in

both jaws. Others are known as the Porpoise, *Phocaena*, the Dolphin, *Delphinus*, and the Grampus, *Orca*. The common Porpoise, *Ph. communis*, is the most abundant and best known of British Cetaceans. It is not more than six feet long and is often




FIG. 309. A, Lateral view, and B, Longitudinal section of the Skull of a young Ca'ing Whale, *Globicephalus melas* $\times \frac{1}{2}$.

- | | | | |
|--------------------|--------------------|--------------------------------|---------------------|
| 1. Basi-occipital. | 2. Exoccipital. | 3. Supra-occipital. | 4. Basisphenoid. |
| 5. Alisphenoid. | 6. Parietal. | 7. Interparietal fused with 3. | |
| 8. Presphenoid. | 9. Orbitosphenoid. | 10. Frontal. | 11. Mesethmoid. |
| 12. Tympanic. | 13. Periotic. | 14. Squamosal. | 15. Jugal. |
| 16. Vomer. | 17. Palatine. | 18. Pterygoid. | 19. Nasal. |
| 20. Maxilla. | 21. Premaxilla. | 22. Mandible. | 23. Anterior nares. |

cast ashore. In the Gulf of St Lawrence the White Whale, *Delphinapterus leucas*, is fairly common. It attains a length of twelve feet.

The whalebone Whales, MYSTACOCETI, have no teeth. The orbital plate of the frontal is uncovered and there is a small ethmo-turbinal covered with olfactory epithelium. They are all large animals, although they feed on the smallest prey, such as

minute pelagic mollusca, jelly-fish, and crustacea. The "whale-bone" consists of a large number of horny plates hanging down like curtains from the palate into the cavity of the mouth. These are placed in pairs, one on each side of the mouth, one pair behind the other, and the fellows of a pair nearly meet in the middle. The lower edges of these plates are frayed out so as to form a fringe or strainer. After the whale has taken water into its mouth it raises its tongue against the edges of the plates and allows the water to trickle out through the strainer described above; all the small animals taken in the water are thus retained and then swallowed. The best quality of whalebone is obtained from the Right Whale, *Balaena mysticetus*, an animal about fifty feet long, found only in the Arctic regions. The great Rorqual Whale, *Balænoptera sibbaldi*, has a fin in the middle of its back, and attains a length of from 60—80 feet; it is the largest animal now found on the globe and is very abundant.

Order III. Sirenia.

Sea-cows differ from whales in so many respects that they cannot have any close relation to them. They are vegetable-feeders, and




FIG. 310. Skull of African Manatee, *Manatus senegalensis* $\times \frac{1}{2}$.

browse on sea-weed and other water-plants. As these habits necessitate their staying under the water for some considerable time, the bones are heavy and solid, quite different in structure from the

bones of whales, which are much more spongy in texture. The skull is long, not rounded, and the face bones are only moderately developed. The parietals are not pushed aside by the development of the supra-occipital; the supra-orbital plate of the frontal is small, while the orbit is large and bounded below by a very powerful jugal. The teeth are broad and crushing, and front teeth sometimes are found developed as tusks. There is no such snout as is found in Whales but there are large moveable lips by means of which food is seized (Fig. 311). The teats are placed on the breast as in a woman, and the mother holds the young under the arm, which is quite flexible, and not a mere fin as in whales. It is supposed that the legends of mermaids have been suggested to sailors by the sight of these strange parents holding their young above water. There




FIG. 311. Front view of head of American Manatee, *Manatus americanus*, showing the eyes, nostrils, and mouth. A, with the lobes of the upper lip divaricated. B, with the lip contracted. From Murie.

are two genera, each represented by a single species; the Manatee, *Manatus*, found on the warmer parts of the coasts of the Atlantic and in the estuaries of rivers, both in America and Africa, and the Dugong, *Halicore*, found all around the coasts of the Indian Ocean and around Australia, where it is fished for and eaten. Until 1768 a third species, *Rhytina stelleri*, of great size—20 to 25 feet long—inhabited some islands in the Behring Sea. It had no teeth, horny plates on the gum supplying their place. This species was exterminated by Russian seal-hunters.

Leaving aside these curious groups of animals, we find that the relations to one another of the remaining Mammals are more easily understood. We have first of all to deal with the Insectivora.

Order IV. **Insectivora.**

This is a group of small animals, which as their name implies feed chiefly on insects. They have three or four sharp pointed cusps on each of their back teeth, adapted for piercing the shells of insects, whilst their front teeth in both jaws are directed outwards so that they act like a pair of pincers in seizing the prey. The Insectivora are plantigrade, that is, they place the whole palm and the whole sole on the ground when they walk (Figs. 312, 313); in



FIG. 312. African Jumping-shrew, *Macroscelides tetradactylus* $\times \frac{1}{2}$. From Peters.

nearly every case they have the full number (five) of fingers and toes; they have long flexible snouts projecting beyond the mouth, and their brains are of a low and simple structure. In Great Britain this group is represented by three well-marked types, viz. the shrews, the hedgehogs, and the moles. The Shrews, **SORICIDAE**, are mouse-like animals clothed with soft fur. There are three British species, the Common Shrew, *Sorex vulgaris*, about the size of an ordinary mouse, and the Lesser Shrew, *S. pygmaeus* or *minutus*,

very much smaller, the latter being one of the smallest mammals known. The Water Shrew, *Crossopus fodiens*, is aquatic in its habits. The ERINACEIDAE are animals of larger size covered with spiny hairs. The single British species, the common Hedgehog, *Erinaceus europaeus*, is about the size of a rat; as is well known it rolls itself up into a ball when it is alarmed, drawing its fore- and hind-feet together and tucking its head between the former, and in this condition it bids defiance to its enemies. The TALPIDAE or



FIG. 313. Russian Desman, *Myogale moschata*.

Moles are burrowing animals with greatly enlarged hands and very small eyes; they are represented in Britain by the Mole, *Talpa europaea*. The genus *Talpa* is confined to the Old World. The Mole lives on worms and insect larvae and remains almost always underground; hence its eyes are vestigial and are very small. Its hands are very large and broad and suited for digging, whilst its chest is exceedingly narrow in front so as to give room for the arms to work in a burrow. The African Jumping-shrews include fourteen species, most of which are contained in the genus *Macroscelides*

(Fig. 312). These animals have a greatly elongated tarsus by means of which they execute leaps of considerable length.

The Russian Desman, *Myogale moschata*, once extended as far west as Britain. It lives in burrows by the water-side and feeds chiefly on fresh-water insects and their larvae. In correspondence with its mode of life the hind-feet are webbed and the tail large and compressed, forming an efficient swimming organ. It is hunted for its fur. In North America numerous representatives of the Soricidae and Talpidae occur, but the Erinaceidae are absent. Amongst the most peculiar Soricidae is *Blarina*, the Mole-shrew, which has very small eyes, rudimentary outer ears, and the general aspect of a Mole, but which is at once distinguished from the Talpidae by its normal fore-limb. A peculiar member of the Talpidae is *Condylura*, the Star-nosed Mole, which has a circle of fleshy prominences round the tip of its snout.

The most interesting circumstance about the Insectivora is the fact that when by means of fossils we trace back the higher groups of mammals, they seem all to merge imperceptibly into Insectivora. There is therefore really good ground for supposing that the living Insectivora, though modified in special details, nevertheless represent, so far as their general organisation is concerned, the earliest type of Eutheria which appeared on the globe. From these original Insectivores advance seems to have taken place along five lines:— I. some Insectivora took to attacking larger prey, including their own less fortunate relatives, and gradually developed into the Carnivora or flesh-eating mammals: II. some became vegetable feeders and gave rise to the great group of hoofed animals, relying either on their swiftness, or size, or strength for defence: III. some took to burrowing and developed into gnawers or Rodents, relying chiefly on their holes for safety: IV. some took to the air, the fore-limb becoming changed into a wing; these are the Bats: V. the remainder took to escaping into trees when hard pressed and eventually gave rise to the great group of the Primates which includes Monkey and Man.

Order V. Carnivora.

The Carnivora are distinguished above all by their teeth (Fig. 292). They have small insignificant front teeth or incisors, but the eye-teeth or canines, situated in the maxilla just where it meets

the premaxilla, are large and pointed. With these the animal seizes and kills its prey. The premolars have cutting edges consisting typically of a large central cusp and two smaller ones, one in front and one behind. The molars with the exception noted below are broad and crushing (Figs. 292 and 314). The last premolar in the upper jaw and the first molar in the lower jaw constitute what




FIG. 314. Vertical longitudinal section taken a little to the left of the middle line through the Skull of a Dog, *Canis familiaris* $\times \frac{3}{5}$.

1. Supra-occipital. 2. Interparietal. 3. Parietal. 4. Frontal. 5. Cribriform plate. 6. Nasal. 7. Mesethmoid. 8. Maxilla. 9. Vomer. 10. Ethmo-turbinal. 11. Maxillo-turbinal. 12. Premaxilla. 13. Occipital condyle. 14. Basi-occipital. 15. Tympanic bulla. 16. Basi-sphenoid. 17. Pterygoid. 18. Palatine. 19. Ali-sphenoid. 20. Internal auditory meatus, the passage for the eighth nerve to the internal ear. 21. Tentorium, a fold of calcified connective tissue projecting into the cranial cavity and separating the cerebrum from the cerebellum. 22. Foramen lacerum posterius, the passage for the tenth nerve. 23. Floccular fossa, the cavity in which the floccular lobe of the cerebellum is lodged. 24. Coronoid process. 25. Condyle. 26. Angle. 27. Mandibular symphysis. 28. Inferior dental foramen. 29—31. Segments of the second visceral arch. 29. Stylo-hyal. 30. Epi-hyal. 31. Cerato-hyal. 32. Basi-hyal. 33. Thyro-hyal, the third visceral arch. XII. Condylar foramen, the aperture through which the twelfth cranial nerve leaves the skull.

are called the carnassial teeth. These are very large blade-like teeth which bite on one another like a pair of scissors. The upper one has enlarged central and posterior cusps, the anterior cusp being small or wanting; the lower carnassial has an anterior blade-

like portion consisting of two cusps and a posterior flattened portion or heel. The nails are sharp, curved claws.

The most familiar examples of this class of animals are our Dogs and Cats. The wild ancestors of the domesticated pets are unknown, though the dog's ancestors were no doubt allied to the wolf, whereas the cat is probably descended from some species belonging to the East, allied to but distinct from the Wild Cat, *Felis catus*, still found in remote parts of Scotland and possibly in the mountains of North Wales. Possibly the domestic cat has originated from the Caffre Cat, *F. caffra*, which extends throughout Africa and was considered sacred by the ancient Egyptians, who embalmed their bodies in such amazing numbers that their mummies have been exported from Egypt and used as manure.

In the Dog, *Canis familiaris*, and the other members of the family Canidae, the muzzle is long and the teeth numerous. Their arrangement can be expressed by the dental formula $i. \frac{3}{3}, c. \frac{1}{1}, pm. \frac{4}{4}, m. \frac{2}{3} = 42$, where the upper line shows the teeth in the upper jaw, the under line those in the lower. The first figure denotes incisors, the second canines, the third premolars, and the last molars. The hindmost back teeth, or molars, are still broad. The fore-legs cannot be used for grasping. The claws are comparatively blunt and cannot be retracted.

In the domesticated Cat on the other hand the muzzle is short, and the teeth reduced in number, the formula being $i. \frac{3}{3}, c. \frac{1}{1}, pm. \frac{3}{2}, m. \frac{1}{1} = 30$, whilst the fore-limbs can be used for seizing. The claws are very sharp and can, when not in use, be completely retracted or rather raised, so as not to wear the points. In all these respects Cats are more perfectly adapted for a carnivorous life than Dogs, these latter still retaining traces of their descent from a different kind of mammal. Just as the Wolf, *C. lupus*, the Jackal, *C. aureus*, and the Fox, *C. vulpes*—the last named the only wild species of *Canis* found in Britain—are species of dogs distinguished from each other by size and slight peculiarities of hair, etc., so the Lion, *F. leo*, the Tiger, *F. tigris*, the Leopard or Panther, *F. pardus*, the Lynx, *F. lynx*, and the Puma, *F. concolor* (frequently called a "Panther" in America, where it is found from Canada to Patagonia), are all Cats. The differences in the colour of the skin which help to distinguish them are in all probability due to the fact that the

colours are protective, enabling the animals when in their natural surroundings to escape the notice of their prey. Thus Lions, which as a rule live in dry and rather open places, are of dun colour; the stripes of the tiger's skin deceptively resemble the alternating shadows and sunlit strips of ground found amongst the reeds in which they live; the spots of the leopard are undiscoverable amidst the alternating patches of light and shade caused by the sunlight struggling through the interstices of the foliage of a forest.

The Bears, *URSIDAE*, represent a third type of Carnivora. They are plantigrade, placing the whole sole of the foot on the ground; the molars are blunter than those of the Cats and Dogs and very broad, the carnassials are broad and the premolars very small; the upper carnassial is a comparatively small tooth and the heel of the lower carnassial is larger than the blade; these peculiarities are connected with the fact that the Bears are not merely flesh feeders but can live partly on a vegetable diet. The Brown Bear of Europe, *Ursus arctos*, which used to be abundant in Britain, is so nearly allied to the Grizzly Bear, *U. horribilis*, of the Rocky Mountains, that the latter is by some authorities placed in the same species. In Eastern Canada, especially in the Province of Quebec, the Black Bear, *Ursus americanus*, is very abundant and is trapped for its fur. It is usually an inoffensive animal feeding on berries and bark but occasionally, especially when it has cubs, it will attack man.

The Stoats, Weasels, Martens, Minks, Polecats, Otters, Badgers and Skunks, forming the family *MUSTELIDAE*, are sometimes supposed to be allied to the Bears, but are really very distinct. They have very long necks, long flexible bodies and short limbs, and their habits are exceedingly bloodthirsty and ferocious. The chief resemblances to Bears are found in the skull and teeth, but the contrast in general build and in gait—the *Mustelidae* are digitigrade—is very striking. Six species of *Mustelidae* are found in Great Britain: (1) The Otter, *Lutra vulgaris*, an animal which has webbed toes and a long, somewhat flattened tail. It lives on fish, passing much of its time in the water. (2) The Badger, *Meles taxus*, a heavy, somewhat clumsy animal with blunt claws and short limbs, leading a nocturnal, burrowing life and feeding on mice, reptiles, insects, fruit, acorns and roots. (3) The Pine Marten, *Mustela martes*. (4) The Polecat, *Mustela putorius*, which feeds on small mammals, birds, reptiles and eggs, and has a disagreeable odour. The Ferret is a domesticated variety of the Polecat. (5) The Weasel, *Mustela vulgaris*. In cold regions the Weasel turns white in winter. (6) The Stoat, *Mustela*

erminea, which also turns white in cold climates except the tip of its tail, which remains black. Its fur is much prized. These last four are closely related species with long slender bodies, sharp curved claws and ferocious habits.

In North America there is an interesting family, the PROCYONIDAE, intermediate between the Ursidae and Mustelidae. The members of this family have sharp muzzles but clumsy bodies and short necks; the Raccoon, *Procyon lotor*, is the most familiar. It is omnivorous. The Mustelidae are represented by otters, martens



FIG. 315. The Common Skunk, *Mephitis mephitica*.

and a remarkable form, the Skunk, *Mephitis mephitica* (Fig. 315), which produces a secretion of such repulsive odour as to make it avoided by other animals and a terror to man. It is strikingly marked and affords a much-quoted example of warning coloration; its conspicuous colour enabling would-be enemies to distinguish its possessor from less offensive prey.

The Carnivora mentioned hitherto are often grouped together as the *CARNIVORA VERA* or *FISSIPEDIA*. The second group of recent Carnivora is represented by the Seals and is termed the *PINNIPEDIA*. The name is derived from the fact that fingers and toes are united

by webs of skin. The Seals are almost as purely marine animals as the Whales and Sea-cows, but they have become adapted to their surroundings in quite a different way. Thus their fur is close and thick, and they are protected against the cold of the water by it, instead of being covered all over by a thick layer of fat as are the Whales. The tail is short and insignificant, but they make a powerful stern oar by directing the feet backwards parallel to the body so that the soles are turned up. Thus the feet act just in the same way as the tail does in a whale, making up and down strokes and driving the animal forward. The whole upper




FIG. 316. The Patagonian Sea-Lion, *Otaria jubata*. From Slater.

part of the limb is buried in the body. In one group, the true Eared or Seal-skin Seals, OTARIIDÆ (the fur of some species of which is used for making jackets), the feet can be turned forward when the animal comes on land. There are also some traces of an external ear, whence comes the name OTARIIDÆ or Eared Seals which is given to them (Fig. 316). They are confined to the Pacific coast of America. The Walrus, *Trichechus rosmarus*, of the Arctic seas, is the representative of a second family, the TRICHECHIDÆ. No external ear is present but here also the feet can be turned forward. The canine teeth of the upper jaw are very long and give the animal a fierce appearance. They are however chiefly used for digging up

bivalves from the mud and for climbing on the blocks of ice in the Arctic regions where the animal is found. The name "Old Man" sometimes given to it by whalers is suggested by the tufts of grey hair on the sides of the face. The common Greenland Seal, *Phoca vitulina*, and the Gray Seal, *Halichoerus grypus*, are the two species of PHOCIDÆ, the third and last family of the Pinnipedia, regularly found round about the British coast in out-of-the-way places. The members of this family have harsh fur and no trace of an ear-flap, and are unable to turn their feet forward, so that when they come on land they shuffle along entirely by the aid of their fore-limbs. They are in fact the most thoroughly adapted for aquatic existence of all the Pinnipeds. *Phoca vitulina* is common on the eastern shores of Canada and New England.

Order VI. Ungulata.

The great group of the Ungulata or hoofed animals represents the second line of evolution from the primitive Insectivores. Here we find that all power of grasping with the limbs is absent and the feet are purely adapted for running, the toes being encased in hard blunt nails which are called hoofs. At the present time the Ungulata include a number of very diverse forms. But it must be remembered that a large proportion of the group is extinct, and that to some extent the fossil forms serve to connect the very heterogeneous members of the group that still exist.

Sub-Order I. Sub-ungulata.

In former times there existed a great assemblage of big and often clumsy animals belonging to the Ungulata in which the toes were all nearly equal in length and the bones of the wrist arranged in parallel longitudinal series. Only two families of the *Sub-ungulata*, as these animals are called, survive till the present day. These are the Elephant family, PROBOSCIDEÆ, and the family of the *Hyrax*, HYRACIDÆ.

HYRACIDÆ.

The *Hyrax* (*Procavia*) is the coney mentioned in Scripture.

• The Hyracidæ are small, not unlike rabbits in appearance, but their hind-feet closely resemble those of the Rhinoceros. Their front teeth are, it is true, somewhat chisel-shaped, as in the Rodentia, but there are four of

Family
Hyracidae.

these below and two above, which is quite unlike the arrangement in the rabbit. It is possible however that the two teeth reckoned as lower posterior incisors may really be canines, since they do not, like the others and like the incisors of the Rabbits, grow throughout life (Fig. 317). These animals are found throughout Africa except in the north, Arabia and Syria. Only one genus is now recognized,




FIG. 317. Skull of *Hyrax* (*Procavia*) *dorsalis* $\times \frac{2}{3}$

- | | | | |
|-----------|--------------|--------------------------------|--------------------------------|
| 1. Nasal. | 2. Parietal. | 3. Meatus auditorium externus. | 4. Process of the exoccipital. |
| | 5. Jugal. | 6. Lachrymal foramen. | i. 1. First incisor. |

Hyrax (*Procavia*), with several species. Most of these live amongst rocks, in mountains and in stony places, but some frequent the trunks and large branches of trees and sleep in holes.

PROBOSCIDEAE.

The Elephant is too well known to need description, but it may be pointed out that the trunk is really a long flexible snout, an excessive exaggeration of what is found in Insectivores, and that the tusks are front teeth, only those in the upper jaw being developed (though in some extinct elephants, as for instance *Dinotherium*, those of the lower jaw alone were developed), and finally that the upper parts of the arms and legs are quite free from the body, instead of being, as is usually the case with mammals, buried inside the general contour of the body. There are only two living species, the African Elephant, *Elephas africanus*, inhabiting the forest region of tropical Africa and hunted for its tusks, and the Indian Elephant, *Elephas indicus*, inhabiting the jungles of India, Further India, Ceylon and Sumatra, which

Family
Proboscideae.

is frequently domesticated. The canines are lost and have left no traces. The molars succeed one another in a horizontal row, never more than two being at any one time functional (Fig. 318).




FIG. 318. Skull of a young Indian Elephant, *Elephas indicus*, seen from the right side, the roots of the teeth have been exposed $\times \frac{1}{2}$.

1. Ex-occipital. 2. Parietal. 3. Frontal. 4. Squamosal. 5. Jugal.
6. Premaxilla. 7. Maxilla. 9. Supra-occipital. 13. Basi-occipital.
14. Postorbital process of the frontal. 15. Lachrymal. 16. Pterygoid
process of the ali-sphenoid. i 1. Incisor. mm 3, mm 4. Third and
fourth milk molar. m 1. First molar.

The ridges on these teeth when worn present the appearance of parallel bands in the Indian Elephant, but in the African they form diamond-shaped lozenges. The ears of the latter are very large and the trunk ends in two nearly equal prehensile "lips" attached to its lower margin. In the Indian Elephant the ears are smaller; there is but one finger-like "lip" at the end of the trunk and this is attached to the upper edge of the end of the trunk. The skull is very massive, but the exterior gives an erroneous impression of the size of the brain-case because the bones are enormously thickened and contain large air-spaces, especially in the older specimens, where the frontals may attain a thickness of one foot. Till recent times (geologically speaking), a large elephant, *Mastodon*, inhabited North America, Europe, and parts of Asia. Its remains are being constantly dug up from the bottom of gravel-pits and marshes. Some species of *Mastodon* had tusks in both jaws;

in all the molar teeth were covered with tubercles like those of the pig, instead of ridges of enamel. Another fossil species allied to the Indian Elephant but covered with thick fur, the Mammoth, *Elephas primigenius*, had formerly an extensive range around the North Pole, and at one time was common in Britain.

Sub-Order II. Ungulata vera.

All the rest of the Ungulata have the thigh and the upper arm more or less buried in the body, whilst the heel and the wrist are raised in walking so that the creature goes along on the tips of its toes. The bones of the wrist are arranged in transverse rows, the members of two adjacent rows alternating with one another. The first digit in both fore- and hind-limb is entirely absent. These true Ungulates, *UNGULATA VERA*, as they are called, are divided into two great groups: (1) the *PERISSODACTYLA*, in which there are an odd number of toes, and in which the true central axis of both arm and leg runs down through the centre of the third finger or toe (Fig. 319), and (2) the *ARTIODACTYLA*, in which there is an even number of toes, and in which the axis of the limb passes down between the third and fourth toes (Fig. 322).

Division I. *PERISSODACTYLA*.

The Perissodactyla were formerly a numerous class of animals but now three families alone survive, the tapirs, *TAPIRIDÆ*; the various species of rhinoceros, *RHINOCEROTIDÆ*; and the horse and numerous species of ass, *EQUIDÆ*.

Of these the oldest and most primitive are the *TAPIRIDÆ*. They still have four toes on the fore-feet, which is an even number; but as they have only three on the hind-feet, and in both fore- and hind-feet the axis of the limb runs through the third toe, there is no doubt that they are to be classed with the Perissodactyla (Fig. 319). The snout is long and flexible, longer than the snout of the Insectivores but not so long as the snout of the Elephant. A most interesting feature in the natural history of the Tapirs is that they are now found only in two widely separated parts of the world, viz., the north of South America, and in the Malay Peninsula with the neighbouring islands of Borneo and Sumatra. We need not however suppose that there was at one time a land

bridge across the Pacific, for in recent rocks we find remains of *Tapirs* all over Europe, Asia and America, so that the present species are to be regarded as two separated remnants of a great race of animals which once had a very wide distribution. Their present range affords an often quoted example of what is known as "discontinuous distribution."




FIG. 319. Bones of right Fore-foot of existing *Perissodactyles*. A, *Tapir*, *Tapirus indicus* $\times \frac{1}{2}$. B, *Rhinoceros*, *Rhinoceros sumatrensis* $\times \frac{1}{2}$. C, *Horse*, *Equus caballus* $\times \frac{1}{2}$.

- c. Cuneiform (ulnare). l. Lunar (inter-medium). m. Magnum (third distal carpal). p. pisiform. R. Radius. s. Scaphoid (radiale). td. Trapezoid (second distal carpal). tm. Trapezium (first distal carpal). U. Ulna. u. Unciform (conjoined 4th and 5th distal carpals). II—V, second to fifth digit. From Flower.

The RHINOCEROTIDAE are represented at the present day by the genus *Rhinoceros*. The *Rhinoceros* is a heavier and clumsier animal than the *Tapir*: it has three toes on both fore- and hind-feet and no projecting snout. Its chief peculiarity however is the horn which it carries so to speak on the bridge of its nose. The horn has no bony core, and as it is entirely composed of horny matter may be said to be a mass of hairs stuck together. There are several species found in Asia and in

Rhinocero-
tidae.

Africa; the best known is perhaps the Indian, *Rh. unicornis* (Fig. 320); the Javan, *Rh. sondaicus*, is smaller. Both these species have but one horn. Two-horned rhinoceroses (the two horns standing one behind the other), are now found in the Malay Peninsula,




FIG. 320. Indian Rhinoceros, *Rhinoceros unicornis*. From Wolf.

Borneo, and in Sumatra (*Rh. sumatrensis*), and in Africa there are several species; the commonest, *Rh. bicornis*, is frequently met with in menageries. It is supposed that the idea of the unicorn was derived from the one-horned rhinoceros, but if this be so the imagination must have played a powerful part in evolving the graceful animal which figures in the royal arms out of the clumsy rhinoceros.

The general appearance of the horse, *Equus caballus*, is sufficiently well known, but the structure of its feet, which, next to the wings of a bird, are the most highly finished organs of locomotion in the animal kingdom, demand special attention.

The apparent "knees" of the horse correspond to the joints of the wrist and the ankle, the true elbow and knees are concealed in the body of the animal, although the motion of these joints can be clearly seen if a running horse be watched. A horse walks on the very points of its finger and toe nails, and it possesses only one finger on each hand and one toe on each foot (Fig. 319), the fingers and toes corresponding to the outer fingers and toes of the Rhinoceros being represented merely by bones entirely concealed beneath the skin

and applied like splints to the great middle finger and toe respectively. Thus the whole limb instead of being a loosely jointed flexible organ for grasping, becomes a firmly jointed lever bending only in one plane and suitable for quick locomotion.

The Horse, as we know it, has been domesticated and bred by man for thousands of years, and is doubtless very unlike its wild ancestor. The wild animals at present existing which are called Wild Horses are all more like donkeys, with longer ears and without the peculiar wisp-like tail of the Horse; they are also all more or less striped. The Zebras and Wild Donkeys are found in Africa, on the great plains in the south, in the deserts of Syria and Persia and in the central plains of India. Another African form, the Quagga, has become extinct in recent times. In America when discovered there were no horses, although the horse has since run wild there; but in the most recent geological period the horse abounded in America, and why it should have died out in a country which afterwards proved to be well suited for it is a mystery.

Division II. *ARTIODACTYLA*.

Unlike the Perissodactyla, the Artiodactyla or even-toed Ungulates constitute an immense assemblage of animals, and until the invention of the modern fire-arms were the dominant animals on the great plains of Africa and we may add of North America. The Artiodactyla may be divided into a higher and a lower section.

The lowest section may broadly be called the Pigs, *SUINAE*.

Suinae. They retain four toes on fore- and hind-feet, have a snout ending in a round flat surface and are all gross

feeders, eating not only roots of various kinds but also small animals if they come in their way. Their teeth are covered with tubercles a good deal blunter than the cusps on the teeth of an Insectivore but still of the same essential nature. Such teeth are termed bunodont, whence the name *BUNODONTIA* (Gr. *βουνός*, a hill or mound) has sometimes been applied to this division. The Hippopotamus, the sole representative of the family *HIPPOPOTAMIDAE*, is nothing but an enormous Pig; it differs from the ordinary Pig in having all its toes of equal length, whereas in the true Pig the outer (second and fifth) toes are small and do not reach the ground. The Hippopotamus spends most of its time in rivers and swamps feeding on the reedy vegetation of such places. It has exceedingly powerful jaws and when wounded has been known to crush a canoe

between them. The true Pig belongs to the Family SUIDAE and is a domesticated variety of the wild boar, *Sus scrofa*, which, as is well known, survived in England until the middle ages and still survives in Europe. In the male the canines, or eye-teeth, are powerfully developed, those of the lower jaw projecting upwards outside the mouth. In the Babirusa, *Babirusa alfurus*, of Celebes, the upper canines do not enter the mouth but are bent upwards and appear through special holes in the skin, curving back over the head like horns. They grow persistently, their roots being kept open. The Pigs are not strictly vegetable feeders, but are really scavengers, eating every vegetable or animal substance they encounter, the food they especially seek consisting of roots. A very interesting genus, the Peccary, is represented by two species, *Dicotyles tajacu* and *D. labiatus*, which inhabit the American continent. The former ranges from Patagonia to the Red River of Arkansas, the latter between Paraguay and British Honduras. The name means 'two navels' and was suggested by the presence of a large gland in the middle of the back resembling a navel. On the hind-foot the fifth toe is wanting, so that there are only three toes; but the position of the axis of symmetry is still between the third and fourth toes. The Peccaries go in droves and are most dangerous antagonists; climbing a tree is the only chance of safety to a hunter who meets a herd.

When we leave the Pigs we have to deal with the higher section of the Artiodactyla, the *SELENODONTIA* or *RUMINANTIA*, which include most of our domestic animals, the cow, sheep, goat, camel, etc., as well as all the deer and antelopes. The name is derived from the habit of ruminating, that is of bringing the food back from the stomach into the mouth after it has been swallowed, and chewing it again. Corresponding to this habit we find that the stomach has acquired a complicated structure. Just where the gullet opens into it we find a large pouch projecting laterally with the walls covered with little projections or papillae. This is called the paunch or rumen; just below the oesophagus is another smaller pouch divided by a constriction from the first (Fig. 321). The second pouch is called the reticulum because its walls are raised into intersecting folds producing cavities like the cells of a honeycomb. The food is swallowed without chewing, mixed with saliva, and after traversing the oesophagus it is driven from rumen to reticulum and back by the action of the muscles, and well soaked with gastric juice. After some time it is pressed up again into the

mouth and thoroughly ground up by the great broad premolar and molar teeth. When swallowed for the second time it is nearly fluid. It now passes down a groove or channel in the side of the gullet enclosed between two ridges. Reaching the spot where the gullet opens into the stomach, the grooves are continued along the upper wall of the stomach and the fluid food is led away from the paunch into the third division of the stomach, the manyplies or psalterium, which has numerous folds of membrane projecting into its cavity; by means of these the food is completely filtered from all the solid matter it contains. It then passes on into the




FIG. 321. Stomach of a Sheep, cut open to show the various chambers.

- | | | | |
|----------------|--------------|---------------|----------------|
| 1. Oesophagus. | 2. Rumen. | 3. Reticulum. | 4. Psalterium. |
| 5. Abomasum. | 6. Duodenum. | | |

fourth and last compartment, the abomasum, whose walls are raised into but a few ridges and which is lined with an epithelium containing numerous gastric glands. This leads into the duodenum or first part of the intestine, in which the digestion is completed. The teeth of the Ruminants have no distinct tubercles like those of the Pig, since these projections have become confluent so as to form hard curved ridges of enamel; and as the jaws shift on each other sideways, the upper and lower back teeth produce a grinding action just as two millstones do. The name *SELENODONTIA*

that the selenodont teeth always pass through a bunodont stage in their development. The canines in the upper jaw are long in the male *Moschus*, who no doubt uses them in his fight for the

possession of the female. The lower canines however are usually placed close to the lower front teeth and indistinguishable from them. There are—with few exceptions—no front teeth in the upper jaw, and the grass is bitten off by pressing the lower front teeth against a patch of hardened gum.

The feet of the Ruminants are organs beautifully formed for quick motion, the ideal which Nature has, so to speak, striven to attain, being the same in their case as in that of the horse, though she has had to start from a different basis. As in the case of the horse, the end striven after has been a firm jointed lever moving only in one plane; but in Ruminantia this has been attained by keeping two fingers and two toes, and so to speak glueing them together except in the bones of the hoof. Ruminants, like Horses, walk on the points of their finger- and toe-nails; the metacarpels of the third and fourth digits are fused together, whilst of the outer fingers and toes only vestiges remain which hardly ever reach the ground, and often do not appear externally. The “cloven hoof” is therefore formed by the nails of two fingers or two toes (Fig. 322).

The families composing the division Ruminantia are the TRAGULIDAE or Chevrotains; the CAMELIDAE or Camels
 Classification. (Tylopoda); the CERVIDAE or Deer; the GIRAFFIDAE or Giraffes; the ANTILOCAPRIDAE which has but one species, the Prongbuck, *Antilocapra americana*; and the BOVIDAE or hollow-horned cattle (Cavicornia) including antelopes, goats, sheep and oxen.

The TRAGULIDAE comprise some small animals found in Africa and India, in which the foot is intermediate in structure between that of the pigs and that of the higher Ruminants: the outer toes are complete although very slender, and the two inner imperfectly joined with one another. The stomach and teeth however are like those of a Ruminant, except that there is no third compartment or psalterium. The African Chevrotain from the West Coast is larger than its Asiatic allies (Fig. 323). It frequents water-courses and is said to have the habits of a pig.

The Camels are familiar to all as far as their general appearance is concerned. The humps—of which the Arabian camel, *Camelus dromedarius*, has one, and the Bactrian or Asiatic camel, *C. bactrianus*, two—are masses of fat, reserve material on which the animal supports its life when deprived of food. In the foot the main weight rests on a pad behind the hoofs; these latter are separated from each other, so that the animal has a broader support than a cow or a deer. A camel does not walk on its finger and toe-nails, but

on the last joints of the fingers and toes. The stomach has no psalterium, but both the rumen and reticulum have a large number of water-cells, that is deep pouch-like outgrowths in which a quite undrinkable fluid is stored. It will be noted that all the peculiarities of the structure of the Camel which have just been mentioned are directly related to the exigencies of a life on arid, sandy wastes. Thus the diverging toes and leathery pad on the foot enable them to secure a broader surface of the yielding sand on which to support the animal's weight: the humps are a provision of food,



FIG. 323. The African Water-chevrotain, *Dorcatatherium aquaticum*.

and the water-cells in the stomach contain a supply of fluid to serve the animal in its long wanderings from oasis to oasis over the desert. The Arabian Camel is only known in the domesticated state, but the Bactrian Camel ranges wild over some of the more inaccessible regions of Central Asia.

It is a remarkable and interesting fact that we find some members of the Camel tribe in South America. These animals, the Llama, *Auchenia glama*; the Vicuna, *A. vicugna*; the Alpaca, *A. pacos*; and the Huanaco, *A. huanacus*; live in the Andes. They have no humps but possess long fleeces which are used for making

cloth. The skeleton of one of these animals is almost indistinguishable from that of a camel, and they have the same stupid, stubborn ways as their relatives in the Old World. It is curious to see in the stomach the same provision as is found in the camel, although water is, as a rule, plentiful enough where the Llama lives. In such a case the only explanation that can be given is that the Llama's ancestors originated in the Old World, and like man colonised the New World later.

The higher Ruminants are divided into two main groups according to the character of their horns. In the CERVIDAE or true Deer the horns are bony outgrowths of the frontal bones. The horns are shed every year and are nearly always branched. They may be termed antlers to distinguish them from the true horns of the Bovidae. The antlers are usually confined to the male, but in the Reindeer, *Rangifer tarandus*, which is called the Caribou in Canada, they also occur in the female. When the antler has attained its full growth, the blood supply ceases and the skin peels off. In a rim round the base called the "fur" absorption takes place, so that the greater part is easily detached. In the Cavicornia or BOVIDAE, the core of the horn is an unbranched bony outgrowth into which air spaces continuous with the cavity called the frontal sinus of the skull often extend. This core is permanent and is covered by a hard horny sheath made of compacted hairs. Two species occupy an intermediate position, and have been made the types of distinct families: these are the Giraffe, *Giraffa camelopardalis*, and the Prongbuck, *Antilocapra americana*. The Giraffe is confined to the grassy plains of the interior of Africa; it is a conspicuous inmate of Zoological Gardens, on account of its extraordinarily long neck, in which however there are as usual only seven vertebrae. The Giraffe has two short horns, unbranched and covered throughout with soft fur. In the Prongbuck, which is found in the prairies of North America, the horn bears a small lateral branch and is covered with a horny sheath, and this sheath, not the horn itself, is shed once a year.

In the family BOVIDAE are included everything from an Antelope to an Ox, and, strange as it may appear, we have practically a complete series of links filling up the gap between the graceful light-limbed Gazelle and the thick-necked Buffalo, so that we cannot say very precisely where Antelopes end and Oxen begin. The Musk-ox, *Ovibos moschatus* (Fig. 324), which ranges over the Arctic wastes of Canada in large herds, is intermediate in some

respects between the Sheep and the Goats on the one hand and the Oxen on the other, but is more closely allied to the former series.

At present in Britain there are but two indigenous species of deer found wild, the Red-deer of Scotland, *Cervus elaphus*, and the Roe-deer, *Capreolus caprea*; the Fallow-deer, *C. dama*, is probably an introduced species, and at present is only represented in Britain by semi-domesticated animals. In Roman times there were wild Oxen, and some suppose that a breed of wild Oxen kept at Chillingham in Northumberland and in one or two other large parks are descended from these ancestors.




FIG. 324. The Musk-Ox, *Ovibos moschatus*.

In Canada a large variety of the Red-deer, the Wapiti, *Cervus canadensis*, is found, also the Reindeer or Caribou, *Rangifer tarandus*, and the Elk or Moose, *Alces machlis*, with broad fan-like horns. Throughout the whole of Eastern America the so-called "red-deer," *Cariacus virginianus*, is found in the mountains. The Bovidae are represented by the Musk-ox, *Ovibos moschatus*, with horns curved like a ram, and by the Rocky Mountain Goat, *Haploceros montanus*. Until recently the American Bison, the so-called "Buffalo," *Bos americanus*, ranged in enormous herds over the Western plains of North America; but before 1883,—with the exception of a few scattered stragglers which are "protected,"—this magnificent animal had been exterminated.

Order VII. Rodentia.

The Rodentia or Gnawers (Lat. *rodo*, to gnaw) are another of the main divisions of the Mammalia and include our rabbits, hares, squirrels, rats and mice, besides the porcupine, beaver, guinea-pig and many other foreign species. These are all sharply marked off from other mammals by the structure of their teeth. The incisors, of which there are typically only one pair in each jaw, are chisel-




FIG. 325. Side view of the Skull of the Rabbit, *Lepus cuniculus*.

1. Nasal bone. 2. Lachrymal bone. 3. Orbito-sphenoid. 4. Frontal.
5. Optic foramen. 6. Orbital groove for ophthalmic division of trigeminal nerve. 7. Zygomatic process of squamosal. 8. Parietal. 9. Squamosal.
10. Supra-occipital. 11. Tympanic bone. 12. External auditory meatus. 14. Lower incisor. 15. Anterior premolar tooth. 16. Anterior upper incisor. 17. Mandible. 18. Maxilla. 19. Premaxilla.
20. Occipital condyle.

shaped and covered with hard enamel on their outer sides only. They constantly grow and are only kept down to proper size by continual gnawing and rubbing against each other (Fig. 325). If one of the teeth is destroyed the opposite one grows until it may pierce the other jaw, prevent the mouth from being opened, and thus starve the animal to death. There are no canines, so that there is a great space or diastema between the front teeth and back teeth. The claws are always blunt and nail-like, and walking is done on the last joints of fingers and toes, not as in the case of the

Ungulates on the points of the nails (Fig. 295). Our English Rodents are the Hares and Rabbits, *LEPORIDAE*; the Squirrels, *SCIURIDAE*; the Voles, Rats and Mice, *MURIDAE*; and the Dormouse, the sole British representative of the family *MYOXIDAE*. In North America there are allied species, and in addition the Ground-squirrels, or Chipmunks, *Tamias*, and three species of Woodchuck or Marmot, *Arctomys*; also Porcupines, represented by the common Canadian Porcupine, *Erethizon dorsatus*, the Beaver, *Castor canadensis*, and many others. *Hystrix cristata* is the Porcupine of Southern Europe and Northern Africa. The guinea-pig is probably a domesticated variety of the South American species *Cavia cutleri*. These various species are very like each other in their general anatomy, differing in the character of their molars, in their fur and in their tails.

Hares and Rabbits constitute the *DUPLICIDENTATA*, one of the two sub-orders into which the order is divided.

The name is derived from the possession of an extra pair of upper incisors, which however are so small as to be useless. The tail is short and the cusps of the premolar and molar are joined so as to form ridges or folds running across the tooth. The Common Hare, *Lepus timidus*, and the Mountain Hare, *L. variabilis*, are both British; they have longer legs than the third British form, the Rabbit, *L. cuniculus*, and have fewer young at a time. In the temperate part of North America there are at least six species of Duplicidentata all referable to the genus *Lepus*. Of these the most interesting are *Lepus americanus* and *Lepus campestris*. The fur of both




FIG. 326. Dorsal view of the Skull of a Rabbit, *Lepus cuniculus*.

1. Nasal bone. 4. Frontal. 7. Process of squamosal supporting the jugal.
8. Parietal. 10. Supra-occipital.
12. External auditory meatus. 13. Angle of lower jaw. 17. Interparietal.

these species turns white at the tips in winter, enabling the animals to escape observation on the snow-covered ground.

L. americanus, the Northern Hare, is abundant in New England and Eastern Canada: its summer fur has a cinnamon colour. *L. campestris* is the famous "Jack-Rabbit" of the western prairies, which has fur of a yellowish-gray colour in summer. It can run with great swiftness.

The remaining Rodentia are called *SIMPLICIDENTATA*, and possess only two incisors above, one on each side.

The Squirrel, *Sciurus*, is distinguished by its bushy tail, its large hind limbs, and the fact that the cusps on its back teeth are distinct. *Sciurus vulgaris* is the common British Squirrel; it extends from Ireland to Japan. Two species are very common in Canada and New England, viz. *Sciurus hudsonicus*, the Red Squirrel, and *S. carolinensis*, the Grey Squirrel. These lively little animals can be seen in autumn disporting themselves in the trees lining the avenues of the suburbs of Montreal. *Sciuropterus volans* is the Flying Squirrel; this animal is provided with a furry expansion of the skin of its sides joining the elbow and knee. This expansion forms a parachute-like membrane which supports it in its great leaps from tree to tree. In these manœuvres it is assisted by the broad flattened tail. The Flying Squirrel is common in the temperate part of the United States. A similar but larger species (*S. sabrinus*) may be seen at dusk leaping from tree to tree on the Mountain of Montreal. *Anomalurus*, found in West and Central Africa, is also a Flying Squirrel, the skin of whose sides is prolonged into a parachute-like membrane (Fig. 327). It differs from *Sciuropterus* however in having a round tail provided with horny scales underneath, which assist in climbing, and in having its "parachute" supported by a cartilaginous rod arising from the elbow.

The Mice and Rats, *MURIDAE*, have naked tails with scales underneath. The ordinary Rat is the brown Norway Rat, *Mus decumanus*, which was introduced some time ago into England and has almost everywhere driven out the old English Black Rat, *M. rattus*. The Common British Mouse is *M. musculus*; and the Wood-mouse, *M. sylvaticus*, and the Field-mouse, *M. minutus*, also occur in Britain. The Water-rat or Vole, *Arvicola*, is distinguished from the true Rat by the fact that the cusps on its back teeth, instead of being as in the true Rat rounded, are angular. *A. amphibius*, the Water-vole, *A. agrestis*, the Field-vole, which often does much damage to crops, and *A. glareolus*, the Bank-vole,

represent the genus in Britain. The Dormouse, *Muscardinus avellanarius*, which like the Squirrel passes the winter in a hole in a tree, has a long bushy tail, and, in outer appearance at any rate, more resembles a tiny squirrel than a rat. In its skull it resembles the MURIDAE, but it differs from both Squirrels and Rats in not



FIG. 327. The African Flying Squirrel, *Anomalurus fulgens*.

possessing a caecum on the intestine. On this account it, along with five or six allied species from Europe and Africa, has been separated as a distinct family, the MYOXIDAE.

Amongst the most interesting American Rodents are the Beaver, the Porcupine, the Ground-squirrel, the Marmots and the Musquash. The Beaver, *Castor canadensis*, has a broad flat tail, suited for swimming, which is covered with horny scales above and below. The Beaver, by means of its sharp incisors, cuts down trees growing on the banks of streams, so that they fall across streams damming them up, and thus raise the level of the water so as to cover the entrance to their burrows. By this means large tracts of country have been converted into swamp. The Porcupines have some of their hairs developed into sharp spines which make them awkward objects to

handle. In the Canadian Porcupine, *Erethizon dorsatus*, the spines are concealed by the fur. The commonest Ground-squirrel of North America is the Chipmunk, *Tamias*, an active little animal with large eyes and a short hairy tail. The Prairie Marmot, *Cynomys*, or so-called Prairie-dog, lives together in communities, burrowing in the ground. Their homes are often shared by a small burrowing Owl, *Athene cunicularia*, and by a Rattlesnake, which probably eats the young Marmots. The Musquash or Musk-Rat,



FIG. 328. The Musquash, *Fiber zibethicus*.

Fiber zibethicus, is peculiar to North America, and very widely distributed in suitable places (Fig. 328). It is aquatic, living on roots and water-plants and most active at night. It constructs burrows in the banks of streams, the openings of which are under water. Its fur is valued.

Order VIII. Cheiroptera.

The Cheiroptera (Gr. χείρ, a hand ; πτερόν, wing) or Bats have not in their general organization, in teeth or brain or stomach, departed far from the Insectivora ; their great distinguishing feature is the modification of the arm into a wing. As in Birds, the fore-arm is bent up on the upper arm, the wrist bent down on the fore-arm ; but unlike Birds' wings the flying membrane is of skin, the

greater part of which is stretched between the fingers of the five-fingered hand, only the smaller part extending, as in Birds, between the elbow and the side of the body. The hand is enormous, the little finger being, as a rule, very greatly developed and as long as the rest, whilst the thumb alone is small and is not included in the




FIG. 329. Skeleton of *Pteropus medius*, a fruit-eating Bat \times about $\frac{1}{2}$.

- | | | | | |
|--------------|------------------------|-------------|-------------|------------|
| Clavicle. | 2. Keel. | 3. Scapula. | 4. Humerus. | 5. Radius. |
| 6. Ulna. | 7. Little finger. | 8. Thumb. | 9. Ilium. | 10. Pubis. |
| 11. Ischium. | 12. Obturator foramen. | 13. Femur. | 14. Tibia. | |
| 15. Fibula. | 16. Tarsus. | | | |

membrane, but ends in a hook-like nail (Fig. 329). Part of the membrane extends down the thighs, and in some even the tail is involved. The knees are turned outwards and backwards, a most extraordinary position which would mean dislocation if the hip-joint of any other mammal were forced into it but which is rendered possible in Bats owing to the fact that in them the pubes are not directed inwards so as to meet one another in a symphysis but slope outwards and are consequently widely separated from one another (Fig. 329). When the Bat crawls it hooks itself along with its thumb-nail and pushes itself awkwardly with its hind feet. It is a most awkward gait, and the animal is consequently very helpless when not flying.

One of the most extraordinary things about Bats is the development of sensitive patches of skin on the face for the purpose of perceiving faint disturbances in the air. It has been shown that the eyes of Bats, although apparently normal, are really imperfect, that in fact the layer of visual rods in the retina, which is the special organ of light-perception, is most imperfectly developed. To compensate for this we find, in some species, the outer ear, in others the skin around the nostrils, in others again the skin on the lips and chin, developed into curious outgrowths richly supplied with nerves. By means of these sense-organs Bats are enabled to avoid obstacles, and a blind Bat, let loose in a room across which numerous strings have been stretched, will fly about without touching one. Owing to their powers of flight Bats are exceedingly widely distributed, being found on small oceanic islands where there are no other mammals. The true blood-sucking Bat or Vampire, *Desmodus rufus*, is found in Central and in South America. Its back teeth are rudimentary, but its front teeth are razor-edged. The so-called Flying Foxes or Fox-bats, *Pteropus*, of India and Madagascar, are the largest Bats known; they feed exclusively on fruit and the cusps on their teeth are blunter than is usual amongst Bats. Allied to them is the African *Xantharpyia*, one species of which frequents the interior of the Pyramids and other dark ruins in Egypt (Fig. 330). Both are included in the family PTEROPIDÆ. In Great Britain we have some fifteen species of Bat divided amongst five genera. Of these the Long-eared Bat, *Plecotus auritus*; the Whiskered Bat, *Vespertilio mystacinus*; the Horse-shoe Bats, *Rhinolophus hipposiderus* and *Rh. ferrumequinum*; the Barbastelle, *Synotis barbastellus*; and the Pipistrelle, *Vesperugo pipistrellus*; represent the genera. Besides

the species just mentioned there are three more species of *Vesperugo* and three more of *Vespertilio* in Britain. South America has a large fauna of peculiar Bats, but the North American forms are



FIG. 330. Female and young of *Xantharpyia collaris*. From Sclater.

allied to the British, although the species are distinct. The Serotine, *Vesperugo serotinus*, is the only species common to the two regions. *Scotophilus humeralis* is one of the most familiar species peculiar to North America.

Order IX. Primates.

The last order of the Mammalia is that of the Primates, which include Lemurs, Monkeys, and Man. As was mentioned before, this order is characteristically arboreal, that is to say they live among trees, climbing from branch to branch. This circumstance may explain why they retain certain primitive characteristics found elsewhere only amongst the Insectivora. Thus the thigh and upper arm are quite free from the body, and the whole sole and palm are placed on the ground when walking; and there are five fingers and five toes. On the other hand the eyes are pushed round to the front of the skull instead of being placed at the sides of the head, and the jugal joins the post-orbital process of the frontal, so that the orbit is surrounded by a bony ring (Fig. 331). Some at least of the toes have flat nails. The big toe is shorter than the rest, and, except




FIG. 331. Half front view of the skulls, A, of an old, B, of a young Gorilla, *Gorilla savagei* $\times \frac{1}{4}$.

1. Parietal. 2. Sagittal crest. 3. Frontal. 4. Supra-orbital ridge.
5. Squamosal. 6. Maxilla. 7. External auditory meatus.

in Man, can be separated from them so as to be used for grasping. In most but not in all Monkeys, the thumb can be used similarly, so that monkeys are said to have four hands. There are two large mammae or nipples situated on the breast. Other mammae when present are vestigial and situated behind the functional ones.

There are two great divisions of the Primates, the *LEMUROIDEA* and the *ANTHROPOIDEA*. The first of these includes some curious little animals, of which the great majority are found in the Island of Madagascar, the rest in Africa and the Malay Archipelago. Many

of the species are nocturnal, move silently and have large eyes, whence the name Lemur (Lat. *lemures*, goblins, spectres). These animals have heads recalling those of rats, with no suggestion of the human face, and in their brains and some other points they are far below the Monkeys. The cerebral hemispheres do not cover the cerebellum; the placenta of the embryo is spread evenly all over the surface of the womb, and there are occasionally additional mammae on the abdomen. Their incisor teeth are separated in the middle line, but, as in all Primates, there are never more than two on each side. The Ring-tailed Lemur, *Lemur catta* (Fig. 332), is said to be an



FIG. 332. The Ring-tailed Lemur, *Lemur catta*.

exception to the rule that the group is arboreal and to live amongst rocks and bushes, but other authorities say that it lives in troops amongst the forests of Madagascar. It is a gentle, graceful creature with a plaintive cry.

The *ANTHROPOIDEA*, including the true monkeys and man, are distinguished by the fact, that the bony ring surrounding the orbit sends inwards a plate of bone, which completely separates the orbit from the temporal fossa. Further, the cerebral hemispheres conceal the cerebellum when the brain is viewed from above; the placenta is highly developed and concentrated on one part of the wall of the womb, and there are never more than two mammae. This sub-order of Primates is divided into five families, viz. HAPALIDAE, CEBIDAE, CERCOPITHECIDAE, SIMIIDAE, and HOMINIDAE, the last being constituted of the single species, *Homo sapiens*, man.

The HAPALIDAE and CEBIDAE are confined to South and Central America, and are sometimes grouped together as *PLATYRRHINI* (Gr. πλατύς, broad, ῥίς, ῥινός, nose). The animals belonging to this section have a broad internasal septum and three pairs of premolar teeth. The tympanic bone is without a tube-like prolongation. The HAPALIDAE or Marmosets are small, furry animals inhabiting the forests of Brazil and Columbia; they have the least ape-like feet of any of the Anthropoidea. The great toe is small and it alone has a flat nail; all the other toes and all the fingers bear curved claws. There are only two pairs of molars. The CEBIDAE have flat nails on their fingers and toes and three pairs of molars, making with the premolars six cheek-teeth on each side of each jaw, the largest number found amongst Anthropoidea. The Cebidae have prehensile tails which assist them in climbing. The genus *Ateles* includes the Spider-monkeys, in which this function of the tail is prominent, the under side of this organ being naked and scaly so as to allow the animal to obtain a hold. The genus *Cebus* has the tail hairy all round; several species of this genus are often seen in captivity.

The CERCOPITHECIDAE and SIMIIDAE are confined to the Old World. They constitute the section *CATARRHINI*, characterised by the possession of a narrow internasal septum, a spout-like prolongation of the tympanic bone extending into the base of the ear-flap, and the reduction of the number of premolar teeth to two pairs, whilst there are always three pairs of molars. The CERCOPITHECIDAE have the legs as long as the arms, or longer, and go habitually on all-fours. There are always bare patches of thick callous skin on the buttocks forming the so-called ischial callosities, on which the animals rest when they assume a sitting posture, and there is in almost every case a well-developed tail. This family includes the Indian and African monkeys—the Bandar-log

of Kipling's Jungle Tales. One species, *Macacus inuus*, the Barbary ape, is found on the Rock of Gibraltar, and this is the only species which enters Europe. It is remarkable for being completely tailless. *Semnopithecus entellus* is the sacred Langur of India, and owing to its immunity from persecution has become very abundant.




FIG. 333. The Orang-utan, *Simia satyrus*, sitting in its nest. From a specimen in the Cambridge Museum.

The SIMIIDAE include those monkeys which in structure and appearance most resemble man. In this family the tail is completely absent, the arms are longer than the legs, and the gait might be described as that of a baby learning to walk. They never go completely on all-fours, but usually shuffle along unsteadily on

their two feet, which like those of a baby show a tendency to turn inwards under them; they usually steady themselves either by means of a stick or by bending forward so that their knuckles touch the ground. Four genera are included in this section, viz. *Hyllobates*, *Simia*, *Gorilla*, and *Anthropopithecus*. *Hyllobates* includes several species known as Gibbons, inhabiting South-Eastern Asia and the Malay Archipelago. These are apes with exceedingly long arms; they assume a completely upright position when on the ground, and run along holding up their long arms in the air as if they were balancing poles. In their power of supporting themselves without any help from the arms they approach man; but in other respects they depart widely from him, as for instance in the brain, where the cerebellum is not completely covered by the cerebrum. *Simia* is represented by a single species, *S. satyrus*, the Orangutan, a large animal about $4\frac{1}{2}$ feet high, which is found in the islands of Borneo and Sumatra. This animal walks on two feet supporting itself on its knuckles. It lives however almost entirely in trees, constructing a sort of nest for itself out of branches (Fig. 333). It is remarkable for its high rounded cranium enclosing the large brain, which presents the closest approximation to the human brain of all the brains of apes. The cranium is however still overshadowed by the bones of the face and lower jaw. There exists only a single species of *Gorilla*, viz. *G. savagei*, confined to a limited region of Equatorial Africa. This is the largest of all the apes, reaching a height of $5\frac{1}{2}$ feet. It is distinguished from *Simia* by its shorter arms and more receding forehead. The skull of the young gorilla strikingly resembles a child's skull, but in the adult it is deformed by the development of great bony ridges which give attachment to the muscles of the face (Fig. 331). *Anthropopithecus* is represented only by *A. troglodytes*, the Chimpanzee, which lives in Western Africa in the same region as the Gorilla but has a wider distribution. It is distinguished by its shorter arms, which do not reach below the knee, and by its smoother and rounder skull. It does not reach a height of more than 5 feet, and is on the whole the most Man-like of all the Simiidae, though each of the other species of the family approaches more closely to the human standard in some particular feature.

Man is distinguished above all by the great size of the brain, which is double the size of that of the highest monkey, and by the modification of the leg so as entirely to support the body, in consequence of which the big toe is no longer used for grasping.

Some hold that it was this latter modification which brought about the great development of the intelligence of man, arguing that when once the hand was entirely at the service of the brain the varied uses to which it could be put would give the opportunity for the use of the mind. This seems probable, but the great factor which has stimulated the mental development of Man is his habit of living together in societies and undertaking concerted enterprises for the benefit of the community. To this power of combination not only intellect but also language and morals may eventually be traced back. Man did not make society; it was society that made Man.

Men are divided into three great races which are as distinct from one another as are many groups of allied species amongst other animals. All races of Men are however mutually fertile but a mixed race shows a tendency to revert to one or other of the parent races—this is true at any rate of mixtures which have taken place within the historical period. Many authorities explain the peculiarities of some island populations on the assumption that they are due to an early crossing of two of the principal races at a time when perhaps their leading features were less fixed than they are now. The three races alluded to are characterized as follows:—

(i) **Ulotrichi.** Woolly hair characterised by numerous close, often interlocking, spirals, 1—9 mm. in diameter. The hair of the head is usually long in the Melanesians and very short in the Negritos and Bushmen. It is almost invariably black. Ellipsoidal in transverse section.

Ex. Bushmen, Negrillos, Negritos, Negros and Bantus, Papuans and Melanesians.

(ii) **Cymotrichi.** Wavy hair; undulating or it may form a curve or imperfect spiral from one end to the other (as in the Indonesians), sometimes the extremity forms long curls (as in some Europeans and Todas), in another variety the hair is rolled spirally to form clustering rings or curls a centimetre or more in diameter (as in Australians, some Dravidians and Ethiopians). The hair of non-European peoples is generally black, with often a brownish or reddish tinge. Oval in transverse section.

Ex. Dravidians, Australians, Ethiopians, Semites, Mediterraneans, Northern Europeans, Indo-Afghans, Indonesians, Polynesians, Armenians, Central Europeans.

(iii) **Leiotrichi.** Straight or smooth hair. Lank hair that usually falls straight down, occasionally with a tendency to become wavy (as in the Finns, some Amerinds). It is almost invariably black. Circular in transverse section.

Ex. Lapps, Ugrians, Turko-Tartars, Northern and Southern Mongols, Northern, Central and Southern Amerinds, Patagonians, Eskimo.

The Class Mammalia is divided as follows :

Sub-class 1. PROTOTHERIA.

Mammalia which lay large eggs and in which the two oviducts are completely separated, and there is a persistent cloaca. No placenta.

Ex. *Ornithorhynchus*, *Echidna*.

Sub-class 2. METATHERIA.

Mammalia in which the young are born in a most imperfect condition, and are carried by the mother in a pouch on the abdomen. The oviducts are differentiated into vagina, uterus, and Fallopian tube, the two vaginae partially united. The cloaca is divided into an anus and a urinogenital aperture. An allantoic placenta may or may not be developed but when present is more or less vestigial. In all cases there is an adhesion between the yolk-sac of the embryo and the womb.

Order I. Polyprotodontia.

Metatheria with four or five incisors on each side of the upper jaw and with at least three pairs of incisors in the lower jaw of approximately equal size.

Family (1) DIDELPHIDAE.

Polyprotodontia with a large opposable great toe, the other digits of the hind-foot being subequal in size. American.

Ex. *Didelphys*.

Family (2) DASYURIDAE.

Polyprotodontia with a rudimentary great toe, the other digits of the hind-foot subequal in size. Australian.

Ex. *Thylacinus*.

Family (3) PERAMELIDAE.

Polyprotodontia with a rudimentary great toe, the other digits of the hind-foot united by a web of skin, the second and third being excessively slender: the muzzle long and pointed. Australian.

Ex. *Perameles*.

Family (4) NOTORYCTIDAE.

Polyprotodontia with rudimentary eyes, an enlarged manus and burrowing habits. Australian.

Ex. *Notoryctes*.

Order II. Diprotodontia.

Metatheria with not more than three incisors on each side of the upper jaw, and with, as a rule, one pair of large chisel-shaped incisors in the lower jaw, the other lower incisors being vestigial or absent.

Family (1) EPANORTHIDAE.

Diprotodontia with all the toes of the hind-foot free from one another and subequal. American.

Ex. *Coenolestes*.

Family (2) PHASCOLOMYIDAE.

Diprotodontia with the toes of the hind-foot united by a web of skin: only one pair of chisel-shaped incisors in upper jaw: limbs subequal. Australian.

Ex. *Phascolomys*.

Family (3) PHALANGERIDAE.

Diprotodontia in which the toes of the hind-foot are united by a web of skin, the great toe being well-developed, free from the web, and opposable to the rest: limbs subequal: three incisors on each side of the upper jaw. Australian and Papuan.

Ex. *Phalanger*.

Family (4) MACROPODIDAE.

Diprotodontia in which the toes of the hind-foot are united in a web of skin, and the great toe is rudimentary: the fore-limbs very short and suited only for grasping:

three incisors on each side of the upper jaw. Australian and Papuan.

Ex. *Macropus*, *Bettongia*, *Petrogale*.

Sub-class 3. EUTHERIA.

Mammalia in which the young are born able to suck, and in which there is no pouch. The two vaginae are always completely confluent. The cloaca is divided into an anus and a urinogenital aperture. An allantoic placenta always present and greatly developed.

Order I. Edentata.

Eutheria devoid of enamel on the teeth, and without median teeth, the limbs are, as a rule, provided with heavy hook-like claws.

Family (1) BRADYPODIDAE.

Limbs long and the fore-limbs greatly longer than the hind-limbs: face short: arboreal in habit. South American.

Ex. *Bradypus*.

Family (2) MYRMECOPHAGIDAE.

Limbs short and stout: muzzle exceedingly long: no teeth. South American.

Ex. *Myrmecophagus*.

Family (3) DASYPODIDAE.

Limbs short and stout: muzzle long with numerous teeth: a shield of dermal bones covered by horny scales. South American.

Ex. *Dasypus*.

Family (4) MANIDAE.

Covered externally with large, overlapping horny scales: no teeth: long protractile tongue. Asian and African.

Ex. *Manis*.

Family (5) ORYCTEROPIDAE.

● Covering of bristly hairs: teeth numerous and heterodont: no thumb on anterior limb: femur with a third trochanter. African.

Ex. *Orycteropus*.

Order II. Cetacea.

Large aquatic Eutheria which have lost the hind-limbs and have developed horizontal flukes on the tail. The fore-limb is a paddle; the cranium is globular and the teats are posterior.

Sub-order 1. Mystacoceti.

Cetacea devoid of teeth in the adult: with plates of whalebone in the mouth.

Ex. *Balaena*, *Balaenoptera*.

Sub-order 2. Odontoceti.

Cetacea with teeth at any rate on the lower jaw and no whalebone.

Ex. *Physeter*, *Globicephalus*, *Delphinapterus*, *Phocaena*.

Order III. Sirenia.

Aquatic Eutheria, with limbs and tail as in the Cetacea: the cranium is cylindrical and the teats pectoral.

Ex. *Manatus*, *Halicore*.

Order IV. Insectivora.

Small plantigrade Eutheria, with pointed cusps on the molar teeth: the brain of low type: a flexible snout often present. The more familiar families are

Family (1) ERINACEIDAE.

Insectivora with the body covered with harsh spines, limbs subequal.

Ex. *Erinaceus*.

Family (2) SORICIDAE.

Small mouse-like Insectivora, with soft fur.

Ex. *Sorex*, *Blarina*.

Family (3) TALPIDAE.

Mouse-like Insectivora with rudimentary eyes, and large hands adapted to burrowing.

Ex. *Talpa*, *Condylura*, *Myogale*.

Order V. Carnivora.

Eutheria with sharp recurved claws and powerful canine teeth: the premolars adapted for clipping flesh: the incisors small.

Sub-order 1. Fissipedia.

Carnivora with separated digits: a distinct carnassial tooth, and one or more broad molars.

Family (1) FELIDAE.

Fissipedia with short face, a reduced number of premolar and molar teeth, and with retractile claws.

Ex. *Felis*.

Family (2) CANIDAE.

Fissipedia with long face and full number of premolar teeth: claws non-retractile.

Ex. *Canis*.

Family (3) URSIDAE.

Fissipedia with long face: teeth blunt and partially adapted for a vegetable diet: plantigrade in gait.

Ex. *Ursus*.

Family (4) PROCYONIDAE.

Fissipedia with a sharp pointed muzzle and reduced number of teeth, otherwise like *Ursus*.

Ex. *Procyon*.

Family (5) MUSTELIDAE.

Fissipedia with long necks and exceedingly flexible bodies: a reduced number of teeth: in the skull and in the shape of the carnassial tooth they resemble Ursidae but they are digitigrade in gait.

Ex. *Lutra*, *Meles*, *Mustelus*, *Mephitis*.

Sub-order 2. Pinnipedia.

Aquatic Carnivora with the toes united by a web of skin: the tail is rudimentary, but the two hind-limbs are turned backwards and closely apposed so as to form a paddle: no distinct carnassial tooth, and no broad molars.

Family (1) OTARIIDAE.

Pinnipedia still retaining a trace of the external ear, and capable of turning the hinder-limbs forward so as to walk on land.

Ex. *Otaria*.

Family (2) **TRICHECHIDAE.**

Pinnipedia devoid of external ear, but capable of walking on land: the upper canines form long tusks.

Ex. *Trichechus*.

Family (3) **PHOCIDAE.**

Pinnipedia devoid of external ear, and incapable of turning the feet forward, so that when on land they can only wriggle along with the help of their anterior limbs: the canines not specially enlarged.

Ex. *Phoca*.

Order VI. **Ungulata.**

Eutheria with limbs adapted entirely for progression, the terminal phalanx of each functional digit is enclosed in a short blunt nail.

Sub-order 1. **Sub-ungulata.**

Ungulata with short sub-equal toes, and with the bones of the carpus and tarsus arranged in parallel longitudinal series.

Family (1) **HYRACIDAE.**

Small Sub-ungulata with a very short snout: a pair of chisel-like incisors in each jaw.

Ex. *Hyrax* (*Procavia*).

Family (2) **PROBOSCIDEAE.**

Large Sub-ungulata with a very long flexible snout (trunk) used for prehension: incisors long and curved, forming tusks: molars very broad, only one pair in use at a time.

Ex. *Elephas*.

Sub-order 2. **Ungulata vera.**

Ungulata in which the bones of the carpus and tarsus are arranged in transverse rows, the members of successive rows alternating with one another. The first digit is lost.

Division I. **PERISSODACTYLA.**

Ungulata in which there is, with rare exceptions, an uneven number of digits in each limb, and in which the axis of symmetry passes through the third digit.

Family (1) TAPIRIDÆ.

Perissodactyla with four digits in the fore-limb and three in the hind limb : a short flexible snout.

Ex. *Tapirus*.

Family (2) RHINOCEROTIDÆ.

Perissodactyla with three subequal digits in each limb : one or two median horns without bony cores carried on the nasal bones.

Ex. *Rhinoceros*.

Family (3) EQUIDÆ.

Perissodactyla with only one complete digit in both fore- and hind-limbs.

Ex. *Equus*.

Division II. ARTIODACTYLA.

Ungulata in which there is almost always an even number of digits, and in which the axis of symmetry passes between the third and fourth digits, these digits being flattened against each other so as to form two symmetrical halves of a cylinder.

Section A. Bunodontia.

Artiodactyla with comparatively simple stomachs, and separate cusps on the molar teeth.

Family (1) HIPPOPOTAMIDÆ.

Large Bunodontia with four subequal toes in both fore and hind-limbs.

Ex. *Hippopotamus*.

Family (2) SUIDÆ.

Bunodontia of moderate size, in which the two outer toes though complete are shorter than the others.

Ex. *Sus*, *Babirusa*, *Dicotyles*.

Section B. Selenodontia.

Artiodactyla with complex stomachs adapted for ruminating. The cusps on the molars coalesce so as to form crescents.

Family (1) TRAGULIDAE.

Small Selenodontia without horns, and with only three compartments in the stomach: the outer toes although excessively slender are still complete.

Ex. *Tragulus*.

Family (2) CAMELIDAE.

Selenodontia without horns, with only three compartments in the stomach: the outer toes entirely absent, the inner toes slightly diverging below, the weight resting on a pad behind them.

Ex. *Camelus*, *Auchenia*.

Family (3) CERVIDAE.

Selenodontia with antlers in the form of bony outgrowths of the frontal bone annually shed: four compartments in the stomach: the second and fifth digits incomplete.

Ex. *Cervus*, *Cariacus*, *Capreolus*, *Rangifer*, *Alces*.

Family (4) BOVIDAE.

Selenodontia with horns which are outgrowths of the frontal, never shed, and covered with a thick horny sheath: four compartments in the stomach: the second and fifth toes rudimentary.

Ex. *Bos*, *Ovis*, *Ovibos*, *Haploceros*.

Family (5) GIRAFFIDAE.

Selenodontia with short horns which are outgrowths of the frontal, never shed, and permanently covered with soft fur: immensely elongated neck and very long limbs.

Ex. *Giraffa*.

Family (6) ANTILOCAPRIDAE.

Selenodontia with branched horns which are outgrowths of the frontal covered with a horny sheath. This sheath is annually shed.

Ex. *Antilocapra*.

Order VII. Rodentia.

Eutheria with one large pair of chisel-shaped incisors in each jaw growing throughout life and no canines. The Rodentia walk on the whole surface of the last joint of the

digit, not on the extreme tip as do the Ungulata: the nails are blunt but not usually hoof-like.

Sub-order 1. Duplicidentata.

Rodentia in which there is a second pair of rudimentary incisors in the upper jaw.

Ex. *Lepus*.

Sub-order 2. Simplicidentata.

Rodentia in which there is only one pair of incisors in the upper jaw.

Ex. *Sciurus*, *Tamias*, *Mus*, *Fiber*, *Arvicola*, *Muscardinus*, *Castor*, *Erethizon*, *Hystrix*, *Cavia*.

Order VIII. Cheiroptera.

Eutheria in which the fore-limb is converted into a wing, the hand being greatly enlarged, and the fingers elongated in order to support the wing-membrane, the leg small, and the knee-joint rotated backwards: teeth and brain resembling those of the Insectivora.

Ex. *Vespertilio*, *Vesperugo*, *Rhinolophus*, *Xantharpyia*.

Order IX. Primates.

Eutheria with long limbs, the brachium and femur not being buried in the body: five digits in each limb, some of them having flat nails: the great toe or thumb or both are opposable to the other digits. The orbits are rotated on to the anterior aspect of the skull and are completely surrounded by bone: the brain is large.

Sub-order 1. Lemuroidea.

Primates in which the orbit is merely surrounded by a bony ring: front teeth separated by a space in the middle line.

Ex. *Lemur*.

Sub-order 2. Anthroipoidea.

Primates in which the orbit is completely separated from the temporal fossa by an inwardly projecting sheet of bone: front teeth in contact in the middle line.

Section (1) Platyrrhini.

Anthroipoidea with a broad internasal septum, three pairs of premolar teeth and a simple tympanic bone: the great toe

opposable to the other toes: the thumb imperfectly or not at all opposable to the other fingers.

Family (1) HAPALIDAE.

Small thickly furred Platyrrhini with a flat nail on the great toe only, claws on all the other digits: two molar teeth on each side.

Ex. *Hapale*, *Midas*.

Family (2) CEBIDAE.

Platyrrhini with flat nails on all toes and three molar teeth on each side.

Ex. *Ateles*, *Cebus*.

Section (2) Catarrhini.

Anthropoidea with a narrow internasal septum, two pairs of premolar teeth and three pairs of molars in each jaw. The tympanic bone has a tube-like prolongation. The great toe is opposable to the other toes, the thumb imperfectly opposable to the other fingers.

Family (1) CERCOPITHECIDAE.

Catarrhini with arms not longer than their legs: bare patches on the buttocks, and with rare exceptions, a well-developed tail.

Ex. *Macacus*, *Semnopithecus*.

Family (2) SIMIIDAE.

Catarrhini with arms much longer than legs and a semi-erect gait: no tail.

Ex. *Gorilla*, *Hyllobates*, *Simia*, *Anthropopithecus*.

Section 3. Hominidae.

Anthropoidea with arms of moderate length and long legs: the foot entirely adapted to support the body, the great toe not opposable to the other toes: the thumb completely opposable to the other fingers: the upright attitude habitual: no tail: brain very large.

Ex. *Homo*.

CHAPTER XX.

PHYLUM PLATYHELMINTHES.

FROM the Earthworm up to Man we have been considering animals which either in the embryo or in the adult exhibit the coelom in a characteristic and unmistakable form. Such a space is even indicated in the Actinozoa, where the endoderm lining the lateral compartments of the coelenteron gives rise to the muscular bands and the generative organs, and performs the excretory functions, and is probably the homologue of the mesoderm of higher forms. If this be so the space in the Actinozoa surrounded by this "endoderm" is equivalent to a coelom, but one not yet shut off from the digestive tube.

Thus from the Coelenterata to Man we have traced a series of organisms all of which possess in some form or other this particular organ. Since Vertebrates include the most highly organized animals at present living on the earth, we have placed them last in the series of Coelomata, but this must not be taken to indicate that there is any kind of progression through *all* the series of lower animals up to man. The vertebrate ancestor of man probably separated whilst still of exceedingly simple structure from the ancestors of other animals, and there has been independent progress along many different lines, culminating for instance in an Insect, a Cuttlefish, and a Sea-urchin.

Leaving now the Coelomata we must consider a few phyla which we cannot definitely assert to be Coelomata. All of these groups possess between the ectoderm and endoderm a mass of various tissues, muscular, connective, excretory and generative, hollowed out by spaces or traversed by systems of tubes; but it has not yet been shown in the case of any one of them that this mass of tissues has had in the embryo the form of sacs lying at the sides of the alimentary canal from the walls of which the said tissues have been differentiated.

In the case of some of the following phyla it is reasonable to expect that fuller knowledge will show that they are coelomate, but at present this has not been definitely proved, and thus it seems more logical to consider them apart from the organisms which undoubtedly possess a coelom.

The Phyla that follow are all Metazoa, and since they possess no notochord are Invertebrates.

The Platyhelminthes consist of three large classes, (i) TURBELLARIA, (ii) TREMATODES, and (iii) CESTODA. These three groups contain animals which are bilaterally symmetrical, each half of the body being a reflex of the other. The alimentary canal may be entirely lost, but when present it has only one aperture, which serves both as mouth and anus, as in the case of the Coelenterata. A separate anus is never found, and there is no evidence from the study of development that the ancestors of Platyhelminthes ever possessed such an opening to the alimentary canal. The alimentary cavity is practically the only cavity in the animal, as there is no space between the skin and the intestine which could be compared to the body-cavity of other animals, and except for the narrow cavities of the excretory system and the genital ducts the bodies of these animals are solid. The excretory system, often termed the water-vascular system, the function of which is the ridding the body of the waste nitrogenous materials which, as explained before, result from the catabolism of living protoplasm, is in its structure eminently characteristic of the Phylum. It consists of a series of narrow tubules permeating the body in every direction; these on the one hand communicate with larger tubes which open on to the surface of the body, and on the other receive a large number of still smaller tubules each of which ends in a cell with a single cilium hanging into the end of the tubule. The constant flickering of this cilium is thought to keep the fluid contents of the tubule in motion. Such a cell is termed a flame-cell from the fancied resemblance of the motion of the cilium to the flickering of a flame. The Platyhelminthes usually contain both male and female reproductive organs in the same animal, and it is characteristic of them to have a special portion of the ovary called the yolk-gland or vitellarium, set apart to produce small yolk-filled cells, which serve as food for the perfect ova during the early stages of development.

Class I. TURBELLARIA.

The Turbellaria are free-living animals, and as a rule swim about in the sea or in fresh-water ponds or streams. A few, however, have taken to living amongst moist earth, and some species, e.g. *Bipalium kewense*, are occasionally met with in hot-houses all over the world, being probably imported with the roots of some tropical orchid or fern. Other species of land Turbellaria are common in the Tropics.

Turbellaria are all very soft animals and capable of considerable change of outline. In their native habitat they are not easy to see, many of them having colours which imitate the sea-weeds, etc., amongst which they live, and many only appear at night from their hiding-places. If, however, a bunch of red sea-weed be shaken out in some clean sea-water in a white china dish, as a rule many of these animals can be seen swimming with an undulating motion like a Sole or clinging to the sides of the dish.

One of the commonest species in the fresh-water ponds of Great Britain is *Mesostoma ehrenbergii*, a flat leaf-like organism, perhaps half an inch long, the transparency of whose tissues permits at times the examination of some of the internal organs. The whole of the outer layer of cells—the ectoderm—bears innumerable cilia, by whose action the animal glides slowly along when it does not swim by the undulations of its whole body. Within this ectoderm are certain circular and longitudinal muscle-fibres, and these surround a mass of cells called the parenchyma. This consists of cells of a stellate shape, united with one another by their out-growths, the interstices between the cells being filled by a semi-fluid jelly-like substance. The parenchyma may be regarded as a primitive form of connective-tissue in which the nervous system, alimentary canal and excretory and reproductive systems are embedded.

The ectoderm cells secrete a great deal of mucus, mingled with which are a number of little rod-like bodies called rhabdites. The exact use of these is not clearly known; in their formation, they recall the nematocysts of the Coelenterata. Like the nematocysts they are extruded on irritation. The mucus forms a bed over which the animal moves and in which the cilia work, so as to propel the animal.

The mouth of the *Mesostoma* is, as its name indicates, near the centre of the body, on the ventral surface. It leads at once into a pharynx with very muscular walls which can act like a sucker. This pharynx can be withdrawn into the body or pushed a little




FIG. 334. *Mesostoma splendidum*, drawn from a compressed individual; the cilia and rhabdites are omitted. Magnified. From von Graff.

1. Brain showing two eyes. 2. Pharynx surrounding the mouth. 3. Food vacuole in an endoderm cell. 4. Ectoderm. 5. Testis lying above alimentary canal, showing developing spermatozoa. 6. Muscle fibres.
7. Genital atrium. 8. Glands of the genital atrium. 9. Penis.
10. Shell-glands surrounding the spermatheca. 11. Germarium. 12. Vitellarium.

way out of the mouth. The chamber in which it lies, and which gives it room to play in and out, is an ectodermal pouch called the pharynx-sheath. This is small in *Mesostoma*, but in other Turbellarians it may be much larger, and the pharynx is consequently capable of stretching out a long distance. This is the case, for instance, with the fresh-water genus *Planaria* (Fig. 335).

Certain glands, called salivary glands, open into the cavity of the alimentary canal at the inner end of the pharynx, and then the cavity enlarges into the stomach, which is a sac-like structure with no other opening than the mouth lying in the centre of the body. The cells lining this cavity are, like the endoderm cells of *Hydra*, amoeboid, and they take up particles of food into themselves in the same way that an *Amoeba* does. This primitive form of digestion has been lost in most of the Coelomata, where the digestive cells pour out solvent fluids into the cavity of the alimentary canal, and the food is rendered soluble in this cavity before being absorbed. In the Turbellaria, as in the Coelenterata, this secondary method of digestion coexists with the amoeboid method.

Mesostoma is carnivorous and eats small worms, minute crustacea and insect larvae. It uses its mucus to ensnare and entangle its prey. Its method of devouring them recalls the habits of the starfish. It holds them fast by means of the pharynx, using this as a sucker. The so-called salivary glands secrete a strong digestive ferment which rapidly dissolves the flesh of the victim, reducing it partly to a fluid condition and partly to a disintegrated mass of particles. There is no vascular system to distribute the digested food to the different parts of the body, so that these products must be passed from cell to cell through the solid body until they arrive where they are needed. The undigested parts are passed out through the mouth.

The two main ducts of the excretory or water-vascular system open near the sides of the mouth, each then passes upwards towards the dorsal surface and divides into two longitudinal vessels, one running towards the head, the other towards the tail. These four longitudinal branches give off innumerable finer ones, which subdivide until each branchlet ends in a flame-cell. These latter are very minute and require a high power of the microscope and very careful focussing to see.

The nervous system consists of a large ganglion called the brain, divided by a shallow depression into two lobes. It is situated in front of the mouth near the anterior end of the animal, embedded

in the parenchyma. It gives off a pair of nerves which run forward to the tip of the body, and another pair of rather stout nerves which run back, one on each side of the pharynx, to the tail. The nerves give off fine branches which are distributed all over the body. A pair of eyes of a simple structure lie on the upper surface of the brain.

The male organs consist of two long sac-like testes which lie above the alimentary canal and are directly continuous with their short ducts, the vasa deferentia. These ducts unite to form the muscular penis which communicates with the genital atrium through which it can be protruded. The proximal portion of the penis is swollen up to form a bulb called the vesicula seminalis, in which the spermatozoa are stored up before being transferred to another individual. The female organs consist of a large ovary on each side, divided by constrictions into numerous lobes; these are not well marked in the species represented in Fig. 334. The whole of one ovary and the greater part of the other produce only yolk-cells, and are therefore to be regarded as yolk-glands or vitellaria. The basal lobe however of one of the ovaries (11, Fig. 334) produces ova capable of development; this is the ovary (*sensu stricto*) or germarium. The two oviducts, or as they are generally styled, the vitellarian ducts, are directly continuous with the yolk-glands and lead directly into the genital atrium. Near their common opening a thick muscular pouch opens into the atrium. This is the spermatheca which receives the spermatozoa from another individual, and emits them on to the ova as they pass its opening. Around the spermatheca are certain glands called the shell-glands, which also open into the atrium. The secretion of these glands forms the egg-cases in which one egg and many yolk-cells are enclosed. As the egg-cases are formed they pass into two great sac-like diverticula of the atrium, one situated on each side of the body, called the uteri. In these they are carried about by the animal for some time, but are eventually laid, and become attached to water-plants by the stickiness of their outside layer. There are two kinds of these egg-cases in *Mesostoma*, one thin-walled, called "summer eggs," and the other thick-walled, called "winter eggs." The former are believed to contain ova fertilized by the spermatozoa of the same individual; these develop rapidly, devouring the surrounding yolk-cells and the resulting young hatch out in April and May. These when they arrive at maturity cross-fertilize one another, and as a result the thick-walled capsules termed "winter-eggs" are produced,

which lie dormant during the winter, whilst the parent turns opaque, sinks to the bottom of the water and dies. In the spring young are hatched from the winter eggs, which produce when mature summer eggs, and in some cases are supposed after laying these to live on and produce the winter eggs of the next season; but in this respect the various species probably differ from one another.

The Turbellaria are a large group, and fall naturally into two main divisions, viz. the *Rhabdocoelida* with a rod-like gut (Gr. ῥάβδος, a staff) and the *Dendrocoelida* with a branched one (Gr. δένδρον, a tree). Each of these divisions is again subdivided; thus the order *Rhabdocoelida* includes the sub-orders *ACOELA*, *ALLOIOCOELA*, and *RHABDOCOELA*, whilst the *Dendrocoelida* are divided into *POLYCLADA* and *TRICLADA*.

To turn first to the divisions of the *Rhabdocoelida*, the sub-order *ACOELA* includes extraordinary forms in which there is no digestive cavity; the alimentary canal is represented by a porous mass of endoderm cells, amongst the interstices of which the digested food soaks. The endoderm completely fills the space surrounded by the ectoderm and muscle layers; there is no parenchyma. In almost every case there is a muscular pharynx by which the animal adheres to its prey, and through which a pseudopodium-like mass of endoderm is protruded. This protrusion secretes a solvent which disintegrates the victim, and it then engulfs the product after the manner of an *Amoeba*. In some cases, however (*Convoluta*), the endoderm is infested with small green Algae, and the animal lives largely on the compounds formed by these, needing only a scanty diet of Protozoa and Diatoms to supplement its internal provision.

The genital organs are simple; the ovary is not divided into vitellarium and germarium and no yolk-cells are produced. It has been suggested that the Acoela are the most primitive of all the phylum, and that they have been directly derived from large multinucleate Protozoa, but their development makes it possible that their peculiarities are due to degeneracy.

The *ALLOIOCOELA* have a parenchyma and a hollow alimentary canal which has slightly developed lateral lobes. The testes are represented by scattered masses of cells without distinct ducts; and the spermatozoa apparently find their way to the main vasa deferentia by passing through the interstices of the parenchyma. The germaria are two in number and have long ducts opening into the genital atrium distinct from those of the vitellaria.

The *RHABDOCOELA* are the most highly developed forms of the Rhabdocoelida; their alimentary canal is cylindrical and surrounded by a mass of extremely watery parenchyma which simulates a body cavity. The arrangement of the genital organs has been described above.

The first division of the Dendrocoelida, the *TRICLADA* (Gk. *τρι-*, triple, *κλάδος*, a branch), derive their name from the circumstance that there are three main branches of the alimentary canal, one in the middle line running forward from the inner end of the pharynx, and one running backwards at each side of the pharynx. There is a pair of germaria formed from the most anterior branches of the great lobed ovaries; they discharge into the same ducts as the vitellaria. The uterus is an unpaired sac. The group includes marine, freshwater and terrestrial forms. *Planaria* (*Dendrocoelum*) is a common form in the streams of both Britain and Canada.




FIG. 335. *Planaria polychroa* \times about 4.

1. Eye. 2. Ciliated slit at side of head. 3. Mouth of proboscis. 4. Outline of the pharynx sheath into which the pharynx can be withdrawn.
5. Reproductive pore.

The *POLYCLADA* are a marine group and are thought by some authorities to be the most primitive of all Turbellaria. Their name is suggested by the fact that the alimentary canal consists of many branches radiating from a central stomach into which the large pharynx opens. The ovary is a lobed organ not divided into vitellarium and germarium. The eggs are laid in plate-like masses bound together by slime. They develop into free-swimming young known as Müller's larvae. These are little oval organisms provided with a ciliated band drawn out into eight longitudinal loops, and on these the cilia are arranged in transverse rows fused at the base so as to resemble the combs of the Ctenophora. The resemblance of these ciliated loops to the "ribs" of the Ctenophora suggested to Lang the idea that Turbellaria were Ctenophora which had become adapted to a creeping life, in which a marked bilateral

symmetry had replaced the generally radial arrangement of the organs of the normal Ctenophora, though traces of the latter arrangement remain in the Polyclada. The brain on this view would be the apical plate which had shifted forward; the stomach with its radiating branches would correspond to the funnel of the Ctenophora and the canals in connection therewith; the pharynx sheath would represent the stomodaeum, the so-called "stomach" of the Ctenophora; but the eversible pharynx, the copulatory organ, and above all the excretory system must be regarded as new acquisitions. This view, which at first was not received with much favour, has received strong support by the investigation of a marine organism known as *Ctenoplana*. This is a flattened animal resembling a Polyclade in shape and in the circumstance that the ventral surface is covered with cilia with which it creeps. It possesses however an apical plate of thickened nervous ectoderm supporting a mass of otoliths on bars of fused cilia, and there are eight short "ribs" radiating from this plate. These ribs as in Ctenophora are thickened bands of ectoderm bearing combs of cilia fused at the base. The funnel and its canals are represented by a lobed alimentary canal, continued on each side into a tentacle canal, from the end of which springs a long retractile tentacle. The genital organs have their independent ducts opening directly to the exterior. In all these respects therefore *Ctenoplana* is intermediate between the Polyclada and the Ctenophora. If we accept Lang's theory it is evident that on this view the Platyhelminthes are not true Coelomata. The evolution of the more complicated systems of genital organs amongst the Turbellaria out of the simpler arrangement in the Polyclada, has probably been the result of laying the eggs in numbers surrounded by a capsule. This led to a struggle amongst the eggs, resulting in the sacrifice of the smaller to the needs of the larger ova, and this to the production of weak ova to serve as food for the others, and to the differentiation of the ovary into germarium and vitellarium.

Class II. TREMATODA.

The remaining two groups of Platyhelminths have taken to a parasitic mode of life, and this has to a great extent influenced their organization. The term parasite is applied to an animal which lives at the expense of another without destroying its life. The Trematodes have lost the external ciliation of the skin the




FIG. 336. Diagram of reproductive and nervous system of *Distoma hepaticum*
 × about 8. From Leuckart.

1. Mouth. 2. Pharynx. 3. Nerve-ring. 4. Chief longitudinal nerve.
5. Beginning of alimentary canal. 6. Opening of penis. 7. Vesicula seminalis. 8. Uterus. 9. Ovary. 10. Shell-gland. 11. Anterior testis. 12. Posterior testis. 13. Yolk-glands. 14. Vas deferens.

ectoderm being everywhere covered with cuticle. In other features of their anatomy they present a great resemblance to the Triclade Turbellaria, and one family the TEMNOCEPHALIDAE may be described as intermediate between the two classes of Platyhelminths since its members still retain patches of ciliated skin. For the most part they live on or in the bodies of Vertebrates, attaching themselves either to the skin or to the alimentary canal or its outgrowths.

One of the most characteristic features of Trematoda is to be found in the suckers by which they adhere to their prey. Often indeed the lips of the mouth are thickened and muscular so as to constitute an oral sucker, but there is always a ventral adhesive disk provided with suckers or hooks or both. The mouth is situated at or near the anterior end of the body; it leads into an oral funnel opening into a muscular pharynx, which by alternate expansion and contraction pumps in the juices of the prey. Its action is thus different from that of the pharynx of Turbellaria, which, as we have seen, can act as a protrusible sucker. Behind the pharynx the alimentary canal divides into two parallel forks running back to the posterior end of the body, and beset with branches which in some cases may unite with one another across the middle line. It thus resembles what the alimentary canal of a Triclade would become were the mouth shifted to the anterior end of the body. The nervous system is remarkable for the fact that several trunks of equal size are given off from each side of the brain. The reproductive organs resemble those of a Rhabdocoele like *Mesostoma*; thus the germarium is only developed on one ovary, of which it is a basal branch, and the testes each consist of a lobed organ directly continuous with the vas deferens. The main peculiarities are as follows: there is no spermatheca; the spermatozoa from another individual enter either by a dorsal pore or two lateral pores, leading into a canal or canals which join the oviducts where they unite with one another. These ducts, totally unrepresented in Turbellaria, are called the "canals" of Laurer. Further, the genital atrium is situated on the anterior part of the body in front of the ventral sucker. There is no uterus comparable with that of Turbellaria; the so-called uterus being a long coiled tube composed of the conjoined oviducts (vitellarian ducts). Finally the testes are so large that there is not room for them side by side, but in order to stow them away one is situated behind the other.

Trematoda are divided into two orders called respectively the




FIG. 337. Diagram of digestive and excretory system of *Distoma hepaticum*
x about 8. From Leuckart.

1. Mouth. 2. Pharynx. 3. Reproductive pore. 4. Branch of alimentary canal. 5. Branches of excretory system. 6. External opening of excretory system. 7. Nerve-ring.

MONOGENEA and the *DIGENEA*. In the first named the egg gives rise to a larva which develops continuously into the adult; the main organ of adhesion is a disk situated at the posterior end of the body and armed with suckers or hooks, usually both, and there are two lateral vaginae from which the canals of Laurer lead inwards. The excretory system opens by two dorsal pores. One of the commonest of the Monogenea is *Polystomum integerrimum* found in the bladder of the Frog. This animal has an adhesive disk bearing six suckers. The fertilized egg of *Polystomum* is discharged through the cloaca of the Frog into the water. After some time a larva hatches out which has a forked alimentary canal, but which is without genital organs and has no suckers, although the posterior adhesive disk is clearly differentiated. It is provided with a number of transverse bands of cilia by means of which it swims about until it finds a tadpole, to the skin of which it attaches itself. It creeps into the branchial chamber of its host and loses its cilia, and commences to develop genital organs and suckers. About the time of the tadpole's metamorphosis the Trematode wanders down the alimentary canal into the bladder. *Sphyanura osleri* is an allied form parasitic on the skin of the Urodele *Necturus*. Its posterior disk carries two large suckers and two hooks.

The *DIGENEA* give rise to larvae which become parasitic in some animal, where they give rise by gemmation to several generations of secondary larvae, which only develop into adult forms when they are swallowed by a second animal. The life-history therefore includes an alternation of generations and is only completed in two hosts. The Digenea further differ from the Monogenea in having as main adhesive organ a sucker situated on the anterior part of the ventral surface, in having only a single "canal" of Laurer which opens on the dorsal surface, and finally in the fact that the main trunks of the excretory system coalesce to form a single trunk which opens to the exterior by a median posterior pore. The Liver-fluke, *Distoma hepaticum*, is an example of the Digenea; it is parasitic in the liver and bile-ducts of the sheep, causing a wasting disease called sheep-rot. It gives rise to a larva consisting of a solid mass of cells, the outermost layer of which is ciliated. This larva cannot survive unless it reaches a pond-snail of the species *Limnaea truncatula*. In the pulmonary chamber of this animal it loses its cilia, enlarges and becomes hollow, forming a structure called the sporocyst, which sometimes divides into two

or more. Germ cells are budded off from the wall of the sporocyst into the cavity. These by division form masses which develop into secondary larvae called *rediae*, provided with a muscular pharynx and a sac-like alimentary canal. These larvae have a pair of blunt processes on the under side near the posterior end, by the aid of which they move. They force their way out of the sporocyst and enter the tissues of the snail, being found especially in the liver. From the inner surface of their body-wall germ cells are budded off which give rise to other *rediae*, which escape from the parent by an opening near the anterior end. After a time the *rediae* give rise to larvae of a third kind called *cercariae*. These have suckers like the adult, and a forked alimentary canal with a pharynx; they are provided with a tail stiffened by a rod of gelatinous tissue recalling the Vertebrate notochord. By the aid of the tail they work their way out of the snail and attach themselves to blades of grass. The tail then falls off and they enclose themselves in a cyst of mucus, and remain there till they are eaten by a sheep, from whose intestine they pass into the liver, where they develop genital organs and become mature.

Class III. THE CESTODA.

The Cestoda are sharply distinguished from the two preceding classes of Platyhelminthes by the total absence of an alimentary canal. They are all internal parasites, living in the alimentary canal of their hosts, and absorb the half-digested juices of their hosts through all parts of their skin.

As in Trematoda there is a well-marked cuticle which protects the animal from the action of the digestive juice of the host. The ectoderm has undergone an extraordinary modification. Its cells have become long and filamentous, having long narrow necks, the body of the cell with the nucleus being pushed downwards into the subjacent tissues. These necks are however of very various lengths, and so the ectoderm, although fundamentally a single layer of cells, presents the appearance of a thick band of many layers of nuclei. The ectoderm cells intermixed with longitudinal muscles form the cortical zone of the animal. Inside this and surrounded by the circular muscles is the medullary zone of parenchyma, in which the genital organs and the excretory and nervous systems are embedded. Many of the cells of the parenchyma secrete calcareous matter and form the so-called calcareous corpuscles.




FIG. 338. *Taenia solium*. Slightly magnified.

- A. Entire worm showing head and proglottides. 1. Sucker on head.
 2. Genital pores. 3. Ripe proglottis.
 B. Head. 1. Rostellum. 2. Hooks. 3. Suckers. 4. Neck. 5. Com-
 mencement of strobilization.
 C. Ripe proglottis broken off from worm. 2. Remains of vas deferens and
 oviduct. 3. Branched uterus crowded with eggs.

Each portion of the body of a Cestode which contains the reproductive organs is called a proglottis, and is budded off from the anterior portion which is called the head. The latter is provided with suckers, and generally, in addition, with a circle of hooks situated on a prominence called the rostellum (1, Fig. 338 B). With the head the Cestode adheres to its host; its hinder part or neck buds off proglottides in which new sets of reproductive organs are formed, and this process is repeated an indefinite number of times so that a chain of proglottides is formed. The oldest proglottis is thus the hindermost. This method of segmentation is called strobilization on account of its resemblance to the formation of the Ephyræ by a Hydra-tuba (p. 65); it differs from




FIG. 339. Transverse section through a mature proglottis of *Taenia*. Magnified about 12.

1. Cuticle. 2. Long-necked cells of ectoderm. 3. Longitudinal muscle fibres cut across. 4. Layer of circular muscles. 5. Split in the parenchyma which lodges a calcareous corpuscle. 6. Ovary. 7. Testis with masses of male germ-cells forming spermatozoa. 8. Longitudinal excretory canal. 9. Longitudinal nerve-cord. 10. Uterus. 11. Oviduct.

the segmentation of the Annelida, where the new segments arise not in the neck but in the tail.

The excretory system consists of a larger and a smaller trunk on each side, which unite in the last proglottis to end in a contractile vesicle opening by a median posterior pore. In each proglottis the trunks on each side are connected with their fellows on the opposite side by transverse canals. The nervous system consists of a ring in the head, whence two lateral trunks arise. There is no brain—the impressions the animal receives from the outside world being few and simple.

The reproductive organs have the same general structure as those of the Trematoda. The vitellarium is however often unpaired,

whereas there is usually a pair of germaria. There is a large uterus (8, Fig. 340) which appears to be a lateral outgrowth from the conjoined oviducts. From the circumstance that in primitive Cestoda this uterus opens to the exterior independently of the genital atrium it is believed that it corresponds to the canal of Laurer in the Digenetic Trematoda. If this be so the functions of the genital atrium and Laurer's canal have been exchanged in Cestoda, for in Trematoda the atrium permits eggs to escape whilst Laurer's canal admits spermatozoa from another individual, in Cestoda these spermatozoa enter through the atrium whilst the canal is enlarged to form a uterus. The testes are in Cestoda




FIG. 340. Diagram of a ripe proglottis of *Taenia solium*. From Cholodkowsky \times about 10.

1. Longitudinal water-vascular canal. 2. Transverse water-vascular canal.
3. Vas deferens. 4. Vagina. 5. Ovary. 6. Yolk-gland. 7. Shell-gland.
8. Uterus. 9. Testes. 10. Longitudinal nerve.

represented by a multitude of small rounded bodies (7, Fig. 339, 9, Fig. 340) from which excessively fine ducts are given off uniting to form the single vas deferens ending in the penis. As the proglottis gets older the eggs all pass into the uterus, which swells enormously, displacing and destroying the other organs. In this condition the proglottis drops off. This process is continually being repeated so that a single parasite keeps on casting off portion after portion, each charged with ova capable of developing. In this way

a Cestode firmly lodged in the alimentary canal of its host can produce an almost indefinite number of eggs.

In the more primitive Cestoda the egg-cases, which as in Trematoda contain an ovum and a multitude of yolk-cells, escape from the detached proglottis through the opening of the uterus into water. In a short time a larva hatches out, consisting of an outer layer of ciliated cells surrounding a solid internal mass which develops six chitinous hooks. After swimming in the water for a short time the larva is swallowed by an aquatic animal, loses its outer layer of cells, thus exposing the hooks and becoming what is now termed an onchosphere. In the more modified Cestoda the uterus has no external opening, and the eggs escape from the proglottis only by decay. The remains of the proglottis, including the eggs, are swallowed by some animals, and soon after an onchosphere hatches out, no cilia being formed. In every case the onchosphere bores through the alimentary canal of its host, and is carried by the blood-stream to a suitable spot in the tissues where it fixes itself. Once fixed, the larva increases very much in size, and generally becomes hollow so as to resemble a bladder. An infolding or invagination of part of the outer layer now takes place, forming a pouch, on the inner side of which the suckers and hooks of the adult head make their appearance. The pouch is then turned inside out, and a well-marked head is thus formed. The larva is now known as a bladder-worm or Cysticercoid, and is found parasitic in a great number of animals. A very common form is *Cysticercus pisiformis* found in the coelom of the Rabbit attached to the mesentery. *Coenurus cerebralis* is a dangerous Cysticercoid in which the bladder can become as large as a plum, and on which not one but numerous heads are formed. It is found lodged in the brain of the sheep and other domestic animals, and causes the disease known as gid or staggers. A still more dangerous form is *Echinococcus polymorphus*, in which the bladder may become as large as a man's head. This enormous vesicle buds off from its inner surface secondary vesicles on each of which numerous heads are formed. This parasite is found in the Pig, Sheep, and even Man, in the liver and other internal organs.

The Cysticercoid can only complete its development when its first host is eaten by another animal. Then the bladder is cast off whilst the head firmly attaches itself by its hooks and suckers to the alimentary canal of its new host, and commences to bud off proglottides. Though the adult may attain an immense

length (as much as 20 feet) it is a much less dangerous parasite than the larva, and rarely produces worse symptoms than giddiness and a certain amount of abdominal pain. The adults are found chiefly in carnivorous animals, above all in the Dog, Wolf and allied species. Thus *Cysticercus pisiformis* becomes *Taenia serrata*; *Coenurus cerebralis* gives rise to *Taenia coenurus*, and *Echinococcus polymorphus* to *Taenia echinococcus*, all three infesting the alimentary canals of the dog and its allies. The common *Taenia solium* found in the human intestine is developed from a *Cysticercus* found in the muscles of the Pig.

Bothriocephalus latus, which may attain a length of 30 feet, is the largest Cestode found in Man. It belongs to a more primitive division of the class than *Taenia*, for it gives rise to a free-swimming ciliated larva, which is swallowed by the Pike or the Perch. In this it develops into a solid larva which gives rise to the adult when the fish is eaten by man.

It is obvious that an animal which like a Digenetic Trematode or a Cestode depends for its survival on such a combination of lucky chances as that of transference from one particular species of animal to another animal of a definite kind must develop large powers of reproduction. In the Trematode this is chiefly manifested in the power of the larva to reproduce itself asexually, but in the Cestoda the power is in most cases only developed when the animal is in the adult condition. Considerable discussion has taken place as to whether the process of strobilization is, or is not to be regarded as a production of new individuals. When we recollect that the separated proglottides often retain life for some time after being cast out of their host, it would seem that there was much to be said in favour of regarding them as sexual individuals and the head as an asexual one. The most probable view on the whole is that of Lang, who suggests that in the ancestor of modern Cestoda the hinder part of the body which contained the genital organs was separated at maturity, as occurs in the case of some Polychaeta. When the Cestode took to living in the alimentary canals of Vertebrata, the abundant food supply and favourable temperature stimulated the powers of regeneration so that the missing part was quickly reproduced, and by the hurrying on of this process of regeneration the process of strobilization was evolved, exactly as occurred in the Scyphistoma of *Aurelia*. It is interesting to notice that *Archigetes*, found mature in the coelom of the Oligochaet *Tubifex*, is the only Cestode which completes its development

elsewhere than in a Vertebrate, and in this case only one proglottis is produced, which never separates from the head. To the posterior end of this proglottis an appendage is attached representing the bladder of the *Cysticercus*, in which the six hooks of the onchosphere still remain embedded.

The Platyhelminthes are classified as follows:

Class I. **TURBELLARIA.**

Platyhelminthes with soft, usually leaf-like bodies and a ciliated ectoderm: rhabdites are often present: free-living.

Order I. **Rhabdocoelida.**

Turbellaria with a straight, rod-like alimentary canal and a protrusible pharynx.

Sub-order 1. **Acoela.**

The digestive system is represented by a mass of endoderm cells which contains no cavity: a short pharynx and single otocyst are present.

Sub-order 2. **Alloicoela.**

The digestive canal is lobed: the testes are scattered.

Sub-order 3. **Rhabdocoela.**

The digestive canal is rod-shaped, the pharynx protrusible.

Order II. **Dendrocoelida.**

Turbellaria with a branched alimentary canal.

Sub-order 1. **Triclada.**

The alimentary canal has three main branches, one running forward and two running back. Male and female openings united.

Sub-order 2. **Polyclada.**

The alimentary canal has many branches sometimes anastomosing. Male and female openings as a rule distinct. Marine.

Class II. TREMATODA.

Parasitic Platyhelminthes with usually leaf-like, rarely cylindrical bodies : no cilia on ectoderm : forked alimentary canal : ventral sucker or suckers and hooks often present : not segmented.

Order I. Monogenea.

Trematodes with a sucker or suckers at the posterior end and in some cases another anteriorly. Often external parasites or in the mouth, nose or branchial cavities. Development direct.

Order II. Digenea.

Trematodes with a sucker at the anterior end and another on the ventral surface or posteriorly. Internal parasites and their organs of adhesion more weakly developed than in the Monogenea. Development with an alternation of generation.

Class III. CESTODA.

Parasitic Platyhelminthes with elongated and usually segmented body : no mouth or alimentary canal : suckers and hooks present but on the head only : the segments break off when ripe.

CHAPTER XXI.

PHYLUM NEMERTINEA.

THE Nemertines belong to that category of animals which would by most people be styled "worms"; that is to say they are long, soft-bodied animals, without limbs or appendages of any kind, that progress by undulatory movements of the body. Most Nemertines are marine, living under stones and amongst the roots of seaweed; a few are fresh-water, and one or two species are terrestrial.

They swim in a graceful, undulating fashion, but they are much more sluggish in their movements than Annelida. It is a common and characteristic sight to see an isolated contraction passing slowly back along the body. Some species are minute, others, e.g. *Lineus marinus*, attain a length approaching 100 ft., and are perhaps the longest animals known.

The ectoderm consists of long, narrow, ciliated cells. In this they resemble the Turbellaria, but they differ from the latter animals profoundly in the structure of the alimentary canal. This organ is straight and unbranched; it begins in a mouth placed a short distance behind the anterior end of the body, and it ends in an anus placed at the extreme posterior end. For most of its course the alimentary canal is sacculated; that is, produced at the sides into a series of short broad pouches; otherwise it is not differentiated in any way.

The most characteristic organ of the Nemertine is the proboscis. This is a long tube lying above the alimentary canal, ending blindly behind, and opening to the exterior in front. The proboscis is a part of the outer skin invaginated, and when retracted it is surrounded by a closed space lined by a well-defined epithelium called the proboscis-sheath. This space contains a watery fluid, and its wall beneath the epithelium possesses powerful circular

muscles. When these contract the proboscis is partially forced out of the sheath by being turned inside out and consequently protruding from the front end of the body at the same time. It can never be completely turned inside out, for certain cords traversing the proboscis-sheath restrain it. At the point in its wall which is at the anterior end when the process of turning inside out has reached its utmost limits, there is in the higher Nemertines a short lateral pouch in which a horny spike, the stylet, is secreted. Round the base of this open poison-glands, so it can be seen that the proboscis is an offensive organ for seizing prey. So far as we know all Nemertines are carnivorous. Amongst the lower Nemertines the stylet is not developed, nevertheless the proboscis can be employed to catch prey; it is quickly thrust out and coiled spirally round the victim and then retracted so as to push the prey into the mouth. This retraction is brought about by a muscular band which attaches the end of the proboscis to the sheath. The land Nemertines (*Geonemertes*) are said to travel by thrusting out the proboscis, attaching to it foreign objects and drawing up the body after it.

Underneath the ciliated ectoderm of Nemertines there

is a series of powerful circular and longitudinal muscles: these layers are of course continued, but in the reverse order, on to the walls of the proboscis, since this is only invaginated skin. Under extreme irritation the extended proboscis is sometimes torn from the body—by the heightened pressure of the fluid in the sheath—




FIG. 341. *Linceus geniculatus* $\times \frac{3}{4}$.

1. Lateral slits on head. 2. Anus.

and in one instance such a disjoined proboscis was mistaken on account of its active contractions for a new species of Nemertine.

There is a well-defined central nervous system amongst Nemertines, consisting of a pair of ganglia lying at the front of and above the mouth—less frequently at the sides of it—and connected by a commissure which passes above the proboscis-sheath. The hinder parts of the ganglia are more or less distinctly separated as posterior lobes, and come into close relation with curious pouches of invaginated ectoderm, termed cephalic pits (Fig. 341), which seem in some cases at any rate to subserve the respiration of the nervous tissue, for the latter in some species contains haemoglobin. The ganglia are continued backwards into two powerful nerve-cords lying at the sides of the body. In the lower species these cords can be seen to lie just beneath the ectoderm and to be but thicker portions of a sheath of nerve-fibrils extending all round the body, and derived from the bases of the ectoderm cells. In the higher species the nerve-cords lie well within the muscles, and this sheath is not so evident.

Sense-organs in the form of *eyes* of simple structure often occur immediately over the region of the ganglia.

The interstices between the various organs inside the muscles are filled up with connective tissue, but there exist three longitudinal tubes with well-defined walls which are regarded as blood-vessels. Two of these tubes lie at the sides of the alimentary canal, and one is situated above it and below the proboscis-sheath. These vessels are connected anteriorly by arches and they unite with one another in both the head and tail.

The excretory organs have the form of a pair of branched tubes opening at the sides of the body not far behind the cephalic pits. Their branches end blindly and the terminations of these are closely applied to and even indent the wall of the lateral blood-vessel, and in each termination there is a tuft of cilia.

The Nemertinea are dioecious. The generative organs are exceedingly simple, consisting in both sexes of packets of cells situated along the sides of the body alternating with the pouches of the alimentary canal. No permanent genital ducts exist, but when the ova and spermatozoa are ripe they appear to make temporary ducts for themselves. The egg develops in many casts into a remarkable larva called a *Pilidium*. This is shaped something like a policeman's helmet with ear lappets. The edge of the helmet, including the lappets, is fringed with powerful cilia, and

there is besides a tuft of long cilia at the apex. Underneath the helmet is the opening of the mouth, which leads into a sac-like gut devoid of an anus.

The adult is developed from the Pilidium in an extraordinary way. Four invaginations of ectoderm appear on the under side of the larva, at the sides of the alimentary canal. These grow both upwards and inwards until they completely surround the canal. The inner walls of the pockets form the ectoderm of the adult. When the process is complete the alimentary canal surrounded by the new ectoderm drops out of the Pilidium and forms the Nemertine.

Many species of Nemertine are found on the British coast. As examples we may mention *Lineus* (Fig. 341), a long thin form without stylets in the proboscis, and *Tetrahelminth*, a short broad form with four eyes and stylets in the proboscis.

The Nemertines, so far as our present knowledge extends, form a completely isolated group in the animal kingdom.

From the circumstances that some Rhabdocoel Turbellarians have a protrusible organ in the anterior part of the body, and that the excretory organs of Nemertines bear a certain resemblance to those of Platyhelminthes, it was supposed that Nemertines and Platyhelminthes were allied. The totally different character of the generative




FIG. 342. *Cerebratulus fuscus*. Young transparent form $\times 7$. After Bürger.

1. Cephalic slits. 2. Opening leading into the retracted proboscis. 3. Dorsal commissure of nervous system. 4. Ventral commissure. 5. Brain. 6. Posterior lobe of brain which comes into connection with the cephalic slit. 7. Mouth. 8. Proboscis sheath. 9. Lateral vessel. 10. Proboscis. 11. Pouches of alimentary canal. 12. Stomach.

organs in the two groups and the presence of an anus in Nemertines tells strongly against this view, and the resemblances indeed will not stand minute investigation.

Of all the groups, however, about the nature of whose so-called "mesoderm" we are in doubt, the Nemertines have perhaps the greatest probability of turning out to be true Coelomata. The cavity of the proboscis-sheath, termed *Rhynchocoelom* by German authors, may very possibly be part of a true coelom; but we are not justified in assuming this until more exact observations have been made on its development.

The Nemertinea are divided into classes in accordance with the condition of the nervous system and the arrangement of the layers of muscles in the skin. These classes are as follow :

Class I. PROTONEMERTINI.

A nervous sheath underlies the entire ectoderm; the lateral nerve-cords, mere thickenings of this sheath, are situated outside the layers of muscles: no stylets in the proboscis.

Ex. *Carinella*.

Class II. MESONEMERTINI.

A nervous sheath underlies the entire ectoderm; the lateral nerve-cords are more deeply situated, lying between the outer circular and the inner longitudinal muscles: no stylets in the proboscis.

Ex. *Cephalothrix*.

Class III. HETERONEMERTINI.

A nervous sheath surrounds the body. Both it and the nerve-cords lie inside a special layer of longitudinal muscles, which are derivatives of the ectoderm cells, but inside all the other muscles: no stylets on the proboscis.

Ex. *Lineus*, *Cerebratulus*.

Class IV. METANEMERTINI.

No nervous sheath but definite peripheral nerves: the lateral nerve-cords lie within all the muscle layers: the proboscis is armed with stylets.

Ex. *Tetrastemma*, *Geonemertes*, *Malacobdella*.

Classes I—III are often united as the Class *ANOPLA*, characterised by the absence of stylets in the proboscis. Class IV is sometimes termed *ENOPLA* (i.e. armed) to contrast it with the remaining Nemertines or Anopla.

CHAPTER XXII.

PHYLUM ROTIFERA.

THE Rotifera are minute animals mostly confined to fresh water, a few only being found in the sea. Many of them swim about by means of a loop of cilia which encircles the front end of the body, but some are sessile. The motion of these cilia induced the early observers to think that the animal had wheels in front, whence the name (Lat. *rota*, a wheel; *fero*, to carry). There is a complete transparent alimentary tube, ending in an anus situated on the dorsal side in front of the hind end of the body, the latter forming a ventral projection called the foot. The first part of the tube is a stomodaeum, and lined like the rest of the skin with cuticle. This cuticle is thickened to form teeth which work on one another, the whole organ being called a mastax. The activity of the mastax enables one at once to distinguish a Rotifer from other minute animals.

Floscularia cornuta, often termed *F. appendiculata*, is a widely distributed species. It lives in ponds, ditches and pools, usually attached by its posterior end to some water-weed or other body and surrounded by a gelatinous tube into which the animal can retire. The length of the animal when extended is 0·2 to 0·3 mm. The body is covered by a thin cuticle, and may be divided into three regions, the head, the trunk, and the foot. When the animal is extended the last-named is stretched out and smooth, but it is wrinkled when the animal withdraws into its tube. It terminates in a disk, on which opens the duct of two large glands which secrete an adhesive substance, by means of which the foot is anchored.

The anterior end of a Rotifer, on which the mouth opens, is called the disk. In *Floscularia* this is produced into five long tentacle-like processes fringed with stiff bristles which serve as a net to entangle small animals and plants. The cilia which produce

the current by means of which the prey is captured, are situated inside the ring of tentacles. They take the form of a horseshoe-shaped band open dorsally, the mouth being situated in the centre




FIG. 343.

- A. *Floscularia cornuta*. Female magnified. From Hudson. 1. Head.
 2. Trunk. 3. Foot. 4. Gelatinous tube in which the animal lives.
 B. *F. campanulata*. Male magnified. 1. Vesicula seminalis. 2. Penis.

of the horseshoe. This band of cilia is termed the velum: in other Rotifera it is doubled back on itself in such a way that a loop is produced which lies dorsal to the mouth. This loop is called the

trochus; it usually consists of more powerful cilia than the rest of the velum, which is termed the cingulum. The groove between the two bands in which the mouth lies is covered with fine cilia. In the genus *Rotifer* the trochus is composed of two almost circular lobes, which were described as wheels by the first naturalist who observed them, and this circumstance suggested the name given to the genus and afterwards bestowed on the whole phylum.

Within the cuticle which covers the body is the ectoderm. This takes the form of a protoplasmic layer with scattered nuclei, showing no cell-outlines. It surrounds a spacious body-cavity, probably a haemocoel, which contains a fluid with no amoebocytes; in this float the various organs of the body connected more or less closely together by connective tissue-cells. The muscles do not form a continuous layer underneath the ectoderm as is the case with the Platyhelminthes and the Nemertinea but consist of isolated bands, chiefly longitudinal, which retract the disk and the foot and bend the body in various ways, the recovery of its original shape being largely due to the elasticity of the cuticle.

The food, which consists of Protozoa and other small organisms, is swept into the mouth by the action of the surrounding cilia. The mouth leads through a wide vestibule into an oesophagus, which is ciliated and projects down into the so-called gizzard or mastax which, next




FIG. 344. Diagram of *Floscu-*

1. Circle of tentacles bearing bristles.
2. Velum. 3. Mouth leading to vestibule. 4. Brain. 5. Oesophagus hanging like a funnel into the crop.
6. Mastax with trophi. 7. Stomach.
8. Rectum. 9. Opening of cloaca.
10. Strands of muscles. 11. Yolk-gland part of ovary. 12. Ovarian part of ovary. 13. Oviduct. 14. Excretory duct opening into 15, urinary bladder. 16. A tag with a tuft of cilia. 17. Longitudinal and circular muscles in foot.

to the ciliary rings on the head, is the most characteristic organ of a Rotifer. The vestibule, oesophagus and mastax are all part of the stomodaeum. The cuticle lining the mastax is thickened so as to produce the trophi, which are hard, chitinous, chewing organs; of these there are typically three, two mallei and an incus on which they strike. The incus, a Y-shaped piece, consists of two rami and a central piece or fulcrum. Each malleus is composed of a manubrium and an uncus or head, which may be toothed. The shape and arrangement of these hard parts is of great value in classification. In some species the mallei are absent altogether, and the two rami of the incus then work against one another like two lateral teeth. In the NOTOMMATIDAE the mallei can be protruded through the mouth, and are used to cut into the cells of Algae on which the animals browse. In *Floscularia* and its allies there is a dilatation of the stomodaeum, called the crop, interposed between the mastax and the "oesophagus," and the latter hangs down into the crop just as a funnel might hang into a tumbler; the crop can be everted through the mouth.

After passing between the jaws the food enters the stomach, which is lined with cilia; here the food loses its original colour and becomes tinged with the brown secretion of the walls of the stomach. In most forms two salivary glands open into the gizzard, and two gastric glands into the stomach, but these have not been clearly made out in *Floscularia*. The stomach is separated by a constriction from the ciliated rectum, and this ends in a non-ciliated proctodaeum into which the genital and excretory organs open. The alimentary canal of Rotifera, like that of the lower Vertebrata, thus terminates in a cloaca.

The excretory system consists of two longitudinal ducts consisting of columns of perforated cells, which bear a number of small tags hanging freely into the body-cavity (Fig. 345). Each tag consists of a cavity in which are several flagella, which show during life the peculiar flickering motion which is usually associated with the excretory system of Platyhelminths. In *Floscularia* four or five pairs of tags have been seen. The longitudinal ducts are usually connected by a transverse duct just under the disk, and they open as a rule into a capacious bladder which contracts at intervals and expels its contents into the cloaca, and thus out of the body. It has been calculated that in some species this bladder expels a bulk of fluid equal to that of the animal about every ten minutes, and this fluid must be replaced by water which diffuses through the body-wall. This water doubtless

brings with it oxygen and carries off carbonic acid which it has taken up from the tissues.

The principal part of the nervous system is a bilobed ganglion called the brain. This lies just under the disk on the dorsal side of the mastax; it bears two red eyes in *Floscularia*. In *Notomata* the brain is large, and on it more than one pair of eyes are situated. In the Bdelloida there is also a ganglion on the ventral side of the mastax, and a pair of circumoesophageal cords unite this with the brain. In *Floscularia*, as in Rotifera generally, there are three well-marked sense organs called antennae, consisting of prominences bearing stiff sense-hairs; one is situated in the mid-dorsal line, two are latero-ventral; these latter are in some genera fused with one another.

As in the Platyhelminthes, so in Rotifers, the ovary, which occupies a good deal of space in the body-cavity, usually consists of a vitellarium or yolk-gland and a germarium or true ovary. The latter lies between the former and the stomach; it is inconspicuous and is more or less hidden by the large cells of the vitellarium. Both glands may be paired. They are enclosed in a membrane continuous with the oviduct which opens into the cloaca behind the excretory duct.

The above description relates chiefly to the female *Floscularia*, and in fact until 1874 the male was unknown. It is much smaller than the female (B, Fig. 343). As a rule the male Rotifer has a single circlet of cilia, a brain, eyes, excretory system, and muscles all more or less reduced, but




FIG. 345. Diagram of a Rotifer.

1. Anus. 2. Brain. 3. Trochus.
4. Cingulum. 5. Gland in foot.
6. Cloaca. 7. Cuticle. 8. Ectoderm.
9. Dorsal antenna. 10. Eye.
11. A ciliated "tag" of the excretory system. 12. Intestine.
13. Muscles. 14. Mouth. 15. Nephridial tube.
16. Ovum. 17. Oviduct. 18. Ovary.
19. Mastax. 20. Stomach. 21. Bladder.
22. Vitellarium.

there is no mouth or alimentary canal. The testis is large and the penis is introduced into the cloaca of the female, or in some cases is thrust through the wall of the body, and then the eggs are probably fertilized in the ovary.

Floscularia lays two kinds of eggs during the summer, both of which are thought to develop parthenogenetically. Both kinds accumulate between the foot and the tube in which the mother lives. The larger eggs, which average five to eight in number, produce females, the smaller eggs, whose origin seems to be determined by the temperature, may amount to eighteen or twenty. These produce the males. Towards the autumn the males fertilize the females, and the resulting eggs termed "winter-eggs" are clothed with a thick shell capable of withstanding cold and drought. These live through the winter and give rise to females in the spring. A similar alternation of summer and winter eggs is met with in certain Crustacea (Phyllopoda and Ostracoda).

Rotifera are cosmopolitan, but as a rule they inhabit fresh water; about 700 species are known, of which only one-tenth live in the sea or in brackish water. One species, *Syncyba baltica*, is pelagic and phosphorescent. A few are parasitic.

Hydatina senta is one of the commonest Rotifers, and is usually to




FIG. 346. *Hydatina senta*, ventral view.
After Plate. Magnified.

1. Lateral antenna. 2. Bladder.
3. Cingulum. 4. Eggs. 5. Vitellarium or yolk-gland. 6. Foot-gland.
7. Gizzard. 8. Gastric gland. 9. Germarium or ovary.
10. Lobes of "groove" bearing stiff setae. 11. Intestine. 12. Excretory tube. 13. Mouth. 14. Ciliated tag of the excretory system. 15. Oesophagus.
16. Renal commissure, transverse tube uniting kidneys above mouth. 17. Stomach overlaid by reproductive organs. 18. Trochus. 19. Uterus.

be met with swimming about amongst the algae of green ponds. It possesses a shortly elongated, cylindrical body (Fig. 346). The disk bears a circular cingulum separated by a groove from the trochus; in this groove are five prominences bearing stiff setae. The posterior end of the body tapers and ends in a bifurcated foot on which a pair of glands open.

A great many of the Bdelloida live amongst the roots and leaves of mosses, etc., and these can survive being dried up for a long time, the body shrinking and sealing itself up in the cuticle. Apart from the species which possess this power Rotifera as a class are short-lived, and this is especially true of the males.

In certain respects, such as the nature of their excretory organs and of their ovaries, the Rotifers show some resemblance to the Platyhelminthes; but they differ from them profoundly in the alimentary canal. The velum, in its typical form consisting of trochus and cingulum, has been compared to the ciliated band which encircles the Trochophore larva. This band like the velum is seen on close inspection to consist of a prae-oral and a post-oral loop. The Trochophore larva is found in the life-history of the Polychaeta and some of the more primitive Mollusca, and it is believed by many to represent a common ancestral form. Should the comparison of the Rotifera with this larva be a just one we must regard the Rotifera as having been derived from the common stock of Annelida and Mollusca, and to be therefore a very ancient group. There are however difficulties which arise when the comparison is carried into details, and for the present it is better to regard the Rotifera as a completely isolated phylum.

Leaving out of sight a few parasitic and aberrant forms the bulk of the Rotifera are classified as follows:

Class I. RHIZOTA.

Rotifera in which the foot is not retractile but forms a permanent organ of attachment. The animal lives in a tube.

Ex. *Floscularia*.

Class II. BDELLOIDA.

Rotifera which creep like a leech, using the foot as a sucker. They are provided with a protrusible adhesive proboscis on the

dorsal surface, by which the anterior end of the animal may be made to adhere.

Ex. *Rotifer*.

Class III. PLOIMA.

Rotifera which swim freely, only occasionally attaching themselves by the forks of the bifurcated foot.

Ex. *Hydatura*, *Synchaeta*, *Notommata*.

Class IV. SCIRTOPODA.

Rotifera provided with hollow moveable outgrowths from the body by means of which they leap.

Ex. *Pedalion*.

CHAPTER XXIII.

PHYLUM NEMATODA.

THE Nematoda include a very great number of species commonly termed Thread-Worms, or from the shape of their cross section Round-Worms. Certain species attain a great length, as long as a man, but more commonly they are small and insignificant and often microscopic. The general shape of the body is cylindrical, usually pointed slightly at each end, the surface is smooth with at most a few bristles, so that they easily insinuate themselves into the cracks in the damp earth, or between the tissues of the animals and plants in which for the most part they live.

As a rule, like most animals which pass their time in the dark, Nematodes are white or whitish-yellow in colour. The body is glistening and smooth, but not slimy. It is ensheathed in a thick cuticle, which is in some cases ringed. No locomotor organs exist, and the animals progress by wriggling, bending first to one side and then to the other. The cuticle, which is moulted about four times during the life of the animal, is secreted by an underlying layer called the ectoderm, in which no trace of cell limits can be detected, but nuclei are scattered in it. Along the middle dorsal and middle ventral line, and along each side, this layer is thickened and projects inward. The median ridges support two nerves, the lateral ridges two canals, which are believed to be excretory.

By these ectodermal thickenings the body-wall is divided into quadrants. In each quadrant there is a layer of longitudinal muscle-fibres of very peculiar appearance. In all muscle-fibres, as we have seen (p. 95), there is a patch of unmodified protoplasm surrounding the nucleus, the rest being modified into those fibrils which are the visible sign of a heightened contractile power. In the Nematoda, in which all metabolism is at a low ebb, only the outer-




FIG. 347. Female *Ascaris lumbricoides*, cut open along the median dorsal line to show the internal organs $\times 1$.

1. The muscular oesophagus. 2. The intestine. 3. The ovary. 4. The uterus. 5. The vagina. 6. Its external opening. 7. The excretory canals. 8. Their opening.

most layer of the muscle-cell is converted into fibrils, the great bulk consisting of unmodified protoplasm, which is often drawn out into an internal process running towards the dorsal or ventral ectodermal ridge. Muscle-cells of such a character are only known in Nematoda.

The body-wall, which has just been described, encloses a space which is traversed from end to end by the alimentary canal. This space is full of a fluid in which amoebocytes float, and it further lodges the reproductive system. It has no epithelial lining and appears to be a haemacoele. Besides this there is no circulatory system or heart.

The mouth is terminal, and is usually surrounded by certain papillae or lobes, often three or six in number. It leads into an oesophagus, usually with a triangular cavity and thick muscular walls (Fig. 347). The oesophagus may be immediately followed by a second muscular bulb, called the pharynx, which sometimes has an armature of some bristles or spines. Both oesophagus and pharynx are parts of the stomodaeum. Then follows the intestine, which is by far the largest part of the alimentary canal. The muscular oesophagus no doubt acts as a sucking organ, but there are no muscles and no cilia in the intestine. It is a simple tube formed of a single layer of cells, which both inside and out secrete a thin cuticle. Posteriorly it passes into a proctodaeum with muscular walls, and

this terminates in the anus situated a little in front of the end of the tail.

The nervous system consists of a ring round the oesophagus, which sends off in front six nerves to the mouth and its papillae, and behind it also gives off six nerves, the two more important of which run down the body in the above-mentioned median dorsal and ventral ectodermic ridges. Transverse commissures unite these main nerve-trunks at irregular intervals. With the exception of certain hairs and papillae to which a tactile sense has been ascribed, and in the free-living species certain eye-spots, no organs of sense are known in the Nematoda.

The excretory function is usually assigned to two long tubes which run along the lateral thickenings of the ectoderm. These tubes end blindly behind, but anteriorly the tubes approach one another ventrally and open by a common pore in the middle ventral line some little distance behind the mouth (Fig. 347). Each of these tubes is stated to consist of one immensely elongated hollow cell.

Nematoda are with few exceptions bisexual. The male is often smaller than the female and frequently has a curved tail. In both sexes the reproductive organs are tubular. In the male the organ consists of a long tapering tube much folded on itself opening into the proctodaeum close to the anus. In the uppermost and narrowest part of the tube there is a mass of protoplasm with nuclei; lower down the mother-cells of the spermatozoa become separated, and the lowest part contains ripe spermatozoa. The names testis and vas deferens are given to the upper part and lower part respectively of this organ, but the whole is one continuous structure developed from a single cell in the embryo. In the female there are two similar tubes which unite to open in the mid-ventral line by an exceedingly short median piece termed the vagina. The vagina is situated about one-third the body-length from the head. In each tube it is usual to distinguish an upper ovary consisting of a mass of nucleated protoplasm, a middle oviduct where the bodies of the egg-cells have become separated from one another, and lastly a uterus where the eggs having been already fertilized are each provided with a shell. Each tube however, like the testis of the male, is developed in the embryo from a single cell.

In order to introduce the spermatozoa the male distends the vagina of the female by inserting two cuticular hairs, developed from the lining of the proctodaeum, called copulatory spicules.

It is a most peculiar characteristic of the Nematoda, which they

share with the great group Arthropoda, that no cilia are found in any organ of their body. Even the spermatozoa have no flagella but move in an amoeboid manner. This absence of cilia, which are found in every other group of the animal kingdom and in many plants, has received hitherto no explanation. It is possibly correlated with the strong tendency of the protoplasm in both phyla to produce chitin. The eggs of Nematoda have a structure well adapted for histological investigation, and have been much utilized in researches on the behaviour of the nucleus before and during fertilization. As a rule the eggs are laid, but there are many species which produce their young fully formed.

Comparatively few species are free-living throughout their whole career, but these few are interesting. They are of small size and inhabit damp earth or mud, one family being marine. The mouth is often provided with moveable spines and there are frequently eyes. These features suggest a relationship with the Chaetognatha, which like the Nematoda have a thick cuticle and only longitudinal muscles; and this idea receives support from the existence of a group of small marine "worms" called the CHAETOSOMATIDAE, which are probably also to be regarded as free-living Nematodes. These animals have two semicircles of moveable bristles, situated one at each side of the mouth, and in addition a double ventral row of similar spines by means of which they creep about. Should this conjecture turn out to be well founded the Nematoda must be regarded as Coelomata, and it is interesting to speculate what has become of their coelomic sacs. Possibly, as in the Arthropoda, these have been reduced in size by the development of a




FIG. 348. *Ascaris lumbricoides*, cut open along the dorsal middle line $\times 1$.

1. Oesophagus. 2. Intestine. 3. Testis.
4. Vas deferens. 5. Lateral excretory canals.

haemocoel and are now represented only by the excretory and genital tubes; but until the details of the development both of Nematoda and Chaetognatha are known it would be unsafe to pursue these speculations further.

Taking the free-living forms as starting-point we can arrange the other families of Nematoda in an ascending scale of increasing parasitism, culminating in a form like *Trichina spiralis*, which is a perpetual parasite. This Nematode inhabits the intestine of its host (Pig, Man, &c.) where it lays its eggs. From these eggs larvae hatch out which bore through the walls of the intestine and get into the circulation, by which they are carried all over the body. They encyst themselves in the muscles (Fig. 349) and do not develop further unless the flesh of their host is eaten by another animal, in whose intestine they become mature and the cycle of development recommences. Their natural home is the body of the Pig; this animal




FIG. 349. *Trichina spiralis*, encysted amongst muscular fibres. Highly magnified. After Leuckart.

being a gross feeder no doubt often devours the remains of its own species, and thus the parasite is propagated. *Trichina* can however live perfectly well in Man, as the prevalence of the disease Trichinosis testifies. This disease is contracted by eating insufficiently cooked pork infested by the encysted larvae of the *Trichina*. These become mature in the human intestine, and give rise to a second generation which cause severe and occasionally fatal symptoms by boring through the intestinal wall.

Most Nematodes pass the earlier part of their existence in damp earth, during which they are known as Rhabditis larvae, and bear a strong resemblance to some of the free-living forms. *Tylenchus tritici* forms the so-called Ear-cockles in wheat; these are brown galls replacing the wheat-grains, and filled with encysted Nematodes. If the grains are beaten to the earth by rain the worms escape from the cysts and climb up the wheat stalks, where after a generation, which lives in the flower, they again enter the grains. In *Sphaerularia bombi* the males and females live together in damp earth, but the fertilized female enters the body of a bee and here develops into a great sac filled with eggs. In *Syngamus trachealis* the eggs are laid in damp earth, and here develop into larvae, which are swallowed by poultry and develop in their wind-pipes into the sexual form, causing the disease called Gapes, which is often fatal. *Filaria sanguinis-hominis* lives in the human lymphatic glands; the embryos escape into the blood, whence they are

taken up by the mosquito in whose body they develop. When the mosquito bites they make their way again into the blood of man. They are believed to be the cause of the strange tropical disease called "sleeping-sickness." But it would lead us too far to enumerate all the modifications of the life-history produced by parasitism. Suffice it to say that the Nematoda are perhaps the most successful of all parasites; there is scarcely a phylum in the animal kingdom which they do not attack. A smooth slippery body which as a general rule causes little inconvenience to the host, and a low grade of metabolism requiring small supplies of oxygen, seem to have been the leading features in their success.

INDEX.

Names of genera are printed in italics. The figures in thick type refer to an illustration. In all cases the references are to the page.

- Aard-vark, 526
 Abdomen, 114, 134, 143, 159, 183
 Abdominal pores, 348
 Abdominal ribs, 456, **471**
 Aboral, 50, 66
 Acalephae, 62, 68
Acanthia, 180
Acanthias, 395
Acanthobdella, 105
 Acanthopteri, 392, 393, 398
 Acarids, 190
 Acarina, 190
 Aciculum, 101
Acineta, 39
Acipenser, 379, **380**, 396
 Acoela, 583, 596
 Acopa, 315
Acridium, 178
Acris, 436
Actinometra, 270
Actinophrys, **26**, 39
 Actinopterygii, 376, 378, 396
Actinosphaerium, 26, **27**, 39, 43
 Actinozoa, 56, 68
 Adrenal body, 434
 Aegithognathous, 496
Aeschna, **112**, 178
 Aglossa, 435, 438
 Alary muscles, 167
 Albumen gland, 208
Alces, 552, 574
 Alecyonaria, 68
Alecyonium, **56**, **57**
 Alimentary canal, 79
 Allantois, 440, 521
Alligator, **442**, **469**, **472**, 473, 474
 Alligator turtle, 468
 Alloicoela, 583, 596
Allolobophora, 100, 108
 Alpaca, 550
 "Alternation of generations" in Coelenterata, 55; in Tunicata, 317
Alytes, 433
Amblystoma, 421, 437
 Amblystomatidae, 422, 437
Amia, 379, 397
Amiurus, **390**, 397
 Amnion, 440
 Amniota, 440
Amoeba, 13, **14**, 38
 Amoebocytes, 85, 90, 122, 238
 Amoebula, 25
 Amphibia, 350, 400
 Amphicoelous, 377, 456
Amphioxus, 295, **296**, **297**, **298**, **299**, **300**, **301**, **302**, **303**, **304**, **305**, **306**, **307**; origin of mesoderm in, 77
 Amphipoda, 150
 Amphisbaenidae, 446
 Amphistylic, 357
Amphitoma, 421, 437
 Amylopsin, 333
 Anabolism, 5
 Anacanthini, 392, 398
 Anal cerci, 160
 Anal styles, 164
Anas, **481**, **482**
 Anchovy, 391
 Anguidae, 459
Anguilla, 391, 397
 Anguillidae, 390, 391, 397
Anguis, **458**, 459, 474
 Animal, 1
 Anisopleura, 233
 Ankle, 450
 Annelida, 82, 108
 Annuli, 104
Anodonta, 209, **211**, **213**, **214**, **216**, **218**, 235
Anomalurus, 555

- Anopla, 602
 Ant, 180
 Ant-eater, American, 523; banded, 519;
 Cape, 523; scaly, 525; Tamandua,
 523
 Ante-brachium, 401
Antedon, 269, 270
 Antelope, 549, 551
 Antenna, 111, 122, 160, 170
 Antennary gland, 131
 Antennata, 111, 151
 Anterior, 80
 Anthropeoidea, 561, 563, 575
Anthropopithecus, 565, 576
Antilocapra, 549, 551, 574
 Antilocapridae, 549, 574
 Ant-lion, 178
 Anura, 405, 423, 438, 453
 Anus, 79
 Aphis, 180
 Aphis-lion, 178
Aphrophora, 180
Apis, 179, 180
Aplysia, 206, 234
 Aptera, 172, 176, 177
 Apteris, 476
Apteryx, 496, 497
Apus, 134, 135, 137
 Aqueous humour, 328
 Arachnida, 111, 116, 182
 Araneida, 183
Arcella, 17, 19, 28, 38
Archigetes, 595
 Archinephric duct, 341
 Arcifera, 429, 435, 438
Arctomys, 554
Argiope, 279, 281
Argyroneta, 129
 Aristotle's lantern, 257, 259
 Armadillo, 524, 525
Artemia, 134, 137
 Arthrobranchs, 128
 Arthropoda, 110; appendages of, 116;
 definition of, 133
 Arthrostraca, 146, 149
 Artiodactyla, 542, 545, 573
Arvicola, 555, 575
Ascaris, 612, 614
Ascidia, 309
 Ascidiaceae, 315
Asellus, 120, 151
 Aspidobranchiata, 233
 Aspidochirotae, 269
 Ass, 545
 Assimilation, 5
Astacus, 119, 124, 132, 148
Asterias, 236, 239, 246, 274
 Asteroidea, 236, 248, 274
 Asymmetry, 209
Ateles, 563, 576
Athene, 557
 Atlas, 443
 Atrial cavity, 297
 Atrial pore, 297
Auchenia, 550, 574
 Auditory ossicles, 505
Aurelia, 62, 63, 64
 Automatism, 6
 Autostylic, 369, 410
 Aves, 351, 475
 Avicularium, 285
 Axis, 443
 Axis-cylinder, 322
Babirusa, 546, 573
 Bacteria, 17
 Badger, 536
Balaena, 529, 570
Balaenoptera, 529, 570
 Balanoglossus, 292, 297
Balanus, 141
 Banded Ant-eater, 519
 Bandicoots, 520
 Bank-vole, 555
 Barbastelle, 559
 Bass, 393
 Bastard wing, 481
 Bat, 557, 558
 Batoidei, 368, 395
 Batrachia, 423
 Bdelloidea, 609
Bdellostoma, 350
 Bear, 536
 Beaver, 553, 554, 556
 Bee, 173, 179, 180
 Beetle, 173, 179, 180
Bettongia, 518, 521, 569
 Bill-fish, 380
 Biogens, 4, 5
 Biology, definition of, 1
 Bionomics, 9
Bipalium, 579
 Birds, 447, 450, 475
 Birth, 522
 Bisexual, 7
 Bison, 552
 Bivalves, 202, 207, 209
 Black bear, 536
 Bladder, 405
Blarina, 570
 Blind-worm, 458, 459
 Blood, 120
 Blood-sucking Bat, 559
 Blue-bottle, 181
Bombinator, 433
Bombus, 180
Bombyx, 176, 177, 182
 Bone, 318
Bos, 552, 574
 Bot-fly, 181
Bothriocephalus, 595
Botryllus, 315, 316

- Bougainvillia, 51, 55
 Bovidae, 549, 551, 574
 Box-turtles, 468
 Brachiopoda, 276
 Brachium, 401
 Brachyura, 146
 Bradypodidae, 523, 569
Bradypus, 569
 Brain, 319
Branchellion, 103, 106
 Branchia of *Nereis*, 102
 Branchial hearts, 228
 Brachiopoda, 137
 Branchiostegite, 128, 144
Branchipus, 134, 135, 137
 Breathing, 4
 Brill, 393
 Brittle-stars, 236, 248
Bubalus, 548
 Buccal-mass, 204
Buccinum, 202, 234
 Buffalo, Cape, 548, 551, 552
Bufo, 423, 427, 435, 438
 Bufonidae, 423, 435, 438
 Bugs, 172, 180
Bugula, 285
 Bunodont, 545
 Bunodontia, 545, 573
 Butterfly, 174, 181
 Byssus, 220

 Caddis fly, 176, 178
 Caecum, 105
Caiman, 469, 472
 Ca'ing whale, 527, 528
 Cake-urchins, 264
Calamoichthys, 376
 Calcareo, 75
 Calciferous glands, 86
Callorhynchus, 370
 Calyptoblastea, 68
Cambarus, 148
 Camel, 549
 Camelidae, 549, 574
Camelus, 549, 574
 Canidae, 571
Canis, 501, 502, 504, 508, 534, 535, 571
 Capillary, 91, 337
 Capillitium, 25
 Capitulum, 408
Capreolus, 574
 Carapace, 134, 144, 182
 Carbon dioxide, 4
Carcharodon, 367, 395
Carcinus, 147
 Cardinal tooth, 213
Cardium, 220
Cariacus, 552, 574
 Caribou, 552
 Carina, 141
 Carinatae, 496

Carinella, 602
Carmarina, 53
 Carnassial teeth, 534
 Carnivora, 533, 570
 Carp, 392
 Carpalia, 402
 Carpus, 401
 Cartilage, 318
Caryophyllia, 61
 Cassowary, 496
Castor, 554, 556, 575
Casuarinus, 496, 497
 Cat, 535
 Catarrhini, 563, 576
 Caterpillar, 175, 182
 Cat-fish, 390
Cavia, 554, 575
 Cavicornia, 549
 Cebidae, 563, 576
Cebus, 563, 576
Cecidomyia, 181
 Cell, 27, 43
 Cellulose, 25
 Centipedes, 111, 114
 Centrarchidae, 393, 399
 Cephalochordata, 291, 295
 Cephalopoda, 209, 221, 235
 Cephalothorax, 115, 128, 182
Cephalothrix, 602
Ceratodus, 371, 372, 373, 374, 395
 Cercaria, 590
 Cerci anales, 164
 Cercopithecidae, 563, 576
 Cerebellum, 321
Cerebratulus, 601, 602
 Cerebrum, 321
 Cervidae, 549, 551, 574
Cerrus, 552, 574
 Cestoda, 578, 590, 597
Cestracion, 357
 Cetacea, 526, 527, 570
 Chaeta, 83, 84, 108
 Chaetognatha, 287
 Chaetopoda, 101, 108
Chaetosoma, 290
 Cheese-mite, 190
 Cheilostomata, 285, 286
 Cheiroptera, 557, 575
 Cheiropterygium, 353, 401
 Cheliceræ, 182, 183
Chelone, 465, 474
 Chelonia, 442, 463
 Chelonidae, 468
Chelydra, 468
 Chelydridae, 468
 Chevron bones, 443
 Chevrotain, 549, 550
 Chilopoda, 154, 159
Chimaera, 324, 369, 370, 395
 Chipmunk, 554
 Chitin, 18, 111, 125, 131, 160

- Chiton*, 233
Chlamydozoores, 37
Chlamydothorax, 293
Choana, 407
Choanocytes, 70
Chondrin, 195
Chondriodermis, 24, 39
Chondrostei, 379, 396
Chordata, 291
Chorophilus, 436
Chrysomys, 468
Chylific ventricle, 165
Cicada, 180
Ciliata, 27, 32, 39
Cilium, 28
Cingulum, 605
Cinosternidae, 468
Ciona, 312, 313
Cirripedia, 141
Cirrus, 101
Cistudo, 468
Cladocera, 137
Clam, 211, 220
Class, 9
Classification, 9, 11
Clava, 64
Clepsidrina, 37, 38, 39
Clepsine, 104, 107, 109
Clitellum, of *Lumbricus*, 84, 100: of *Hirudo*, 104
Cloaca, 404, 457
Clupea, 391, 398
Clupeidae, 390, 391, 398
Clypeasteridae, 264, 275
Clypeastra, 275
Cnidoblast, 45, 46, 52
Cnidocil, 45, 46
Coccidia, 38
Coccinella, 179
Cochlea, 325
Cockchafer, 115, 121, 122, 123
Cockle, 211, 220
Cockroach, ecdysis of, 114
Cocoon, of *Hirudo*, 104; of *Lumbricus*, 98, 99; of *Periplaneta*, 170; of silk-worm, 176, 182
Cod, 382, 392
Cocilia, 437, 439
Coelenterata, 40; classification of, 67
Coelenteron, 41
Coelom, 76, 577; of *Arthropods*, 117, 168; of *Brachiopods*, 277, 280; of *Cephalochordata*, 297; of *Chaetognatha*, 287; of *Echinoderms*, 238; of *Hemichordata*, 293; of *Molluscs*, 200; of *Vertebrates*, 338
Coelomata, 76, 81
Coelomic cavity, in *Lumbricus*, 76, 84; in *Leeches*, 105
Coelomic fluid, 90
Coenolestes, 520, 563
Coenurus, 595
Coleoptera, 172, 176, 178
Colleterial glands, 165
Colon, 165
Colubridae, 462
Columba, 486, 490, 494, 497
Condylura, 533, 570
Coney, 539
Conger, 391
Conjugation, 7, 31
Connective-tissue, 96, 118, 318
Consciousness, 2
Convoluta, 583
Copelata, 315
Copepoda, 138
Coral, 60, 61; -islands, 61
Coralline-crag, 285
Corallum, 60
Coregonus, 392
Coronella, 462
Cortical layer, 28, 34
Corticata, 39
Coverts, 481
Coxa, 163
Coxal glands, 118, 132, 157, 169
Crab, 147
Crania, 276, 279, 281
Craniata, 318
Cray-fish, ecdysis of, 113, 122, 124, 132
Cricket, 178
Crinoidea, 269, 274
Crocodyles, 457
Crocodylia, 442, 448, 468
Crocodylus, 470, 471, 473, 474
Crop, 86, 165, 204
Cross fertilization, 99
Crossopterygii, 376, 396
Crossopus, 532
Crotalinae, 463
Crotalus, 462, 463, 474
Crural glands, 152
Crus, 401
Crustacea, 110, 133
Cryptobranchus, 420
Crystalline-cone, 125
Ctenidium, 200, 214, 219, 225
Ctenoid scales, 393
Ctenophora, 65, 68, 584
Ctenoplana, 585
Ctenostomata, 285, 286
Cuckoo-spit, 180
Culex, 181
Cunaceae, 146, 149
Cursores, 495
Cuticle, 28, 34, 84
Cuttle-fish, 197, 206, 207, 221
Cuvierian organs, 267
Cycas, 205
Cycloid scales, 372
Cyclops, 139, 140

- Cyclostomata, 318, 344
 Cymotrichi, 566
Cynips, 180
Cynomys, 557
Cypridina, 138
 Cyprinidae, 390, 392, 398
Cyprinus, 398
Cypris, 138
 Cyst, 16, 25, 32, 37
 Cysticeroid, 594
Cysticercus, 594, 595

 Dab, 393
 Daddy-long-legs, 181
Daphnia, 135, 136, 137
 Dart-sac, 208
 Dasypodidae, 525, 569
Dasypus, 524
 Dasyuridae, 519, 567
 Dead men's fingers, 56
 Decapoda, 146, 148, 235
 Deer, 549, 552
 Degeneration, 11
Delphinapterus, 528, 570
Delphinus, 528
 Demospongiae, 75
 Dendrites, 322
 Dendrochirotae, 269
 Dendrocoelida, 583, 584, 596
Dendrocoelum, 584
 Dental formula, 505
Dentalium, 234
 Dentine, 354
 Dermal glands, 404
 Dermis, 95, 118
 Desman, 532, 533
Desmodus, 559
 Desmognathidae, 422, 437
 Desmognathous, 496
Desmognathus, 422, 438
 Development, definition of, 7
 Diastema, 553
Diastylis, 149
 Dibranchiata, 235
Dicotyles, 546, 573
 Didelphidae, 518, 567
Didelphys, 519, 567
Diemyctilus, 422
 Differentiation, 11
Diffugia, 17, 18, 38
 Digenea, 589, 597
 Digestion, 5
 Digit, 401
Dinornis, 496
 Dinosauria, 473
Dinoherium, 540
Diodon, 394, 399
 Diphycecul, 348, 373
 Dipleurula, 273
 Diplopoda, 154, 158, 159
 Dipnoi, 353, 371, 395
 Diprotodontia, 518, 568
 Diptera, 172, 176, 181
 Discontinuous distribution, 543
 Distal, 80
Distoma, 586, 588
Dodicophryne, 429
 Dog, 501, 502, 504, 534, 535
 Dog-fish, 365
 Dolphin, 528
 Donkey, 545
Dorcatherium, 550
 Dormouse, 554, 556
 Dorsal, 81
Draco, 459
 Dragon-fly, 112, 173, 174, 178
 Dromacognathous, 496
Dromacrus, 496
 Duck, 482, 495, 496
 Duckbill, 514
 Dugong, 530
 Duplicidentata, 554, 575

 Eagle, 496
 Ear, 53, 322, 324, 325
 Ear-shell, 206, 209, 210
 Eared Seals, 538
 Earth-pig, 526
 Earthworm, 82; British species of, 100
 Earwig, 174, 178
 Ecardines, 281
 Ecdysis, 113, 175, 441
Echelus, 391, 397
Echidna, 514, 516, 567
Echinarachnus, 265, 275
Echinaster, 236, 237, 241, 274
Echinocardium, 265
Echinococcus, 595
Echinocyaneus, 264
 Echinodermata, 236
 Echinoiden, 255, 274
Echinus, 255, 256, 257, 260, 262, 264, 275
 Ectoderm, 43, 58, 577
 Ectoplasm, 14
 Ectoprocta, 286
 Edentata, 522, 569
 Eels, 390
 Effodientia, 526
 Eft, 406
 Elapidae, 462
Elaps, 463
 Elaspipoda, 268
 Elasmobranchii, 353, 354, 395
Elatr, 111
 Elephant, 539, 540, 541
Elephas, 540, 541, 572
 Eleutherozoa, 274
 Elk, 552
 Flytra, 163, 173
 Embryo, definition of, 8

- Emeu, 496
 Emydidae, 467
 Enamel, 355
 Endocyclica, 275
 Endoderm, 43, 58, 118
 Endodermal lamella, 50
 Endoplasm, 14
 Endopodite, 139
 Endoprocta, 286
 Endoskeleton, 195
 Endosternite, 195
 Endostyle, 300, 304, 310, 331
 Enopla, 602
 Enteropneusta, 292
 Entomology, 160
 Entomostraca, 133
 Epanorthidae, 520, 568
Epeira, 116, 183, 184, 186
Ephemera, 178
Ephippium, 137
Ephydatia, 74, 75
 Ephyra, 65
Epierum, 437, 439
 Epidermis, 95
 Epiphyseae, 476
 Epistome, 283
 Epitrichial layer, 441
 Equidae, 542, 544, 573
Equus, 543, 544, 573
Erethizon, 554, 557, 575
 Erinaceidae, 532, 533, 570
Erinaceus, 532, 570
Euglena, 34, 35, 39
 Euglenoid; 35
 Eulamellibranchiata, 235
Euphausia, 146
Euplectella, 75
 Eurypterina, 196
Euscorpius, 123
Euspongia, 74
 Eustachian tube, 424, 506
 Eutheria, 514, 521, 568
 Euthyneura, 234
 Evolution, 11
 Excreta, 4
 Excretion, 4; in Arthropods, 131
 Exopodite, 139
 Exoskeleton, 111, 129, 197
 Extensor muscle, 121
 Exumbrella, 50
 Eye, 53; of Arthropods, 122, 123, 145, 170, 187; of Molluscs, 199, 229; of Vertebrates, 322, 325
 Falciform embryo, 38
 Fallow-deer, 552
 Family, 9
 Fat-body, 165
 Feathers, 475, 476
 Feather-stars, 236
 Felidae, 571
Felis, 583, 571
 Femur, 163, 401
 Fertilization, 48
Fiber, 557, 575
 Fibriale, 402
 Fibrils, 29
 Field-vole, 555
Filaria, 615
 Filibranchiata, 235
 Fins, 352, 359, 400
 Firmisternia, 435, 436, 439
 Fish-lice, 141
 Fission, 7, 16, 31; in *Hydra*, 48
 Fissipedia, 537, 571
 Flagellata, 34; reproduction of, 36, 39
 Flagellula, 25
 Flagellum, 25; of *Helix*, 208
 Flea, 181
 Flexor muscle, 121
 Flight, 481
Floscularia, 603, 604, 605, 609
 Flowers-of-Tan, 16, 24
 Fly, 172, 181
 Flying Foxes, 559
 Flying Squirrel, 555
 Food, of animals and plants, 2
 Foot of Mollusc, 198, 211
 Foraminifera, 21, 38
Forficula, 178
Formica, 179, 180
 Fowl, 483
 Fox, 535
 Fox-bats, 559
Fredericella, 286
 Freshwater Polyp, 40
 Frog, 400, 423
 Frog-hoppers, 180
 Fruit-eating Bat, 558
 Functions, 15
Fungia, 65
 Funicle, 283
 Gadidae, 392, 398
Gadus, 382, 386, 398
 Galea, 162, 163
Galeus, 367
 Gall-fly, 180, 181
Gallus, 483
Gammarus, 117, 150
 Ganglion, 93
 Gannet, 478
 Ganoidei, 376, 396
 Gar-pikes, 380
 Gasteropoda, 198, 210, 233
 Gastric filaments, 62
Gavialis, 473, 474
 Gemmation, 7; in *Hydra*, 48
 Generative organs, 54
 Genus, 9
Geonemertes, 599, 602

- Germ, 7
 Gestation, 521
 Giant-fibres, 96
 Gibbon, 565
 Gills, of Arthropods, 127; of *Bran-*
chellion, 103; of Molluscs, 199; of
Nereis, 102
 Gill-book, 129, 130, 183, 194
 Gill-slits, 291
Giraffa, 551, 574
 Giraffe, 549, 551
 Giraffidae, 549, 574
 Gizzard, 86, 165
 Gland, 5
 Glass-snake, 459
Globicephalus, 527, 528, 570
Globigerina, 24, 38
 Glochidia, 219
Glossinia, 181
 Glottis, 404, 407
 Gnat, 172, 181
 Gnathite, 117, 159, 162, 171
 Gnathobase, 117, 155, 162, 182, 185
 Gnathobdellidae, 104, 107
 Gnathostomata, 344, 350, 403
 Goat, 549
 Gobiidae, 393
 Goblet-cells, 95
 Gonads, 54
 Gonophore, 55
 Gopher, 468
Gorilla, 561, 565, 576
 Gallatores, 495
 Grampus, 528
Grantia, 73, 74, 75
 Grasshopper, 173, 174, 178
 Gray Seal, 539
 Green gland, 131
 Greenland Seal, 539
 Green Turtle, 465, 466, 467
 Grizzly Bear, 536
Gromia, 18, 20, 38
 Ground Squirrels, 554, 556
 Growth, 1, 5, 6, 113
 Grubs, 177
Gryllus, 178
 Guinea-pig, 553, 554
 Gull, 495
 Gullet, 57
 Gurnard, 393
 Gymnoblastea, 68
 Gymnomyxa, 38
 Gymnophiona, 405, 436, 439
 Haddock, 392
Haemamoeba, 38, 39
Haemocoel, 118, 126, 167
 Haemoglobin, 91
Haemomenas, 38
 Hag-fish, 345
 Hair, 498, 499
 Halecomorphi, 378, 397
 Halibut, 393
Halichoerus, 539
Halicore, 530, 570
Haliotis, 206, 207, 209, 210, 233
 Halteres, 181
 Hammerhead, 367
Hapale, 576
 Hapalidae, 563, 576
Haploceros, 552, 574
 Hare, 553, 554
 Harlequin Snake, 463
Harriotta, 370
 Harvestmen, 183, 188, 189
 Head, 159
 Heart-urchins, 265
 Hedgehog, 532
Heliosphaera, 23, 39
 Heliozoa, 25, 39
Helix, 198, 200, 201, 202, 203, 234
Hemerobius, 178
 Hemichordata, 291, 302
 Hemiptera, 172, 174, 176, 180
 Heredity, 8
 Hermaphrodite, 7, 83
 Hermaphroditism, 208
 Herrings, 390
 Hessian-fly, 181
 Heterocercal, 359
 Heteronemertini, 602
 Hexactinellida, 75
 Hinge, 212
Hippocampus, 394, 399
Hippoglossus, 393, 398
 Hippopotamidae, 545, 573
Hippopotamus, 545, 573
 Hirudinea, 103, 109
Hirudo, 103, 106, 109
 Hog-water-louse, 151
 Holocephali, 353, 369, 395
Holothuria, 266, 275
 Holothuroidea, 265, 275
 Holotrichous, 32
 Hominidae, 563
Homo, 576
 Homology, 12
 Homoplasy, 12
 Hoof, 539, 549
Hormiphora, 66
 Horned "toad," 459
 Hornet, 180
 Horse, 542, 545
 Horse-fly, 181
 Huanaco, 550
 Humble-bee, 180
 Humerus, 401
 Hybrids, 8
Hydatina, 605
Hydra, species of, 40, 41, 42, 44, 45,
 47
 Hydranth, 52

- Hydra-tuba, **64**, 592
 Hydrida, 67
 Hydroid person, 52, 55
 Hydromedusae, 48, 67
 Hydrozoa, 67
Hyla, 436, 438
 Hylidae, 435, 436, 438
Hylobates, 565, 576
 Hymenoptera, **173**, 176, 179
 Hyoid, 410, 427
 Hyomandibular, 356, 384
 Hyostylic, 357
Hypogeophis, 437, 439
 Hypopharynx, 172
 Hyracidae, 539, 572
Hyrax, 539, **540**, 572
Hystrix, 554, 575

Ichneumon, 180
 Ichthyoida, 420, 437
 Ichthyopterygium, 353
 Ichthyosauria, 473
Ictalurus, 391, 397
 Iguanidae, 459
 Imago, 176
 Indian ink, 229
 Infusions, organisms in, 17
 Ingestion, 5
 Insecta, **111**, 159
 Insectivora, 531, 570
 Insessores, 495
 Interorbital septum, 445, 485
 Interstitial cells, 44, 51
 Intertentacular organ, 284
 Invertebrata, 13
 Irritability, 6
 Isopleura, 210, 233
 Isopoda, 151
 Ixodidae, 190

 Jackal, 535
 Jack-rabbit, 555
 Jelly, 46, 50, 58, 72
 Jelly-fish, 52, 62
Julus, **111**, **158**, 159
 Jumping Shrew, 531

 Kangaroo, 521
 Kangaroo-rat, **518**
 Katabolism, 4, 15, 17
 Keber's organ, 218
 King-crab, 129, 193, **194**, **195**
 Kiwi, 496
Krohnia, 290

 Labium, 162, **163**, 172
 Labridae, 393
 Labrum, 162
Labrus, 399
Lacerta, 442, **452**, 455, 474
 Lacertilia, 442, 459, 473

 Lacinia, 162, **163**
 Lady-bird, **179**
 Lamellibranchiata, 202, 211, 215, 234
 Lamprey, **345**
 Land nemertines, 599
 Land tortoises, 467
 Langur, 564
 Larva, 8; of Acalephae, 64; of Amphibia, 405, 419, 434; of Echinoderms, 273; Ephyræ, 65; of Hydro-medusae, **54**; of Insects, 175; of Nemertines, 600; of Sponges, 73; of Teleostomi, 388; of Trematodes, 589; of Tunicata, 308; of Turbellaria, 584
 Larvacea, 315
 Larynx, 491
 Lateral line, 331
 Leiotrichi, 567
Lemur, 561, **562**, 575
 Lemuroidea, 561, 575
 Lens, 122, 328
 Leopard, 535
Lepas, **142**
 Lepidoptera, 172, 175, 181
Lepidosiren, **371**, 395
 Lepidosteidae, 378, 397
Lepidosteus, 375, 381, 397
Lepisma, 177
 Leporidae, 554
 Leptostraca, 144
Lepus, **507**, **509**, **554**, 555, 575
Leuciscus, **389**
Leucosolenia, 69, **70**, **71**, 73, 75
Libellula, 178
 Lice, 180
 Life, 1, 3
 Ligula, 162, 173
 Lily-encrinites, 269
 Limicolae, 100
Limnaea, 198, **206**, 589
 Limpet, 202, 203, 209
Limulus, 111, 129, **130**, 193, **194**, **195**
Lineus, 598, **599**, 601
Lingula, 276, 279, 280, 281
 Lion, 535
Lithobius, 111, **114**, 154, **155**, **157**, 159
 Liver-fluke, 589
 Lizards, 442, **454**, **458**
 Llama, 550
 Lobosa, 17, 18, 38
 Locomotor organ, 6
Locusta, 178
Loenanthus, **444**
 Loggerhead turtle, 464
 Lophobranchii, 392, 393, 399
 Lophophore, 278, 283
Lucanus, 172
Lumbricus, **83**, **86**, **87**, **92**, **94**, **97**;
 British species of, 100, 108
 Lung-book, 130, 183, 185

- Lutra*, 536, 571
 Lymph, 424
 Lynx, 535

Macacus, 564, 576
 Mackerel, 393
 Macropodidae, 521, 568
Macropus, 521, 569
Macroscelides, 531, 532
Macrura, 146
 Maggots, 177
Malacobdella, 602
Malacostraca, 133, 143
 Malpighian capsule, 342
 Malpighian layer, 404
 Malpighian tubules, 131, 157, 167, 169
 Mammalia, 351, 498
 Mammals, 450
 Mammary glands, 500
 Mammoth, 542
 Man, 561, 563
 Manatee, 529, 530
Manatus, 529, 530, 570
 Mandible, 116, 162, 163, 172
 Manidae, 523, 569
Manis, 525, 569
Mantis, 178
 Mantle, 197, 212
 Mantle-cavity, 197, 199
 Manubrium, 52, 62
 Maus, 401
 Marine mammals, 526
 Marine turtles, 468
 Marmosets, 563
 Marmot, 554, 556
 Marsipobranchii, 348
 Marten, 536
 Mastax, 603
Mastodon, 541
 Maxilla, 116, 162, 163, 172, 185
 Maxillary gland, 131
 Maxillipede, 116, 148
 May-fly, 178
 Meckel's cartilage, 356, 410, 446, 505
 Medulla oblongata, 321
 Medullary plate, 291
 Medusa, 50, 52
 Medusoid person, 52, 55
 Megapodes, 497
Meles, 536, 571
Melolontha, 115, 121, 122, 128
Menopoma, 420, 437
 Mentum, 162, 163
Mephitis, 537, 571
 Mesenteric filament, 59
 Mesenteron, 126
 Mesentery, 57, 60
 Mesoderm, 76
 Mesogloea, 46
 Mesoneimertini, 602
 Mesosoma, 115, 182, 191, 193

Mesostoma, 579, 580
 Meso-thorax, 162
 Metabolism, 3
 Metacarpus, 401
 Metamorphosis, 175, 311
 Metanemertini, 602
 Metasoma, 115, 183, 191, 193
 Metatheria, 514, 516, 567
 Meta-thorax, 162
 Metazoa, 13
 Micronucleus, 31, 33
Midas, 576
 Mink, 536
 Mites, 183, 191
 Moa, 496
 Mole, 532
 Mole-shrew, 533
Molge, 401, 403, 406, 409, 410, 411, 412, 413, 416, 417, 418, 419, 420, 422, 437
 Mollusca, 197
 Molpadidae, 269
 Monkey, 561
Monocystis, 38, 39
 Monogenea, 589, 597
 Moose, 552
 Morphology, 9
Moschus, 548
 Mosquito, 172, 181
 Moth, 174, 175, 182
 Mother-of-pearl, 212
 Mound-birds, 497
 Mouse, 554, 555
 Mouth-parts of Insects, 171
 Movement, 5
 Mucous glands, 208
 Mud-puppy, 421
 Mud-turtle, 468
 Müller's larva, 584
 Multicellular, 27, 43
 Multiplication, 1, 5
 Muridae, 554, 555
Mus, 575
Musca, 172, 181
Muscardinus, 556, 575
 Muscle, 6; of *Anodonta*, 213; of Arthropods, 120
 Muscle-cell, of *Lumbricus*, 95
 Musk-ox, 551, 552
 Musk-rat, 557
 Musquash, 556, 557
 Mussels, 197
 Mustelidae, 536, 571
Mustelus, 338, 536, 571
Mya, 220
 Mycetozoa, 16, 24, 39
 Myocoel, 300
 Myo-epithelial cell, 47, 95
Myogale, 532, 533, 570
 Myotome, 298
 Myoxidae, 554
 Myriapoda, 111, 116, 131, 154, 159

- Myrmecobius*, 519
Myrmecophagidae, 523, 524, 569
Myrmecophagus, 569
Myrmeleo, 178
Mysis, 146
Mystacoceti, 527, 528, 570
Mytilus, 219, 235
Myzine, 350
Myxinidae, 345, 348
Myxomycetes, 25

Nacreous layer, 212
Naris, 407
Natatores, 495
Natterjack, 423, 435
Natural selection, 10
Nauplius, 134, 144, 146
Nautilus, 200, 210, 225, 232, 235
Nebalia, 144
Necturus, 421, 437, 589
Nematocyst, 44
Nematoda, 611
Nemertinea, 598
Neomenia, 234
Nephele, 107, 109
Nephridium, of Arthropods, 131, 169;
of *Hirudo*, 104; of *Lumbricus*, 83,
89; of Molluscs, 209, 217
Nephrostome, 89
Nereis, 101, 102, 108
Nerves, 6
Nervous system, of Arthropods, 121,
169, 187; of Brachiopods, 279; of
Cephalopods, 229; of Chaetognatha,
288; of Echinoderms, 244; functions
of, 93; of Gasteropoda, 206; of
Haliotis, 207; of *Helix*, 204; of La-
mellibranchiata, 219; of *Lumbricus*,
92; minute structure of, 321; of
Turbellaria, 581; of Vertebrata, 291,
319, 329, 487, 506
Nervures, 173
Nests, 495
Neurenteric canal, 303
Neuroglia, 322
Neuron, 321
Neuropodium, 101
Neuroptera, 172, 176, 178
Newt, 400, 419
Nidamental glands, 231
Nipple, 500
Nose, 322, 323
Notidanidae, 357
Notochord, 79, 291, 296
Notonecta, 180
Notopodium, 101
Notoryctidae, 519, 520, 568
Notoryctes, 520, 568
Nucleic acid, 3
Nucleus, 3, 16, 26, 29, 32
Nucula, 209, 219, 234

Nyctiphanes, 145

Obelia, 48, 49, 55
Octopoda, 231, 235
Octopus, 197, 232, 235
Odontaspis, 355
Odontoceti, 527, 570
Odontoid process, 443
Oesophagus, 57, 86, 126
Oestrus, 181
Oligochaeta, 100, 101, 108, 152
Oligolophus, 189
Ommastrephes, 221, 232, 235
Oncorhynchus, 391, 397
Oniscus, 151
Ontogeny, 12
Ooecium, 284
Oostegites, 146
Opalina, 32, 39, 43
Operculum, of *Limulus*, 194
Ophidia, 442, 458, 459, 474
Ophioglypha, 249, 252, 274
Ophisaurus, 459
Ophiuroidea, 248, 250, 251, 274
Opisthobranchiata, 208, 210
Opisthocoeleous, 380
Opossum, 516, 518, 520
Oral-cone, 40, 56; -surface, 50, 66
Orang-utan, 564
Orca, 528
Organ-pipe coral, 58
Organs, 28
Organs of Bojanus, 217
Ornithorhynchus, 514, 515, 567
Orthoptera, 172, 176, 178
Orycteropodidae, 523, 569
Orycteropus, 525, 569
Osculum, 70
Ospiradium, 207, 219
Ostia, 126, 156, 167
Ostracion, 394, 399
Ostracoda, 134, 137
Ostrea, 220
Ostrich, 484, 487, 495, 496
Otaria, 538, 571
Oteriidae, 538, 571
Otocyst, 205, 219, 231
Otter, 536
Ovary, 44; of *Lumbricus*, 97
Ovibos, 551, 552, 574
Ovis, 574
Ovotestis, 208
Ovum, 7; of *Hydra*, 44
Owl, 557
Ox, 549, 551
Oyster, 197, 205, 211, 220

Palatal flap, 446, 452, 470
Palp, 162, 163
Palpal organs, 188
Pangolin, 525

- Panther, 535
 Parachordals, 319
 Paraglossa, 162, 179
 Paramoecium, 32, 33, 39
 Para-oesophageal commissures, 92, 121
 Parasitic, 36, 585
 Parenchyma, 579
 Passeres, 497
 Patella, 202, 209, 233
 Pavo, 479
 Peacock, 479
 Pea-urchin, 265
 Peccary, 546
 Pecten, 215, 220
 Pectines, 191
 Pectinibranchiata, 234
 Pedalion, 610
 Pedicellaria, 246, 256
 Pedipalpi, 183
 Pelagic, 290
 Pelecypoda, 211
 Pelmatozoa, 274
 Pelodytidae, 436, 438
Penaus, 127
 Penis, 455
 Pentacrinoids, 273
Pentacrinus, 272, 273
 Pentadactyle, 401, 450
 Peracopods, 143
Perameles, 568
 Peramelidae, 519, 520, 568
Perca, 399
 Perch, 393
 Percidae, 393, 399
 Pericardium, 126, 167, 200
 Periostracum, 212
Peripatus, 111, 116, 151, 152, 153, 169
Periplaneta, 160, 161, 163, 166
 Perisarc, 49
 Perissodactyla, 542, 543, 572
 Peristalsis, 87
 Peristome, 28
 Peritoneum, 85, 96
 Peritrichous, 32
 Periwinkle, 197, 199
 Perspiration, 500
 Pes, 401
Petrogale, 517, 521, 569
Petromyzon, 345, 346, 347
 Petromyzontidae, 348
Phalanger, 568
 Phalangeridae, 520, 568
 Phalangida, 188
 Phalangids, 115
Phaneroglossa, 435, 438
 Pharyngognathi, 392, 393, 399
 Pharynx, 29, 85
Phascolarctus, 520
 Phascolomyidae, 520, 568
Phascolomys, 568
Phasma, 178
 Pheasant, 497
Phoca, 539, 572
Phocaena, 528, 570
 Phocidae, 539, 572
Pholas, 220
 Phosphorescence, 145
Phryganea, 178
Phrynosoma, 459
 Phyllactolaemata, 285, 286
Phyllium, 178
 Phyllopoda, 134
Phylloxera, 180
 Phylogeny, 12
 Phylum, 9, 11
Physeter, 527, 570
 Physiology, 9
 Physoclisti, 390, 398
 Physostomi, 390, 397
Phytoptus, 191
 Pig, 545
 Pigeon, 486, 490, 494
 Pilchard, 391
 Pilidium, 601
 Pilot whale, 527
 Pineal gland, 321, 349
 Pinnipedia, 537, 571
Pipa, 435, 438
 Pipe-fish, 393
 Pipistrelle, 559
 Pisces, 350, 352
 Pituitary body, 319, 331
 Placenta, 317, 521
 Placoid scales, 354
 Plaice, 392
Planaria, 584
Planorbis, origin of mesoderm, 78
 Plant-louse, 174, 180
 Plants and animals, 1, 25, 35
 Planula, 54, 64
 Plasmodium, 25
Platessa, 398
 Platyhelminthes, 577
Platypus, 514
 Platyrrhini, 563, 575
Plecotus, 559
 Plectognathi, 392, 394, 399
 Pleopods, 143
 Plesiosauria, 473
Plethodon, 423, 438
 Plethodontidae, 422, 438
 Pleural membrane, 163
 Pleurobranch, 128
Pleuronectes, 392
 Pleuronectidae, 393, 398
 Ploima, 610
Plumatella, 283
 Podical plates, 164
 Podobranch, 128
 Polecat, 536
 Pole-cells, 77

- Polian vesicles, 244, 267
 Pollack, 393
 Polychaeta, 101, 108
 Polyclada, 583, 584, 596
 Polyp, 40, 52
 Polyprotodontia, 518, 567
Polypterus, 375, 377, 396
Polystomella, 19, 22, 26, 38
Polystomum, 589
 Polyzoa, 282
 Pond-mussel, 209
 Pond-turtle, 467
Porcellio, 151
 Porcupine, 554, 556
 Pores, dorsal, 85, 90
 Porifera, 69, 70
 Porocytes, 72
 Porpoise, 528
 Portal system, 335
 Post-axial, 402
 Posterior, 80
 Post-zygapophyses, 404
 Prairie-dog or -marmot, 557
 Prawn, 127
 Pre-axial, 402
 Prepotency, 8
 Pre-zygapophyses, 404
 Primates, 561, 575
 Prismatic layer, 212
Pristis, 368
 Proboscideae, 539, 540, 572
Procavia, 539, 540, 572
 Proctodaeum, 57, 79, 125, 165
Procyon, 537, 571
 Procyonidae, 537, 571
 Proglottis, 592
 Pronation, 403
Proneomenia, 234
 Pronephros, 341
 Prongbuck, 549, 551
 Prosobranchiata, 208, 210
 Prosoma, 115, 182, 193
 Prosopyle, 74
 Prostomium, 85
 Protective colouration, 536
 Proteids, 3, 4
Proteus, 421, 437
 Proteus animalcule, 13
 Protobranchiata, 234
 Protonemertini, 602
 Protoplasm, description of, 1, 3, 5
 Protopodite, 139
Protopterus, 395
 Prototheria, 514, 567
 Prototracheata, 111, 151
 Protozoa, 12, 13; in infusions, 17;
 classification of, 38
 Proximal, 80
 Pseudopodia, 15; in *Hydra*, 47
 Pteropidae, 559
Pteropus, 558, 559
 Pterosauria, 473
Pterotrachea, 205, 206
Ptychodera, 292, 294, 295
Pulex, 181
 Pulmonata, 234
 Puma, 535
 Pupa, 176
Pyrosoma, 316
 Python, 460
 Quagga, 545
 Rabbit, 507, 553, 554
 Radiale, 402
 Radiolaria, 23, 39
 Radiolarian ooze, 24
 Radula, 202, 207
Raia, 367, 368, 395
Rana, 423, 425, 426, 427, 428, 429, 434,
 436, 439
Rangifer, 551, 574
 Ranidae, 423, 436, 439
 Raptores, 495
 Rat, 553, 555
 Ratitae, 195, 497
 Rattlesnake, 462, 463
 Rays, 365
 Razor-shell, 220
 Recapitulation theory, 12
 Receptaculum ovarum, 98
 Rectum, 165
 Red-deer, 552
 Redia, 590
 Red-spider, 191
 Reindeer, 551
 Reno-pericardial canal, 201, 217, 225
 Reproduction, 7; by fission, 16
 Reptilia, 351, 440, 447, 450
 Respiration, 4
 Reticularia, 38
 Retina, 321
 Retinula, 122
 Rhabdites, 579
 Rhabdocoela, 583, 584, 596
 Rhabdocoelida, 583, 584, 596
 Rhabdome, 122
Rhea, 496, 497
Rhinoceros, 539, 542, 543, 544, 573
 Rhinocerotidae, 542, 543, 573
Rhinolophus, 559, 575
Rhizocrinus, 272
 Rhizota, 609
 Rhynchobdellidae, 104, 107
 Rhynchocephala, 442, 455, 473
 Rhynchocoelum, 602
Rhynchonella, 276, 281
Rhytina, 530
 Right Whale, 529
 River bass, 399
 Roach, 389
 Robin, 496

- Rock-wallaby, 521
 Rodentia, 553, 574
 Rods and cones, 327
 Rorqual, 529
Rotifer, 610
 Rotifera, 603
 Round-worms, 611
 Ruminantia, 546

 Sacculus, 325
 Sacral, 403
Sagitta, 288
 Salamander, 400
Salamandra, 412, 437
 Salamandridae, 422, 437
 Salamandroidea, 420, 421, 437
 Salivary glands, of *Helix*, 204; of *Lithobius*, 157; of Mammals, 513; of *Periplaneta*, 165
Salmo, 384, 385, 387, 391, 397
 Salmon, 384, 390
 Salmonidae, 390, 391, 397
Salpa, 316, 317
Salvelinus, 391, 397
 Sand-dollar, 265
 Sauria, 442, 457, 473
 Sauropsida, 475
 Saw-fly, 176, 180
 Scale-insects, 180
 Scales, of Elasmobranchii, 354; of Reptiles, 441
 Scallop, 215, 220
 Scansores, 495
Scaphiopus, 436, 438
 Scaphognathite, 128
 Scaphopoda, 234
 Schizognathous, 496
 Schizopoda, 145, 148
 Scirtopoda, 610
 Sciuridae, 554
Sciuropterus, 555
Sciurus, 555, 575
 Scleroblasts, 73
Scomber, 398
 Scombridae, 393, 398
Scorpio, 192
 Scorpion, 122, 130, 183
 Scorpionida, 191
Scotophilus, 560
 Scutum, 141
Seyllium, 320, 323, 335, 339, 356, 358, 359, 362, 364, 366, 395
 Scyphistoma, 65
 Sea-anemones, 56, 60
 Sea-bass, 399
 Sea-cows, 526, 529
 Sea-cucumbers, 236, 265
 Sea-hare, 206
 Sea-horse, 394
 Sea-lion, 538
 Sea-mussel, 219
 Sea-urchins, 236, 253, 258, 261
 Seal, 526, 538
 Sebaceous glands, 500
 Secondaries, 481
 Secretion, 4, 17
 Segmentation, 82
 Selachii, 367
 Selachioidei, 395
 Selenodont, 548
 Selenodontia, 546, 547, 573
 Semi-circular canals, 324
Semnopithecus, 564, 576
 Sense-hairs, 52
Sepia, 221, 222, 224, 226, 227, 228, 230, 235
 Serotine, 560
 Serranidae, 393, 399
 Sexual union, 7
 Shad, 391
 Sharks, 365
 Sheep, 546, 547, 549
 Shell-fish, 197
 Shell-gland, 131
 Shrew, 531
 Silk, 186
 Silk-worm, 176, 182
 Siluridae, 390, 397
 Silver-fish, 177
Simia, 564, 565, 576
 Simiidae, 563, 564
 Simplicidentata, 555, 575
 Sinus, 105
 Siphon in Lamellibranchiata, 215
 Siphonoglyph, 60
Siphonostoma, 393
 Siphuncle, 232
Siredon, 421
Siren, 421, 437
 Sirenia, 526, 529, 570
Sirex, 180
 Skates, 365
 Skin, 95, 329, 403
 Skunk, 536, 537
 Sloths, 523
 Sloughing, 441
 Slow-worm, 459
Smittia, 282
 Snake, 442, 457, 458, 460, 461
 Snapper, 468
 Snapping turtle, 468
Solaster, 248
 Sole, 393
Solea, 393, 398
Solen, 220
 Solenogastres, 209, 234
Sorex, 531, 570
 Soricidae, 531, 533, 570
Spadella, 283
 Spatangidae, 265, 275
Spatangus, 275
 Species, 7; origin of, 9

- Spelerpes*, 422, 438
 Spermathecae, of *Lumbricus*, 83, 99;
 of *Helix*, 208
 Spermatophores, of *Helix*, 208; of *Hirudo*, 107; of *Sepia*, 231
 Spermatozoa, 7; of *Hydra*, 44; of
 Lumbricus, 97
 Sperm-whale, 527
Sphenodon, 442, 448, 455, 456, 473
Sphyrnura, 589
 Spicules, 58, 73
 Spider, 115, 116, 129, 130, 183; web
 of, 186
 Spider-monkeys, 563
 Spinnerets, 183, 185
 Spiny ant-eater, 514
 Spiracle, 357
Spirula, 210
 Splanchnic, 96
 Sponges, 69; Bath-, 74
Spongilla, 72, 74, 75
 Spores, 25, 37
 Sporocyst, 589
 Sporozoa, 36, 39
 Sport, 9
 Sprat, 391
Squalus, 367
 Squid, 197, 221
Squilla, 148
 Squirrel, 553, 554, 555
 Star-fish, 236, 241, 242
 Star-nosed Mole, 533
 Statoblasts, 285
 Steapsin, 333
 Steganopodes, 484
 Stegocephala, 405, 437, 447
 Stercoral pocket, 187
 Sternum, 158, 163
 Stigmata, 129, 168
 Sting-ray, 367
 Stoat, 536
 Stolon, 59, 316
 Stomatopoda, 146, 148
 Stomodaeum, 57, 64, 67, 79, 125, 165,
 301
 Stone-canal, 243
 Streptoneura, 233
 Streptoneurous, 210
 Strobilization, 64, 592
Strongylocentrus, 254
 Structureless lamella, 46
Struthio, 487, 496, 497
 Sturgeon, 379, 380
 Sub-mentum, 162, 163
 Sub-umbrella, 50
 Sub-ungulata, 539, 572
 Suctoria, 34, 39
 Suidae, 546, 573
 Suinae, 545
Sula, 478
 Summer-eggs, 137
 Supination, 403
 Surinam toad, 435
Sus, 546, 573
 Suspensorium, 410, 424
 Sweat-glands, 500
Sycon, 74
 Symmetry, 80; bilateral, 81, 114, 209;
 radial, 81
 Sympathetic nervous system, 329
 Symphysis, 450
 Symplectic, 384
 Synapticulae, 306
 Synaptidae, 269
Synchaeta, 608, 610
Syngamus, 615
Syngnathus, 399
 Syrinx, 491

Tabanus, 181
 Tadpole, 435
Taenia, 591, 592, 593, 595
Talpa, 532, 570
 Talpidae, 532, 533, 570
Tamandua, 523, 525
Tamias, 554, 557, 575
 Tapir, 542, 543
 Tapiridae, 542, 573
Tapirus, 543, 573
 Tarsalia, 402
 Tarsus, 163, 401
 Tasmanian wolf, 519
 Teat, 500
 Teeth, origin of, 355; of Mammalia,
 503, 504
Tegenaria, 118, 185
 Teleostei, 376, 380, 397
 Teleostomi, 353, 375, 396
 Telson, 143
 Temnocephalidae, 587
 Tendon, 119
 Tentacles, 40; of Actinozoa, 57; of
 Hydromedusae, 49; of *Nereis*, 102
 Tentaculocyst, 63
Tenthredo, 180
Terebratula, 277, 281
Teredo, 220
 Terga, 158, 163
 Tergum, 141
Termes, 178
 Terricolae, 100
 Tertiaries, 481
 Testicardines, 281
 Testis, 44
 Testudinidae, 467, 468
Testudo, 468, 474
 Tetrabranchiata, 235
Tetradon, 394, 399
Tetranynchus, 191
Tetrastemma, 601, 602
Textrix, 184
 Thalamencephalon, 321

- Thalassicola*, 39
Thalassochelys, 464
 Thaliaceae, 315
 Thoracostraca, 144
 Thorax, 114, 134, 143, 159
 Thread-capsule, 44, 45
 Thread-worms, 611
Thrips, 178
Thylacinus, 519, 567
 Thyroid gland, 331, 349
 Tibia, 163
 Tibiale, 402
 Tick, 190
 Tiger, 535
 Tinamou, 496
Tipula, 181
 Toad, 400, 423
 Toothed whales, 527
Torpedo, 367
 Tortoise, 442, 467
 Trabeculae, 319
 Trachea, 111, 129, 156, 168, 452
 Tracheata, 129
 Tragulidae, 549, 574
Tragulus, 574
 Tree-frog, 435
 Trematoda, 578, 597
 Triclad, 583, 596
 Trichechidae, 538, 572
Trichechus, 538, 572
Trichina, 615
 Trichocysts, 34
 Triglidae, 393
Triton, 406
 Trochanter, 163
 Trochus, 605
Tropidonotus, 460, 462
 Trout, 390, 391
 Trunk-fish, 394
Trygon, 367, 395
 Tryonychidae, 468
 Trypsin, 333
 Tsetse-fly, 181
 Tube-feet, 241
 Tuberculum, 408
Tubifex, 595
Tubipora, 58
Tubularia, 55
Tubulipora, 282
 Tunicata, 308
 Turbellaria, 578, 579, 596
 Turbot, 393
 Turtle, 442, 457
Tylenchus, 615
 Tylopoda, 549
 Tympanum, 424
 Typhlosole, 86, 96
Tyroglyphus, 190
 Ulnare, 402
 Ulotrichi, 566
 Uncinate processes, 456
 Ungulata, 539, 572
 Ungulata vera, 542, 572
 Unicellular, 43
Unio, 209, 211, 212, 214, 235
 Urea, 4
 Ureter, 201
 Uric acid, 4, 157
 Urino-genital organs, 341
 Urochordata, 291, 308
 Urodela, 405, 415, 437, 457
 Ursidae, 536, 571
Ursus, 536, 571
 Uvula, 502
 Vacuole, food-, 14, 30; contractile-, 15, 30, 33
 Vampire, 559
Varanus, 445, 449, 451
 Variation, 8, 9, 10
 Velum, 52, 53, 301
 Ventral, 81
 Venus' flower-basket, 75
 Vertebrata, 13, 81, 291
 Vesicula seminalis, 98
Vespa, 180
Vespertilio, 559, 575
Vesperugo, 559, 575
 Vibraculum, 285
 Vicuna, 550
 Viperidae, 463
 Visceral hump, 198
 Vitellarium, 578, 582
 Vitreous humour, 326
 Viviparous, 193
 Vole, 554, 555
Forticella, 28, 30; reproduction of, 31, 39
Waldheimia, 277, 278, 281
 Wallaby, 517
 Walrus, 538
 Wapiti, 552
 Wasp, 173, 180
 Water-boatman, 180
 Water-rat, 555
 Water-shrew, 532
 Water-vascular system, 578
 Weasel, 536
 Whalebone whale, 528
 Whale, 526, 527
 Whelk, 199, 202, 234
 White-ant, 178
 White-whale, 528
 Whiting, 393
 Wild duck, 481
 Wings of Insects, 173; of Birds, 478
 Winter-eggs, 137, 582, 608
 Wire-worm, 111
 Wolf, 535
 Wolffian duct, 341

- Wombat, 520
 Wood-ant, 179
 Woodchuck, 554
 Wood-louse, 114, 151
 Wrass, 393

Xantharpyia, 559, 560, 575
Xiphosura, 193

 Yellow-cells, in *Lumbricus*, 90

 Yolk, 7; -glands, 578

 Zebra, 545
 Zoantharia, 68
 Zooecium, 283
 Zoology, definition of, 1; object of, 3;
 subdivisions of, 9
Zygæna, 367
 Zygapophyses, 404

